33 e 15

PHYTOLOGIA;

OR THE

PHILOSOPHY

OF

AGRICULTURE

AND

GARDENING.

WITH THE THEORY OF DRAINING MORASSES,

AND WITH AN

IMPROVED CONSTRUCTION OF THE DRILL PLOUGH.

By ERASMUS DARWIN, M.D. F.R.S.

AUTHOR OF ZOONOMIA, AND OF THE BOTANIC GARDEN.

Suadent hæc CREATORIS leges a ſimplicibus ad compoſita. LIN. ORD. NAT.

LONDON:

PRINTED FOR J. JOHNSON, ST. PAUL'S CHURCH-YARD;

BY T. BENSLEY, BOLT COURT, FLEET STREET.

1800.

Entered at Stationers' Hall.



DEDICATION.

To Sir John Sinclair, Baronet, to whoſe unremitted exertions, when Preſident of the Board of Agriculture, many important improvements in the cultivation of the earth were accompliſhed and recorded; this Work, which was began by the inſtigation of his letters to the author, is dedicated with great reſpect.

Derby, Jan. 1, 1799.

CONTENTS.

Introduction.

PART THE FIRST.

PHYSIOLOGY OF VEGETATION.

SECT. I. *Individuality of the Buds of Vegetables.*
II. *Their Abſorbent Veſſels.*
III. *Their Umbilical Veſſels.*
IV. *Their Pulmonary Arteries and Veins.*
V. *Their Aortal Arteries and Veins.*
VI. *Their Glands and Secretions.*
VII. *Their Organs of Reproduction.*
VIII. *Their Muſcles, Nerves, and Brain.*

PART THE SECOND.

ECONOMY OF VEGETATION.

IX. *The Growth of Seeds, Buds, and Bulbs.*
X. *Manures, or the Food of Plants.*
XI. *Of Draining and Watering Lands.*
XII. *Aeration and Pulverization of the Soil.*
XIII. *Of Light, Heat, Electricity.*
XIV. *Diſeaſes of Plants.*

PART

PART THE THIRD.

AGRICULTURE AND HORTICULTURE.

XV. *Production of Fruits.*
XVI. *Production of Seeds.*
XVII. *Production of Roots and Barks.*
XVIII. *Production of Leaves and Wood.*
XIX. *Production of Flowers.*
XX. *Plan for disposing a Part of the System of Linneus into more Natural Classes and Orders.*

APPENDIX.

Improved Construction of the Drill Plough.

INTRO-

INTRODUCTION.

AGRICULTURE and GARDENING, though of ſuch great utility in producing the nutriment of mankind, continue to be only Arts, conſiſting of numerous detached facts and vague opinions, without a true theory to connect them, or to appreciate their analogy; at a time when many parts of knowledge of much inferior conſequence have been nicely arranged, and digeſted into Sciences.

Our imperfect acquaintance with the phyſiology and economy of vegetation is the principal cauſe of the great immaturity of our knowledge of Agriculture, and Gardening. I ſhall therefore firſt attempt a theory of vegetation, deduced principally from the experiments of Hales, Grew, Malpighi, Bonnet, Du Hamel, Buffon, Spallanzani, Prieſtley, and the Philoſophers of the Linnæan School, with a few obſervations and opinions of my own; ſome of which have in part already appeared in Zoonomia, and in the notes to the Botanic Garden, but are here corrected and enlarged. To the former of which works I hope this may be eſteemed a ſupplement, as it is properly a continuation of the ſubject.

My inducement to commence this work, after it was ſuggeſted to me by the letters of Sir John Sinclair, was a belief, that the experiments and obſervations already made on the growth of plants, with the modern improvements in chemiſtry, were ſufficiently numerous and accurate for the eſtabliſhment of a true theory of vegetation; ſo much wanted to connect the various facts in the memory, to appreciate their value, and to compare them with each other; and finally to direct the proſecution of future experiments to uſeful purpoſes.

PHYTOLOGIA.

PHYTOLOGIA.

PART THE FIRST.

PHYSIOLOGY OF VEGETATION.

SECT. I.

THE INDIVIDUALITY OF THE BUDS OF VEGETABLES.

1. *Vegetables are inferior animals. A bud torn from a tree will grow; vines and hawthorns ſo planted. Many kinds of fruit ingrafted on one tree.* 2. *The bark and branches of hollow trees remain alive. Caudex of herbaceous plants. Caudex of buds.* 3. *Which deſcending, form a new bark over the old one. Theſe bark veſſels occaſionally inoſculate. Upper lip of wounds of the bark grows downwards.* 4. *Flower-buds are individual beings; do not ſo certainly grow by inoculation as leaf-buds; are biennial plants like leaf-buds, but die in autumn without enlarging the ſize of the tree by their progeny.* 5. *In what vegetables differ from animals; they have not muſcles of locomotion; nor organs of digeſtion.* 6. *In what they reſemble animals. They have abſorbent, umbilical, placental, and pulmonary veſſels, arteries, glands, organs of reproduction, with muſcles, nerves, and brain.* 7. *Progreſs of a young bud, and of a ſeed. The plumula, radicle, and caudex of a bud.* 8. *Buds and ſeeds are biennial beings. How they differ. The diſunion of the pith diſtinguiſhes buds from each other, and thus evinces their individuality.*

1. We have ſo accuſtomed ourſelves to conſider life and irritability to be aſſociated with palpable warmth and viſible motion, that we find a renitency in ourſelves to aſcribe them to the comparatively cold and motionleſs fibres of plants. But to reaſon rightly on many vegetable phenomena we ſhall find it neceſſary firſt to ſhew, that vegetables are in reality an inferior order of animals.

If a bud be torn from the branch of a tree, or cut out and planted

in the earth with a glaſs cup inverted over it, to prevent the exhalation from being at firſt greater than its power of abſorption; or if it be inſerted into the bark of another tree, it will grow, and become a plant in every reſpect like its parent. This evinces that every bud of a tree is an individual vegetable being; and that a tree therefore is a family or ſwarm of individual plants, like the polypus, with its young growing out of its ſides, or like the branching cells of the coral-inſect.

The preſent moſt approved method of propagating vines in hot-houſes conſiſts in cutting off a ſingle eye of a vine-ſtalk with about an inch of the ſtem above the eye, and two or three inches below it; and ſetting this aſlant in the bark-bed with the eye about an inch or leſs beneath the ſurface, pointing upwards; and I have ſeen a quick-ſet or hawthorn hedge, cretægus, propagated in the ſame manner by planting twigs in the ground with one bud only above the ſoil.

Mr. Barns, in a treatiſe on Propagating Fruit-trees (1759, Baldwin, London) aſſerts, that he cut a branch into as many pieces, as there were buds or leaves upon it; and wiping the two wounded ends dry, he quickly applied to each a cement previouſly warmed, which conſiſted chiefly of pitch, and planted them in the earth with unfailing ſucceſs. The uſe of this cement I ſuſpect to conſiſt in its preventing the bud from bleeding to death, though the author aſcribes it to its antiſeptic quality. And laſtly, in the inoculation and ingrafting of fruit-trees, five or ſix different kinds of pears are frequently ſeen on the branches of one tree, which could not then properly be termed an individual being.

2. When old oaks, or willows, loſe by decay almoſt all their ſolid internal wood, it frequently happens, that a part of the ſhell of the ſtem continues to flouriſh with a few healthy branches. Whence it appears, that no part of the tree is alive but the buds, and the bark, and the root-fibres; that the bark is only an intertexture of the cau-

dexes

dexes of the numerous buds, as they paſs down to ſhoot their radicles into the earth; and that the ſolid timber of a tree ceaſes to be alive; and is then only of ſervice to ſupport the numerous family of buds in the air above the herbaceous vegetables in their vicinity.

A bud of a tree therefore, like a vegetable ariſing from a ſeed, conſiſts of three parts; the plumula or leaf, the radicle or root-fibres, and the part which joins theſe two together; which is called the caudex by Linneus when applied to intire plants; and may, therefore, be termed caudex gemmæ when applied to buds.

In herbaceous plants the caudex is generally a broad flat circular plate, from which the leaf-ſtem aſcends into the air, and the radicles or root-fibres deſcend into the earth. Thus the caudex of a plant of wheat lies between the ſtem and the radicles, at the baſis of the lowermoſt leaf, and occaſionally produces new ſtems and new radicles from its ſides. Thus the caudex of the tulip lies beneath the principal bulb, and generates new ſmaller bulbs in the boſom of each bulb-leaf, beſides one principal or central bulb; the caudex of orchis, and of ſome ranunculuſes, lies above their bulbous roots; whereas the caudexes of the buds of trees conſtitute the longitudinal filaments of the bark, reaching from the plumula or apex of the bud on the branch to the baſe of it, or its root-fibres beneath the ſoil.

Nor is this elongation of the caudexes of the buds of trees unanalogous to what happens to ſome herbaceous plants, as in wheat; when the grain is buried two or three inches beneath the ſoil, an elongation of the caudex occurs almoſt up to the ſurface, where another ſet of fibrous roots are protruded, and the upright ſtem commences. The ſame happens to tulip-roots when planted too deep in the earth, as I have witneſſed, and I ſuppoſe to thoſe of many other vegetables.

This caudex of the buds of trees not only deſcends as above deſcribed, but alſo aſcends from each bud to that above it; as on the

long ſhoots of vines, willows, and briars; in this reſpect reſembling the wires of ſtrawberries and other creeping plants. Thus the caudex of perennial herbaceous plants conſiſts of a broad plate, buried beneath the ſoil to protect it from the froſt; while the caudex of buds of trees conſiſts of a long vaſcular cord extending from the bud on the branch to the radicle beneath the earth, and endures the winter froſts without injury.

3. Theſe buds are properly biennial plants, as they are generated in one ſummer, and in the next either produce ſeeds and die, or produce other buds, whoſe caudexes form a new bark over the former one, that of the laſt year firſt becoming a ſofter or more porous wood, called alburnum, or ſap-wood, and gradually hardening into ſolid timber, which ceaſes to poſſeſs vegetable life.

Theſe long caudexes of the individual buds of trees, which conſtitute their bark, are well ſeen in the cloth made from the mulberry-bark brought from Otaheite. On inſpecting this cloth the long fibres are ſeen in ſome places to adhere, where it is probable they occaſionally inoſculate, like ſome of the veſſels in animal bodies; becauſe when ſome buds are cut off, the neighbouring ones flouriſh with greater vigour, being ſupplied with more of the nutritious juices.

This informs us why the upper lip of an horizontal wound made in the bark of a tree grows downwards with ſo much greater expedition than the under one grows upwards to meet it; as the deſcending caudexes of the individual buds are ſupplied directly with nutriment from the vegetable arteries after the oxygenation of the blood in their leaves; whereas the under lip of the wound is nouriſhed only by the lateral or inoſculating veſſels, which ſupplies us with another argument againſt the individuality of trees, and in favour of that of buds.

4. The buds producing flowers are each an individual being as well

as

as the leaf-buds above deſcribed, though they are probably not ſo eaſily capable of tranſplantation into the bark of other trees by inoculation; as, I believe, it is from the miſtake of the gardeners in chooſing flower-buds inſtead of leaf-buds to inoculate with, that ſo many buds die in this mode of propagation. Nor does the exiſtence of many male and female parts in one flower deſtroy its individuality any more than the number of paps of a ſow or bitch, or the number of their cotyledons, each of which during geſtation belongs to a ſeparate fetus.

The flower-buds as well as the leaf-buds are properly biennial plants, as they are produced in the ſummer of one year, and periſh in the autumn of the next; but as the new buds generated by leaf-buds continue to adhere to the parent, they are furniſhed with their numerous caudexes, which form a new bark over the old one, whereas the flower-buds generate ſeeds, which when mature fall upon the ground, and thus they die in the autumn without increaſing the ſize of the parent-tree by the adheſion of their progeny like the leaf-buds.

5. Theſe buds of plants, which are each an individual vegetable being, in many circumſtances reſemble individual animals; but as animal bodies are detached from the earth, and move from place to place in ſearch of food, and take that food at conſiderable intervals of time, and prepare it for their nouriſhment within their own bodies, after it is taken; it is evident, that they muſt require many organs and powers, which are not neceſſary to a ſtationary bud. As vegetables are immoveably fixed to the ſoil, from whence they draw their aliment ready prepared, and this uniformly, and not at returning intervals; it follows, that in examining their anatomy we are not to look for muſcles of locomotion, as legs and arms; nor for organs to receive and prepare their aliment as a mouth, throat, ſtomach, and bowels, by which contrivances animals are enabled to live many hours without new ſupplies of food from without.

6. The parts, which we may expect to find in the anatomy of vegetables,

vegetables, which correſpond to thoſe in the animal economy, are firſt a threefold ſyſtem of abſorbent veſſels, one branch of which is deſigned to imbibe the nutritious moiſture of the earth, as the lacteals imbibe the chyle from the ſtomach and inteſtines of animals; another to imbibe the water of the atmoſphere, opening its mouths on the cuticle of the leaves and branches, like the cutaneous lymphatic veſſels of animals; and a third to imbibe the ſecreted fluids from the internal cavities of the vegetable ſyſtem, like the cellular lymphatics of animals.

Secondly, in the vegetable fetus, as in ſeeds or buds, another ſyſtem of abſorbent veſſels is to be expected, which may be termed umbilical veſſels, as deſcribed in Sect. III. of this work, which ſupply nutriment to the new bud or ſeed, ſimilar to that of the albumen of the egg, or the liquor amnii of the uterus; and alſo another ſyſtem of arterial veſſels, which may be termed placental ones, correſponding with thoſe of the animal fetus in the egg or in the womb, which ſupply the blood of the embryon with due oxygenation before its nativity.

Thirdly, a pulmonary ſyſtem correſpondent to the lungs of aerial animals, or to the gills of aquatic ones, by which the fluid abſorbed by the lacteals and lymphatics may be expoſed to the influence of the air. This is done by the leaves of plants, or the petals of flowers; thoſe in the air reſembling lungs, and thoſe in the water reſembling gills.

Fourthly, an arterial ſyſtem to convey the fluid thus elaborated to the various glands of the vegetable for the purpoſes of its growth, nutrition, and ſecretions; and a ſyſtem of veins to bring back a part of the blood not thus expended.

Fifthly, the various glands which ſeparate from the vegetable blood the honey, wax, gum, reſin, ſtarch, ſugar, eſſential oil, and other ſecretions.

Sixthly, the organs adapted to the lateral or viviparous generation of

of plants by buds, or to their ſexual or oviparous propagation by ſeeds.

Seventhly, longitudinal muſcles to turn their leaves to the light, and to expand or cloſe their petals or their calyxes; and vaſcular muſcles to perform the abſorption and circulation of their fluids, with their attendant nerves, and a brain, or common ſenſorium, belonging to each individual ſeed or bud; to each of which we ſhall appropriate an explanatory ſection.

7. An embryon bud, therefore, whether it be a leaf-bud or a flower-bud, is the viviparous offspring of an adult leaf-bud, and is as individual as a ſeed, which is its oviparous offspring. It conſiſts, firſt, of a central organization or caudex like the corculum of a ſeed, which contains the rudiments of arteries, veins, abſorbent veſſels, and glands, with an internal pith or brain.

Secondly, it is furniſhed with a ſyſtem of umbilical veſſels, which are inſerted into the alburnum or ſap-wood of the tree, or form a part of it, and deſcending into the earth ſupply it in the early ſpring with its firſt nutrition, like the ſeminal roots, ſo called, which paſs from the corculum of the ſeed, and are ſpread on the cotyledons, as ſeen in the garden bean, repreſented in Plate I. Fig. 1. which is taken from Dr. Grew's Anatomy of Plants.

Thirdly, this umbilical ſyſtem probably contains alſo what may be termed a placental artery, terminating on the coats of the lateral air-veſſels, which penetrate the bark of trees horizontally, for the purpoſe of oxygenating the blood of the vegetable fetus, like thoſe diſtributed from the umbilical veſſels of the chick on the air-bag at the broad end of the egg. See Sect. II. 4. and III. 1—4.

Fourthly, it contains the rudiments of organs adapted to lateral generation or the production of new buds; or to ſexual propagation, and the conſequent production of ſeeds.

In the early ſpring the umbilical veſſels ſupply the embryon buds of trees with ſap-juice, which is then ſeen to exſude from wounds of

the alburnum, as in the vine, vitis; the birch, betula; and the maple, acer; which I ſuppoſe to become oxygenated in the circulation of the vegetable fetus by the horizontal air-veſſels of the bark.

As the ſeaſon advances, the leaf-bud puts forth a plumula, like a ſeed, which ſtimulated by the oxygen of the atmoſphere riſes upwards into leaves to acquire its adapted pabulum, which leaves conſtitute its lungs; it alſo protrudes from its long caudex, which forms the new bark over the old one, a radicle, which ſtimulated by moiſture paſſes downwards, and deſcends into the earth to acquire its adapted pabulum; and it thus becomes an adult vegetable being with the power of producing new buds.

The flower-bud under ſimilar circumſtances puts forth its bractes or floral-leaves, which ſerve the office of lungs to the pericarp and calyx; and expands its petals, which ſerve the office of lungs to the anthers, and ſtigmas, which are the ſexual organs of reproduction, and which die and fall off, when the ſeed is impregnated; and thus, like the leaf-bud, it becomes an adult vegetable being with the power of producing ſeeds.

8. As the flower-bud produces many ſeeds during the ſummer, ſo the leaf-bud produces many budlets during the ſummer, as may be ſeen in the long ſhoots of the vine and willow, vitis et ſalix. In this climate both the buds and ſeeds are properly biennial vegetables; that is, they are produced in one ſummer, and periſh in the next. But the ſeed differs from the bud in this circumſtance, that it drops on the earth, and is thus ſeparated from its dead parent in the autumn; whereas the bud continues to adhere to its dead parent, and grows over it as it advances.

Now as the internal pith of a bud appears to contain or produce the living principle, like the brain and medulla oblongata, or ſpinal marrow of animals, we have from hence a certain criterion to diſtinguiſh one bud from another, or the parent bud from the numerous budlets,

PLATE I.

PLATE I.

FIG. 1. repreſents the umbilical veſſels ſpread on the lobes of a bean, when it begins to vegetate, as mentioned in Sect. I. 7. but more particularly deſcribed in Sect. III. 1. 3; which are believed to conſiſt of a ſyſtem of abſorbent veſſels, and another ſyſtem of placental veſſels, for the purpoſe of acquiring nutriment, and of oxygenating the vegetable blood. The plate is copied from Grew, Tab. I. *f.* 14. *a* the plumula, *b* the corculum, *c c* the lobes. See Sect. I. 7. and III. 1. 3.

FIG. 2. is copied from Malpighi, Tab. II. Fig. 6, and repreſents the longitudinal fibres of the bark of willow, which adhere together, and ſeparate from each other alternately, with horizontal apertures between them; which are believed to be air-veſſels, for the purpoſe of oxygenating the blood of the embryon buds, like the air-bag at the broad end of an egg. *b b b* are the longitudinal filaments of the bark, *a a a* are the horizontal perforations.

Duhamel obſerved by a microſcope ſimilar apertures of different diameters in the bark of oak; the ſmaller ones he believed to be the excretory ducts of the perſpirable matter, and larger ones I ſuppoſe to be air-veſſels. The extremities of ſome of theſe in the birch-tree ſtood above the level of the cuticle. Phyſique des Arbres, Plate I. Fig. 7. and 11. See Sect. I. 7. and II. 4. of this work.

Fig. 1.





Fig. 2.



London, Published Jan.ʸ 1.st 1800, by J. Johnson, St Paul's Church Yard.

budlets, which are its offspring, as *there is no communication of the internal pith between them.*

This obſervation was made by ſlitting the young branches of horſe-cheſnut, æſculus hippocaſtanum; of aſh, fraxinus; of willow, ſalix; and of elder, ſambucus nigra; and I plainly diſcerned that there exiſted no communication of pith between the lateral budlets and their parent ſhoots, or between the central larger budlet at the ſummit of the branch, and its parent ſhoot. This alſo afforded me one reaſon to conclude that the different joints of wheat, triticum, of ſouthiſtle, ſonchus, and of teaſel, dypſacus, are different buds growing on each other, thoſe at the ſummit only producing ſeeds; becauſe there is a diviſion which ſeparates the pith contained in each joint of their hollow ſtems, as is further explained in Sect. IX. 2. 4. and 3. 1. and which perfectly evinces the individuality of buds.

SECT. II.

THE ABSORBENT VESSELS OF VEGETABLES.

1. *Roots, leaves, bark, ſap-wood, ſhewn to abſorb by not moiſtening them, by placing them in water.* 2. *Abſorbent veſſels coloured by a decoction of madder, by dilute ink. They form a ring in the ſap-wood beneath the bark, with a ring of arteries exterior to them.* 3. *Abſorbents erroneouſly believed to be air-veſſels, are viſibly full of ſap-juice in a vine-ſtalk. Vegetable veſſels have rigid ſides, which do not collapſe, and hence become full of air when cut; not ſo in animal veſſels.* 4. *Some horizontal veſſels in trees are truly air-veſſels for the embryon bud, like the air in the broad end of the egg.* 5. *Abſorbent veſſels conſiſt of long cylinders; air will paſs through them either way in the dead vegetable; are not reſpiratory organs, as they exiſt in the roots of trees. May receive air diſſolved in water.* 6. *Abſorbent veſſels act either direct or retrograde. A forked branch in water. An inverted tree. A ſuſpended tree. So in the operation of an emetic, and in ruminating cows.* 7. *They conſiſt of a ſpiral line without valves; and by its vermicular contraction forcibly carry on their contained fluids either way.* 8. *Thoſe of the root act occaſionally in winter; but vines in hot-houſes muſt have their roots guarded from froſt in ſpring. Accumulated ice deſtroys trees in ſpring.* 9. *They ſometimes abſorb poiſonous fluids, as ſpirit of wine, ſolution of arſenic, vitriolic acid; roots ſaid to creep aſide from bad ſoil erroneous.* 10. *Abſorbents of trees like the receptacle of chyle.*

1. THE exiſtence of that branch of the abſorbent veſſels of vegetables, which reſembles the lacteals of animal bodies, and imbibes their nutriment from the moiſt earth, is evinced by their growth, ſo long as moiſture is applied to their roots, and their quickly withering when it is withdrawn.

Beſides

Beſides theſe abſorbents in the roots of plants there are others, which open their mouths on the external ſurfaces of the bark and leaves to abſorb the moiſture of the atmoſphere, reſembling the cutaneous lymphatics of animal bodies; the exiſtence of theſe is ſhewn, becauſe a leaf plucked off and laid with its under ſide on water will not wither ſo ſoon as if left in the dry air. The ſame if the bark alone of a branch, which is ſeparated from a tree, be kept moiſt with water.

A third branch of abſorbent veſſels opens its mouths on the internal ſurfaces of the cells and cavities of the vegetable ſyſtem to abſorb the ſecreted fluids, after they have performed their adapted offices, ſimilar to the cellular lymphatics of animal bodies, as may be ſhewn by moiſtening the alburnum or ſap-wood, and the internal ſurface of the bark of a branch detached from a tree, which will not then ſo ſoon wither as if left in the dry air unmoiſtened.

Another means of demonſtrating the abſorbent powers of the parts of vegetables is by inſerting them into glaſs tubes, or into tall narrow veſſels filled with water, and obſerving how much more rapidly the ſurface of the water ſubſides than in ſimilar veſſels by evaporation alone.

2. By the following experiment theſe vegetable abſorbent veſſels were made agreeably viſible by a common magnifying glaſs. I placed in the ſummer of 1781 ſome twigs of a fig-tree with leaves on them about an inch deep in a decoction of madder (Rubia tinct), and others in a decoction of logwood (hæmatoxylum campechenſe), along with ſome ſprigs cut off from a plant of picris. Theſe plants were choſen becauſe their blood is white. After ſome hours, and on the next day, on taking out either of theſe, and cutting off from its bottom about an eighth of an inch of the ſtalk, an internal circle of red points appeared, which I believed to be the ends of abſorbent veſſels coloured red with the decoction, and which probably exiſted in the newly formed alburnum, or ſap-wood, while an external ring of arteries was

ſeen to bleed out haſtily a milky juice, and at once evinced both the abſorbent and arterial ſyſtem.

Many ſimilar experiments were made by M. Bonnet, by placing parts of the ſtem or roots of various vegetables, as of kidney-beans, peach-tree, and elder, in dilute ink; in all theſe the veſſels of the bark were uncoloured, and thoſe of the pith; but thoſe beneath the bark, which he terms woody, were coloured black, which I ſuppoſe to have been the circle of abſorbent veſſels above mentioned. Uſage de Feuilles, Plate XXIX.

3. Theſe abſorbent veſſels have been called bronchia by Malpighi and Grew, and ſome other philoſophers, and erroneouſly thought to be air-veſſels; in the ſame manner as the arteries of the human body were ſuppoſed to convey air by the antients, till the great Harvey by more exact experiments and juſter reaſoning evinced, that they were blood-veſſels. This opinion has been ſo far credited becauſe air is ſeen to iſſue from wood, whether it be green or dry, if it be covered with water, and placed in the exhauſted receiver of an air-pump; and theſe veſſels have therefore been ſuppoſed to conſtitute a vegetable reſpiratory organ; but it will be ſhewn hereafter, that the leaves of plants are their genuine lungs, and that the abſorbent veſſels and arteries become accidentally filled with air in the dead parts of vegetables.

For as the veſſels of vegetables are very minute, and have rigid coats, their ſides do not collapſe when they are cut or broken, as their juices flow out or exhale; they muſt therefore receive air into them. This may be readily ſeen by inſpecting with a common lens the end of a vine-ſtalk two or three years old, when cut off horizontally. At firſt the veſſels, which are ſeen between the partitions radiated from the center, appear full of juice; but in a minute or leſs this juice either paſſes on, or exhales; and the veſſels appear empty, that is filled with air. This experiment I have twenty times repeated with

with uniform ſucceſs, and it is ſo eaſily made by haſtily applying a common lens after the diviſion of a vine-ſtalk, that I think there can be no error in it; and it is wonderful that theſe veſſels, which are found in the alburnum, and conſiſt of a ſpiral line, whether they may properly be called abſorbent or umbilical veſſels, or conſiſt of both, ſhould ever have been ſuppoſed to be air-veſſels.

There is nevertheleſs an experiment by Dr. Hales, which would at firſt view countenance the aſſertion, that vegetables abſorb air. He cemented the lower end of a ſmall twig of a tree with leaves on it into a glaſs tube about four inches long, and ſet the other end of the tube an inch deep in water, and obſerved in a little time, that the water roſe an inch in the tube; but this muſt happen from the vegetable veſſels emptying themſelves by the aſcent of their juices, and having rigid coats, and therefore not contracting, a portion of the air was forced into them by the preſſure of the atmoſphere, as in the above obſervation on the vine-branch cut horizontally.

This reception of air does not happen to the veſſels of animal bodies, when they are emptied of their blood, owing to the leſs rigidity of their coats; whence the weight of the atmoſpheric air preſſes their ſides together, and cloſes the veſſel, inſtead of paſſing into it. In the ſame manner no air would paſs into the veſſels of the lungs of animals in reſpiration, unleſs the preſſure of the atmoſphere on their ſides was prevented by the action of the muſcles, which enlarge the cavity of the thorax by elevating the ribs.

4. There are nevertheleſs certain horizontal veſſels of large diameter, which paſs through the bark of trees to the alburnum, which probably contain air, as they are apparently empty, I believe, in the living vegetable; for the bark of trees conſiſts of longitudinal fibres, which are joined together, and appear to inoſculate at certain diſtances, and recede from each other between thoſe diſtances like the meſhes of a net, in which ſpaces ſeveral horizontal apertures are ſeen to penetrate through the bark to the alburnum, according to Malpighi,

who has given a figure of them, which is copied in Plate I. Fig. 2. of this work. Very fine horizontal perforations through the bark of trees are alſo mentioned by Duhamel, which he believes to be perſpiratory or excretory organs, but adds, that there are others of much larger diameter, ſome round and ſome oval, and which in the birch-tree ſtand prominent, and pierce the cuticle or exterior bark. Phyſique des arbres, T. 1. Tab. III. Fig. 8. and 11.

Theſe veſſels probably contain air during the living ſtate of the tree, as they pierce the external bark, which frequently conſiſts of many doubles, like a roll of linen cloth ; as a new cuticle is annually produced beneath the old one, like a new ſcarf-ſkin beneath a bliſter in animal bodies ; and the old one ſometimes continues, and ſometimes peels off like the cuticle of a ſerpent, as is ſeen on the trunks of many cherry-trees and birches. Theſe veſſels, when contracted in dry timber, appear like horizontal inſertions in many planed boards, in which the ſpiral abſorbent veſſels become by their contraction the longitudinal fibres, as appears in the figure of a walking cane given by Dr. Grew, Tab. XX.

Theſe horizontal veſſels I ſuppoſe to contain air incloſed in a thin moiſt membrane, which may ſerve the purpoſe of oxygenating the fluid in the extremities of ſome fine arteries of the embryon buds, in the ſame manner as the air at the broad end of the egg is believed to oxygenate the fluids in the terminations of the placental veſſels of the embryon chick, as further noticed in Sect. III. 2. 6. and III. 1. 4.

5. The abſorbent veſſels of trees in paſſing down their trunks conſiſt of long hollow cylinders, whoſe ſides I believe to be compoſed of a ſpiral line, and are of ſuch large diameters in ſome vegetables as to be viſible to the naked eye, when they become dry and empty, as in cane. Air will rapidly paſs through theſe veſſels in either direction, as may be ſeen in lighting a cane ſome inches long at either end, and drawing the ſmoke through the pores of it into the mouth, as through a tobacco-pipe. Dr. Hales readily paſſed both air and water through a recent

a recent vegetable ſtick both upwards and downwards, by ſetting one end of it in a cup of water in the receiver of an air-pump, and exhauſting the air, Veg. Stat. p. 154; whence he concludes with Grew, that theſe are air-veſſels or lungs for the purpoſe of reſpiration, and that they receive atmoſpheric air in their natural ſtate.

There is one objection to their uſe as air-veſſels, which is, that they have no communication with the horizontal air-veſſels above deſcribed; for by blowing forcibly through a piece of dry cane immerſed deep in water, no air is ſeen to bubble out of the ſides, but only from the bottom of it. It may indeed be ſuppoſed, that the longitudinal cavities in dry cane may not conſiſt of the abſorbent veſſels above deſcribed, but of the interſtices between them, as the coats of thoſe abſorbent veſſels, conſiſting of a ſpiral line, may be thought to cloſe up by their vermicular contraction; and their interſtices, conſiſting of vegetable cellular membrane, may be ſuppoſed, when dry, to become the tubes in cane. But in this caſe the longitudinal canals in dry cane would not be circular cylinders, whereas they are ſo repreſented in a figure of a piece of cane much magnified by Dr. Grew, Tab. XX. who has in the ſame figure given the mouths of horizontal air-veſſels of circular form and larger diameter.

But there is another inſuperable objection to this idea of their uſe, which is, that theſe veſſels equally exiſt in the roots of plants as in their trunks; and according to Malpighi with larger diameters; and probably terminate externally only in the roots; and, as they are there not expoſed to the atmoſphere, they cannot ſerve the purpoſe of reſpiration; air nevertheleſs in its combined ſtate, or even as diſſolved in water, may be abſorbed by theſe veſſels; and may appear, when the preſſure of the atmoſphere is removed in the exhauſted receiver; or when expanded by heat, as is ſeen in the froth at one end of a green ſtick, when the other end is burning in the fire.

6. Theſe vegetable abſorbents differ from thoſe of animals in the facility, with which they carry their fluids either way; for a forked

branch

branch of a tree, torn from its trunk, and having one of its forks with the leaves on it inverted in a veſſel of water, will continue for ſeveral days unwithered, nearly as well as if the whole had been placed upright in the water. A willow rod on the ſame account will grow almoſt equally well, whether the apex or baſe of it be ſet in the ground; and Dr. Bradley, I think, mentions a young gooſeberry-tree having been taken up, and replanted with its branches in the earth, and its roots in the air; and that the branches put forth root-fibres, and the roots put forth leaf-buds. There is likewiſe a curious experiment by Dr. Hales, who attached the eaſtern branch of a young tree to its neighbour by inarching, and its weſtern branch to another of its neighbours in the ſame manner; and after they were united, he cut the ſtem of the middle tree from its root, and thus left it hanging in the air by its two inarched arms, where it flouriſhed with conſiderable vigour.

This power of carrying their fluid contents in a retrograde direction is alſo poſſeſſed in ſome degree by the abſorbents of animals, particularly in their diſeaſed ſtate, and even in the operation of an emetic, as ſhewn in Zoonomia, Vol. I. Sect. 29; and is viſible in the œſophagus or throat of cows, who convey their food firſt downwards, and afterward upwards by a direct and retrograde motion of the annular cartilages, which compoſe the gullet, for the purpoſe of rumination.

7. The ſtructure of theſe large vegetable abſorbents, erroneouſly called air-veſſels, probably conſiſts of a ſpiral line, and not of a veſſel interrupted with valves, and differs in this conſtruction from animal lymphatics; for firſt, on breaking almoſt any tender vegetable, as a laſt year's ſprig of a roſe-tree, or the middle rib of a vine-leaf, and gradually extending ſome of the fibres, which adhere the longeſt, this ſpiral ſtructure becomes viſible even to the naked eye, and diſtinctly ſo by the uſe of a common lens, as is delineated in Duhamel's Phiſique des arbres, T. 1. Tab. II. Fig. 17, 18, 19, and in Plate LI.

and

and LII. of Grew's Anatomy of Plants (fol. edit.), and by this eaſy experiment both that abſorbent ſyſtem, which imbibes nouriſhment from the earth, and brings it to the caudex of each bud; and that which imbibes moiſture from the air, and a part of the perſpirable matter on the ſurface of the leaf, and brings it to the caudex of each bud, are agreeably demonſtrated. See Plate II. Fig. 1. And that theſe veſſels of large diameter, with their ſides conſiſting of a ſpiral line, are not arteries or veins, is evinced by inſpecting a ſtem of euphorbia, ſpurge; or the ſtalk of a fig-leaf, ficus, immediately on dividing them, as the milky juice oozes from a ring of veſſels exterior to thoſe large abſorbents.

Secondly, that theſe veſſels are not furniſhed with frequent valves is countenanced by the experiments before mentioned in No. 5 of this ſection, one of which conſiſted of lighting a piece of cane, and drawing the ſmoke through it, as through a tobacco-pipe, in either direction; and the other in placing a bit of recent twig with one end of it in a cup of water in the receiver of an air-pump, and cauſing both air and water to paſs through it in either direction.

If the minuter branches of vegetable abſorbents be of a ſimilar ſtructure, it is eaſy to conceive how a vermicular or periſtaltic motion of the veſſel, beginning at the loweſt part of it, each ſpiral ring ſucceſſively contracting itſelf, *till it fills up the tube*, muſt forcibly puſh forwards its contents without the aid of valves; and if this vermicular motion ſhould begin at the upper end of the veſſel, it muſt with equal facility carry its contained fluid in a retrograde or contrary direction.

8. As the abſorbent veſſels in the roots of plants are protected from the froſt in ſome degree by the earth which covers them; they ſeem at all times to be ſufficiently alive to drink up and puſh forwards their adapted fluid, ſince if a branch of a tree is brought into a warm room, it will in general pullulate in the winter, as ſoon as the veſſels of the upper part of the branch are rendered ſufficiently irritable by warmth to act in concert with the abſorbents of the root,

Nevertheleſs, in ſevere froſts it is neceſſary to guard all the parts of the ſtem which is expoſed to the open air, as is experienced in the vines brought through holes into hot-houſes, otherwiſe after the buds are put out a ſevere froſt ſo affects the ſtems on the outſide of the houſe as to deſtroy all the fruit of that year. Kenedy on Gardening, Vol. I. p. 270. And it is obſerved in Mr. A. Aikin's Natural Hiſtory of the Year, that much ice was carried from the ſtreets in London in 1794, and piled round ſome elm trees in Moorfields, many of which were deſtroyed in the enſuing ſpring by the ſlow melting of it.

9. The abſorbent veſſels of vegetables, like thoſe of animal bodies, are liable to err in the ſelection of their proper aliment, and hence they ſometimes drink up poiſonous fluids, to the detriment or deſtruction of the plant. Dr. Hales put the end of a branch of an apple-tree, part of which was previouſly cut off, into a quart of rectified ſpirit of wine and camphor, which quantity the ſtem imbibed in three hours, which killed one half of the tree. Veg. Stat. p. 43. Some years ago I ſprinkled on ſome branches of a wall-tree a very ſlight ſolution of arſenic, with intent to deſtroy inſects; but it at the ſame time deſtroyed the branches it was thrown upon. And I was informed by Mr. Wedgewood, that the fruit-trees planted in his garden near Newcaſtle in Staffordſhire, which conſiſted of an acid clay beneath the factitious ſoil, became unhealthy as ſoon as their roots penetrated the clay; and on inſpection it appeared, that the ſmall fibres of the roots, which had thus penetrated the clay, were dead and decayed, probably corroded by the vitriolic acid of the clay, beneath which is a bed of coals.


It is, however, aſſerted by M. Buffon, that the roots of many plants will creep aſide to avoid bad earth, or to approach good. Hiſt. Nat. Vol. III. But this is perhaps better accounted for by ſuppoſing, that the roots put out no abſorbent veſſels, where they are not ſtimulated by proper juices; and that an elongation of roots in conſequence only ſucceeds, when they find proper nutriment.

10. Theſe long and large cylindrical abſorbent veſſels, which paſs from

PLATE II.

PLATE II.

Repreſents the ſpiral veſſels of a vine-leaf conſiderably magnified, copied from Grew, Tab. LI. On ſlowly tearing aſunder almoſt any tender vegetable ſhoot or leaf, the ſpiral ſtructure of theſe veſſels becomes viſible to the naked eye. They have been erroneouſly believed to be air-veſſels; but as they exiſt equally in the roots of plants, as in their barks, and have no communication with the horizontal perforations of the cuticle of the bark, they cannot be air-veſſels, and are therefore believed to conſtitute the abſorbent veſſels of the adult vegetable, and the umbilical ones of the embryon bud. A ſimilar plate of the ſpiral ſtructure of theſe veſſels is given by Duhamel. As they are larger than the vegetable blood-veſſels, and paſs along the whole caudex of each bud from its plumula to its radicle, as well as to the cutaneous abſorbents, thoſe of the trunks of trees or herbaceous plants may be thought to reſemble the receptaculum chyli of animal bodies. See Sect. II. 7.



London, Published Jan.ʸ 1.st 1800, by J. Johnson, S.t Paul's Church Yard.

from the roots of trees up to the ſummit of the caudex of each bud at the foot-ſtalk of the leaf, I ſuppoſe to be analogous to the receptacle of the chyle of animals, as the ſmall abſorbent branches of the roots probably unite beneath the ſoil into thoſe large veſſels, which are ſo eaſily viſible; hence the caudex of each bud conſiſts of an elongation of abſorbent veſſels, and of arteries and veins reaching from the union of the root-branches to the foot-ſtalk of each leaf, and the plumula of the bud in its boſom, as deſcribed in Sect. I. 7.

SECT. III.

THE UMBILICAL VESSELS OF SEEDS AND BUDS.

I. 1. Seeds *are a ſexual offſpring like eggs. Some ſeeds and eggs contain two kinds of nouriſhment. Other ſeeds and ſpawn of fiſh contain but one kind of nouriſhment.* 2. *Air-bag in eggs, and in ſome fruits; not in ſeeds, nor in ſpawn.* 3. *Veſſels improperly called umbilical; thoſe properly called umbilical conſiſt of abſorbents, and a placental artery and vein. Seed embryon and chick begin their growth by the action of their abſorbents.* 4. *Seminal roots of Grew, and chorion of the chick of Malpighi, are reſpiratory organs.* 5. *In what the chick differs from the ſeed-embryon. Nothing is found in ſeeds ſimilar to the yolk of the egg.* II. 1. Buds and bulbs *are a paternal offſpring; exactly reſemble their parents.* 2. *Have umbilical veſſels, in which the ſap-juice riſes in the ſpring. Why the bark is then eaſily ſeparated from the alburnum.* 3. *Sugar in the ſap-juice exiſts in the alburnum, and in roots. Dry rot of timber owing to fermentation. Why lower branches firſt pullulate.* 4. *Sap aſcends not by capillary attraction, but by the irritative motions of abſorbent veſſels. Inſtances of vegetable irritability. Abſorbent veſſels ſometimes act as capillary ſyphons, and as capillary tubes.* 5. *Umbilical veſſels coaleſce. Why trees do not bleed in ſummer.* 6. *Umbilical veſſels of buds like thoſe of ſeeds. Poſſeſs air-veſſels like thoſe of the chick. Buds, like eggs, ſeparate from the parent; their umbilical veſſels improperly called placental ones, as they convey nutriment; hence plants become dwarfs if the cotyledons of the ſeed are deſtroyed. Birch-trees die if ſmeared with oil or pitch.* 7. *Reſervoir of nutriment in the alburnum of trees, and in the roots of biennial plants. Experiment of boiling the alburnum and fermenting the liquor. As buds are formed at midſummer, they may then be tranſplanted by inoculation, but in the ſpring muſt be ingrafted, and grow by inoſculation of veſſels, like inflamed parts of animals.* 8. *A pauſe in vegetation at midſummer. New umbilical veſſels act in autumn, and the bark ſeparates eaſily as in ſpring. Honey-dew. Sap-juice riſes in winter occaſionally both in ever-*

ever-green trees and deciduous ones, and after the ſummit of the plant is cut off.
9. Umbilical veſſels and abſorbents ſeen in a vine-ſtalk, the latter exterior to the former. Exiſt in the alburnum.

I. 1. THE ſeeds of vegetables are a ſexual offſpring correſponding with the eggs of animals, and contain, like them, not only the rudiment of the new organization, but alſo a quantity of aliment laid up for its early nouriſhment.

The eggs of birds contain two kinds of albumen, or white, one leſs viſcid than the other, which is firſt conſumed, and the yolk or vitellum, which is drawn up into the bowels of the chick at its excluſion from the ſhell, and ſerves it for nouriſhment a day or two, till it can learn to ſelect and digeſt grains or inſects. In like manner many ſeeds are furniſhed with two kinds of nouriſhment, the mucilaginous or oily meal of the ſeed-lobes, and the ſaccharine or aceſcent pulp of the fruit, as in pears, plums, cucumbers, which ſupply nutriment to the embryon plant, till it is able to ſtrike into the earth ſufficient roots for the purpoſe of abſorbing its nutritious juices.

The ſpawn of fiſh, and of frogs, and of inſects, as of ſnails and bees, which are almoſt as innumerable as the ſeeds of plants, and are in the ſame manner excited into life by the warmth of the ſun, are analogous to thoſe ſeeds, I believe, which are not ſurrounded with fruit, and which contain but one kind of nouriſhment for the embryon plant, as grains of corn, and legumes; but perhaps theſe have not yet been ſufficiently attended to by philoſophers.

Theſe eggs of animals and ſeeds of vegetables are produced by the congreſs of male and female organs; the former ſupplying the ſpeck of animation or cicatricula in the egg, and the corculum or heart in the ſeed; and the latter producing the nidus, or neſt for its reception, and the nutritive material for its firſt ſupport. Thus the eggs of fowls are formed long before they are impregnated, and are ſometimes laid in their unimpregnated ſtate; and the ſeeds of legumes are

viſible

viſible many days before the flower opens, and in conſequence before they are impregnated, as obſerved by Spallanzani.

2. The eggs of birds contain a bag of air at their broad end for the purpoſe of oxygenating the blood of the chick. In this one circumſtance the ſeeds of plants ſeem to differ from the eggs of birds, as they contain no air-bag, though it is probable they may agree with the ſpawn of fiſh, which I ſuppoſe poſſeſs no included air. When the ſeeds fall on the ground in their natural ſtate of growth, or are buried an inch or two beneath the ſoil, which has recently been turned over, and thus contains much air in its interſtices, their coats do not continue dry like the ſhells of eggs during incubation, but immediately become moiſt membranes, like the external membrane of the ſpawn of fiſh immerſed in water, and in conſequence can admit the oxygenation of the air through them to an adapted ſet of arteries on their internal ſurface, according to the curious obſervations of Dr. Prieſtley on the oxygenation of the blood by the air through the moiſt membranes of the lungs.

It ſhould be here obſerved, that many ſeeds, before they fall on the moiſt earth, are included in a bag of air, as thoſe of the ſtaphylea, bladder-nut; of the phyſalis alhekengi, winter-cherry; of colutea, bladder-ſenna; in the pods of peas and beans; in the cells ſurrounding the ſeeds of apples and pears; and in the receptacle of ketmia, which probably ſerves to oxygenate the blood of the infant ſeed, which in theſe plants may thus be of forwarder growth, before it is ſhed upon the ſoil.

3. There exiſts a ſeries of glands, and their ducts, improperly called umbilical veſſels by ſome writers, which ſupplies the ſeed with nouriſhment from the parent plant, ſo long as it adheres to the ovarium of its mother, as the veſſels by which a pea adheres to the pod, in which it is included; in fruits and nuts, where the kernel is covered with a ſtone or ſhell, a long cord of veſſels paſſes into the bottom of the ſtone or ſhell, and riſing to the top bends round the lobes of the ker-

nel, and is inſerted near or into the corculum or heart of the ſeed, where the living principle reſides, and affords not only preſent nutrition to the vegetable embryon, but alſo ſecretes the farinaceous or oily materials for its future nouriſhment, which conſtitute the cotyledons of the ſeed.

But the veſſels, which may be properly called umbilical, paſs from the heart or corculum of the ſeed, which is the living embryon of the future plant, into the ſeed-lobes, commonly called cotyledons, and imbibe from thence a ſolution of the farinaceous or oily matter there depoſited for the nutriment of the new vegetable. Theſe veſſels are delineated in their magnified appearance by Dr. Grew, Plate LXXIX. fol. edition, and are by him termed ſeminal roots. See Plate I. Fig. 1.

Theſe umbilical veſſels probably conſiſt of a ſyſtem of abſorbents, which ſupply nutriment to the embryon plant from the cotyledons of the ſeed, and alſo of a ſyſtem of placental arteries and veins ſpread on the humid membrane, which covers the cotyledons, and is moiſtened by its contact with the earth, for the purpoſe of oxygenating the vegetable blood. This idea is countenanced by many plants bringing up their cotyledons, or ſeed-lobes, out of the ground into the air, which are then converted into leaves, and perform the office of lungs, after they have given up beneath the ſoil the nutriment, which they previouſly contained, as in the young kidney-bean, phaſeolus; ſo the white corol of the helleborus niger, chriſtmas roſe, is changed into a green calyx by looſing one ſyſtem of arteries after the impregnation of the ſeeds.

The ſeed-embryon therefore reſembles the chick in the egg, firſt as when vivified by the influence of external warmth they both begin their growth by the abſorbent ſyſtem of veſſels being ſtimulated into action by their adapted nutriment; and the fluids thus puſhed forwards ſtimulate into action the other parts of the ſyſtem, conſiſting at firſt principally of arteries and glands.

Secondly, they ſeem to reſemble each other in their poſſeſſing each of

of them an abſorbent ſyſtem of veſſels, which imbibe the nutritious matters laid up for them in the albumen or white of the egg, and in the cotyledons or lobes of the ſeed; and alſo of a placental ſyſtem of arteries for the purpoſe of oxygenating their fluids, as deſcribed above in the ſeed, and which appears in the egg to be ſpread on a membrane, which covers the white, as is ſhewn in the plates of Malpighi, and called by him the chorion, and expoſes the blood of the chick to the oxygen of the air contained at the broad end of the egg through a moiſt membrane.

4. The uſe of the large apparent artery ſpread on the cotyledons of a germinating ſeed of a garden-bean, called ſeminal roots by Grew, as ſhewn in Plate I. Fig. 1, and that ſpread on the chorion of the chick in the egg, ſo called by Malpighi, and ſhewn in Tom. II. Fig. 54, and by Fabricius ab Aquapendente, Tab. I. Fig. 13, which muſt be an artery, as it carries red blood, are believed to be reſpiratory organs, like the placental veſſels of the fetus of viviparous animals, becauſe the cotyledons of ſome ſeeds riſe out of the ground, and become leaves, after the nutriment they contained is expended, and are then called ſeminal leaves, as in the kidney-bean, phaſeolus; and becauſe thoſe which do not riſe out of the ground periſh beneath the ſoil, as ſoon as the young plant gains its leaves, which are its aerial reſpiratory organ.

Secondly, the chorion of the chick conſiſts of a membrane including the white, or albumen, and is not only in contact with the air-bag at the broad end of the egg, which, as the chick advances, covers more than half of the internal ſurface of the ſhell, but alſo with the membrane which lines all the other part of the ſhell, as appears in Plate III. which is copied from Malpighi: yet this extenſive chorion, with the numerous arteries and veins which are ſpread upon its ſurface, is not drawn up into the body of the chick like the yolk and its including membrane, but periſhes at the nativity of the chick like the placental veſſels of the fetus of viviparous animals; or ſometimes,

times, I ſuppoſe, before its nativity, as the chick perforates the air-bag, and is heard to chirp, before it is excluded from the ſhell.

Hence it would appear, that both the artery attending the ſeminal roots above mentioned, and this artery on the chorion of the chick, muſt perform ſome more important office than to ſupply nouriſhment to the coats of the abſorbent veſſels, which imbibe the mucilage of the ſeed, or the white of the egg, and which abſorbents muſt themſelves poſſeſs their proper vaſa vaſorum. And what more important office can they have than that of oxygenating the blood of the vegetable or animal embryon? And this becomes more probable as they both periſh at its nativity like the placenta and cotyledons of viviparous animals.

5. As the incubation of the chick advances, it differs from the ſeed-embryon in the production of inteſtines, with a ſtomach, on the internal ſurfaces of which the mouths of the abſorbents now terminate; and laſtly in the production of a mouth and throat to receive and ſwallow the remainder of the albumen, in which it ſwims; whereas the ſeed-embryon ſhoots down new roots into the earth with an abſorbent ſyſtem to acquire its nutriment, as that from the cotyledons of the ſeed becomes exhauſted. See Sect. VII. 1, 2.

Nor is there any thing ſimilar to the yolk of the egg found in the ſeeds of vegetables, which is drawn up into the inteſtines of the young chick about the time of its excluſion from the ſhell to ſerve it with nutriment for a day or two, till it can learn of its parent by imitation to ſelect and ſwallow its adapted food. Nor is the fetus of viviparous animals furniſhed with any thing ſimilar to the yolk of oviparous ones, as they have milk ready prepared for their firſt nutriment in the breaſt of the mother.

As ſoon as the new foliage of the plant riſing out of the ground becomes expanded, and the root deſcending penetrates the earth with its fibrous ramifications, the umbilical ſyſtems of veſſels ceaſe to act, both the abſorbents, which previouſly ſupplied the young embryon

with nutriment from the cotyledons, and alſo the placental artery, which was ſpread on the exterior membrane of the cotyledons for the purpoſe of oxygenation. Theſe veſſels now either coaleſce and decay beneath the ſoil, or wither and fall off, when raiſed above it in the form of ſeed-leaves.

II. 1. The ſeeds of plants are thus a ſexual or amatorial progeny, produced principally by the male part of the flower, and received into a proper nidus, and ſupplied with nutriment by the female part of it, and which can thus claim both a father and a mother. But the buds of vegetables are a linear pogeny, produced and nouriſhed by a father alone, to whom they adhere, not falling off like the ſeeds, as is farther treated of in Zoonomia, Vol. I. Sect. XXXIX. II. 2. and in Sect VII. I. 3. of this work. For in this moſt ſimple kind of vegetable reproduction, by the buds of trees, and by the bulbs of ſome plants, and by the wires of others, which are their viviparous progeny, the caudex of the leaf is the parent of the bud or bulb, or wire, which riſes in its boſom, according to the obſervation of Linneus.

This linear or paternal progeny of vegetables in buds or bulbs, or wires, is attended with a very curious circumſtance, which is that they exactly reſemble their parents, when they are arrived at their maturity, as ſhewn in Sect. VII. 1. 3. as is obſerved in grafting fruit-trees, and in propagating flower-roots, or ſtrawberries, or potatoes, by their wires or roots; whereas the ſeminal offspring of plants, as it derives its form in part from the mother as well as father, is liable to perpetual variation, both which events are employed to great advantage by ſkilful gardeners.

2. As the embryons in the buds are the viviparous offspring of vegetables, it becomes neceſſary, as they have no mouths, that they ſhould be furniſhed like the embryons in the ſeeds with umbilical veſſels to ſupply them with nouriſhment, till they acquire roots with another ſet of abſorbent veſſels to imbibe moiſture from the earth, and leaves to act like lungs for the purpoſe of oxygenating their blood.

Theſe

Theſe umbilical veſſels, which ſupply the buds of plants with nouriſhment in the early ſpring, and unfold their foliage, have been much attended to by Dr. Hales and Dr. Walker (Edinb. Phil. Tranſact. Vol. I.) The former obſerved, that the ſap from the ſtump of a vine, which he had cut off in the beginning of April, aroſe twenty-one feet high in glaſs tubes affixed to it for that purpoſe, but which in a few weeks ceaſed to bleed. Dr. Walker alſo marked the progreſs of the aſcending ſap in various branches of trees, and obſerved, that in cold weather it ſtopped many hours in a day, as well as in the night, and found likewiſe as ſoon as the leaves became expanded, that the wounded trees ceaſed to bleed.

The veſſels, which convey the ſap-juice with ſuch amazing force, are ſituated in or compoſe the alburnum, or ſap-wood, of the trunk or root of the tree; nor is it ſurprizing, that ſome of it when preſſed by ſo high a column ſhould exſude into the cells between the alburnum and bark, as in theſe cells much ſap-juice was obſerved by Dr. Walker, and this accounts for the great eaſe with which the barks of willows and of oaks are ſeparated in the ſpring from their wood. The abſorbent mouths of theſe ſap-veſſels open externally in the moiſt earth on the roots of trees, and alſo into the air on their trunks; and thus mix the aqueous fluids, which they thus imbibe, with the ſaccharine and mucilaginous materials depoſited previouſly in the alburnum of theſe roots and trunks.

3. This aſcending ſap-juice during the ſpring ſeaſon is in ſome trees ſo ſweet, that it is uſed in making wine, as that of the birch-tree in this country; and ſugar is procured in ſuch quantity from a maple in Penſylvania, that from each tree five or ſix pounds of good ſugar have been made annually without deſtroying it. Ruſh, on Sugar Maple. Phillips, London. This ſugar is depoſited I believe in the ſap-wood of the trunk and roots of trees, as in the manna-aſh, and is diſſolved in the ſpring by the moiſture, which is drank up by the abſorbents from the earth and atmoſphere, and forcibly carried on to

expand the buds. Its exiſtence in the ſap-wood as well as in the roots is ſhewn from the pullulation of oak-trees, which have been ſtripped of their bark, and alſo from the expanſion of the eyes of a vine-ſhoot, when it is cut from the tree, and planted in the earth, as deſcribed in Sect. XV. 1. 3.

This ſuggeſts to us the reaſon why the wood of trees is ſo much ſooner ſubject to decay, when they are felled in the vernal months; becauſe the ſugar, which the ſap-wood then contains, ſoon runs into fermentation, and produces what is called the dry rot; whence the cuſtom has prevailed of debarking oaks in the ſpring, and felling them in the autumn; and it is probable that the wood of all other trees would laſt much longer, if it was thus managed, as the growth of the new leaves would exhauſt the ſugar of the ſap-wood.

Sweet juices for a ſimilar purpoſe of expanding the buds of herbaceous plants are depoſited during the autumn in their roots, as in turnep, beet, tragapogon; or in the knots or joints of the ſtem, as in graſſes, and the ſugar-cane; which like the farina and oil in ſeeds, and the dulcet mucilage of fruits, and the honey of flowers, were deſigned for the food of the young progeny of plants, but become the ſuſtenance of mankind!

As the ſaccharine matter which is thus depoſited in the roots, or in the alburnum, or in the joints of plants, muſt be diluted by the moiſture abſorbed from the earth by their roots, we underſtand why the leaves of the lower branches of trees are firſt expanded, as is ſeen diſtinctly in the hawthorn hedges in April, as theſe muſt firſt receive the aſcending ſap-juice, as was obſerved by Dr. Walker in his account of the maple.

4. The force of the riſing ſap from a vine-ſtump in the bleeding ſeaſon, as diſcovered by Dr. Hales, is at ſome times equal to the whole preſſure of the atmoſphere, which is about fourteen pounds on a ſquare inch of ſurface. This great power in raiſing the ſap he aſcribes to capillary attraction, and to the variations of heat during the day

day and night. In regard to capillary attraction, however high it may raiſe a fluid in very ſmall tubes, it can not make it flow over them, as the ſap-juice did in Dr. Hales's vine-ſtump; nor can it raiſe a fluid quite to a level with the upper rim of a glaſs tube, as the fluid is there more attracted downwards by the glaſs beſides its gravity, and is left in conſequence with a concave ſurface.

The means by which vegetable abſorbent veſſels in their living ſtate imbibe the fluids of the earth and atmoſphere, and carry them forwards with ſo much force, muſt be ſimilar to thoſe, with which animal abſorbent veſſels perform the ſame office; that is by their mouths being excited into action by the ſtimulus of the fluids, which they abſorb.

This circumſtance is confirmed by the evident proofs of the irritability of plants in various other inſtances, as the cloſing and opening of the petals and calyxes of flowers by light and darkneſs, warmth and cold, dryneſs and moiſture, and by the motions of the leaves of mimoſa, or ſenſitive plant, and of dionœa muſcipula, by any mechanical ſtimulus. To this might be added a variety of inſtances of the irritability of vegetables to the ſtimulus of heat, being increaſed after a previous expoſure to cold, exactly in the ſame manner as happens to animal bodies, which are enumerated in a note in the Botanic Garden, Vol. I. Canto I. l. 322, whence the reciprocal times of the acting and the ceaſing to act of theſe vernal vegetable abſorbents, which are here termed umbilical veſſels, in the experiments both of Dr. Hales and Dr. Walker, may be readily explained by their having been benumbed by the cold, or excited into action by the warmth of the air or earth. See Sect. XIII. 2. 3.

From one experiment nevertheleſs of Dr. Walker's theſe veſſels occaſionally act as capillary ſyphons, becauſe when he bent down a branch much lower than its origin from the tree, and cut off the end of it in the bleeding ſeaſon, the ſap flowed from the extremity of this branch ſo bent down, when ſome wounds two or three feet lower

lower than the origin of this branch did not bleed. This may be accounted for from the aſcent of the fluid in theſe veſſels being at this time principally owing to the action of their abſorbent mouths, and to their conſiſting of long cylinders with minute diameters and rigid coats, like thoſe which are viſible to the eye in dry cane, through which ſmoke will paſs in either direction, and which at this early ſeaſon may not be excited into vegetable action; there is nevertheleſs a power of abſorption exiſting in any part of them in the warmer ſeaſon, becauſe a branch or flower-ſtalk cut from the root, and ſet in a glaſs of water, will drink up a conſiderable quantity of it. There is alſo a ſituation in their diſeaſed or dead ſtate, where they appear to act for ſome years like capillary tubes, as in the decorticated part of a pear-tree, deſcribed in Sect. XV. 2, 3.

5. During the great action of theſe umbilical abſorbent veſſels the buds become expanded, that is the young vegetable beings put forth leaves, which are their lungs, and conſiſt of a pulmonary artery, vein, and abſorbents, and alſo acquire a new bark over that of the branches, trunk, and roots, of the laſt year, which conſiſts of aortal arteries, veins, and abſorbents, and new radicles, which terminate in the ſoil. At this time the umbilical veſſels, which exiſted in the alburnum, or ſap-wood, ceaſe to act, and coaleſce into more ſolid wood, perhaps ſimply by the contraction of the ſpiral fibre, of which they are compoſed; and the ſwarm of new vegetables, which conſtitute a tree, are now nouriſhed by their proper lacteal and lymphatic ſyſtems.

A curious circumſtance now occurs, which is that wherever a tree is now wounded, no moiſture appears. On the contrary, the wound from Dr. Hales's experiments is in a ſtrongly abſorbing ſtate, inſomuch that on applying water to wounds made in the ſummer ſeaſon, it was found to be drank up with great force, as was ingeniouſly ſhewn by mercurial ſyphons contrived to reſiſt its abſorption.

This evinces, that though during the bleeding ſeaſon in the vernal months the ſap-juice is imbibed by the umbilical abſorbents, and carried

ried upwards probably by the annular contraction of the ſpiral fibres, which I believe compoſe theſe abſorbent veſſels, in ſuch quantities as to bleed wherever the alburnum is expoſed or wounded, yet that afterwards the exhalation by the numerous leaves becomes ſo great, that the actions of the new radical and lateral abſorbents do not ſupply a fluid ſo faſt, as it could otherwiſe be expended in the growth of the plant, or diſſipated into the air; and as the veſſels, which paſs down the trunks of trees, inoſculate in variety of places, as is ſeen in the cloth made at Otaheite from the bark of a mulberry-tree, when a wound is made through ſome of theſe veſſels, the fluid, which might otherwiſe ooze out, is carried away laterally by thoſe in their vicinity; and as the veſſels of vegetables are rigid, and do not collapſe when wounded like thoſe of animals; and as the circulation in them is comparatively ſlow, but little of their contained fluids are poured out of them when wounded in the ſummer months.

6. From all theſe obſervations it finally appears, that the umbilical veſſels of each bud are ſimilar to thoſe of a ſeed, which are called by Dr. Grew ſeminal roots, and that like the umbilical cords, which form the wires of ſtrawberries above ground, and of potatoes under ground, they ſupply the new vegetable with nutriment, till the leaves are expanded in the air, and new roots are puſhed out and penetrate the earth.

There is alſo a curious analogy between theſe umbilical veſſels of buds, which exiſt in the alburnum of trees, and thoſe belonging to the chick in the egg, which conſiſts in their both poſſeſſing certain air-veſſels; thoſe of trees paſs horizontally from the bark to the alburnum, and that of the egg exiſts at the broad end of it. Thus it is probable, that the fluid in the fine extremities of the new veſſels of the embryon bud becomes oxygenated by theſe horizontal air-veſſels, in the ſame manner as the fluid in the terminations of the arteries on the chorion of the chick is believed to become oxygenated by the air

contained

contained at the broad end of the egg, as alluded to in Sect. II. 4. and III. 1. 4.

A circumſtance, in which the bud may be conceived to differ from the egg, conſiſts in the ſeparation of the egg from its parent, as ſoon as the fetus has acquired a certain maturity, along with its umbilical veſſels, and its reſervoir of nutriment. But in vegetables ſomething ſimilar occurs, for the parent bud is ſeparated by death in the autumn from its embryon offspring; the leaf falls off, which was the lungs of the parent bud, and the veſſels of its caudex, which formed the bark, coaleſce into alburnum, or ſap-wood, ſurrounding the umbilical veſſels of the new bud; which thus may be ſaid to looſe its parent like the egg, but retains its umbilical veſſels, and a reſervoir of nutriment, which exiſts in the ſap-wood, and alſo another ſyſtem of veſſels, which conſtitute the new bark of the tree, conſiſting of the interwoven caudexes of each individual new bud.

But as the umbilical veſſels of plants above deſcribed, which conſtitute the alburnum of the trunks of trees, and the ſeminal roots, ſo called, of the growing ſeed, convey nutriment to the embryon bud, or to the riſing plumula, as well as oxygenation, they are not ſimilar in that reſpect to the placenta of the animal fetus, and were improperly called placental veſſels in the notes to the Botanic Garden, as the placenta of the animal fetus is ſhewn in Zoonomia, Vol. I. Sect. XXXVIII. to be an organ of reſpiration only, like the gills of fiſh, and not an organ for nutrition.

Hence when the cotyledons of ſeeds are cut away from the riſing plume, the plant becomes a dwarf for want of nutriment; and the wounding or expoſing the alburnum of bleeding trees, as of the birch or maple, in the vernal months to obtain the ſap-juice retards the expanſion of the new buds, and the conſequent growth of the tree. Hence alſo it appears, why ſmearing the bark of a tree with pitch, or oil, or paint, is liable to deſtroy the new buds, and conſequently the

tree, by ſtopping up their ſpiracula; and why covering an egg with greaſe or varniſh is ſaid to prevent the production of a chicken, by preventing a change of air at the broad end of it.

7. We may conclude that the umbilical veſſels of the new bud are formed along with a reſervoir of nutritious aliment about midſummer in the bark, which conſtitutes the long caudex of the parent bud, in the ſame manner as a reſervoir of nutritious matter is formed in the root or broad caudex of the turnep or onion, for the nouriſhment of the riſing ſtem. And that theſe umbilical veſſels of the embryon bud, and the reſervoir of nutriment laid up for it, which is ſecreted by the glands of the parent bud, and now intermixed with the preſent bark of the tree, become gradually changed into alburnum, or ſap-wood, as the ſeaſon advances, in part even before the end of ſummer, and entirely during the winter months.

That the alburnum of trees, which exiſts beneath the bark both of the trunk and roots of them, contains the nutritious matter depoſited by the mature leaves or parent buds for the uſe of the embryon buds, appears not only from the ſaccharine liquor, which oozes from the wounds made in the vernal months through the bark into the alburnum of the birch and maple, betula et acer; but alſo from the following experiment, which was conducted in the winter before the vernal ſap-juice riſes.

Part of a branch of an oak-tree in January was cut off, and divided carefully into three parts, the bark, the alburnum, and the heart. Theſe were ſhaved or raſped, and ſeparately boiled for a time in water, and then ſet in a warm room to ferment; and it was ſeen that the decoction of the alburnum or ſap-wood paſſed into rapid fermentation, and became at length acetous, but not either of the other, which evinces the exiſtence both of ſugar and mucilage in the alburnum during the winter months; ſince a modern French chemiſt has ſhewn by experiments, that ſugar alone will not paſs into the vinous fermentation, but that a mixture of mucilage is alſo required; and

from this experiment it may be concluded, that in years of ſcarcity the ſap-wood of thoſe trees, which are not acrid to the taſte, might afford nutriment by the preparation of being raſped to powder, and made into bread by a mixture of flour, or by extracting their ſugar and mucilage by boiling in water, as mentioned in Zoonomia, Part III. Article I. 2. 3. 6.

Now as the embryon buds of deciduous trees of this climate are formed about midſummer, ſecreted by the generative glands in the caudex of the parent leaf-bud, and are ſupplied with due nouriſhment from the ſame ſource, not having yet ſhot out radicles of their own from the lower end of their long caudexes into the earth, they may be readily tranſplanted at this ſeaſon from one tree to another by inoculation, or into different parts of the ſame tree; as the new caudex of the young bud of one tree will readily unite with the new caudex of that of another tree, and as they can be removed entire during the early ſtate of their growth along with a part of the bark only, as ſcarcely any alburnum is yet formed beneath the bark of the young twig, from whence the bud is cut or torn.

But after their greater maturity, ſo that many buds exiſt on one twig, or ſcion, and are already furniſhed with radicles paſſing down into the ground, as in the enſuing ſpring, it becomes neceſſary to ingraft them by cutting off a part of the alburnum, as well as of the bark of the new bud; and to apply theſe in contact with the bark and alburnum of another tree, to which they may grow by inoſculation of veſſels; whence it appears why budding or inoculation muſt be performed ſoon after midſummer, and ingrafting in the early ſpring, as in the former the buds continue to grow by the junction of the caudex or bark veſſels alone with thoſe of the tree into which they are inſerted, and in the latter by the inoſculation of their veſſels with thoſe of the bark and alburnum of the tree, to which they are applied and bound.

The inoſculation of the veſſels of a bud cut out of one tree and inſerted into the bark and alburnum of another, as in the ingraftment of ſcions, is exactly reſembled by a ſimilar operation on animal bodies, when a tooth is taken from one perſon and inſerted into the head of another, and where two inflamed parts grow together. Thus an experienced anatomiſt is ſaid to have cut the two ſpurs from a young cock, and applied them to the oppoſite ſides of his comb, which was previouſly excoriated, where they continued to grow and appeared like horns; and Talicotius, whoſe book lies by me, ſerioufly aſſerts, that he ſucceeded in making artificial noſes from a part of the ſkin of the arm of his patients, and has publiſhed prints of the manner of the operation, ſo ridiculed by the author of Hudibras. Cheirurgia Caſparis Talicotii.

The growth of an inoculated bud on the bark of another tree, where the upper part of the caudex of the inoculated bud joins with the lower part of the caudex of another bud belonging to the ſtock, is ſtill more nicely reſembled by the union of the head and tail part of two different polypi in the experiment of Blumenbach, mentioned in Sect. VII. 3. 2. of this work.

8. As the leaves of trees become expanded, the ſap-juice above deſcribed ceaſes to flow, and the bark of the tree then adheres to the alburnum. Afterwards from the middle of June to the middle of Auguſt, as Dr. Bradley has obſerved, there ſeems to be a pauſe in vegetation; at which time the new buds in the boſom of each leaf ſeem to be generated, and the bark, which during the two preceding months adhered to the wood, now eaſily ſeparates, as in the ſpring, according to the obſervation of Duhamel, Vol. II. 261; and vegetation, which appeared to languiſh during the heats of midſummer, acquires new vigour at the approach of autumn like that of ſpring.

This circumſtance, which ſeems to have puzzled many naturaliſts, is to be explained from the action of the umbilical veſſels of the new

buds, which begin to enlarge as ſoon as they are formed, and in this climate have their progreſs ſtopped by the cold during the winter, and the moiſture which exſudes from the ſides of theſe veſſels, and is extravaſated between the alburnum and the bark, cauſes an eaſy ſeparation of them from each other.

From the new flow of ſap in theſe veſſels about midſummer, being probably in part conveyed to the leaves by the rotrograde action of their lymphatics in very hot weather, the honey-dew ſeems to originate either as an exſudation from the leaf, or from the veſſels being punctured by the aphis, which drinks the vegetable chyle in ſuch great quantity that it paſſes through the inſect almoſt unchanged; ſee Sect. XIV. 1. 7. and 3. 2; and thus cauſes the ſuffuſion of honey on the leaves below them for a time in the heat of ſummer.

Add to this that M. Du Hamel, by nicely meaſuring ſome buds, found that they were gradually enlarged at ſome times during the winter, and concludes from thence that the ſap-juice, which nouriſhes them, continues to flow, though ſlowly, in the milder parts of the winter days, Vol. II. p. 262; and adds, that it muſt riſe continually during the winter months in ever-green trees, otherwiſe their foliage would wither; and alſo in deciduous trees, becauſe the branch of an ever-green tree will grow on a deciduous tree, and not loſe its leaves in the winter, as the lauro-ceraſus on a cherry-tree, and an ever-green oak on a common oak.

It muſt nevertheleſs be obſerved, that as the umbilical veſſels are a part of the new bud, as the lacteals and other abſorbents are a part of the chick or fetus, the perpetual action of theſe umbilical veſſels muſt depend on the bud to which they belong, in the caudex of which, between the plumula and radicle, the brain or common ſenſorium, and the conſequent vital energy, are believed to reſide; and that whether an ingraftment exiſts between the bud and the umbilical abſorbent veſſels or not. But as in thoſe animals which have a very

ſmall

ſmall portion of brain in the head compared with that in the ſpine of the back, as in eels, ſnakes, worms, butterflies, if the head be cut off, the other parts will continue to live with great activity for hours, and even days; ſo it happens to theſe umbilical abſorbent veſſels, which in vine-ſtumps, and many herbaceous plants, will continue to pour out the ſap-juice in great force and great quantity for many days after the exſection of the whole upper part of the plant.

The continuance of the motion of theſe umbilical veſſels conſiſting of a ſpiral line, which are believed to be air-veſſels by many authors, is mentioned by Malpighi; who aſſerts, that when he examined them in the winter, he could often obſerve them for ſome time to continue their vermicular motion ſo as to aſtoniſh him. See Duhamel. Phyſ. des arb. Vol. I. p. 43.

9. The umbilical veſſels of this ſection, like the abſorbents of the preceding one, both which are believed to conſiſt of a ſpiral line, as ſhewn in Sect. II. 7. may be readily ſeen in cutting a vine-ſtalk horizontally, as they at firſt appear full of fluid; but in a very little time, as the fluid exhales or becomes effuſed, a circular area of round holes appears to paſs longitudinally interior in reſpect to the bark; which I ſuppoſe to conſiſt both of the umbilical veſſels, which bleed during the vernal months, and of the other radical, cellular, and cutaneous abſorbents; the latter of which I ſuſpect to be exterior to the former, and to reſide between the bark and the umbilical veſſels, though both of them are believed to conſtitute the alburnum of the plant.

From many ingenious obſervations on vegetables monſieur de la Baiſſe draws the following concluſions, which are aſſented to by M. Bonnet, and which I ſhall here tranſcribe, as they ſo accurately coincide with the theory above delivered, and as they were deduced from different experiments, are a confirmation of it. He ſays, "that the veſſels deſtined to convey nouriſhment to plants are neither in the pith, nor in the bark, nor between the bark and the wood; but

but in the ligneous ſubſtance itſelf; or, to ſpeak more accurately, that thoſe veſſels are themſelves the woody fibres included between the pith and the bark of plants, which have their origin in the roots, and extend themſelves to every part of the plant." Bonnet uſage des feuilles, p. 275.

SECT.

PLATE III.

PLATE III.

Is copied from Malpighi Appendix de ovo Incubato, Tom. II. Fig. 54, and repreſents the chick in the egg on the fourteenth day of incubation. The chick rolled up ſwims in the amnios *a a*, which is kept moiſt by very minute veſſels. Round this is placed the yolk *b b*, to which adjoins the thicker part of the white. The whole is ſurrounded with chorion *d d d*. On this are ſpread the blood-veſſels, of which the large one *e* emerging from the navel of the chick, and generating the various branches *f f f*, terminates in a capillary network. In contact with theſe a redder ſet of veſſels paſſes with ſimilar ramifications. Another ſet of veſſels *g g* ariſes from the navel, which are ſmaller ones, and are propagated amidſt the ramification of *f f*. The lungs are white; the ſtomach full of milk, or of coagulated albumen or white; and the inteſtines hang out from the navel.

As two ſets of blood-veſſels terminate on the chorion, and as one branch of the larger ſet carries redder blood, and as the lungs are ſtill white; it ſeems evident, that this larger ſet of veſſels reſemble the placental arteries and vein of viviparous animals, and that the blood receives its red colour by acquiring oxygen from the air included between the external moiſt membrane and the ſhell of the egg; which air at firſt is ſeen only at the broad end, but afterwards extends from thence to the equator of the egg, and probably paſſes through the other end of the ſhell to that part of the internal membrane, which adheres to it. See an analogous plate in Fabricius ab Aquapendente, Tom. I. Fig. 13. See alſo Sect. III. 1. 4. and III. 2. 6. of this work.



London, Published Jan.ʸ 1.ˢᵗ 1800, by J. Johnson, St. Paul's Church Yard.

SECT. IV.

THE PULMONARY ARTERIES AND VEINS OF VEGETABLES.

I. 1. Leaves *not perſpiratory organs, nor excretory nor nutritious organs, nor electric nor luminous ones.* 2. *Vital air in the atmoſphere, in water. Lungs of aerial animals; gills of aquatic ones.* 3. *Leaves are the lungs of vegetables. Arteries and veins viſible in a leaf of ſpurge and picris coloured by madder, and in bloody dock.* 4. *Upper ſurface only of the leaf reſpires, and repels moiſture, and dies if ſmeared with oil, and exhales much leſs than the under one.* II. 1. Aquatic leaves *are like the gills of fiſh; have larger ſurfaces, as the uncombined oxygen in water is leſs than in air; are divided like the leaves on high mountains.* 2. *Are furniſhed with numerous points like gills of fiſh.* 3. *Which ſet at liberty oxygen from ſome waters.* III. 1. Root-leaves *of many plants differ from ſtem-leaves.* 2. *As they produce only buds.* 3. *They differ as common leaves from floral leaves.* 4. *And ariſe ſometimes from the cotyledons.* IV. 1. Floral leaves *or bractes are reſpiratory organs to the calyx and pericarp.* 2. *In ſome plants they do not appear till the corol drops off.* 3. *Recapitulation. Leaves die in the exhauſted receiver.* V. 1. The corol *is a pulmonary organ; its colours.* 2. *Its vaſcular texture, its glands. Some flowers have no bractes. The corol is not for defence. The corol of helleborus niger changes to a calyx.* 3. *Corol of colchicum and crocus fall off before the bractes appear. Vines bear alternate flowers and leaves. Fruit deprived of green leaves.* 4. *Vegetable uterus requires the bractes. Flowers enlarged by deſtroying the green leaves.* 5. *Plants do not reſpire in their ſleep.* 6. *Concluſion. The anthers and ſtigmas are ſeparate vegetable beings; live on honey and acquire greater irritability, and amatorial ſenſibility.*

I. 1. THERE have been various opinions concerning the uſe of the leaves of plants in the vegetable economy. Some have contended, that they are perſpiratory organs. This does not appear probable from an experiment of Dr. Hales, Veg. Stat. p. 30. He found, by cutting off branches

branches of trees with apples on them, and taking off the leaves, that an apple exhaled about as much as two leaves, the ſurfaces of which were nearly equal to that of the apple; whence it would appear, that apples have as good a claim to be termed perſpiratory organs as leaves.

Others have believed them the excretory organs of excrementitious juices; but as the vapour exhaled from vegetables has no taſte, this idea is no more probable than the other. Add to this, that in moiſt weather they do not appear to perſpire or exhale at all, as ſhewn by ſome ſtatical experiments of Dr. Hales, like thoſe of Sanctorius on the perſpiration of the human body; which perſpiration has alſo been ſuppoſed to be an excrement, which is ſhewn to be an erroneous opinion; and that its deſign is ſimply to preſerve the ſkin ſupple, like the tears diffuſed on the eye-ball to preſerve its tranſparency, as explained in Zoonomia, Vol. II. Claſs I. 1, 2. 14.

Others have believed that vegetables abſorb much nutriment by their leaves, and quote an experiment of Dr. Prieſtley's, who found plants placed in water under glaſſes grew much faſter, when the air, in which they grew, was occaſionally impregnated with putrid exhalations. But there is another experiment of Dr. Prieſtley's, which ſhould be mentioned, and that is, that he agitated one part of a veſſel of water beneath a glaſs filled with putrid exhalation, and the whole of the water preſently became very fetid. Hence we may conclude, that in the firſt caſe the water, in which the vegetable grew, abſorbed the putrid exhalations from the air over it, and that theſe were again abſorbed from the water by the roots of vegetables, which correſpond to the lacteals of the ſtomach and inteſtines of animals; and that they thus received nouriſhment from the putrid vapours, and not by their leaves, which we ſhall endeavour to ſhew to be ſimply reſpiratory organs.

Other philoſophers have conceived, that the leaves of plants acquire electricity from the air. In anſwer to theſe it may be obſerved, that

no

no electricity is ſhewn by experiments to deſcend through the ſtems of trees, except in thunder ſtorms; and that if the final cauſe of vegetable leaves had been to conduct electricity from the air, they ought to have been gilded leaves with metallic ſtems.

Others again have ſuppoſed that the leaves of plants acquire a phlogiſtic material from the ſun's light, whence it was believed that on this account they turn their upper ſurfaces to the ſun. But though light is more or leſs attracted by all opake bodies, yet if the final cauſe of vegetable leaves had been to abſorb light, they ought to have been black and not green; as by Dr. Franklin's experiment, who laid ſhreds of various colours on ſnow in the ſun-ſhine, the black ſunk much deeper than any other colour, and conſequently abſorbed much more light. The uſe of light in vegetable reſpiration will be treated of in Sect. XIII.

2. The air of our atmoſphere has been ſhewn by the experiments of Prieſtley, Cavendiſh, and Lavoiſier, to conſiſt of twenty-ſeven parts of reſpirable air, called oxygene gas, with ſeventy-three parts of unreſpirable air, termed azotic gas, which are mixed together, not chemically combined; whereas water conſiſts of eighty-five hundreth parts of oxygen to fifteen of hydrogen, which exiſt in their ſtate of combination, and are not therefore fit for reſpiration. But in water a conſiderable quantity of common air is alſo diſſolved, which eſcapes on boiling; and even pure vital air was diſcovered in the water of ſome ſprings by ſir Benj. Thomſon, when it was expoſed to the ſun's light. Philoſoph. Tranſact. The former of theſe fluids is thus adapted to the reſpiration of aerial animals, and the latter to that of aquatic ones; and the analogy between the aerial and aquatic leaves of vegetables and the lungs and gills of animals embraces ſo many circumſtances, that we can ſcarcely withhold our aſſent to their performing ſimilar offices.

The internal ſurface of the air-veſſels of the lungs of men are ſaid to be equal to the external ſurface of the whole body, or about fif-

teen ſquare feet. On this ſurface the blood is expoſed to the influence of the reſpired air, through the medium of a thin moiſt pellicle. By this expoſure to the air it has its colour changed from deep red to bright ſcarlet, and acquires ſomething ſo neceſſary to the exiſtence of life, that we can live ſcarcely a minute without this wonderful proceſs.

In aquatic animals, as fiſh, the blood is expoſed to the air, which is diffuſed in the water by the gills; the ſurface of which is probably greater in proportion to the external ſurface of their bodies, than that of the air-veſſels of the lungs of aerial animals to their external ſurfaces. Through theſe gills, or aquatic lungs, a current of water is made perpetually to paſs by the gaping of the fiſh, as it moves, like the air in reſpiration; and from this water it is probable the ſame material is acquired by the gills of fiſh as from the air by the lungs of aerial animals.

3. The great ſurface of the leaves compared to that of the trunk and branches of trees is ſuch, that it would ſeem to be an organ well adapted for the purpoſe of expoſing the vegetable juices to the influence of the air. This however we ſhall ſee afterwards is probably performed only by their upper ſurfaces, which are expoſed to the light as well as air, and on that account acquire greater oxygenation, as will be ſhewn hereafter: yet even in this caſe the upper ſurfaces of the leaves muſt bear a greater proportion to the ſurface of the bark of the tree than that of the air-cells of the lungs of animals to their external ſurfaces.

Aerial or aquatic animals, by their muſcular exertions, produce a current of air or water reciprocally to and from their lungs, and can occaſionally change the place, where they reſpire, when the air or water becomes vitiated. But as vegetables have but little muſcular power to move their leaves, except in a few inſtances; and as the air or water is frequently nearly ſtationary, where they exiſt, it ſeems to have been neceſſary to expoſe their fluids to the air or water on a

greater

greater expanſe of ſurface than in the lungs or gills of animals, which well accounts for the exuberant extent of their foliage.

In the lungs of animals the blood, after having been expoſed to the air in the extremities of the pulmonary artery, is changed in colour from deep red to bright ſcarlet, and is then collected and returned by the pulmonary vein. So in the leaves of plants the vegetable blood is rendered yellow in ſome plants, as in celandine, chelidonium; white in others, as in fig-leaves, ficus; and in ſpurge, euphorbia; and red in others, as in red beets, beta. And the ſtructure of the leaf, as conſiſting of arteries and veins to expoſe the vegetable blood to the influence of the air, and to return it to the caudex of the bud at the foot-ſtalk of the leaf, beautifully became viſible by the following experiment.

A ſtalk with the leaves and ſeed-veſſels of large ſpurge (euphorbia helioſcopia) in June 1791, had been ſeveral days placed in a decoction of madder, (rubia tinctoria) ſo that the lower part of the ſtem and two of the inferior leaves were immerſed in it. After having waſhed the immerſed leaves in much clean water, I could readily diſcern the colour of the madder paſſing along the middle rib of each leaf. This red artery was beautifully viſible both in the under and upper ſurface of the leaf; but on the upper ſide many red branches were ſeen going from it to the extremities of the leaf, which on the other ſide were not viſible except by looking through it againſt the light. On this under ſide a ſyſtem of branching veſſels carrying a pale milky fluid, were ſeen coming from the extremities of the leaf, and covering the whole underſide of it, and joining into two large veins, one on each ſide of the red artery in the middle rib of the leaf, and along with it deſcending to the foot-ſtalk or petiole. On ſlitting one of theſe leaves with ſciſſars, and having a common magnifying lens ready, the milky blood was ſeen oozing out of the returning vein on each ſide of the red artery in the middle rib, but none of the red fluid from the artery.

All theſe appearances were more eaſily ſeen in a leaf of picris treated in the ſame manner; for in this milky plant the ſtems and middle-rib of the leaves are ſometimes naturally coloured reddiſh, and hence the colour of the madder ſeemed to paſs further into the ramifications of their leaf-arteries, and was there beautifully viſible with the returning branches of milky veins on each ſide.

In a plant which was ſent to me under the name of ſenecio bicolor, but which I have not yet ſeen in flower, the upper ſurface of the leaf is green like moſt other leaves, but during the vernal months the under ſurface is of a deep red, whence I conclude that the vegetable blood acquires the red colour in the terminations of the pulmonary artery in the upper ſurfaces of the leaves, which becomes viſible as it paſſes in the large veins on the inferior ſurface. In the ſame manner the red colour of the blood is moſt viſible in the large veins beneath the leaf of the red veined dock, rumex ſanguinea.

4. From theſe experiments the upper ſurface of the leaf appeared to be the immediate organ of reſpiration, becauſe the coloured fluid was carried to the extremities of the leaf by veſſels moſt conſpicuous on the upper ſurface, and there changed into a milky fluid, which is the blood of the plant, and then returned by concomitant veins on the under ſurface, which were ſeen to ooze when divided with ſciſſars, and which in picris particularly rendered the under ſurface of the leaves greatly whiter than the upper one.

As the upper ſurface of leaves conſtitutes the organ of reſpiration, on which the vegetable blood is expoſed in the terminations of arteries beneath a thin moiſt pellicle to the action of the atmoſphere, theſe ſurfaces in many plants ſtrongly repel moiſture, as cabbage-leaves, whence the particles of rain lying over their ſurfaces without touching them, as obſerved by Mr. Melville, (Eſſays Literary and Philoſ. Edinb.) have the appearance of globules of quick-ſilver. And hence leaves laid with their upper ſurfaces on water wither as ſoon as in the dry air, but continue green many days if placed with their under ſurfaces on water,

water, as appears in the experiment of monſieur Bonnet, (Uſage des Fevilles); hence ſome aquatic plants, as the water-lily (nymphæa) have the lower ſides of their leaves floating on the water, while the upper ſurfaces remain dry in the air.

This repulſion of the upper ſurfaces of the leaves of aerial plants to water bears ſome analogy to the renitency of the larinx to the admiſſion of water into the lungs of animals; for if a ſingle drop accidentally falls into the windpipe, a convulſive cough is induced till it is regurgitated. For the ſame reaſon ſeveral plants cloſe together the upper ſurfaces of their leaves when it rains, in the ſame manner as in their ſleep during the night, as mimoſa, the ſenſitive plant, and the young ſhoots of chick-weed, alſine; and of kidney-bean, phaſeolus.

As thoſe inſects which have many ſpiracula, or breathing apertures, as waſps and flies, are immediately ſuffocated by pouring oil upon them, in the year 1783 I carefully covered with oil the ſurfaces of ſeveral leaves of phlomis, of Portugal laurel, and balſams; and though it would not regularly adhere, I found them all die in a day or two, which ſhews another ſimilitude between the lungs of animals and the leaves of vegetables.

There is an ingenious experiment of M. Bonnet, (Uſage des feuilles) which ſhews that the upper ſurfaces of leaves exhale much leſs than their under ſurfaces. He put the ſtalks of many leaves freſh plucked from trees or herbaceous plants into glaſs tubes filled with water; of theſe he covered with oil or varniſh the upper ſurface of many leaves, and the under ſurface of many others, and uniformly obſerved by the water ſinking in the tubes that the upper ſurfaces exhaled much leſs than half the quantity exhaled by the under ſurfaces, which ſhews them to be organs deſigned for different purpoſes.

II. 1. There exiſts a ſtrict analogy between the leaves of aquatic plants, which are conſtantly immerſed beneath the water, and the gills

of aquatic animals, which conſiſts in the largeneſs of their ſurface, owing to their hair-like ſubdiviſions, and to their being terminated with innumerable points. The gills of fiſh conſiſt of many folds of blood-veſſels lying over each other, each reſembling a fringe, or the downy part on one ſide of a feather attached to the middle rib of it, by which means they expoſe a greater ſurface of blood to the water than is expoſed to the air by the internal membranes of the air-cells of the lungs of other animals; and undoubtedly for this final cauſe, becauſe water contains leſs oxygen in its uncombined ſtate, which is the material neceſſary to life, than air, though much more of it in its combined ſtate, as water conſiſts of eighty-five parts of oxygen to fifteen parts of hydrogen; but it is the uncombined oxygen only diſſolved in heat, and diffuſed in water, which can ſerve the purpoſe of animal or vegetable reſpiration.

The apparatus for this purpoſe, according to Duverney's Anatomy of a Carp, is truly curious. He found 4386 bones in the gills, which had ſixty-nine muſcles to give them their due motions. See Bomare's Dictionaire raiſoneé, Art Poiſſon. And Monro obſerved by the numerous diviſions and folds of the membrane of the gills, that their ſurface in a large ſkate was nearly equal to the furface of the human body. Phyſiol. of Fiſh, p. 15. He adds that in the whole gills there exiſt 144,000 ſubdiviſions or folds, and that the whole extent of this membrane may be ſeen by a microſcope to be covered with a network of exceedingly minute veſſels.

2. In this reſpect the gills of fiſh are reſembled by the ſubaquatic leaves of plants, which are ſlit into long wires terminated in points, as in trapa, œnanthe, hottonia, the water-violet, and the water-ranunculus. This laſt plant, and ſome others, have frequently ſome leaves erect in the air, and others immerſed in water, ariſing from the ſame ſtem; and it is curious to obſerve that the aerial leaves are nearly entire, or divided only into a few lobes; whilſt the aquatic leaves are ſlit into innumerable branches like a fringe, and have thus

their ſurfaces wonderfully enlarged for the purpoſe of acquiring uncombined oxygen from the air, which is diffuſed in the water, and which abounds ſo much leſs there than in the atmoſphere; for the ſame purpoſe the plants on the ſummits of high mountains, where the air is ſo much rarer, and conſequently abounds leſs with oxygen, have their leaves much more divided than in the plains, as pimpinella, petroſelinum, and others, that they may expoſe a more extenſive ſurface of veſſels to the influence of the thinner atmoſphere.

3. This great enlargement of the ſurface by ſo minute a diviſion does not however ſeem to be the only uſe of this uniform ſtructure of gills and aquatic leaves; but there is another very important one, which hath hitherto I believe eſcaped the notice of philoſophers; and that is that points and edges contribute much to the ſeparation of the air, which is mechanically mixed or chemically diſſolved in water, as appears on immerſing a dry hairy leaf into water freſh from a pump, on which innumerable globules of air, like quick-ſilver, appear on almoſt every point. Nor is it improbable that points immerſed in water may in a bright day contribute to decompoſe it, or certainly to ſet at liberty its ſuperabundant oxygene, as occurs in the perſpiration of leaves when expoſed to the ſunſhine, and to the green matter in the experiments of Dr. Prieſtley, which is probably owing to the fine points of both of them; and laſtly, when points of ſilk are immerſed in ſpring water, which is frequently hyperoxygenated, as in the experiments of Count Rumford, related in the Philoſ. Tranſact. See Sect. XIII. I. 5.

III. 1. The *root-leaves* of many perennial plants, which do not produce flowers in the firſt year from the ſeed, are different from thoſe of future years, as in the rheum palmatum, palmated rhubarb, the leaves are ſmall and nearly circular, and not divided into fingers till the ſecond year; and in tulip the leaf the firſt year from the ſeed is ſmall like a blade of graſs, riſing from a diminutive bulb. In other perennial plants the root-leaf is undivided, but at the ſame time larger than

than thoſe on the riſing ſtem, as in geum, averns; in ſenecio aureus, and the campanula rotundifolia, ſo named from the round form of the root-leaf, which is alſo much broader than thoſe on the ſtem, as well as undivided. The root-leaves of many biennial, and of ſome annual plants, are likewiſe larger, as well as of a different form from thoſe on the riſing flower-ſtem, as in turneps and carrots. And laſtly, the root-leaves of ſome plants, which riſe immediately from ſeeds, conſiſt of the cotyledons of the ſeed, and are thus different from the leaves above them.

2. In reſpect to the root-leaves of palmated rhubarb and of tulips, when theſe plants are raiſed immediately from ſeed, as theſe firſt plants are not deſigned to generate flowers and conſequent ſeeds, but to produce ſimply another plant like a leaf-bud of a tree, leſs oxygenation ſeems to have been neceſſary, and the leaves therefore require leſs ſurface, and are in conſequence undivided. In reſpect to the root-leaves of geum, and of campanula rotundifolia, which are larger than their ſtem-leaves, it is probable that they lay up a reſervoir of nutritious matter for the riſing ſtem, like thoſe of turneps and carrots, and thus require greater oxygenation, and in conſequence a greater ſurface.

3. Another difference of root-leaves from thoſe of the ſtem in annual plants often conſiſts in the latter being properly bractes or floral-leaves, which will be ſpoken of below, while the root-leaf reſembles thoſe belonging to the leaf-buds of trees. Thus in the riſing ſtem of wheat the root-leaf produces the firſt joint above the ſoil, and the ſecond and third leaf produce joint above joint, which are each a ſeparate bud riſing on that below it, as is ſeen by the diviſion of the pith or hollow part of one joint from another, and at length the uppermoſt leaf is a bracte or floral-leaf belonging to the ear.

4. And laſtly, the ſeed-leaves which riſe out of the ground with the firſt joint of the flower-ſtem, as in kidney-bean, phaſeolus, as they conſiſt of the placental artery, which was ſpread on the cotyledons

dons of the ſeed, and, now riſing out of the earth, when the nutritive part has been diſſolved in the terrein moiſture and abſorbed, they ſerve the office of an aerial pulmonary organ, or lungs, which before ſerved that of an aquatic one, or gills; but wither and fall off as the true leaves become expanded.

IV. 1. The common foliage of deciduous plants conſtitutes the organ of reſpiration already ſpoken of, which belongs to the leaf-buds during the ſummer months, and drops off in the autumn, when thoſe buds periſh by the cold, or by the natural termination of their exiſtence. But there is another kind of foliage diſſimilar to the former, conſiſting of bractes or floral-leaves, which ſupply an organ of reſpiration to the calyx and pericarp of the flower-bud. Theſe frequently differ in ſize, form, and colour from the other leaves of the plant, and are ſituated on the flower-ſtalk often ſo near the fructification as to be confounded with the calyx. In ſome plants there are two ſets of floral-leaves, or bractes, one at the foot of the umbel, and another beneath each diſtinct floret of it; and in others they appear in a tuft above the flower, as well as on the ſtalk beneath it, as in fritillaria imperialis, crown imperial; and in others they are ſo ſmall as to be termed ſtipulæ or props.

All theſe kinds of bractes, or floral-leaves, ſerve the office of lungs for the purpoſe of expoſing the vegetable blood to the influence of the air, and of preparing it for the ſecretion, or production and nouriſhment of the vegetable uterus, or pericarp, and of the ſeeds produced and retained in it, frequently before their impregnation, and always after it.

2. It muſt be obſerved that in many plants theſe floral-leaves, or bractes, do not appear till after the corol and nectaries, with the anthers and ſtigmas, drop off; that is, not till after the ſeed is impregnated, as in colchicum autumnale, crocus, hamamelis, and in ſome fruit-trees. The production of the vegetable uterus, or pericarp, with the unimpregnated ſeeds included in it, is in theſe plants accompliſhed or

evolved, like the bractes themſelves with the corol and ſexual organs, by the ſap-juice, forced up in the umbilical veſſels from ſome previouſly prepared reſervoir, without the neceſſity of any expoſition to the air in leaves or lungs, which are not yet formed, though it may acquire oxygenation in the fine arteries of the embryon buds, which are ſuppoſed to ſurround the horizontal air-veſſels obſerved in the bark of trees.

As ſoon as the ſeeds become impregnated, the corol and nectaries with the ſexual organs fall off, and the pericarp and its contained ſeeds are then nouriſhed by the blood, which is aerated or oxygenated in the bractes, or floral leaves. Thus the flower of the colchicum appears in autumn without any green leaves, and the pericarp with its impregnated ſeeds riſes out of the ground in the enſuing ſpring on a ſtem ſurrounded with bractes, and with other green leaves below them, which produce new bulbs in their boſoms.

The blood, which thus ſupplies nutriment to the pericarp and its included ſeeds, does not ſeem to require ſo much oxygenation as that which ſupplies nutriment to the embryon buds; whence the floral leaves are in general much leſs than the root-leaves in many plants, and than the common green leaves of almoſt all vegetables. And in the plant mentioned in No. I. 3. of this ſection, under the name of ſenecio bicolor, the under ſurfaces of the ſtem-leaves near the expected flower ceaſed to be red like thoſe of the radical leaves, which ſeemed to ſhew that the vegetable blood was in them leſs oxygenated.

Whence it may be believed that leſs irritability may be neceſſary for the growth of the ſeed than of the embryon bud, as the former does not yet perhaps poſſeſs ſo much vegetable life as the latter. And laſtly, that as the anthers and ſtigma require greater irritability, and ſome ſenſibility, it was neceſſary a ſecond time to oxygenate the blood which ſupplies them with nutriment in the corols of the flowers. See Sect. VII. 2. 4.

3. Recapitulation of the arguments tending to ſhew that the leaves of

of vegetables are their lungs. 1. They conſiſt of an artery, which carries the ſap to the extreme ſurface of the upper ſide of the leaf, and there expoſes it under a thin moiſt pellicle to the action of the air; and of veins, which there collect and return it to the foot-ſtalk of the leaf, like the pulmonary ſyſtem of animals. 2. In this organ the pellucid ſap is changed to a coloured blood, like the chyle in paſſing through the lungs of animals. 3. The leaves of aquatic plants are furniſhed with a larger ſurface, and with points like the gills of aquatic animals. 4. The upper ſides of aerial leaves repel moiſture, like the larynx of animals. 5. Leaves are killed by ſmearing them with oil, which in the ſame manner deſtroys inſects by ſtopping their ſpiracula, or the air-holes to their lungs. 6. Leaves have muſcles appropriated to turn them to the light, which is neceſſary to their reſpiration, as will be ſhewn in the Section on Light. 7. To this may be added an experiment of Mr. Papin related by M. Duhamel. He put an intire plant into the exhauſted receiver of an air-pump, and it ſoon periſhed; but on keeping the whole plant in this vacuum except the leaves, which were expoſed to the air, it continued to live a long time, which he adds is a proof that the leaves are the organs of reſpiration. Phyſic des arbres, V. I. p. 169.

V. 1. The organs of reſpiration already deſcribed conſiſt of the green leaves belonging to leaf-buds, and of the bractes belonging to flower-buds. But there is another pulmonary ſyſtem totally independent of the green foliage, which belongs to the ſexual or amatorial parts of the fructification only, I mean the corol or petals. In this there is an artery belonging to each petal, which conveys the vegetable blood to its extremities, expoſing it to the light and air under a delicate moiſt membrane covering the internal ſurface of the petal, where it often changes its colour, as is beautifully ſeen in ſome party-coloured poppies, though it is probable that ſome of the irrideſcent colours of flowers may be owing to the different degrees of tenuity

of the exterior membrane of the petal refracting the light like ſoap-bubbles.

The vegetable blood is then collected at the extremities of the corol-arteries, and returned by correſpondent veins exactly as in the green foliage, for the ſuſtenance of the anthers and ſtigmas, and for the important ſecretions of honey, wax, eſſential oil, and the prolific duſt of the anthers, and thus conſtitutes a pulmonary organ, as is ſhewn by the following analogies.

2. Firſt, the vaſcular ſtructure of the corol, as above deſcribed, and which is viſible to the naked eye; and its expoſing the vegetable juices to the air and light during the day evinces that it is a pulmonary organ.

Secondly, as the glands which produce the prolific duſt of the anthers, the honey, wax, and frequently ſome odiriferous eſſential oil, are generally attached to the corol, and always fall off and periſh with it, it is evident that the blood is elaborated or oxygenated in this pulmonary ſyſtem for the purpoſe of theſe important ſecretions.

Thirdly, many flowers, as the colchicum and hamamelis, ariſe naked in autumn, no green leaves appearing till the enſuing ſpring; and many others put forth their flowers, and complete their impregnation early in the ſpring, before the green foliage or bractes appear, as mezereon, and ſome fruit-trees, which ſhews that theſe corols are the lungs belonging to theſe parts of the fructification.

Fourthly, this organ does not ſeem to have been neceſſary for the defence of the ſtamens and piſtils, ſince the calyx of many flowers, as tragopogon, performs this office; and in many flowers theſe petals themſelves are ſo tender as to require being ſhut up in the calyx during the night. For what other uſe then can ſuch an apparatus of veſſels be deſigned?

Fifthly, in the helleborus niger, Chriſtmas-roſe, after the ſeeds are grown to a certain ſize, the nectaries, and ſtamens, and ſtigmas, drop off,

off, and the beautiful large white petals change their colour to a deep green, and gradually thus become a calyx, incloſing and defending the ripening ſeeds; hence it would ſeem that the white veſſels of the corol ſerved the office of expoſing the blood to the action of the air, for the purpoſes of ſeparating or producing the honey, wax, and prolific duſt; and when theſe were no longer wanted, that theſe veſſels coaleſced, like the umbilical veſſels of animals after their birth, and thus ceaſed to perform that office, and loſt at the ſame time their white colour. Why ſhould they loſe their white colour unleſs they at the ſame time loſt ſome other property beſides that of defending the ſeed-veſſel, which they ſtill continue to defend?

Sixthly, neither the common green leaves nor the bractes are neceſſary to the progreſs of the corol, and ſtamens, and ſtigma, or to the ſecretion of honey, after the laſt year's leaves are fallen off, as is evinced by the flowers of colchicum in the autumn, and of crocus in the ſpring, in both which the ſeeds riſe out of the earth with their common leaves and bractes ſo long after the diſappearance of the flower. In deciduous plants the common green leaves ſerve as lungs in the ſummer and autumn to each individual bud, which then produces the new buds in its boſom, which are either leaf-buds or flower-buds. In the enſuing ſpring the new common leaves are the reſpiratory organ belonging to the leaf-buds, and the bractes are the reſpiratory organ to the pericarp, and its included ſeeds before or after impregnation; and the corols, as ſoon as expanded, become the lungs to the amatorial parts of the fructification, and require neither the green leaves nor bractes.

3. Hence the vine bears fruit at one joint without leaves, and leaves at the other joint without fruit. Hence the flower of the colchicum riſes out of the ground without bractes or other green leaves, and flouriſhes till the ſeed is impregnated; and the bractes, which riſe out of the ground on the ſtem in the following ſpring, are lungs to give maturity to the pericarp and ſeed; and the other green leaves are

for the purpoſe of producing new bulbs round the old one, but can have nothing to do with the corol, anthers, ſtigmas, and nectaries, which have long ſince fallen off, and periſhed. And laſtly, when currant or gooſeberry trees loſe their common green leaves, and their bractes, by the depredation of inſects; the new leaf-buds become ſmall and weak, but the corol, anthers, ſtigmas, and nectaries, continue to flouriſh, and the fruit becomes impregnated, though it is leſs ſweet and of leſs ſize from the pericarp and included ſeed wanting their due nutrition by the bractes before or after impregnation.

4. It hence appears that the flower-bud, after the corol, ſtamens, ſtigmas, and nectaries fall off, becomes ſimply a vegetable uterus, for the purpoſe of ſupplying the growing embryons with nouriſhment, and poſſeſſes a ſyſtem of abſorbent veſſels, which brings the ſap-juice to the foot-ſtalk of the fruit, and which there changes into a pulmonary artery, which conſtitutes the bractes or floral-leaves, and expoſes the acquired juices to the oxygenation of the air, and converts them into vegetable blood. This blood is collected again by the veins of the bractes, and conveyed by an adapted or aortal artery for the various ſecretions of ſaccharine, farinaceous, or aceſcent materials, for the nouriſhment of its included embryons, or the conſtruction of the fruit and ſeed-lobes.

At the ſame time, as perhaps all the veſſels of trees inoſculate, the fruit may become ſweeter and larger when the green leaves as well as the bractes continue on the tree; but the corols with the ſtamens, ſtigmas, and nectaries, (the ſucceeding fruit not conſidered) ſuffer, I believe, no injury, when the green leaves and even the bractes are taken off, as by the depredations of inſects. Some floriſts have obſerved this circumſtance, and affirm that in many plants when the leaves are pulled off, the flowers become ſtronger from their then producing no bulbs, as in tulips and hyacinths. The inoſculation of vegetable veſſels is evinced by the increaſed growth of one bud, when others in its vicinity are cut away.

5. The

5. The ſleep of plants has been much ſpoken of by Linneus and others, but there is a wonderful circumſtance occurs in it, which has not been noticed; which is, that it ſeems to reſemble the torpor of winter-ſleeping inſects and other animals, as many plants do not appear to reſpire during this part of their exiſtence; for ſome vegetables cloſe together the upper ſurfaces of their leaves, both during their ſleep and in rainy weather, as mimoſa, ſenſitive-plant; phaſeolus, kidney-bean; and the terminal ſhoots of alſine, chickweed. Many other plants cloſe their petals and calyxes during their ſleep as well as in rain, as convolvulus; and ſome even in the bright daylight, as tragapogon; and yet all theſe plants are believed by gardeners to grow, when young, faſter in the night.

We muſt obſerve, that this ſleep of plants, though it may reſemble the torpor of winter-ſleeping animals, is not to be confounded with the ſtate of deciduous plants in the winter, as that conſiſts in the death of the laſt year's bud, and the embryon condition of the new buds. It would hence appear, that perpetual reſpiration is leſs neceſſary to the vegetable than to the animal world; and that as leſs is waſted during the inactive ſtate of ſleep, it is poſſible that young plants may increaſe in weight, or grow faſter, during this ſtate of inactivity, as animals are obſerved to reſpire leſs frequently during their ſleep, and yet are believed when young to grow faſter during their hours of reſt than of exerciſe. So both in the experiments of Dr. Hales and Dr. Walker on plants during the bleeding ſeaſon, the aſcent of the ſap-juice not only ſtopped during the night, but ſometimes became retrograde, which might nevertheleſs be aſcribed to the torpor of the abſorbent ſyſtem induced by cold, as well as to that of ſleep.

6. We may draw this general reſult, that the common leaves of trees are the lungs of the individual vegetable beings, which form during the ſummer new buds in their boſoms, whether leaf-buds or flower-buds, and which in reſpect to the deciduous trees of this cli-

mate

mate periſh in autumn ; while the new buds remain to expand in the enſuing ſpring. Secondly, that the bractes, or floral-leaves, are the lungs of the pericarp or uterus, and to the growing ſeeds which it contains, as the bractes on the ſtem of the crown-imperial, fritillaria imperialis, and the tuft above its flowers. And thirdly, that the corol or petals are the lungs belonging to the anthers and ſtigmas, which are the ſexual or amatorial parts of the plant, and to the nectaries for the ſecretion of honey, and to the other glands which affords eſſential oil and wax.

Laſtly, the ſtamina and ſtigma with the petals and nectary, which conſtitute the vegetable males, and the amatorial part of the female, as they in ſome plants appear before the green leaves or bractes, as in colchicum and mezereon, and in all plants fall off when the female uterus is impregnated, would appear to be diſtinct beings, totally different both from the leaf-buds, which produce a viviparous progeny ; and alſo from the bractes with the calyx and pericarp, which conſtitute the vegetable uterus.

They muſt at firſt receive nutriment from the vernal ſap-juice, like the expanding foliage of the leaf-buds, or the bractes of the flower-buds. But when the corol becomes expanded, and conſtitutes a new pulmonary organ, the vegetable juices are expoſed to the air in the extremities of its fine arteries beneath a moiſt pellicle for the purpoſe of greater oxygenation, and for the important ſecretion of honey; and then the anthers and ſtigmas are ſupplied with this more nutritious food, which they abſorb from its receptacle, the nectary, after it has there been expoſed to the air, and are thus furniſhed with greater irritability, and with the neceſſary amatorial ſenſibility, and live like bees and butterflies on that nutritious fluid. See Sect. VII. II. 4.

SECT.

SECT. V.

THE AORTAL ARTERIES AND VEINS OF VEGETABLES.

1. *Aortal arteries in vegetables have correſpondent veins. Shewn by experiment on picris, tragopogon, and euphorbia. Seen in the calyx of flowers. Circulation ſhewn by ingrafting ſtriped-paſſion-flower, and jaſmine, and hardier ſcions on cankered ſtems, from fruit-grafts on bad ſtocks degenerating.* 2. *Vegetable circulation performed without a heart, as in the aorta and liver of fiſh.* 3. *Force of the mouths of abſorbents greater than that of the heart in producing circulation. Why there is no pulſation in the vena portarum. Circulation in the veins of animals produced by abſorption. Very ſmall reſiſtance in the capillaries and glands. Wounds in trees ſtrongly abſorb fluids except in the bleeding ſeaſon.* 4. *Vegetable veſſels too minute to carry red blood, hence not eaſily injected with coloured fluids. Charcoal injected with quickſilver, or melted wax.* 5. *Recapitulation. Circulation performed by irritability of the veſſels, and by the great power of abſorption, and the action of the ſides of veſſels conſiſting of a ſpiral line.* 6. *Veſſels unite at the lower and upper caudex gemmæ. Abſorbents and umbilical veſſels conſiſt of a ſpiral line. Experiment by placing euphorbium firſt in a decoction of galls, and then in a ſolution of green vitriol. Junction of great vein, abſorbent trunk, and pulmonary artery in the upper caudex gemmæ. Embryon bud ſeen in contact with the pith. Experiments with charcoal injected with white paint, ſuet, wax, and quickſilver.*

1. THE two principal arteries in animal bodies are the pulmonary artery and the aorta. The former receives the blood from the right cavity of the heart, and diſperſing it round all the air-cells which terminate the bronchia, or air-pipes of the lungs, expoſes it to the influence of the atmoſphere through the thin moiſt membrane, which lines them. This we have ſhewn in Sect IV. I. 3. to be reſembled in its office by the vegetable arteries, which carry their blood up the

foot-ſtalks of the leaves, and expoſe it on the upper ſurface of them to the influence of the air through a thin moiſt pellicle, where it changes its colour, and returns by correſpondent veins like the blood of animals.

The aortal arteries of the more perfect animals receive the blood from the left cavity of the heart, after it has been expoſed to the influence of the air in the lungs, and diſperſe it by numerous ramifications over the whole body for the purpoſes of ſecretion and nutrition. In leſs perfect animals the aorta itſelf has a pulſation, and carries forward the blood without the aſſiſtance of a heart, as may be ſeen in the back of a full-grown ſilk-worm by the naked eye, and very diſtinctly by the uſe of a common lens. After the blood has paſſed the various glands and capillaries, it is received by another ſyſtem of veſſels, the veins, which conſtitute a kind of reſervoir for the quantity of blood, that remains unexpended by the ſecretions, excretions, nutrition, and growth of the animal; by theſe it is again carried to the right cavity of the heart, and again expoſed in the lungs to the influence of the air.

In a ſimilar manner the branching veins, which bring the blood from the leaves of plants, after it has been expoſed to the influence of the air, unite at the foot-ſtalk of each leaf into more or fewer trunks, as may be ſeen in tearing off the foot-ſtalk of a leaf of a cheſnut-tree from the ſtem; and there without the interpoſition of a heart, like the circulation in the aorta of fiſh, and that in the livers of red-blooded animals, theſe venous trunks take the office of arteries, and diſperſe the blood downwards along the bark to the roots, and to every other part of the vegetable ſyſtem, performing the various purpoſes of ſecretion, excretion, and nutrition, as was ſhewn in the experiment of placing a fig-leaf in a decoction of madder, deſcribed in Sect. IV. 1. 3. of this work.

But as vegetables drink up their adapted nouriſhment perpetually from the moiſt earth, and in conſequence muſt be ſuppoſed to take

up

up no more than their perpetual waſte may require, I formerly believed, that this reſervoir, or venous ſyſtem, was not neceſſary in vegetables; and that therefore probably it did not exiſt. I was induced to adopt this idea from having obſerved in cutting aſunder a ſtem of large ſpurge, euphorbia helioſcopia; in which the riſing ſap could not be miſtaken for the milky blood; that much more of the vegetable blood flowed from the upper part of the plant than from the lower part of it; and I therefore ſuſpected, that there was no returning veins correſpondent to the deſcending aortal arteries. But firſt this muſt neceſſarily occur from the veins returning from the root effuſing their blood ſlower than the arteries of the upper part of the plant. And ſecondly, if there were no returning veins from the lower part of the plant, there ought to have been no effuſion of blood from it. I have ſince obſerved on cutting aſunder a large plant of picris, and alſo a large plant of tragopogon ſcorzonera, and inſtantly inſpecting them with a common lens; that two concentric circles of veſſels were viſible, which oozed a milky juice; the internal circle of the upper diviſion of the two plants, and the external one of the lower diviſion, appeared to bleed more copiouſly, and in quicker ſtreams, than the external circle of the upper diviſion, and the internal one of the lower diviſion; whence I concluded, that the veſſels of the internal circles were arteries, and thoſe of the external ones veins; and that the arteries of the upper part of the plant, which ariſe from the upper part of the caudex of each individual bud, were thus ſeen to pour out more blood, and in a quicker ſtream, than the veins of the lower part of the plant, as they return from the roots.

Add to this, that as the pulmonary arteries in the green leaves of plants, and in their petals, have correſpondent veins viſible to the eye; and that theſe are alſo ſeen in the calyxes of ſome flowers, which from their other evident uſes can not be eſteemed pulmonary organs: There is the ſtricteſt analogy to believe, that the aortal arteries of the bark of the trunk and roots have alſo their correſpondent veins.

Nevertheleſs to evince that the veſſels returning from the roots of plants, which oozed out a milky juice, were in reality not abſorbent veſſels, I cut off the ſtem of a large ſpurge plant, euphorbia helioſcopia, about a foot and half from the ground, and bent it down into a cup of a decoction of madder, rubia tinctoria, in which it was confined two or three minutes; and wiping the end clean, I preſently cut off about an eighth of an inch of it with a ſharp penknife, and obſerved with a common lens the large abſorbent veſſels to be coloured with the madder, while the veins continued to effuſe a little white blood; and thus demonſtrated both the exiſtence of abſorbent veſſels and returning veins. See Sect. II. 2.

At the ſame time the upper part of the plant had alſo its ſtem ſet in the decoction of madder, and after two or three minutes on cutting off about the eighth of an inch of it, or ſimply by wiping the extremity, the large abſorbent veſſels were ſeen by the naked eye to be coloured with the madder, and the arteries continued to effuſe a large quantity of milky blood. The ſame experiments were tried on a plant of tragopogon with the ſame event.

It ſhould be here obſerved, that the decoction of madder ſhould be freſh made, as otherwiſe the colouring matter is liable to form itſelf into molecules, too large to be imbibed by any other veſſels but the trunks of the abſorbents, which may be ſaid to reſemble the receptaculum chyli of animals, as they paſs from the lower extremity of the caudex of each bud to the upper one.

A proof of the circulation of the juices of plants has been deduced from the communication of white ſpots from a grafted ſcion to the whole of the tree in which it was ingrafted. Mr. Fairchild budded a paſſion-tree, whoſe leaves were ſpotted with yellow, into one which bears long fruit. The buds did not take, nevertheleſs in a fortnight yellow ſpots began to ſhew themſelves about three feet above the inoculation; and in a ſhort time afterwards yellow ſpots appeared on a ſhoot,

a ſhoot, which came out of the ground from another part of the plant. Bradley on Gardening, Vol. II. p. 129.

And Mr. Lawrence obſerves, that the yellow ſtriped jaſſamine has afforded a demonſtration of the circulation of the juices in a tree; he inoculated in Auguſt the buds of ſtriped jaſſamine-trees into the branches of plain ones; and aſſerts, that he has ſeveral times experienced, that if the bud lives but two or three months, it will communicate its virtue or diſeaſe to the whole circumfluent ſap, and the tree will become entirely ſtriped. Art of Gardening, p. 66. Theſe are both of them important facts, as they are related from reſpectable authorities.

And I think I have myſelf obſerved in two pear-trees about twenty years old, whoſe branches were much injured by canker, that on ingrafting hardier pear-ſcions on their ſummits, they became healthier trees, which can only be explained from a better ſanguification produced in the leaves of the new buds.

It has alſo been obſerved by an ingenious lady, that though fruit-trees ingrafted on various kinds of ſtocks are ſuppoſed to bear ſimilar fruit, yet that this is not accurately ſo; as on ſome ſtocks ſhe has known the ingrafted ſcions of apple-trees to ſuffer conſiderable change for the worſe compared with the fruit of the parent-tree; whereas thoſe ſcions, which can be made to grow by ſtriking roots into the earth, ſhe believes to ſuffer no deterioration. If this really occurs, it ſhould be in a very ſlight degree, as the fruit is formed by the action of ſecretion, and depends on the glands of the part more than on any ſlight change of the vegetable blood, from which the ſecretion is ſelected or produced. Nevertheleſs if the fact be aſcertained, it confirms the truth of the exiſtence of a vegetable circulation.

2. The circulation of the vegetable juices in the leaves of plants, and in their trunks and roots, is performed without a heart, and is very ſimilar to that in the aorta of fiſh. In fiſh the blood, after having paſſed through their gills, does not return to the heart, as from

the

the lungs of air-breathing animals; but the pulmonary vein, taking the ſtructure of an artery, after having received the blood from the gills, which there gains a more florid colour, diſtributes it to the other parts of their bodies. A ſimilar ſtructure obtains in the livers of fiſh, as well as in thoſe of air-breathing animals; the blood is collected from the meſentery and inteſtines by the branches of their proper veins, which unite on their entrance into the liver, branch out again, and aſſume the office of an artery, under the name of vena portarum, diſtributing the blood through that large viſcus for the purpoſe of the ſecretion of bile; whence we ſee in theſe animals two circulations independent of the power of the heart. Firſt, that which begins in the meſentery and inteſtines, and paſſes through the liver; and ſecondly, that beginning at the termination of the veins of the gills, and paſſing through the other parts of the body; both which circulations are carried on by the action of thoſe reſpective arteries and veins. Monro's Phyſiology of Fiſh, p. 19.

The courſe of the fluids in the leaves, and in the trunks and roots of vegetables, is performed in a ſimilar manner. Firſt, the abſorbent veſſels of the roots, of the internal cells, and of the external bark, with the venous blood returning from thoſe parts, unite at the foot-ſtalk of the leaf; and then, like the vena portarum, an artery commences without the intervention of a heart, and receiving the ſap and venous blood ſpreads it in numerous ramifications on the upper ſurface of the leaf; here it changes its colour, and becomes vegetable blood; and is again collected by a pulmonary vein, and returns on the under ſurface of the leaf. This vein, like that which receives the blood from the gills of fiſh, aſſumes the office of an artery, which correſponds with the aorta of animals, and branching again diſperſes the blood upward to the plumula or ſummit of the bud, from its caudex at the foot-ſtalk of the leaf, and downward along the bark of the trunk to the roots; where it is received by a vein correſponding to the vena cava of animals, after having expended what was required for the ſecretions,

tions, excretions, and nutritition, and returns to the caudex of the bud, and to the foot-ſtalk of the leaf.

3. The power, which produces a circulation without a heart in vegetables, acts with an aſtoniſhing force. In ſome of the experiments of Dr. Hales, who fixed glaſs tubes to vine-ſtumps in the ſpring, the ſap-juice roſe above thirty feet; and in ſome trees muſt probably ariſe ſtill higher in the vernal months before the leaves are expended; and this either ſolely by the activity of the abſorbent mouths of theſe veſſels, or aſſiſted by the vermicular action of their ſides, which appear to conſiſt of a ſpiral line, as deſcribed in Sect. II. 7. of this work.

When the ſap-juice riſes thirty-five feet high, which is about the weight of the atmoſphere, the column preſſes about fourteen pounds on every ſquare inch. Now if the area of the mouth of an abſorbent veſſel be only one ten thouſandth part of the area of a ſquare inch, the ten thouſandth part of fourteen pounds is the whole that counteracts the efforts of each abſorbent mouth; and as the veſſels of vegetables appear to have both very minute diameters, and very rigid ſides, they are thence prevented from aneuriſm or rupture by the preſſure of ſo high a column of ſap-juice.

The ſame philoſopher, by fixing glaſs tubes to the arteries of horſes, as near the heart as was practicable, found the blood in them to riſe only nine or ten feet; whence it appears, that a circulation of blood may be carried on more forcibly by the action of the mouths of abſorbent veſſels, than by the apparently more violent exertions of the heart, the power of which was calculated by Borelli and others to be ſo enormouſly great, as to equal the preſſure of ſome thouſand pounds, as the counter preſſure of the moving blood acts on ſo large a ſurface as that of the whole internal ſides of the heart.

But as a column of blood nine feet high preſſes with leſs than one third of the weight of the atmoſphere, or about four pounds on every ſquare inch of ſurface; and as the internal ſurface of the left cavity

of

of the heart of a horſe may not exceed thirty ſquare inches, its whole power does not overcome the reſiſtance of more than 120 pounds.

Hence it becomes intelligible, how the circulation of the blood in the vena portarum of the liver is performed without any apparent pulſation, or contraction of its ſides like an artery, which ſome have indeed ſuppoſed it to poſſeſs, but ſimply by the force of abſorption exerted by the mouths of the veins, which ſupply it with blood.

Secondly, how the circulation of the blood in the bodies of fiſh, except in their gills, is carried on through their ſyſtem without the action of the heart. And thirdly, how the blood in the vena cava of the human body, as well as the fluids imbibed by the lacteals and lymphatics, are carried forwards to the heart by the power alone of their abſorbent mouths, which drink up their blood from the capillaries, or their other fluids from the ſurfaces or cavities of the body. And laſtly, how the whole circulation in vegetables is performed in very minute veſſels without valves, and without a heart, ſolely by the power of abſorption, circumſtances which have long perplexed the phyſiology both of the animal and vegetable kingdoms.

Another circumſtance attending the circulation of the juices in vegetables, as well as the circulation of the blood in animal bodies, has not been ſufficiently attended to; and that is, that the reſiſtance to the paſſage of theſe fluids from the terminations of the arteries, in what are termed capillaries, to the beginnings of the veins, and through the glands of various kinds, is much leſs than is generally imagined, as we ſee with what great force the mouths of both the vegetable and animal abſorbents imbibe their fluids; and that the beginnings of the veins, and the mouths of the lacteals and lymphatics, and probably thoſe belonging to every kind of gland, poſſeſs this great power of abſorption. And that on this account, when wounds are made in trees in the ſummer months, when the umbilical ſap-veſſels of the root have ceaſed to act, ſuch wounds powerfully abſorb any fluid, whether ſalutary or poiſonous, which is applied to them, which does

not occur during the bleeding ſeaſon, as the ſap-juice from the diſſevered veſſels of the alburnum ſupplies a greater quantity of fluid than the other parts of the wound can imbibe.

4. The red particles of blood have been ſaid by Lewenhook and others, who have inſpected them in microſcopes, to be of the ſame ſize in all creatures. Hence nature has formed no very ſmall animals with a general circulation of warm red blood; the mouſe and humming-bird are perhaps the leaſt. When it was neceſſary to form the veſſels much more minute, a diluter kind of yellow or milky blood, or one nearly tranſparent, conſtitutes the greateſt part of the vital fluid, as in inſects of various kinds, and in the white muſcles of fiſh; whence aroſe a difficulty to the anatomiſt of viſibly injecting theſe ſmaller ſeries of veſſels, as they are too minute to convey almoſt any coloured particles.

In the vegetable world the finer ſyſtems of their veſſels have ſtill greater tenuity, and hence evade our eyes and microſcopes; and as their coats poſſeſs at the ſame time a greater rigidity, they are in general on that account alſo incapable of receiving coloured injections, which has rendered the anatomy of plants ſo much more difficult to inveſtigate than that of animals, and muſt apologiſe for the imperfections of this part of the work, but affords no argument againſt the exiſtence of a vegetable circulation.

It is probable that by immerſing charcoal, nicely made by ſlow calcination, in quickſilver, or even in melted coloured wax, as it ſo greedily abſorbs almoſt all fluids, when recently taken from the fire, or cooled without the contact of air, we might produce beautiful vegetable preparations, and give more accurate light into the anatomy of plants. But the column of quickſilver employed to puſh forwards the injection ſhould not be too high, leſt it ſhould rupture the veſſels it ought only to fill, as I ſuppoſe has ſometimes happened in thus injecting the glands or capillaries of animal bodies.

5. Recapitulation. We may finally conclude, that the circulation

of vegetables is performed like that of animals by the irritability of their veſſels to the ſtimulus of the fluids, which they abſorb and protrude; that is, that the extremities of the branching veins of the leaves forcibly abſorb the vegetable blood from the extremities of their arteries, which correſpond with the pulmonary arteries of animals; and that it is thus puſhed on to the foot-ſtalk of the leaf, where the veins unite, and branching out again take the office of an artery, like the aorta in fiſh, without perceptible pulſation. The blood in this artery is puſhed forwards by that behind it, the motion of which was given by the power of abſorption in the pulmonary vein, till it arrives at the extremities of theſe aortal branches, and is there again forcibly abſorbed by the terminations of the correſpondent veins, and again puſhed forwards to the caudex gemmæ, and to the foot-ſtalk of the leaf, like the blood in the vena cava of animals.

A part of this blood is at the ſame time forcibly ſelected and abſorbed by the various glands for the purpoſes of the neceſſary ſecretions, excretions, or nutrition; and the ſap-juice or chyle and the water, which is acquired by the abſorbent veſſels, that correſpond to the lacteal and lymphatic veſſels of animals, is carried, as well as the remainder of the blood, to the foot-ſtalk of the leaf. Here theſe abſorbent veſſels are believed to puſh their contents into the veins correſpondent to the vena cava of animals, and which now uniting without the intervention of a heart, aſſume the name and office of the pulmonary arteries; and branching out upon the leaf expoſe the returning blood and new ſap-juice to the influence of the air. And finally, all this is accompliſhed by the power of abſorption, as in the aortal arteries, and vena portarum, of fiſh, which is excited into action by the irritability of the mouths of theſe veſſels to the ſtimulus of the fluids, which they abſorb.

2d. A circulation of vegetable juices, in every reſpect ſimilar to that in the common leaves above deſcribed, exiſts in the bractes or floral-leaves, except that the leaves of the leaf-bud prepare their juices for the

the production and nouriſhment of other buds in their boſoms; but theſe bractes, which are the lungs of the fructification, prepare their juices for the nouriſhment of the pericarp and its included ſeeds, but not for that of the corol with its anthers and ſtigmas, as theſe in many flowers exiſt before the production of the floral-leaves, as in colchicum and hamamelis.

3d. Another circulation of vegetable juices exiſts in the ſexual parts of flowers, including the nectaries and corols. In the corols the vegetable blood is expoſed to the influence of the air, and prepared for the ſecretion of honey, which is the food or ſupport of the anthers and ſtigmas, as treated of in the ſection IV. V. 1. and in Section VII. 4. In theſe the progreſſion and circulation of the fluids muſt be cauſed by the power of abſorption, which we have ſhewn to be a greater force than that of the heart of animals.

4th. The progreſs of the fluids imbibed by vegetable lacteals from the earth, and by their lymphatics from the air, and from the ſurfaces of their internal cells, is evidently began and carried on by the power of abſorption of their terminating mouths, and the annular contraction of their ſpiral fibres.

5th. And laſtly, the wonderful force with which the ſap-juice is drank up and protruded in the umbilical veſſels, which expands and nouriſhes the buds of trees, and which forms the wires of ſtrawberries above ground, and thoſe of potatoes under ground, with the great variety of bulbs and root-ſcions, is to be aſcribed to this ſingle principle of abſorption. Except that ſome of theſe long cylindric veſſels are evidently compoſed of a ſpiral line, as mentioned in Sect. II. 7. and which may by the annular contraction of this ſpiral line carry the fluids they have abſorbed with great force either in a forward or retrograde direction.

6. Finally I conclude, that the branching abſorbents of the roots unite at the lower caudex of each bud, before it riſes out of the earth,

and forms a large trunk, which paſſes up the alburnum of the tree to the upper caudex of the bud at the foot-ſtalk of the leaf, and may be compared to the receptaculum chyli of animals extended to ſo great a length; and that it there joins the great returning vein, which alſo is compoſed of the branching veins of the roots uniting at the lower caudex of the bud, and aſcending terminates at the upper caudex of it, where it becomes again branched, and forms the pulmonary artery.

The aorta or great artery deſcends, I ſuppoſe, along with the great vein, or vena cava above mentioned; and branching in the roots below, and on all other parts of the individual leaf-bud, performs the offices of ſecretion and nutrition. The pulmonary arteries and veins belong to the leaf; the former expoſes the blood to the atmoſphere beneath a thin moiſt pellicle, whence it becomes oxygenated, and probably acquires ſome warmth, and phoſphoric acid, and the ſpirit of vegetable life. The latter collects the aerated blood by its branches, and conveys it to the upper caudex of the bud, at the foot-ſtalk of the leaf, where it becomes the aorta or great artery above mentioned.

The ſides of the long abſorbent trunks, or receptacles of chyle, which riſe from the lower caudex and terminate in the upper caudex of each bud, as well as the long trunks of the umbilical veſſels deſcribed in Sect. III. evidently conſiſt of a ſpiral line, as well as thoſe trunks of abſorbents, which imbibe aqueous fluids from the air, and a part of their perſpirable matter on the ſurfaces of the leaves. But whether the pulmonary and aortal arteries or great veins conſiſt of a ſimilar ſtructure is not yet aſcertained.

I ſhall here relate the following experiments, which were made a few days ago, to confirm or confute the ideas above delivered.

Some ſtems of large ſpurge, euphorbia, were ſet upright in a decoction of oak-galls, and others in a ſolution of green vitriol. On the next day theſe were reciprocally removed from the one to the other, as by this management I ſuppoſed that the black molecules would be

be produced in the veſſels of the plants, and would thence appear higher in thoſe veſſels than if the black molecules had been formed by a mixture of the two fluids previous to their abſorption.

On cutting theſe horizontally ſlice after ſlice with a ſharp knife, and inſpecting them with a common lens, the milky blood was ſeen to ooze, as before deſcribed, from an external ring of the bark; and an interior ring of coloured points was agreeably viſible many inches up the ſtem; but on ſlicing the ſtem from below up to the inſertion of the leaves and buds in their boſoms, I perſuaded myſelf that I could perceive the coloured abſorbents of the ſtem enlarged at the part where each with the attendant vein changes into a pulmonary artery, and paſſes into the leaf, forming three or more of the ribs of it, and thus conſtituting the upper part of the caudex gemmæ.

Another circumſtance was beautifully viſible, which was, that the coloured cylinder of abſorbent veſſels had evidently ſeparated to allow the new bud to apply its interior termination to the pith; which probably, when it was ſecreted by the glands of the caudex of the parent bud, found in this ſituation a proper nidus, and due nutriment for its embryon ſtate, as in the uterus of the female.

Some other kinds of experiments I directed with deſign to ſhew the part of the lower caudex of each bud, where the branching abſorbents and veins of the root unite each into one trunk, before they aſcend along the bole of the tree; and alſo to ſhew, as in the above experiment, the upper caudex of each bud, where the veins are joined by the abſorbents, and become the pulmonary arteries of each leaf, but did not ſucceed quite to my wiſh, though what I could obſerve ſeemed to confirm the above theory. I had not leiſure to repeat the experiments with ſufficient attention, but ſhall here in few words deſcribe the manner of making them, hoping ſome one may be induced to proſecute them with ſucceſs, and to inject vegetable veſſels, as the anatomiſts do thoſe of animals.

A part of a leaf-ſtalk, and the joint to which it adhered, with

about half an inch of the ſtem above and below the joint, were cut off from ſome laſt year's twigs, and alſo the caudex of ſome herbaceous plants. Theſe were covered with ſand in a crucible placed on the fire, till they were red hot, ſo that the vegetable joints were become charcoal. They were then taken out of the ſand, and ſome immerſed in melted ſuet, others in melted bees-wax, others in white paint, and one or two in an amalgama of quickſilver and zinc, which happened to be prepared for the purpoſes of electricity. When they were cold, on ſlicing them, ſome horizontally, and others vertically, I perſuaded myſelf that the blood-veſſels above mentioned, as well as the pulmonary vein and aortal artery, were viſible in the two extremities of the long caudex of the bud, as well as the long trunks of the arteries, veins, and abſorbents, which conſtitute the middle part of it.

SECT.

SECT. VI.

THE GLANDS AND SECRETIONS OF VEGETABLES.

I. 1. Glands *of vegetables. Their veſſels are too minute for coloured injections.* 2. *They poſſeſs appetency. Are ſtimulated by the paſſing blood.* II. 1. Mucilage *in all vegetables.* 2. *Is a part of their nutriment, and convertable into ſugar.* III. 1. Starch *not ſoluble in cold water. Potatoe bread.* 2. *Starch produced from mucilage, whence old grain better than new. Alum coagulates mucilage. Uſe of it in bread. How diſtinguiſhed in bread by the eye. Is ſalutary in London bread. Is uſed in making hair-powder.* 3. *Froſt converts mucilage into ſtarch; ſnow pancakes.* 4. *Starch from poiſonous plants is wholeſome, and may be ob-obtained by elutriation in times of ſcarcity.* IV. 1. Oils *may be ſeparated from bitter or narcotic materials, as the latter adhere to the mucilage.* V. 1. Sugar *formed by animal digeſtion.* 2. *By vegetable digeſtion. Sugar is nutritive, but may injure the teeth.* 3. *In many roots it is found ready prepared. May be ſeparated from mucilage by vinous ſpirit.* 4. *Exiſts in fruit formed from auſtere acids by a vegetable proceſs.* 5. *By heat; by bruiſing auſtere fruit; by drying malt. Sugar converted into ſtarch as well as ſtarch into ſugar. Uſe of ſugar to vegetables and animals.* VI. 1. Honey *guarded from inſects, and from rain.* 2. *Is of great importance. Is expoſed to the air. Is reabſorbed, and is nutritious.* 3. *Depredation of inſects on honey is injurious to vegetation. So is the honey-dew on trees. Bees alſo collect farina from flowers.* 4. *Why the honey is expoſed to the air. Is the food of the anthers and ſtigmas. Differs from ſugar by greater oxygenation. Benevolent economy of nature.* VII. 1. Wax *preſerves the anther-duſt from rain. How wet ſeaſons injure wheat.* 2. *Wax collected from ciſtus labdiniferus Bees much injure flowers.* 3. *Wax from candleberry-myrtle, and from croton ſebiferum. Preſerves or nouriſhes the immature ſeeds.* 4. *Wax depoſited on plants by inſects in China. Gives conſiſtence to oil.* VIII. 1. Turpentines and eſſential oils *are inadmiſſible with water. Moiſt parts of vegetables are ſooneſt deſtroyed by froſt. Evergreen trees contain moſt reſin. Defends the buds of deciduous plants.* 2. *Origin of petroleum, jet, amber, foſſil, coal.*

coal. 3 *Eſſential oils agreeable. Poiſonous. Preſerve wood from inſects. Uſed in Africa to poiſon weapons and pools of water.* 4. *Some eſſential oils burſt into flame with nitric acid. Produce a vapour round dictamnus fraxinella.* 5. *Elaſtic reſin. Bird-lime. Reſinous part of wheat-flower.* IX. 1. Bitter, narcotic, acrid juices, *for the defence of plants. Opium exiſts in the poppy-head, but not in the ſeed. So of hyoſcyamus. Narcotic matter in walnut-huſks not in the ſeed. Oil of bitter almonds taſteleſs.* 2. *Acrid, aſtringent, emetic, cathartic, and colouring matters. Many poiſonous plants in all our hedge-bottoms.* 3. *All theſe are ſtrongeſt in the hybernaculum or winter-lodge of plants. When oaks ſhould be decorticated.* X. 1. Acids *in fruit and leaves of various kinds. Convertible into ſugar. For the nutriment of ſeeds and buds. For the defence of the plants.*

I. 1. THE ſtructure of the glands of animals has not been yet fully aſcertained. They conſiſt of veſſels ſo minute as to exclude all coloured injections, except quickſilver; and the terminations of theſe veſſels are ſo tender, that the neceſſary weight of the quickſilver is liable to break them, and thus miſinform the obſerver, as mentioned in Sect. V. 4. Little more is therefore known of them than their effect, which is, that they ſecrete, that is ſeparate or produce, ſome fluid from the blood; as bile, ſalvia, urine, milk.

The veſſels of vegetables being ſtill more minute, and more rigid, the ſtructure of their glands is ſtill further removed from our diſcovery. Their effects are however as evident as thoſe of the glands of animals in the ſecretion or production of various fluids, which become ſolid, as their aqueous parts are abſorbed or exhaled, as mucilage, ſtarch, oil, ſugar, honey, wax, turpentines, eſſential oils, aromatics, bitters, narcotics, acrids, acids, and a variety of other materials, which fill our barns and granaries, and crowd the ſhops of the druggiſt.

2. There can be no doubt from what has been already ſaid of the circulation of vegetable juices, but that their various ſecretions muſt be effected in a ſimilar manner to that in animal bodies, which is believed

believed to be performed by the mouth of each gland being irritated into action by the ſtimulus of the blood, which is brought to it, and that by a kind of appetite it drinks up a part of the blood, and converts it to the fluid, which it ſecretes, which then becomes more or leſs ſolid, as its aqueous parts are abſorbed or exhaled.

II. 1. Mucilage is found in all parts of plants, as being an eſſential conſtituent of vegetable as of animal bodies; ſo when an extract is made by boiling plants in water, the mucilage makes the greateſt part of this extract. The mucilage called gum arabic is obtained from mimoſa nilotica, gum tragacanth exſudes from aſtragalus tragacantha, as a ſimilar gum exſudes from our cherry and plumb-trees; ſagoe is the pith of the lycas circinalis; and ſalep is the root of the orchis dried in an oven.

This mucilage ſeems to ſerve as nouriſhment to the plant; firſt, becauſe it is found in all vegetable as well as animal materials, as they decompoſe in dunghills; ſecondly, becauſe it forwards the growth of vegetables, when ſpread upon land; thirdly, becauſe thoſe trees, which bleed much gum, are weakened and frequently die; and laſtly, becauſe it is evidently laid up in the roots and ſeeds of various vegetables for the nouriſhment of the young plants. But in theſe it ſeems to undergo a change either in part chemical, or wholly by the digeſtive organs of the embryon plant, and is converted into ſugar, as in the tranſmutation of barley into malt; and as appears from the ſweet taſte of onions and potatoes, when boiled after they have germinated; and as ſugar abounds in the vernal ſap-juice of trees in ſuch quantity as to be capable of fermentation.

III. 1. Starch is another kind of mucilage, which differs from thoſe above mentioned in its property of not diſſolving in cold water, and can hence be eaſily ſeparated from them. If eight pounds of good raw potatoes be grated by means of a bread-grater into cold water; and, after well agitating the mixture, the ſtarch be ſuffered to ſubſide; and this ſtarch be then mixed with eight other pounds of

boiled potatoes, as good bread may be made as from the beſt wheat flour; as is affirmed by Monſ. Parmentier. From this it appears, that the quantity of ſtarch in potatoes and in wheat produces the principal difference of their reſpective flours. See Zoonomia, P. III. Article I. 2. 3. 4.

2. There is reaſon to believe that the mucilage during the growth of the plant is converted into ſtarch; and that this proceſs continues in grain ſome time after it is carried into the barn or granary, which occaſions old wheat to produce better flour for the baker; and old oats and old beans are univerſally believed to give more nouriſhment to horſes. I ſhall here add a conjecture, that I ſuppoſe the uſe of alum in making bread conſiſts in its coagulating the mucilage, and perhaps thus contributing to convert it into ſtarch; for the bakers mix it principally with new wheat; and affirm, that it makes the flour of new wheat equal to old.

Where much alum is mixed with bread, it may be diſtinguiſhed by the eye by a curious circumſtance, which is, that where two loaves have ſtuck together in the oven, they break from each other with a much ſmoother ſurface, where they had adhered, than thoſe loaves do which do not contain alum.

Add to this, that alum is alſo uſed by the London bakers for the purpoſe of clearing the river water, with which they are ſupplied, which is frequently muddy; and alſo for inſtantaneouſly deſtroying the volatile alkali, which is ſaid to exiſt in ſome London wells owing to the vicinity of dunghills. Theſe purpoſes it probably fulfils by coagulating the mucilage, which may occaſionally be mixed with the water and ſupport the mud in it; or by uniting with the calcareous earth, or with the volatile alkali which it may contain, and depoſiting the new-formed gypſum, or its own argillaceous baſe, the deſcent of which may carry down other impurities along with it, in the ſame manner as ſome muddy wines have been rendered fine, not by filtering them through ſand, as then the mud retained on the

ſurface

ſurface of the ſand ſoon prevents the deſcent of the wine through it, but by paſſing clean ſand in ſhowers by means of a riddle through the wine. Alum is ſaid to be uſed by the Chineſe for the purpoſe of cleaning the water of ſome ſtagnant reſervoirs; and when uſed in ſmall quantity may in all theſe reſpects be rather ſalutary than injurious to the bread of London.

Alum is ſaid alſo to be uſed in the manufactory of hair-powder, which ſhould conſiſt of ſtarch without mucilage, that the hair may not be glued together by the perſpirable matter of the head, or by an accidental ſhower. Whether it has the property of converting mucilage into ſtarch might be eaſily aſcertained by experiment, by waſhing in cold water alone one parcel of wheat flour, and waſhing a ſimilar parcel in a ſolution of alum in water.

3. Another conjecture I ſhall introduce here is, that it is probable that the action of froſt alſo may tend to coagulate mucilage, or convert it into ſtarch; for in the colder parts of Britain it is ſaid, that the corn never ripens till they have froſty nights; and I well remember many years ago having obſerved, that ſome book-binder's paſte made by boiling wheat-flour and water, after it had been frozen, ceaſed to cohere on being preſſed together, like the crumbs of ſome bread; and I have been told by ſome houſewives that their pancakes become much lighter if ſnow be mixed with the flour inſtead of water. See Sect. XVI. 3. 2.

4. Now as ſtarch is not ſoluble in cold water, the bitter and acrid particles of plants may be waſhed from it along with the mucilage; whence in times of ſcarcity this nouriſhing part of vegetables may be obtained by elutriation from poiſonous plants; on this circumſtance principally depends the wholeſomeneſs of the bread made from the caſſava, the acrid and poiſonous particles being previouſly waſhed away along with the mucilage. Monſ. Parmentier found the ſtarch from the root of the white bryony to contain no acrimony, and to be a wholeſome article of food.

IV. 1. Many ſeeds contain much oil mixed with their mucilage, or ſtarch; as nuts, almonds, flax-ſeed, rape-ſeed. Some of theſe contain alſo a bitter or narcotic material, as bitter almonds, apricot kernels, acorns, horſe-cheſnuts; which, as it adheres to the mucilage, may be ſeparated from the oil; as in expreſſing the oil from bitter almonds, which is as good as from ſweet ones. And it is probable by grating to powder, and waſhing in cold water, the kernels of acorns, and horſe-cheſnuts; or ſimply by preſſure, that a wholeſome ſtarch, or oil, might be procured. It is probable alſo that the roots of fern treated in this manner would afford good nouriſhment, as theſe are ſaid to be eaten by the inhabitants of New Zealand, and have been uſed in this country in times of great ſcarcity. And that the roots of nymphæa, water-lily, might be thus made into wholeſome bread, (which are ſaid to have been eaten in Egypt by Herodotus) and the roots of many other water-plants, which might thus become articles of ſubaquatic agriculture, which is an art much wanted in this country. See Sect. XI. 2. 5. and XVII. 2. 3.

V. 1. The digeſtive power of animals ſeems to be principally exerted in converting their food into ſugar; ſince the chyle of all animals reſembles milk, which contains much ſugar, and thence ſpontaneouſly runs into fermentation, which terminates in the production of acid, as in butter-milk. In Siberia the natives diſtil a ſpirituous and intoxicating liquor from milk thus fermented. Gmelin. In the diabetes there is reaſon to believe, that the chyle paſſes off into the bladder without being previouſly mixed with the blood; and there is a curious hiſtory of a patient in the infirmary at Stafford, who laboured under a diabetes, he eat and drank thrice as much as moſt moderate men, and from ſixteen to eighteen ounces, and even twenty ounces of coarſe ſugar was extracted for ſome time daily from his urine. Zoonomia, Vol. I. Sect. XXIX. 4.

2. In like manner the digeſtive powers of the young vegetable, with the chemical agents of heat and moiſture, convert the ſtarch or mucilage

mucilage of the root or ſeed into ſugar for its own nouriſhment; or they obtain ſugar ready prepared for them from ſome roots, as the beet-root; from many fruits, as grapes, pears, peaches; from the milk of cocoa-nuts, and from the ſap-juice of the ſugar-maple, birch, and many other trees. And thus it appears probable, that ſugar is the principal nutriment of both animal and vegetable beings. That it is the moſt nutritive part of vegetable ſubſtances is evinced by the well aſcertained fact, that the ſlaves in Jamaica grow fat in the ſugar-harveſt, though they endure at that time much more labour.

Yet there is an idle notion propagated amongſt the people that ſugar is unwholeſome; it is indeed probable, that the moſt nouriſhing materials may be taken more eaſily to exceſs, but not that it is therefore in general unwholeſome; at the ſame time it is probable, that ſome fruits preſerved in ſyrup, or ſweet-meats, may contribute to deſtroy the teeth; ſince, if the ſugar ſhould become in a ſtate of decompoſition, and the ſaccharine acid ſhould abound, it will diſſolve calcareous earth with greater avidity than any other acid.

3. In many plants ſugar is found ready prepared, as above mentioned; thus in the beet-root, the cryſtals of it may be diſcerned by a microſcope; and may be extracted from the mucilaginous matter of the root by diſſolving it in rectified ſpirit of wine; which will unite with ſugar but not with mucilage. In the joints of graſs and of corn it may be diſcovered by the taſte. In the manna-aſh, fraxinus ornus, the ſame ſaccharine matter is produced along with the eſſential ſalt of the plant, which is purgative; and in the ſugar-cane it abounds in ſuch large quantity as to contribute much to the nouriſhment of mankind. And,—and what?—Great God of Juſtice! grant, that it may ſoon be cultivated only by the hands of freedom, and may thence give happineſs to the labourer, as well as to the merchant and conſumer.

4. Another ſource of ſugar in vegetables is in the fruit, which in many plants changes from an auſtere acid to a ſaccharine acid, as in gooſeberries,

gooſeberries, apples, oranges. This change continues to proceed after the pears and apples, or oranges, are taken from the tree into our ſtorehouſes, but the fruit in this ſituation continues to ripen by a vegetable proceſs, as it can not be ſaid to be dead, becauſe it does not yet undergo fermentation or putrefaction, or other chemical diſſolution; and though its progreſs in ripening may be forwarded by warmth, yet it muſt ſtill be aſcribed to a vegetable proceſs; as the plants themſelves grow quicker when expoſed to additional heat.

5. But there are other means of increaſing or haſtening the ſaccharine proceſs in auſtere vegetable fruits, as by bruiſing them, or by baking them, both which muſt deſtroy the life of the fruit; thus when apples are bruiſed for the purpoſe of making cyder, they become ſweeter even in the act of bruiſing them; and many pears change from an auſtere to a ſweet juice ſimply by the heat of baking; and it is probable that malt acquires a great part, though not the whole of its ſaccharine matter, in the act of drying. This chemical production or increaſe of ſugar in vegetable juices is worth being further inquired into; ſince if ſugar could be made from its elements without the aſſiſtance of vegetation, ſuch abundant food might be ſupplied as might tenfold increaſe the number of mankind!

It is a curious circumſtance not yet ſufficiently underſtood, that not only ſtarch appears to be convertible into ſugar by the vegetable proceſs of digeſtion, as in the germination of farinaceous ſeeds; but that ſugar is capable of being converted into ſtarch, as appears in the ripening proceſs of ſome pears, which firſt contain a ſweet-juice, and afterwards become mealy.

The uſe of this ſaccharine matter of the fruit or ſap-juice in the vegetable economy is for the purpoſe of ſupplying the young ſeed or bud with nouriſhment to enable it the better to ſtrike its roots into the earth, and to elevate its leaves into the air, and thus by its quicker

quicker growth to rival its neighbours in their contentions for air, and light, and moiſture, which are neceſſary for its exiſtence.

VI. 1. The production of honey is perhaps one of the moſt important vegetable ſecretions, except that of the prolific farina from the anthers; and of the favilla, or new embryon, in the axilla of the leaf. The glands for this purpoſe, or certainly the reſervoirs, which contain the honey after it is ſecreted, are in many flowers viſible to the naked eye; as in crown-imperial, fritillaria imperialis; in monkſhood, aconitum napellus; hellebore, ranunculus. It is nevertheleſs probable, that this reſervoir of honey is frequently placed at a diſtance from the gland, which ſecretes it, for the purpoſe of preſerving it from inſects and from rain, which is often effected both by a very complicated apparatus, and by an acrid or poiſonous juice, as in the aconites and the hellebores above mentioned.

As the nectary, or honey-gland, always falls off along with the corol, and anthers, and ſtigmas; theſe appear to be parts or appendages to each other. The vegetable blood is expoſed to the air in the corol, and thus is oxygenated or prepared for the ſecretion of this important fluid; which I ſuppoſe is again reabſorbed, and ſupplies nouriſhment to the anthers and ſtigmas. Some acrid juices, and odorous particles, are at the ſame time ſecreted from the blood thus oxygenated in the corol; which ſeem deſigned as one kind of defence againſt the depredations of inſects on this important reſervoir of honey.

2. The univerſality of the production of honey in the vegetable world, and the very complicated apparatus, which nature has conſtructed in many flowers, as well as the acrid or deleterious juices ſhe has furniſhed thoſe flowers with, as in the aconite, to protect this honey from rain, and from the depredations of inſects, ſeem to imply, that this fluid is of very great importance in the vegetable economy; and alſo that it was neceſſary to expoſe it to the open air previous to its reabſorption into the vegetable veſſels.

In

In the animal ſyſtem the lacrymal gland ſeparates its fluid into the open air for the purpoſe of moiſtening the eye; of this fluid the part, which does not exhale, is abſorbed by the puncta lacrymalia, and carried into the noſtrils; but, as this is not a nutritive fluid, the analogy goes no further than its ſecretion into the open air, and its reabſorption into the ſyſtem. The perſpirable matter is another material ſecreted by animal glands into the external air, and is in part reabſorbed, and in part exhaled. And every other ſecreted fluid in the animal body is in part abſorbed again into the ſyſtem, even thoſe which are eſteemed excrementitious, as the urine; and others are probably entirely reabſorbed, as the bile, ſaliva, and gaſtric juice.

That the honey is a nutritious fluid, perhaps the moſt ſo of any vegetable production, appears from its great ſimilarity to ſugar, and from its affording ſuſtenance to ſuch numbers of inſects, which live upon it ſolely during ſummer, and lay it up for their winter proviſion. Theſe proofs of its nutritive nature evince the neceſſity of its reabſorption into the vegetable ſyſtem for ſome uſeful purpoſe.

3. It is probable, that the depredations of inſects on this nutritious fluid muſt be injurious to the products of vegetation; and would be much more ſo, but that the plants have either acquired means to defend their honey in part, or have learned to make more, than is abſolutely neceſſary for their own economy. Thus in ſilene, catch-fly, and in droſera, ſun-dew, it is defended by a viſcid juice from the attack of inſects; in hellebore, and in aconite, it is defended by the difficult paſſage to it, and by the acrid juice of the plant, if inſects ſhould endeavour to creep into the nectary, or pierce it with their proboſcis; and in polygonum melampyrum, buck-wheat, and in cacalia ſuaveolens, alpine colts-foot, there ſeems to be a ſuperabundant quantity of honey ſecreted, as thoſe flowers are perpetually loaded with bees and butterflies, inſomuch that at Kempton-land in Germany, Mr. Worlidge ſays, in his Myſteries of Huſbandry, Ch. IX. 3. that he ſaw forty great bee-hives filled with honey to the amount of

ſeventy pounds in each in one fortnight by their being placed near a large field of buck-wheat in flower; and I well remember being myſelf aſtoniſhed at ſeeing the number of bees on a field of buck-wheat in Shropſhire, as well as on a plant of cacalia ſuaveolens in my garden; from which the ſcent of honey could be perceived at many feet diſtance from the flower.

In the ſame manner the honey-dew on trees is very injurious to them; in which diſeaſe the nutritive fluid, the vegetable ſap-juice, ſeems to be exſuded by a retrograde motion of the cutaneous lymphatics, as in the ſweating ſickneſs of the laſt century, or is devoured by inſects, which pierce the lymphatic veſſels of the leaves at midſummer, feed on the vegetable chyle, and void it almoſt unchanged. See Sect. III. II. 8. and XIV. I. 7.

To prevent the depredation of inſects on honey a wealthy man in Italy is ſaid to have poiſoned his neighbour's bees, perhaps by mixing arſenic with honey, againſt which there is a flowery declamation in Quintillian, No. XIII. This mixture of honey and arſenic may be uſed with effect to poiſon flies, which ſometimes abound in pernicious multitudes; for the flies which frequent our houſes are liable to great thirſt, as is ſeen by their drinking any fluid, which is diffuſed on a table; whence if a ſlight ſolution of arſenic, with a little ſugar, be put thinly on a plate or two, and ſet on chimney-pieces or windows, the flies will eagerly drink it, and periſh almoſt inſtantly. It is probable that waſps might be thus deſtroyed in hot-houſes, if a little honey was added to attract them by its odour.

As the uſe of the wax is to preſerve the duſt of the anthers from moiſture, which would prematurely burſt them, the bees, which collect this for the conſtruction of the combs or cells, and collect the farina alſo probably for bee-bread for their larvæ or maggots, muſt on both theſe accounts alſo injure the vegetation of a country, where they too much abound.

4. It is not eaſy to conjecture, why it was neceſſary, that this ſecre-

tion of honey ſhould be expoſed to the open air in the nectary or honey-cup; for which purpoſe ſo great an apparatus for its defence from inſects and from ſhowers became neceſſary. This difficulty increaſes, when we recollect, that the ſugar in the joints of graſs, in the ſugar-cane, and in the roots of beets, and in ripe fruits, is produced without expoſure to the air. But on ſuppoſition of its ſupplying nutriment to the anthers and ſtigmas, it may thus acquire greater oxygenation for the purpoſe of producing the greater powers of amatorial ſenſibility, as mentioned in Sect. IV. 5. 6. and probably in this circumſtance alone differs from ſugar.

From this proviſion of honey for the male and female parts of flowers, and from the proviſions of ſugar, ſtarch, and mucilage, in the fruits, ſeeds, roots, and alburnum of plants, laid up for the nutriment of the young progeny; not only a very numerous claſs of inſects, but a great part of the larger animals, procure their food. Surely this muſt be called a wiſe proviſion of the Author of nature, as by theſe means innumerable animals enjoy life and pleaſure without producing pain to others; for the embryons in theſe buds, ſeeds, or eggs, as well as the nutriment laid up for them, are not yet endued with ſenſitive life. There is another ſource of nutriment provided for young animals, which ſtill further evinces the benevolence of the Author of nature; and that is the milk furniſhed by the mother to her offspring; by this beautiful contrivance the mother acquires pleaſure in parting with a nutritious fluid, and the offspring in receiving it!

VII. 1. The wax is another vegetable ſecretion produced with the fecundating duſt on the anthers of flowers, which in wet ſeaſons it preſerves from rain, to which it is impenetrable; for the farina, or fecundating duſt of plants, is liable to ſwell if expoſed to much moiſture, and to burſt its ſhell; and it either then becomes inert and ineffectual, or is waſhed away. Whence Mr. Wahlborn obſerves, that as wheat, rye, and many of the graſſes, and plantain, lift up their anthers on long filaments, and thus expoſe the encloſed fecundating

duſt to be waſhed away by the rains; a ſcarcity of corn is produced in wet ſummers; hence the neceſſity of a careful choice of ſeed-wheat; as that, which had not received the duſt of the anthers, will not grow, though it may appear well to the eye.

2. A ſubſtance ſimilar to this is ſaid to be collected from extenſive underwoods of the ciſtus labdaniferus in ſome eaſtern countries by this ſingular contrivance; long leathern thongs are tied to poles, and drawn over the flowers of theſe ſhrubs about noon, which thus collect the wax or reſin with part of the anther duſt, which adheres to the leathern thongs, and is occaſionally ſcraped off for uſe. Thus in ſome degree the depredation of the bee is imitated, except that ſhe loads her thighs only with the anther-duſt, which according to Mr. John Hunter conſtitutes the bee-bread found in hives for the ſupport of the larva or bee-maggot; and that ſhe ſwallows the wax for the conſtruction of her combs, as well as the honey for her winter provender; and thus every way injures the fecundity of flowers.

3. A wax in America is obtained from the myrica cerifera, candle-berry myrtle, the berries of which are boiled in water, and the wax ſeparates. The ſeeds of the croton ſebiferum are lodged in a kind of tallow; in both theſe plants the wax or tallow probably ſerves the purpoſe of preſerving the immature ſeeds from moiſture; or like the oil found in flax-ſeed, rape-ſeed, and in many kernels, they may conſtitute in part the nouriſhment of the new plant.

It muſt nevertheleſs be obſerved, that Mr. Sparman ſuſpects, that the green wax-like ſubſtance on the berries of the myrica cerifera is depoſited by inſects. Voyage to the Cape, V. I. p. 145. And Du Halde deſcribes a white wax made by inſects in great quantity round the branches of a tree in China, which is called Tong-tſin. Deſcript. of China, V. I. p. 230. And laſtly, ſir G. Staunton mentions a white wax on a plant in Cochin-China, which he believes to be ſtrewed on the plant in the form of white powder, which has this ſingular property, that one part of this white powder mixed with three parts of

olive oil made hot, gave it when cold the conſiſtence of bee's-wax. Embaſſy to China, Vol. I. p. 354.

VIII. 1. Turpentines or balſams, reſins, and eſſential oils, are analogous to the vegetable ſecretions laſt mentioned, in their being inadmiſſible with water. Thoſe vegetables, which contain in their veſſels the leaſt water, bear cold climates the beſt; becauſe when water is frozen, it occupies more ſpace than before; and hence burſts the bottles which contain it; in the ſame manner when any ſucculent vegetable is frozen, its veſſels become burſt or bruiſed by the expanſion of the ice, and the plant is deſtroyed; on this account thoſe parts of plants, which are the moſt juicy, as the laſt ſhoots of vines, are ſooneſt deſtroyed in winter. Hence many of the evergreen trees of this climate are replete with turpentine or reſin, which by occupying the place of ſo much water, contributes to their hardineſs. There is alſo a partial ſecretion of balſam or turpentine in many deciduous plants for the purpoſe of defending their buds during the winter, both from froſt and from wet, which is repelled by their balſamic varniſh, as on the buds of the populus tacamahacca.

2. The balſams and reſins of the ſhops are either extracted from the wood by fire, or exſude from wounds of the tree; thus what is called Venice turpentine is obtained from the larch by wounding the bark about two feet from the ground, and catching it as it exſudes. Sandarach is procured from common juniper, and incenſe from another juniper; and there is reaſon to believe that bitumen, or petroleum, with jet, amber, and all the foſſile coal in the world, owes its inflammable part to the recrements of deſtroyed foreſts of terebinthinate vegetables, ſo important to the preſent race of mankind has been this vegetable ſecretion!

3. The eſſential oils are ſometimes raiſed by diſtillation from balſams or reſins, as oil of turpentine; but are chiefly extracted from flowers; where their office has been to prevent the depredations of inſects; though many of them are ſo agreeable to the human ſenſe of

ſmell,

ſmell, when theſe eſſential oils are diſſolved or mixed with water in diſtillation, they have been called the ſpiritus rector of the plant, and conſtitute the odour of it, whether aromatic or fetid.

Some of theſe eſſential oils poſſeſs the moſt poiſonous qualities, as thoſe of lauro-ceraſus, and of tobacco; and are uſed by Indian nations for the purpoſe of poiſoning their weapons, which they cover like a varniſh. And hence ſome of the reſinous woods are ſaid never to be devoured by inſects, as the unperiſhable cheſts of cypreſs, in which the Egyptian mummies have been preſerved for ſo many ages, and the cedar in which black lead is incloſed for pencils.

The acrid poiſon of the large euphorbium of Africa exiſts in the oil of that plant; as M. Vaillant obſerves, that the natives ſometimes poiſon the waters with ſlicing this plant into them, and that the poiſonous oil ſwims upon the ſurface, and may thus be avoided by a careful drinker. This in a country where water is ſcarce, and generally in ſtagnant pools, may be readily effected; as a few ſpoonfuls of oil will cover a large ſheet of water, as it becomes diffuſed upon it without friction, as mentioned in Botanic Garden, Vol. I. Addition. Note XXIX.

4. Some of the eſſential oils are ſo inflammable as to burſt into a vehement flame on being mixed with nitrous acid, as oil of cloves; and even the ſmall quantity diffuſed in the air round the dictamnus fraxinella will take fire on a ſtill evening at the approach of a lighted candle.

5. With theſe ſhould be arranged the elaſtic reſin called Caoutchouc, which is ſaid to exſude from a tree in Guaiana, called Iatropha elaſtica, by M. de la Borde, phyſician at Cayenne. A ſimilar elaſtic reſin is ſaid to be obtained from a plant in Madagaſcar, called Finguere, a kind of wild fig-tree, according to Abbe Rochon; and the bird-lime extracted from the bark of the hollies of our climate ſeems to be a ſimilar material; as like the caoutchouc it becomes ſoft by heat, and is impenetrable by water, but ſoluble in ether. Another elaſtic ſubſtance,

ſtance, which is inſoluble in water, is procured from wheat by long maſtication, or by agitating the flour of it in water; which has been ſaid to approach to animal matter, and is believed to be the moſt nutritious part of that aliment, and was once much talked of, or ſold under the name of alimentary powder for the nouriſhment of marching armies.

IX. 1. The bitter, narcotic, and acrid juices of plants are ſecreted by their glands for the defence of the vegetable from the depredation of inſects and of larger animals. Opium is found in the leaf, ſtalk, and head of the poppy, but not in the ſeeds. A ſimilar narcotic quality exiſts in the leaf and ſtem of hyoſcyamus, henbane, but not in the ſeeds. An acrid juice exiſts in huſks of walnuts, and in the pellicle, or ſkin, of the kernel; but not in the lobes, or nutritious part of it. Theſe ſeem to have been excluded from the ſeed, leſt they might have been injurious to the tender organs of digeſtion of the embryon plant. In ſome ſeeds, however, there is a bitter quality, but which refuſes to mix with the oleagenous part; as the oil expreſſed from bitter almonds is as taſteleſs as that from the ſweet almonds.

2. Other vegetables poſſeſs glands adapted to the ſecretion of various fluids more or leſs aromatic, acrid, or aſtringent; as the herb of water-creſs, the root of horſe-radiſh, the ſeeds of muſtard, the flowers of roſes, the fruit of quince, and the bark of oak. To theſe ſhould be added thoſe which have emetic and cathartic qualities; and other vegetable preparations, which are uſed in the arts of dying, tanning, varniſhing; and which ſupply the ſhops of the druggiſt with medicines and with poiſons. All which deleterious juices ſeem to have been produced for the protection of the plant againſt its enemies, as appears by the number of poiſonous vegetables, which are ſeen in all our hedge-bottoms and commons, as hyoſcyamus, cynogloſſum, jacobæa, and common nettles; which neither inſects nor quadrupeds devour, and which are therefore of no known uſe but to themſelves; and

poſſeſs

poſſeſs a ſafer armour in this panapoly of poiſon, than the thorns of hollies, briars, and gooſeberries.

3. As the bitter, narcotic, acrid, and terebinthinate, as well as the farinaceous, oily, and ſaccharine matters, are ſecreted in ſummer from the vegetable blood, and reſerved for the nutrition and defence of the new buds and bulbs, they are in this climate generally found more concentrated in the hybernaculum, or winter-lodge of plants, before the new ſap is raiſed by the umbilical or abſorbent veſſels in the ſpring. Hence roots and barks, as well as fruits and ſeeds, are beſt collected in autumn, or in winter, for the purpoſes of medicine or of other arts.

Thus the bark of oaks ſhould be taken off for the uſe of the tanner in the winter, or in early ſpring, before the leaves pullulate, as then a great part of its aſtringent or bitter juices is reabſorbed, and carried to the new foliage along with the ſaccharine ſap-juice, which has been depoſited in the cells of the alburnum or ſap-wood. But as the barks of trees become looſer, and much more eaſily detached from the wood, when the ſap-juice riſes in the ſpring, this is the beſt time for debarking them; but the naked bole and branches ſhould ſtand till autumn, till the ſaccharine matter collected in the alburnum has been expended in unfolding the new leaves; otherwiſe it will ſoon ferment and putrefy; and the ſap-wood will thus quickly decay by what is termed the dry-rot of timber, as mentioned in Sect. III. 2. 3.

X. 1. The acids produced by vegetable ſecretion have of late been much ſubjected to chemical inquiry, and have been found to be ſo numerous, that they have been named from the vegetables, or parts of vegetables, from which they have been extracted; as the gallic acid, malic acid, oxalic acid. Many unripe fruits contain an auſtere acid, which is gradually converted into ſugar by vegetable or chemical proceſſes for the nutriment of their ſeeds, as deſcribed in No. V. 4. of this ſection. In other plants it exiſts in the foot-ſtalks of the leaves,

as

as in rheum, rhubarb; or in the leaves themſelves, as in oxalis, ſorrel; in theſe ſituations alſo I ſuppoſe it is ſecreted both for the defence of thoſe plants from the depredation of inſects and of larger animals; and alſo for the purpoſe of its being converted into a ſaccharine juice by the digeſtion of the young bud in the boſom of the leaf.

SECT.

SECT. VII.

THE ORGANS OF REPRODUCTION OF VEGETABLES.

The theory of Linneus for vegetable reproduction too mechanical, and without analogy. Every new fluid is ſecreted by glands, as the liquor amnii and albumen ovi. So alſo is the favilla vitæ, or living entity. I. 1. Lateral progeny. *The new bud is ſecreted in the axilla of the leaf, and requires no female apparatus. It adheres to its parent not by inoſculation of veſſels, but reſembles the chick in the egg.* 2. *Difference of the chick and fetus. Their nutriment and oxygenation. The embryon may be ſeen in the buds of horſe-cheſnut. It is a paternal progeny.* 3. *This lateral offſpring reſembles the parent. Not univerſally ſo. More perfect than ſeeds. Buds of diœcious plants bear ſimilar ſexes. The lateral progeny degenerates from hereditary diſeaſes. Whence curled potatoes, blighted ſtrawberries, bears fruit at the ſame time, and of the ſame kind. Plants live longer if prevented from flowering. Art of producing double hyacinths, ranunculus, tulips.* 4. *Lateral progeny of corallines and ſea-anemonies. Polypi are all males. Wires of knot graſs like the joints of the tape-worm, which are all males.* 5. *Aphis, viviparous and oviparous like vegetable generation.* 6. *Veſſels of the bud and leaf do not inoſculate. Viviparous, oviparous, and paternal generation.* 7. *Leaves on twigs like the progeny of volvox. But in ſome twigs the pith is divided, and the buds ſucceſſive. Hermaphrodite generation. Buds from every part of the caudex. Thoſe from below the graft are like the ſtock. Find numerous uteri like eggs and ſpawn. Paternal generation preceded ſexual generation. The laſt more excellent.* II. 1. Sexual progeny. *Seeds before impregnation. Eggs before impregnation. Seed-embryon ſuſpended by oppoſite points like the cicatricula of the egg.* 2. *Seed-bud and flower. Stamens and ſtigmas. Males bend to females, and females to males. Style of ſpartium bends round like a French horn. Onaniſm of epilobium. Male flowers of valliſneria ſwim to the females. Flowers with long filaments injured by rain. Submarine plants project a liquor.* 3. *The petals are reſpiratory organs.* 4. *Honey is the food of the anthers and ſtigma; which like butterflies propagate and die.*

5. *Seeds are formed and nouriſhed by the umbilical veſſels previous to fecundation, or by the bractes or floral-leaves. Diſperſion of ſeeds by plumes, by hooks, by twiſted awns. Creep on the ground. Hygrometer of a geranium ſeed.* 6. *Sexual generation the chef d'œuvre of nature. Produces variety of ſpecies. Mixed breed of cabbage. Mixed breeds of beans. An apple ſour on one ſide. Vegetable mules.* 7. *Animal mules. They externally reſemble the male, internally the female. Mule from the horſe and female aſs. From the mare and male aſs. From Spaniſh rams and Swediſh ewes, and the contrary. From the goat of angora. Ram without horns.* 8. *How to improve the varieties of fruits and flowers, and produce new ones. Many plants were originally mules, and many animals. How to produce new animal monſters, both quadrupeds and fiſh, by the method of Spallanzani. Mules more frequent in antient times.* III. Vegetable generation. 1. *A triple tree by ingraftment. The caudex of each bud is triple. Lateral or paternal mules. Conferva fontinalis ſplits.* 2. *The lateral propagation of the polypus. The hydra ſtentorea ſplits. Two halves of different polypi unite. So the vegetable filaments or caudexes in ingrafted trees.* 3. *Triple lateral mule. Each part of the triple caudex is produced from that in its vicinity, not from the plumula of the bud.* 4. *Worms multiplied by dividing them. So the caudexes of the buds of trees.* 5. *The parts of the long caudexes of trees are ſecreted from the adjoining parts of the parent caudexes, and combine beneath the cuticle of the tree. Every part of a compound caudex can produce a new bud, reſembling the part of the compound ſtock, where it riſes. Lateral mules conſiſt of parts from three or four parents. Could there be a threefold ſexual mule?* 6. *Power of attraction. Aptitude to be attracted. Chemical combinations by ſingle attraction. By double affinity.* 7. *Union of animated bodies with inanimate matter, as in ſwallowing food. In abſorption by the lacteals. Vitality of the blood. Fibrils with nutritive appetencies. Molecules with nutritive propenſities.* 8. *Fibrils with formative appetencies, and molecules with formative propenſities ſecreted beneath the cuticle of trees, and coaleſce. Hunger and love, thirſt, ſuckling children, they reciprocally ſtimulate and embrace each other.* 9. *Great ſecret of nature. Formative or nutritive particles in the blood more than neceſſary. Secreted by numerous glands. Arranged under the cuticle of trees. Acquire new appetencies, and produce new parts.* 10. *In ſexual generation they are ſecreted by two glands only. Thoſe of the anther and pericarp unite in the matrix.* 11. *Without formative molecules as well as formative fibrils*

there could be no mules, or any reſemblance to the mother. The new doctrine of threefold vegetable mules applied to animal generation. 12. *Concluſion.*

THE theory of Linneus in reſpect of the reproduction of vegetables maintains, that the internal medullary part muſt be joined with the external or cortical part of the plant for the purpoſe of producing a new one. If the medulla be ſo vigorous as to burſt through its containing veſſels, and thus mix with the cortical part, a bud is produced either on the branches or roots of vegetables; otherwiſe the medulla is extended, till it terminates in the piſtillum, or female part of the flower; and the cortical part is likewiſe elongated, till it terminates in the anthers, or male part of the flower; and then the fecundating duſt from the latter being joined to the prolific juices of the former, produces the ſeeds or new plants; at the ſame time the inner rind is extended into the corol or petal, and the outer bark into the calyx.

After the ſeeds are thus produced, the parent bud dies; and in this reſpect the buds bear a very great analogy to thoſe annual inſects, which change from their caterpillar or larva-forms, putting forth painted wings and organs of reproduction, and after depoſing their eggs ceaſe to exiſt. See the account of the vegetable kingdom by Linneus, prefixed to the ſyſtem of vegetables tranſlated by a botanical ſociety at Lichfield. Leigh and Sotheby, London.

However ſimple and ingenious the firſt part of this theory may appear, in which the medulla is ſuppoſed to extend itſelf, till it burſts the incloſing or cortical part, and joining with that produces a new bud; yet it ſeems too mechanical for a living organized ſyſtem; and ſo totally different from any thing we know of ſexual production either in animals or flowers, as not readily to ſatisfy a reaſoning mind.

Every new fluid or ſolid produced in the organic ſyſtem of vegetable or animal bodies is ſecreted from their blood, as the various fluids

of bile, ſaliva, tears, in animals; and thoſe of gum, reſin, ſugar, in vegetables. Amongſt theſe are the juices which conſtitute the nutritious fluid of the amnios in the uterus of viviparous animals, or that of the albumen of the egg in oviparous ones. And laſty, the flavilla vitæ, the new ſpark of being, or living entity, is alſo ſecreted from the blood of male animals by adapted glands to be received into a proper nidus, and nouriſhed by the female.

I. LATERAL PROGENY.

1. As the leaf with its petiole, or foot-ſtalk, and its caudex down the bark of a tree, with its radicle beneath, conſtitutes an individual plant; and the bud in its boſom ſucceeds, and is evidently produced by it; it may be concluded from the ſtrongeſt analogy that this new progeny is ſecreted from a gland or glands of the parent; and that, as it adheres to the parent, it requires no female apparatus for its reception, nouriſhment, or oxygenation.

I was formerly induced to believe, that there was a communication of blood, or inoſculation of veſſels between the parent leaf, and the new bud in its boſom, as expreſſed in Zoonomia, Sect. XXXIX. 2. 2. and that this conſtituted the difference between paternal geſtation and maternal geſtation. But that the veſſels between the new bud and the parent leaf-bud do not inoſculate may be well ſeen by taking away the bark of the foot-ſtalk of a leaf, and of the new bud in its boſom; as the remains of the arteries of the late leaf, as well as the rudiment of the new bud, are ſeen to terminate in the alburnum, or to penetrate the pith, but without any apparent communication; and I therefore ſuſpect, that the embryon bud is not ſerved with vegetable blood from the veſſels of the parent, but that it acquires both nutriment and oxygenation much in the ſame manner as the chick in the egg. See Sect. III. 1. 5.

2. The condition of the chick in the egg differs from that of the fetus

fetus in the womb of viviparous animals in the whole of its nutriment being at firſt provided for it, which conſiſts of the albumen, or white of the egg, which is contained in cells, and is of different degrees of conſiſtency, that which is moſt fluid being firſt conſumed; whereas the liquor amnii, or nutriment of the fetus in utero, is gradually ſecreted by adapted glands from the blood of the mother, as it is wanted.

Another difference between the condition of the chick and of the fetus conſiſts in the manner, by which their blood acquires its neceſſary oxygenation. In the fetus this is done by means of the placental veſſels, whoſe extremities are inſerted into the blood-veſſels of the uterus, and receive oxygen through their moiſt membranes from the paſſing currents of the mother's blood, as deſcribed in Zoonomia, Vol. I. Sect. XXXVIII. Whereas in the egg after a few days incubation a membrane is ſeen, which includes the albumen, and ſpreads the extremities of its fine blood-veſſels on the moiſt membrane, which covers the air at the broad end of the egg; which air is occaſionally renewed, as would appear by its being ſeen ſo eaſily to paſs through the ſhell, when an egg is covered with water in the exhauſted receiver of an air-pump.

The condition of the embryon bud, when the parent leaf-bud dies, I conceive to be ſimilar to that of the chick in the egg, when that is ſeparated from its parent. Each of them has at this time a reſervoir of nutriment provided for it; that of the chick conſiſts of the albumen, or white of the egg above mentioned; and that of the bud conſiſts of mucilage and ſugar, which are depoſited in the alburnum or ſap-wood, or in the roots of the plant. And ſecondly, I conceive that the extremities of a fine ſyſtem of veſſels belonging to the bud may terminate on the moiſt membrane, which covers the horizontal air-veſſels deſcribed in Sect. III. 2. 6. as thoſe on the chorion of the chick terminate on the air-bag of the egg, and thus acquire the neceſſary oxygenation of their vegetable blood.

This

This analogy between the vegetable and animal fetus in reſpect to their production, nouriſhment, and oxygenation, is as forcible in ſo obſcure a ſubject, as it is curious; and may in large buds, as of the horſe-cheſnut, be almoſt ſeen by the naked eye. If with a penknife the remaining rudiment of the laſt year's leaf, and of the new bud in its boſom, be cut away ſlice by ſlice, the ſeven ribs of the laſt year's leaf will be ſeen to have ariſen from the pith in ſeven diſtinct points, making a curve; and the new bud to have been produced in their center, and to have pierced the alburnum and bark, and grown without the aſſiſtance of a mother.

And laſtly, by in part cutting, and in part tearing, the pith and alburnum from the bottom of a new leaf-ſtalk of horſe-cheſnut about the middle of May, an oval prominence may be ſeen in the internal part of the leaf-ſtalk, which fills up a ſpace between the veſſels of the bottom of the leaf-ſtalk and thoſe of the new bud, and ſeems to connect them by its extremities, and to preſs on the pith beneath it. From this apparent gland I conjecture that the now living fibres, or animalcules, are probably ſecreted, which form the new bud adhering to the pith, and nouriſhed by the parent leaf; that thus a paternal progeny is produced without the aſſiſtance of a mother.

3. This paternal offspring of vegetables in their buds and bulbs is attended with a very curious circumſtance; and that is, that they exactly reſemble their parents, as is obſervable in grafting fruit-trees, and in propagating flower-roots; whereas the ſeminal offspring of plants, being generated by two parents, and certainly ſupplied with nutriment by the mother, is liable to perpetual variation. This alſo in the vegetable claſs dioecia, where the male flowers are produced on one tree, and the females on another, the buds of the male trees uniformly produce either male flowers, or other buds ſimilar to themſelves; and the buds of the female trees either produce female flowers, or other buds ſimilar to themſelves; whereas the ſeeds of theſe trees produce either male or female plants. See Sect. III. 2. 1.

This

This ſimilarity of buds and bulbs to their parents is to be underſtood only to exiſt after the maturity of the plant, that is after it has produced a ſexual offſpring in flowers and ſeeds; for a bulb, as of a tulip, and a bud of a fruit-tree, when firſt raiſed from their ſeeds, are very ſmall, but produce one or more improved bulbs, or improved buds annually, for ſome years; which differ from their parent bulbs or buds in the ſize, form, and colour of their leaves, till it arrives at its maturity, or acquires the power of generating a ſexual progeny; from whence it appears, that the leaf-buds of thoſe trees, and the leaf-bulbs of thoſe roots, which have acquired their puberty, if it may be ſo called; that is, their power of generating flowers, are a more perfect progeny than the ſeeds of thoſe plants, as theſe latter, when ſeparated from their parent either by tranſplantation or by ingrafting, can immediately produce ſeeds, or a ſexual progeny; but the buds from many ſeeds are ſome years before they can produce ſeeds. The ſame is probably true of many annual or biennial plants, as of wheat; which produce many ſucceſſive buds upon each other previous to the flower-bud, as appears by the joints of the ſtem; all which may be conſidered as individual plants growing on each other like the annual ſucceſſion of the buds of trees.

Another curious occurrence in this lateral production of vegetables by their buds has been lately publiſhed by Mr. Knight in the Phil. Tranſ. for the year 1795, who obſerves, that thoſe apple-trees, which have been continually propagated for above a century by ingrafting, are now become ſo diſeaſed by canker, or otherwiſe, that though the fruit continues of the ſame flavour, the trees are not worth propagating; as theſe grafts, though tranſplanted into other trees, he eſteems to be ſtill an elongation of the original tree, and muſt feel the effect of age like the tree they were taken from. If this idea ſhould prove true on further examination, there is reaſon to ſuſpect the ſame may occur in the too long propagation of plants from bulbs and wires, as potatoes and ſtrawberries, which may have occaſioned the curled tops of potatoes,

toes, and the black blight in the flowers of the hautbois ſtrawberry, which ſome have aſcribed to its only bearing male flowers; the cure of which muſt ariſe from our applying to other varieties more lately derived from a ſeminal offſpring.

This degeneracy of trees or perennial herbaceous plants propagated by buds or root-ſcions is not I think to be aſcribed ſimply to the age of the original ſeedling-tree, becauſe each ſucceſſive generation of buds or bulbs are as diſtinct from the parent, as the generation by ſeeds. But as the lateral progeny of vegetables have no ſource of improvement after they have arrived at their maturity, but are liable like other plants and animals to injuries from food and climate, which injuries produce hereditary diſeaſes, it is to this circumſtance that their degeneracy ought rather to be aſcribed; whereas the ſexual progeny of vegetables are liable to improvement by the intermixture of the individuals of the ſame, or even of different ſpecies to counteract the effects of hereditary diſeaſes.

Another curious ſimilarity which buds bear to their parent tree is alſo obſerved by Mr. Knight, Phil. Tranſ. for 1795. Part II. p. 292. "Cuttings from ſeedling apple-trees of two years old were inſerted on ſtocks of twenty years old, and in a bearing ſtate; but theſe have now been grafted nine years; and, though they have been frequently tranſplanted to check their growth, they have not yet produced a ſingle bloſſom. I have ſince grafted ſome very old trees with cuttings from ſeedling apple-trees of five years old. Their growth has been extremely rapid, and there appears no probability that their time of producing fruit will be accelerated, or that their health will be injured by the great age of the ſtocks. A ſeedling apple-tree uſually bears fruit in thirteen or fourteen years; and I therefore conclude, that I have to wait for a bloſſom, till the trees, from which the grafts were taken, attain that age; though I have reaſon to believe from the form of their buds that they will be extremely prolific. Every cutting therefore taken from the apple, and probably from

every other tree, will be affected by the ſtate of the parent ſtock. If that be too young to produce fruit, it will grow with vigour, but will not bloſſom; and if it be too old, it will immediately produce fruit, but will never make a healthy tree, and conſequently never anſwer the intention of the planter.

"The durability of the apple and pear I have long ſuſpected to be different in different varieties; but that none of either would vegetate with vigour much, if at all, beyond the life of the parent ſtock, provided that died from mere old age. The oak is much more long-lived in the north of Europe than with us, though the timber is leſs durable; the climate of this country, being colder than its native one, may in the ſame way add to the durability of the elm; which may poſſibly be further increaſed by its not producing ſeeds in this climate; as the life of many annuals may be increaſed to twice its natural period, if not more, by preventing their ſeeding."

It is obſerved above, that the firſt bulb of a tulip raiſed from ſeed produces a more perfect bulb annually for five or ſix years, and perhaps more than one leſs perfect ones, before it acquires the power of generating ſeeds. Now when this period arrives, if the ſeed-ſtem be pinched off, I ſuppoſe that the next year's bulb or bulbs will become more vigorous or luxuriant, and if this be continued for three or four years I ſuſpect the double flowers, which are perhaps owing to a more luxuriant growth, may be formed; and that in this, with ſuperfluous nouriſhment by manure, warmth, and moiſture, conſiſts the art of obtaining hyacinths, ranunculus, and ſometimes tulips, with ſuch wonderful multiplication of petals or nectaries. See Sect. XIX. 3. 1.

4. The analogy, which exiſts between this lateral production of vegetables and that of ſome tribes of inſects, is worth inveſtigation. 1. This paternal or lateral generation of plants, which conſtitutes the buds on the ſtems of trees, and the ſcions on their roots, which continue to adhere to them, are ſo far reſembled by the branching inſects, which form the corals or corallines; and by many other ſea-

animals, as the ſea anemonies, which are ſaid to adhere to the ſhores, or ſubmarine earth, by one extremity, while they pullulate, or ſpread out by the other into living ramifications of unmeaſurable lengths.

Thoſe who have attended to the habits of the polypus, which is found in the ſtagnant water of our ditches in July, affirm, that the young ones branch out from the ſide of the parent like the buds of trees; and after a time ſeparate themſelves from them. This is ſo analogous to the manner in which the buds of trees appear to be produced, that theſe polypi may be conſidered as all male animals, producing embryons, which require no mother to ſupply them with a nidus, or with nutriment and oxygenation.

Secondly, this paternal or lateral vegetable progeny is beautifully ſeen in the wires of knot-graſs, polygonum aviculare; and in thoſe of ſtrawberries, fragaria veſca; and in the roots of potatoes. The lateral generation of theſe plants by wires, while each new plant is thus chained to its parent, and continues to put forth another and another, as the wire creeps onward on or beneath the ground, is exactly reſembled by the tape-worm, or tænia, ſo often found in the bowels, ſtretching itſelf in a chain quite from the ſtomach to the rectum. Linneus aſſerts, "that it grows old at one extremity, while it continues to generate young ones at the other, proceeding ad infinitum, like a root of graſs. The ſeparate joints are called gourd-worms, and propagate new joints like the parent without end, each joint being furniſhed with its proper mouth and organs of digeſtion." Syſtema Naturæ, vermes, tenia. In this animal there evidently appears a power of reproduction without any maternal apparatus for the purpoſe of ſupplying nutriment and oxygenation to the embryon, as it remains attached to its father till its maturity, and in this reſpect exactly reſembles the lateral generation of vegetables.

5. This ſubject of the lateral production of vegetables from male parents without the intervention of a female is further reſembled by the innumerable progeny of the aphis, which riſes from an egg in the ſpring,

ſpring, as a vegetable riſes from a ſeed, and produces a viviparous offspring for many generations like the ſucceſſive buds of a ſeedling apple-tree, or of a ſeedling tulip; and then it generates both males and females, which copulate and depoſit eggs, like the anthers and ſtigmas of flowers, and their conſequent ſeeds; which at length appear on ſeedling apple-trees and on ſeedling tulips; as is further ſpoken of in Sect. IX. 2. 7. and XIV. 1. 6.

6. Whence I conclude, that in ſexual viviparous generation the new entity, or embryon, is ſecreted by the male, and received into a nidus prepared for it by the female, and nouriſhed by fluids ſecreted into the uterus, as they are required, which is probably owing to the ſtimulus of the fetus againſt the ſides of it; that in ſexual oviparous generation a reſervoir of nutriment is prepared, and incloſed in the egg, previous to the reception of the embryon, which is ſecreted by the male, and depoſited in this reſervor of nutriment; becauſe the fetus in theſe animals is to be ſeparated from the parent before its due maturity; and the egg, in which it is incloſed, may be conſidered as an uterus, or womb, ſeparated from the mother. And laſtly, that in paternal or male generation the new entity, or embryon, is as certainly ſecreted from a gland of the male, but probably remains in an adapted reſervoir belonging to this gland, correſpondent to the veſiculæ ſeminales of moſt viviparous animals, and that here it exiſts like the cicatricula in the egg, and has a reſervoir of nutriment prepared for it like that in the egg to ſupport it; when the paternal leaf-bud by its death is ſeparated from it in the autumn, as the egg is ſeparated from its living mother.

7. The production of buds in the axilla of every leaf may thus be eaſily conceived, as the new buds are furniſhed with their caudexes or bark-filaments over thoſe of their dead parents, which ſhoot out root-fibres beneath in the enſuing ſpring, and that I ſuppoſe both in deciduous plants and in evergreens; as in the latter alſo I believe the parent leaf-bud annually falls off, though not by the immediate in-

fluence of the cold of autumn. But how long a twig or ſcion of leaves, as in the vine or willow, ſucceed each other, ſome producing embryon buds in their boſoms before others become expanded, is not eaſy to underſtand; but the embryons of all theſe new leaves, though not of the buds in their boſoms, probably exiſted in the paternal womb, though in different degrees of maturity, which accords with the obſervations of ſome naturaliſts on the ſucceſſive generations of the volvox globator, which Linneus aſſerts to be diaphanous, and that it carries within itſelf ſons and grandſons to the fifth generation, but which are probably living fetuſes produced by the father, of different degrees of maturity, and to be detruded at different periods of time like the unimpregnated eggs of various ſizes, which are found in poultry. See Zoonomia, Vol. I. Sect. XXXIX. 2. and Linnei Syſtem. Naturæ. Vermes. Volvox.

In ſome trees however, as in the vine, vitis, and in many herbaceous plants, as in wheat, ſouthiſtle, teaſel, triticum, ſonchus, dypſacus, each ſucceſſive joint of the plant is evidently an individual vegetable being; becauſe the pith, which conſtitutes the brain or ſpinal marrow of each individual, terminates at every joint by a diviſion, as ſpoken of in Sect I. 8. whence in theſe vegetables every ſucceſſive joint appears to be produced by that beneath it; whereas where there is no diviſion of the pith, the twig ſeems to be ſimply an elongation of the caudex of the leaf-bud, like the wires of ſtrawberries and other creeping plants.

It ſhould nevertheleſs be added, that there are many hermaphrodite inſects, as ſhell-ſnails and dew-worms, which contain both male and female organs of generation; and as they are perpetually ſeen to copulate with each other, it is believed, that they can not impregnate themſelves. Now it may be conceived, that the buds of trees poſſeſs both male and female organs of generation, and that they can impregnate themſelves, and that thus the new buds might be termed an hermaphrodite offspring rather than a paternal one. This would however

however produce a confuſion of terms, as the eggs of ſnails and of worms, as mentioned above, are properly an hermaphrodite off-ſpring.

Another circumſtance occurs in this paternal generation, which differs from that of thoſe hermaphrodite inſects above alluded to, which is, that though in vegetables the new embryon is generally produced in the boſom of the leaf-ſtalk, which is believed to be its parent; yet new buds are occaſionally protruded from almoſt any part of the bark, when the ſummit of a branch is taken off, or the ſide branches of a tree, ſo as to admit light and air, and a ſupply of more nutriment; whence it would ſeem, that though hermaphrodite inſects poſſeſs but one male and one female apparatus for the production and reception of the new entity or embryon, yet that in paternal generation the prolific fluid is occaſionally ſecreted in any part of the caudex of each individual bud from its ſummit on the branch of a tree to its termination in the root; and that wherever a proper nidus can be found, which is ſupplied with nutriment, and expoſed to light and air, that there the new embryon can adhere and grow; although this occurs moſt conveniently, and thence moſt frequently, in the boſom of the leaf-ſtalk, where the prolific fluid is probably firſt ſecreted, and the nutriment moſt copiouſly ſupplied from the vegetable blood newly oxygenated in the leaf. In this I ſuppoſe to conſiſt the great difference between paternal and ſexual generation; and that this mode of reproduction forms an exception to the general axiom of the great Harvey, "all things from eggs."

The exiſtence of a power of generation in every part of the caudex of a vegetable bud from the ſummit to the root is not only ſhewn by the new buds, which grow on the trunks of trees, which were felled in the ſpring, but alſo from a curious circumſtance which occurs in ingrafted trees; which is, that whenever after many years any new buds or ſcions grow from the ſtock beneath the graft, it is always ſimilar to the parent ſtock, and not to the ingrafted ſcion; which

ſhews, that this new bud was generated in the old ſtock, and not that it was owing to an abſorption and depoſition of a prolific fluid ſecreted in any part of the ingrafted head. It muſt however be remembered, that the caudex of each bud extends from the leaf-ſtalk to the root, whether it be a ſimple caudex as in a ſeedling tree, or a compound one as in a grafted tree; and that the generation of new buds in perennial herbaceous plants exiſts in every part of the broad caudex on the root, as it does here in every part of the long caudex on the trunk. Nothing known in the animal world reſembles this univerſality of the generative faculty throughout almoſt the whole of an individual vegetable being, except the number of new polypi ſaid to ariſe at the ſame time from different parts of the ſame individual animal.

Wherever the new vegetable embryons are ſecreted, they alſo find a ſituation or uterus, where they can adhere and be nouriſhed to almoſt any number; which however is not unſupported by ſome analogy even in viviparous animals; as there have been many inſtances of extra-uterine fetuſes, which have attached or inſerted their veſſels into the peritoneum, or on the viſcera of the mother, in the ſame manner as they naturally attach or inſert them into the ſides of the true uterus. And in reſpect to the number of uteri produced we may recollect the number of eggs, and of fiſh-ſpawn, or frog-ſpawn, or of ſeeds, which may all be termed ſo many diſtinct uteri, as they contain every thing, which is found in the uteri of viviparous animals.

The aphis, and probably many other inſects, poſſeſs both the ſolitary and ſexual mode of propagation, as is poſſeſſed by moſt vegetables; but the polypus and tenia, and hydra ſtentorea, and volvox, appear only to be reproduced by the ſolitary or lateral generation; and it is probable that the truffle amongſt vegetables, and ſome ſubmarine plants, and others of the claſs cryptogomia, whoſe ſeeds have not been yet diſcovered, may ſtill be only propagated by the lateral

lateral mode of reproduction, as is well obſerved in an ingenious work by a lady of very accurate botanic knowledge, called "Botanic Dialogues, deſigned for the uſe of ſchools," one volume octavo, Johnſon, London; but which may be ſtrongly recommended to the adult in botany as containing much uſeful information agreeably imparted.

This curious ſubject of lateral or ſolitary generation is well worthy more accurate inveſtigation, as it is the ſimpleſt, and was probably the firſt mode of reproduction which exiſted; and if any accurate knowledge can ever be acquired of animal generation, it will poſſibly occur from a more nice attention to the production of the buds and bulbs of vegetables! which is further ſpoken of in Sect. IX. 2 and 3. At the ſame time it muſt be obſerved, that the ſexual reproduction is the chef d'ouvre, the maſter-piece of nature, as by the paternal or lateral reproduction the ſame ſpecies only are propagated ad infinitum; whereas by the ſexual mode of reproduction a countleſs variety of animals are introduced into the world, and much pleaſure is afforded to thoſe, which already exiſt in it.

II. SEXUAL PROGENY.

1. We come now to the ſeminal mode of the production of vegetables, which originates from the congreſs of the male and female parts of flowers, and may be therefore termed the ſexual or amatorial progeny of vegetation.

From the accurate experiments and obſervations of Spallanzani it appears, that in the Spartium Junceum, ruſh-broom, the very minute ſeeds were diſcerned in the pod at leaſt twenty days before the flower is in full bloom; that is, twenty days before fecundation. At this time alſo the powder of the anthers was viſible, but glued faſt to their ſummits. The ſeeds however at this time, and for ten days after the bloſſom had fallen off, appeared to conſiſt of a gelatinous

ſubſtance. On the eleventh day after the falling of the bloſſom the ſeeds became heart ſhaped, with the baſis attached by an appendage to the pod, and a white point at the apex; this white point was on preſſure found to be a cavity including a drop of liquor.

On the twenty-fifth day the cavity, which at firſt appeared at the apex, was much enlarged, and ſtill full of liquor; it alſo contained a very ſmall ſemi-tranſparent body of a yellowiſh colour, gelatinous, and fixed by its two oppoſite ends to the ſides of the cavity.

In a month the ſeed was much enlarged, and its ſhape changed from a heart to a kidney; the little body contained in the cavity was increaſed in bulk, and was leſs tranſparent, and gelatinous, but there yet appeared no organization.

On the fortieth day the cavity now grown larger was quite filled with the body, which was covered with a thin membrane; after this membrane was removed, the body appeared of a bright green, and was eaſily divided by the point of a needle into two portions, which manifeſtly formed the two lobes; and within theſe attached to the lower part the exceedingly ſmall plantule was eaſily perceived.

The foregoing obſervations evince, 1. That the ſeeds exiſt in the ovarium many days before fecundation. 2. That they remain for ſome time ſolid, and then a cavity containing a liquid is formed in them. 3. That after fecundation a body begins to appear within the cavity fixed by two points to the ſides, which in proceſs of time proves to be two lobes containing a plantule. 4. That the ripe ſeed conſiſts of two lobes adhering to a plantule, and ſurrounded by a thin membrane, which is itſelf covered with a huſk or cuticle. Spallanzani's Diſſertations, Vol. II. p. 253.

The analogy between ſeeds and eggs has long been obſerved, and is confirmed by the mode of their production. The egg is known to be formed within the hen long before its impregnation. C. F. Wolf aſſerts, that the yolk of the egg is nouriſhed by the veſſels of the mother, and that it has from thoſe its arterial and venous branches; but

but that after impregnation theſe veſſels gradually become impervious and obliterated; and that new ones are produced from the fetus, and diſperſed into the yolk. Haller's Phyſiol. Tom. VIII. p. 94. The young ſeed after fecundation I ſuppoſe is nouriſhed in a ſimilar manner from the gelatinous liquor, which is previouſly depoſited for that purpoſe; the uterus of the plant producing or ſecreting it into a reſervoir or amnios, in which the embryon is lodged; and that the young embryon is furniſhed with veſſels to abſorb a part of it, as in the very early ſtate of the embryon in the egg.

Another curious analogy ſeems to exiſt between the embryon of the ſeed and of the egg in their mode of ſuſpenſion. The cicatricula of the egg reſts on the yolk, which is ſuſpended by two points, called chalazæ, ſomewhat above its center of gravity; whence, however the egg is moved, this embryon is always kept upwards, probably the better to receive the warmth of the mother during incubation. The ſeed-embryon ſeems to be ſupported in the ſame manner by the above relation of Spallanzani by two points, and may thus receive a greater warmth from the ſummer ſun.

2. The ſeeds are thus produced in their unimpregnated ſtate in the vegetable uterus, and nouriſhed by the flower-bud, which was formed in the deciduous trees of this climate during the preceding ſummer, and which now puts forth the bractes, or floral-leaves, for the oxygenation of its blood; and protrudes its roots and abſorbents into the ground from the lower part of its caudex, for the purpoſe of acquiring nouriſhment; and on the ſummit of this ſexual apparatus are at the ſame time produced the corol and nectaries of the flower, with the ſtamens, and ſtigmas, which are evidently deſigned to give fecundation to the vegetable ſeeds, or eggs, previouſly depoſited in the pericarp or uterus; becauſe, as ſoon as theſe are impregnated, the corol and nectaries, with the ſtamens, and ſtigmas, fall off and diſappear.

The anthers have been proved by many experiments to be neceſſary to the fecundation of the vegetable ſeeds by the farina, or duſt,

which they diſperſe, and which adheres to the moiſt ſtigma on the ſummit of the ſtyle or pericarp. The amatorial attachment between theſe ſtigmas and the anthers on the ſummits of the ſtamens has attracted the notice of all botaniſts. In many flowers the anthers or males bend into contact with the ſtigmas or females, as in kalmia, fritillaria perſica, parnaſſia, cactus, and ciſtus. In the kalmia the ten ſtamens lie round the piſtil, like the radii of a wheel, and each anther is concealed in a nich of the corol to protect it from cold and moiſture; theſe anthers riſe ſeparately from their niches, and approach the ſtigma of the piſtil for a time, and then recede to their former ſituations. In the fritillaria perſica the ſix ſtamens are of equal lengths, and the anthers lie at a diſtance from the piſtil; of theſe three alternate ones approach firſt, and ſurround the female; and when theſe decline, the other three approach; and in parnaſſia the males alternately approach and recede from the female; and laſtly in the moſt beautiful flowers of cactus grandiflorus, and of ciſtus labdaniferus, where the males are very numerous, ſome of them are perpetually bent into contact with the female; and as they recede, others advance.

In other flowers the females bend into contact with the males, as in nigella, epilobium, ſpartium, collinſonia. In nigella, devil in the buſh, the females are very tall compared to the males, and bending down over them in a circle, give the flower ſome reſemblance to a regal crown. The female of the epilobium anguſtifolium, willow-herb, bends down amongſt the males for ſeveral days, and becomes upright again when impregnated. In the ſpartium ſcoparium, common broom, the males or ſtamens are in two ſets, one ſet riſing a quarter of an inch above the other. The upper ſet does not arrive at their maturity ſo ſoon as the lower; and the ſtigma, or head of the female, is produced amongſt the upper or immature ſet. But as ſoon as the piſtil grows tall enough to burſt open the keel-leaf, or head of the flower, it bends itſelf round in an inſtant like a French horn,

and

and inſerts its head, or ſtigma, amongſt the lower or mature ſet of males. The piſtil or female then continues to grow in length; and in a few days the ſtigma arrives again amongſt the upper ſet, by the time they become mature. This wonderful contrivance is readily ſeen by opening the keel-leaf of the flowers of broom, before they burſt ſpontaneouſly. And laſtly, in the collinſonia the two males widely diverging from each other, the female bends herſelf into contact firſt with one of them; and after a day or two leaves this, and applies herſelf to the other; the anther of which was not mature ſo ſoon as the former. See Sect. VIII. 8. of this work.

Dr. Peſchier of Geneva thinks, he has diſcountenanced this idea of amatorial ſenſibility of vegetables by two experiments, which are related in Journal de Phyſique de Lametherie, T. II. p. 343. One of theſe conſiſted of his tying down the ſtigma of epilobium anguſtifolium, and yet in due time the anthers burſt and ſhed their pollen, and thus committed a kind of vegetable Onaniſm; and alſo that he caſtrated the ſtamens of this flower, and yet the ſtigma opened and aroſe, as if the anthers had been preſent. The other experiment conſiſted in his confining a branch of barbery, berberis, in a glaſs, and ſubjecting the ſtamina of the flowers to the vapour of nitrous acid, which by this ſtimulus aroſe from their petals to the ſtigma, and after a few minutes again retired to their petals. Both theſe experiments rather ſeem to confirm than to enfeeble the analogy between plants and animals; as the amatorial motions of theſe flowers were thus produced by internal or external ſtimuli, as in the healthy or diſeaſed ſtates of animals.

Another mode, in which the prolific duſt is diſperſed, is by the burſting of the anther, and its conſequent diffuſion in air, either ſo as to make a cloud near the females, which exiſt in the ſame flower, or on the ſame plant, which is the moſt uſual manner; or by its being carried by the winds to a greater diſtance, as in the flowers of the claſs monœcia, or one houſe. So in urtica, nettle, the male

flowers are ſeparate from the female, and the anthers are ſeen in fair weather to burſt with force, and to diſcharge their duſt, which hovers about the plant like a cloud.

In plants of the claſs diœcia, or two houſes, the fecundating farina is carried to the diſtance of many miles by the winds, as has been proved by the impregnation of ſome female date trees, which were at a great diſtance from the male ones. And the male flowers themſelves of vallisneria are carried many miles down the rivers, which it inhabits, to the female ones. This plant has its roots at the bottom of the Rhone; the flowers of the female plant float on the ſurface of the water, and are furniſhed with an elaſtic ſpiral ſtalk, which extends or contracts, as the water riſes and falls. The flowers of the male plant are produced under water, and as ſoon as their farina, or duſt, is mature, they detach themſelves from the plant, and riſe to the ſurface, continue to flouriſh, and are wafted by the air, or borne by the currents, to the female flowers. In this reſembling thoſe tribes of inſects, where the males at certain ſeaſons acquire wings, but not the females, as ants, coccus, lampyris, phalæna, brumata, lichanella. See vallisneria in the Families of Plants, tranſlated from Linneus. Johnſon, London.

The plants, which grow in the air, are frequently injured in wet ſeaſons by the moiſture occaſioning the cells of the anthers, which contain the fecundating farina, to burſt, and to ſhed it on the ground. To which a ſcarcity of the quantity of wheat, or an imperfection of its fecundating quality, and the uſtilago, or ſmut, have rationally been aſcribed, as its anthers are expoſed on long filaments to the weather. On this account many flowers cloſe their corols before rain, and the aquatic plants of rivers perform their impregnations in the air. But M. Bonnet remarks another method of the diſperſion of the fecundating influence of ſome marine plants, in which the male organ does not project a fine powder, but a liquor, which forms a perceptible cloud in the water; and adds, that the male ſalamander darts his

ſemen into the water, where it forms a whitiſh cloud, which is afterwards received by the ſwollen anus of the female, and ſhe becomes impregnated. Nor is this vegetable impregnation in water unanalogous to other animal impregnations, as the ſpawn of frogs and of fiſh is delivered from the female before it is fecundated; and its fecundation is ſeen to ſucceed in water; and Spallanzani found, that the ſeminal fluid even of dogs, as well as of frogs, retained its prolific quality when diluted with much water. Bonnet's Œuvres Philoſ. in a letter to Spallanzani.

3. The other parts, which riſe on the edge of the pericarp, and expand themſelves before the impregnation of the ſeed, are the corol and nectaries. The former of theſe has been ſhewn to be a reſpiratory organ for the purpoſe of oxygenating the blood to a greater degree than in the green foliage, as it is there expoſed to the air beneath a finer pellicle, and acquires variety of colours. See Sect. IV. 5. 1. to which may be added, that as the corol in helleborus niger, Chriſtmas roſe, changes after the fecundation of the ſeed into a calyx, loſing its white colour, and becoming green. So in many flowers the calyx falls off along with the corol; in theſe it ſhould be eſteemed a part of or appendage to the corol; whereas thoſe calyxes, which are permanent after the corol falls off, are properly parts of the pericarp or vegetable uterus.

4. The nectary, or honey-cup, is evidently an appendage to the corol, and is the reſervoir of the honey, which is ſecreted by an appropriate gland from the blood after its oxygenation in the corol, as mentioned in Sect. IV. 5. 5. and is abſorbed for nutriment by the ſexual parts of the flower. This purpoſe however has as yet eſcaped the reſearches of philoſophical botaniſts. M. Pontedera believes it deſigned to lubricate the vegetable uterus. (Anthолog. p. 49.) Others have ſuppoſed, that the honey, when reabſorbed, might ſerve the purpoſe of the liquor amnii, or white of an egg, as a nutriment for the young embryon, or fecundated ſeed, in its early ſtate of exiſtence.

But

But as the nectary is found equally general in male flowers as in female ones, and as the young embryon, or ſeed, grows before the petals and nectary are expanded, and after they fall off; theſe ſeem to be inſurmountable objections to both the above-mentioned opinions.

In many tribes of inſects, as the ſilk-worm, and perhaps in all the moths and butterflies, the male and female parents die, as ſoon as the eggs are impregnated and excluded, the eggs remaining to be perfected and hatched at ſome future time. The ſame thing happens to the male and female parts of flowers; the anthers and filaments, which conſtitute the male parts of the flower, and the ſtigma and ſtyle, which conſtitute the ſenſitive or amatorial organ of the female part of the flower, fall off and die, as ſoon as the ſeeds are impregnated, and along with theſe the petals and nectary. Now the moths and butterflies above mentioned, as ſoon as they acquire the paſſion and the apparatus for the reproduction of their ſpecies, loſe the power of feeding upon leaves, as they did before, and become nouriſhed by what?—by honey alone.

Hence we acquire a ſtrong analogy for the uſe of the nectary, or ſecretion of honey, in the vegetable economy; which is, that the male parts of flowers, and the female parts, as ſoon as they leave their fetus-ſtate, expanding their petals, (which conſtitute their lungs) become ſenſible to the paſſion, and gain the apparatus, for the reproduction of their ſpecies; and are fed and nouriſhed with honey like the inſects above deſcribed; and that hence the nectary begins its office of producing honey, and dies or ceaſes to produce honey, at the ſame time with the birth and death of the anthers and the ſtigmas; which, whether exiſting in the ſame or in different flowers, are ſeparate and diſtinct animated beings.

Previous to this time the anthers with their filaments, and the ſtigmas with their ſtyles, are in their fetus-ſtate ſuſtained in ſome plants by their umbilical veſſels, like the unexpanded leaf-buds, as in

colchicum autumnale, and daphne mezereon; and in other plants by the bractes, or floral-leaves, as in rhubarb, which are expanded long before the opening of the flower; the ſeeds at the ſame time exiſting in the vegetable womb yet unimpregnated, and the duſt yet unripe in the cells of the anthers. After this period the petals become expanded, which have been ſhewn to conſtitute the lungs of the flower; the umbilical veſſels, which before nouriſhed the anthers and the ſtigmas, coaleſce, or ceaſe to nouriſh them; and they acquire blood more oxygenated by the air, obtain the paſſion and power of reproduction, are ſenſible to heat, and light, and moiſture, and to mechanic ſtimulus, and become in reality inſects fed with honey; ſimilar in every reſpect except that all of them yet known but the male flowers of vallisneria, continue attached to the plant, on which they are produced.

So water inſects, as the gnat, and amphibious animals, as the tadpole, acquire new aerial lungs, when they leave their infant ſtate for that of puberty. And the numerous tribes of caterpillars are fed upon the common juices of vegetables found in their leaves, till they acquire the organs of reproduction; and then they feed on honey, all I believe except the ſilk-worm, which in this country takes no nouriſhment after it becomes a butterfly. And the larva or maggot of the bee, according to the obſervations of Mr. Hunter, is fed with raw vegetable matter, called bee-bread, which is collected from the anthers of flowers, and laid up in cells for that purpoſe, till the maggot becomes a winged bee, acquires greater ſenſibility, and is fed with honey. Phil. Tranſ. 1792.

Laſtly, though the filaments and ſtyle, as well as the corolla and nectary, belong to the ſexual organs of vegetables; yet it is the anthers alone of the ſtamina, and ſtigmas alone of the piſtilla, which poſſeſs the power, and I ſuppoſe the paſſion of reproduction, as appears from the mutilated filaments of many flowers, as of curcuma, of linum or flax of this country, of gratiola, and hemlock-leaved geranium,

ranium, which have half their ſtamina unterminated by anthers, and in conſequence produce no prolific farina. And ſecondly, from the florets, which form the rays of the flowers of the order fruſtraneous polygamy of the claſs ſyngeneſia, as the ſun-flower, which are furniſhed with a ſtyle only, and no ſtigma, and are thence barren. There is alſo a ſtyle without a ſtigma in the whole order of diœcia gynandria, the male flowers of which are thence barren, and ſhews the neceſſity of the exiſtence of the ſtigma to the fecundation of the vegetable uterus, probably owing to its amatorial action in conveying the living principle to the included ſeeds like the fallopian tubes of the animal womb.

5. The ſeeds are produced in the pericarp, and at firſt acquire nutriment by the umbilical veſſels previous to their fecundation, like the unexpanded leaf-buds; and then by the caudex down the bark with its radicles, which is oxygenated by the bractes, or floral-leaves, as ſoon as theſe are expanded, they afterwards become in one day impregnated in ſome flowers, as in the oenothera, cactus grandiflorus, and ciſtus; and the corol or petals, with the ſtamens and ſtigmas, and nectaries, wither and fall off. In other flowers many days elapſe before the various cells of ſeeds are fecundated, and theſe more animated parts of ſexual reproduction periſh. But in all caſes the ſeeds remain in the pericarp or uterus after fecundation as before it, except in thoſe plants, which are called proliferus, as the polygonum viviparum, and magical onions, which immediately begin to vegetate; in all other plants the ſeed either ſleeps till the enſuing ſpring, as in the colchicum and hamamelis; or they continue to grow to maturity, and to be nouriſhed in the pericarp by the blood of the parent flower-bud, which is oxygenated in the bractes or floral-leaves, till they become perfected like eggs, and fall on the ground, or are otherwiſe diſperſed, for the purpoſe of taking root in the earth.

Whence it appears, that in the ſexual reproduction of vegetables the amatorial organ is diſtinct from the uterus, as is probably the caſe in

in animals; which in female quadrupeds would ſeem to ſleep after impregnation during the time of geſtation and lacteſcence, and afterwards to revive; whereas this amatorial organ in vegetable flowers periſhes, when the uterus is impregnated, along with the male organs, neither of which are any longer of uſe in theſe annual beings.

The various methods, which nature has employed for the diſperſion of ſeeds, are worth the attention of the farmer and gardener, both for the purpoſe of preventing the growth of noxious ſeeds, and of collecting the profitable ones. The pericarp of ſome plants burſts with ſudden violence, when the ſeed is mature, and diſperſes it to conſiderable diſtance; as that of wood-ſorrel, oxalis acetocalla; and of impatiens, touch me not. The ſeeds of many plants of the claſs ſyngeneſia are furniſhed with a plume, by which admirable mechaniſm they are diſſeminated by the winds far from their parent ſtem, and look like a ſhuttlecock, as they fly. Other ſeeds are diſſeminated by animals; of theſe ſome attach themſelves to their hair or feathers by a gluten, as miſletoe; others by hooks, as clivers, galium aperine; burdock, arctium lappa; hound's-tongue, cynogloſſum. Others are ſwallowed whole for the ſake of the fruit, and voided uninjured, as the hawthorn, cratægus, juniper, and ſome graſſes. And the ſeeds of aquatic plants, and of thoſe which grow on the banks of rivers, are carried many miles by the currents into which they fall.

Other ſeeds are ſeparated from each other, and diſperſed by the twiſting of the awn at the ſummit of them, when moiſtened by rain, as a black oat, avena fatua, with hairy awns, which ſeems to crawl like an inſect when moiſtened; geranium alſo, and barley; and as this happens in wet weather, the moiſt ground is then fit to receive and nouriſh them. The awns of the geranium have been uſed as hygrometers by ſticking the baſe of the ſeed into a cork for a pedeſtal, and marking diviſions on a paper circle beneath it; and the awn of barley is furniſhed with ſtiff points, which, like the teeth of a ſaw, are all turned towards one end of it; as this long awn lies upon the ground,

it extends itſelf in the moiſt air of night, and puſhes forward the barley-corn, which it adheres to; in the day it ſhortens as it dries; and as theſe points prevent it from receding, it draws up its pointed end; and thus, creeping like a worm, will travel many feet from the parent ſtem; and may thus be uſed as a travelling hygrometer, when laid on a cloth on the floor, like the automaton of Mr. Edgeworth, deſcribed in Botanic Garden, article Impatiens, Vol. II.

6. The formation of the organs for ſexual generation, in contradiſtinction to thoſe for lateral generation, in vegetables, and in ſome animals, as the polypus, the tænia, and the volvox, ſeems the chef d'œuvre, the maſter-piece of nature, as appears from many flying inſects, as moths and butterflies, which ſeem to undergo a general change of their forms ſolely for the purpoſe of ſexual reproduction; and in all other animals theſe organs are not complete till the maturity of the creature; whereas the lateral generation commences with the infancy of the germ or bud, as on the roots of young herbs, and on the ſtems of infant trees.

There ſeems nevertheleſs to be one circumſtance, in which the ſolitary generation of the buds of plants, when the plants are at their maturity, is ſuperior to the ſexual generation by ſeeds. This conſiſts in the progeny of the former being more perfect than that of the latter, in reſpect to the power of the reproduction of their ſpecies. Thus in many plants, as in tulips and apple-trees, the young vegetable from the ſeed produces other bulbs, or buds, for ſome years, which ſeem annually to improve, till at length they acquire a puberty, if it may be ſo called, and become furniſhed with ſexual organs for the purpoſe of ſeminal reproduction; whereas the leaf-buds, or leaf-bulbs, of the apple-tree and tulip during their firſt years produce other leaf-buds, or leaf-bulbs, rather more perfect than their parents; and when theſe bulbs, and buds, arrive at their puberty, or maturity, ſo as to be capable of ſexual generation, their new bulbs and new buds alſo, if taken from their dying parents, and tranſplanted or ingrafted, or left

adhering to them, are immediately capable of producing flowers, and a conſequent ſeminal progeny.

As the progeny by lateral generation ſo exactly reſembles the parent ſtock, it follows, that though any new variety, or improvement, may be thus continued for a century or two, as in grafted fruit-trees, yet that no new variety or improvement can be obtained by this mode of generation; though ſome hereditary diſeaſes, as the canker, are believed to ariſe in ingrafted trees, which have long been propagated by lateral generation, as explained in No. 1. 3. of this Section.

But from the ſexual, or amatorial, generation of plants new varieties, or improvements, are frequently obtained; as many of the young plants from ſeeds are diſſimilar to the parent, and ſome of them ſuperior to the parent in the qualities we wiſh to poſſeſs; which is another proof that the anthers and ſtigmas of plants are animated beings, different from the green foliage of the tree on which they grow; as they produce varieties in the form of their offſpring like ſexual animals, which buds do not.

Beſides the production of different, and ſometimes more excellent, varieties in the ſpecies of vegetables from ſeeds, another advantage occurs from ſexual generation, which is the production of new ſpecies of plants, or mules, by ſhedding the fecundating duſt of ſome flowers on the ſtigmas of others of a different ſpecies, though generally of the ſame genus.

A mule cabbage is deſcribed in the Bath Agriculture, Vol. I. Art. 4, which is ſaid to fatten a beaſt ſix weeks ſooner than turneps. It is there ſaid, "that the ſort of cabbage principally raiſed is the tallow-loaf or drum-head cabbage; but it being too tender to bear ſharp froſt, I planted ſome of this ſort and the common purple-cabbage uſed for pickling, (it being the hardieſt I am acquainted with) alternately; and when the ſeed-pods were perfectly formed, I cut down the purple, and left the other for ſeed. This had the deſired effect, and produced a mixt ſtock of a deep green colour with purple

veins, retaining the ſize of the drum head, and acquiring the hardineſs of the purple."

In another curious paper of the Bath Society, Vol. V. p. 38, Mr. Wimpey relates, that he planted a field with garden-beans in rows about three feet aſunder in the following order, mazagan, white-bloſſom, long-podded, Sandwich-toker, and Windſor-beans. The mazagan and white-bloſſom were thraſhed firſt, when to his great ſurpriſe he found many new ſpecies of beans; thoſe from the mazagan were mottled black and white; the white-bloſſoms were brown and yellow inſtead of their natural black; and they were both much larger than uſual. See Sect. XVI. 4. of this work.

There is an apple deſcribed in Bradley's work, which is ſaid to have one ſide of it a ſweet fruit, which boils ſoft, and the other ſide a ſour fruit, which boils hard. This Mr. Bradley ſo long ago as the year 1721 ingeniouſly aſcribes to the farina of one of theſe apples impregnating the other; which would ſeem the more probable, if we conſider, that each diviſion of an apple is a ſeparate womb, and may therefore have a ſeparate impregnation, like puppies of different kinds in one litter. The ſame is ſaid to have occurred in oranges and lemons, and grapes of different colours.

Vegetable mules are ſaid to be numerous, and, like the mules of the animal kingdom, not always to continue their ſpecies by ſeed. There is an account of a curious mule from the antirrhinum linaria, toad-flax, in the Amœnit. Academ. V. I. No. 3. and many hybrid plants are deſcribed in No. 32. The urtica alienata is an evergreen plant, which appears to be a nettle from the male flowers, and a pellitory (parietaria) from the female ones and the fruit, and is hence between both. Murray, Syſt. Veg. Amonſt the Engliſh indigenous plants, the veronica hybryda, mule ſpeedwell, is ſuppoſed to have originated from the officinal one, and the ſpiked one; and the Sibthorpia Europæa to have for its parents the golden ſaxifrage and marſh pennywort. Pulteney's View of Linneus, p. 253.

There

There is another vegetable fact publiſhed by M. Koelruter, which he calls " a complete metamorphoſis of one natural ſpecies of plants into another;" which ſhews, that in ſeeds as well as in buds, the embryon proceeds from the male parent, though the form of the ſubſequent mature plant is in part dependent on the female. M. Koelruter impregnated a ſtigma of the nicotiana ruſtica with the farina of the nicotiana paniculata, and obtained prolific ſeeds from it. With the plants, which ſprung from theſe ſeeds, he repeated the experiment, impregnating their piſtilla with the farina of the nicotiana paniculata. As the mule plants, which he thus produced, were prolific, he continued to impregnate them for many generations with the farina of the nicotiana paniculata, and they became more and more like the male parent, till he at length obtained ſix plants in every reſpect perfectly ſimilar to the nicotiana paniculata, and in no reſpect reſembling their female parent the nicotiana ruſtica. Blumenback on Generation.

Mr. Graberg, Mr. Schreber, and Mr. Ramſtrom, ſeem of opinion, that the internal ſtructure or parts of fructification in mule plants reſemble the female parent; but that the habit or external ſtructure reſembles the male parent. See treatiſes under the above names in Vol. VI. Amœnit. Academic.

7. Something ſimilar to this ſeems to obtain in mixing the breeds of the ſame ſpecies of animals, and in animal mules, which may be worth the attention of the grazier. The mule produced from a horſe and a ſhe aſs reſembles the horſe externally with his ears, mane, and tail; but with the nature, or manners of an aſs. But the hinnus, or creature produced from a male aſs and a mare, reſembles the father externally in ſtature, aſh-colour, and the black croſs on his ſhoulders, but with the nature or manners of a horſe. The breed from Spaniſh rams and Swediſh ewes reſembled the Spaniſh ſheep in wool, ſtature, and external form; but was as hardy as the Swediſh ſheep; and the contrary occurred in the breeds which were produced from Swediſh

rams

rams and Spaniſh ewes. The offspring from the male goat of Angora and the Swediſh female goat had long ſoft camel's hair; but that from the male Swediſh goat, and the female one of Angora, had no improvement of their wool. An Engliſh ram without horns, and a Swediſh horned ewe, produced ſheep without horns. Amœn. Acad. Vol. VI. p. 13.

8. From theſe circumſtances it appears, that not only new varieties may be procured from the ſeminal offspring of plants; where thoſe from the lateral offspring become diſeaſed by age, as the cankered apple-grafts, and perhaps the curled potatoes, and barren ſtrawberries; but that more curious or uſeful fruits or flowers may be obtained by ſhedding the farina of ſome valuable plant on the ſtigma of another variety of the ſame ſpecies, as of two different but equally excellent apple-trees, or tulip-flowers, hyacinths, anemonies, and geraniums. And thirdly, that mules may be produced by a mixture of different ſpecies of plants, and perhaps of different genera; as of pines and melons; grapes and gooſeberries; oranges and apples; apricots and nectarines; nuts and acorns; which may be afterwards propagated by the lateral progeny, if not by the ſeminal one.

The facility of generating vegetable mules ſeems forcibly to have ſtruck the great Linneus; who in the preface to his natural orders of plants at the end of his Genera Plantarum thinks, that about ſixty vegetables were at firſt created correſponding with his natural orders. That a mixture of theſe orders amongſt themſelves produced the genera; that a mixture of the genera amongſt themſelves produced the ſpecies; and that a mixture of the ſpecies produced the varieties, which he believes to accord with the general progreſs of nature "*from ſimpler things to the more compound.*"

In the ſame manner it may be ſuppoſed, that many of the preſent ſpecies of animals were originally mules produced by a mixture of animals of different genera; and that all ſuch mules, as had perfect organs of reproduction, continued their ſpecies. But as theſe organs

ſeem

ſeem to be the chef d'œuvre of nature, as above remarked, they often become imperfect in the generation of mules, and the ſpecies then becomes extinct; as it could not be propagated by ſexual generation, it is poſſible, that many new kinds of mules, which might be uſeful for labour, or by their milk or wool, or for food, might ſtill be produced by the method of Spallanzani; who diluted the ſeminal fluid of a dog with much warm water, and by injecting it fecundated a bitch, and produced puppies like the dog.

Thus new animal combinations might poſſibly be generated numerous as the fabled monſters of antiquity; as between the ram and the female goat; the ſtag and the cow; the horſe and the doe; the bull and the mare; boar and bitch; dog and ſow. And ſecondly, as Spallanzani diluted the ſeminal fluid of a male frog with water, and fecundated ſome female ſpawn with it, and produced perfect tadpoles, there is reaſon to conclude, that new combinations of fiſh might thus be generated, and people our rivers with aquatic monſters. And laſtly, that it is not impoſſible, as ſome philoſopher has already ſuppoſed, if Spallanzani ſhould continue his experiments, that ſome beautiful productions might be generated between the vegetable and animal kingdoms, like the eaſtern fable of the roſe and nightingale, and which might be propagated by lateral or paternal, though not by ſexual or ſeminal generation.

The claſſic reader will here be reminded of the metamorphoſes of Ovid, of gods turned into bulls and ſwans, men into frogs and partridges, ladies into trees and flowers, of ſphinxes, griffins, dragons, mermaids, centaurs, and minataurs; Paſiphae and her bull; Leda and her ſwan; Arethuſa and her fiſh-god Alpheus, and conclude that mules in early times were more frequent than at preſent, which occaſioned the poets and the prieſts of antiquity to invent ſo many fabulous monſters, and impoſe them on the credulity of mankind.

III. VEGETABLE GENERATION.

1. The intelligent reader is become, I hope, by this time ſo much intereſted in the further inveſtigation of the circumſtances attending the lateral and ſexual generation of vegetables, that he will not be diſpleaſed with the continuance of the ſubject for a few more pages, ſo agreeable from its novelty, and ſo important from its future application to animal reproduction.

If a ſcion of a nonpareil apple be ingrafted on a crab-ſtock, and a golden pippin be ingrafted on the nonpareil, what happens? The caudex of the bud of the golden pippin conſiſts of its proper abſorbent veſſels, arteries, and veins, till it reaches down to the nonpareil-ſtock; and then the continuation of its caudex downwards conſiſts of veſſels ſimilar to thoſe of the nonpareil; when its caudex deſcends ſtill lower, it conſiſts of veſſels ſimilar to thoſe of the crab-ſtock.

The truth of this is ſhewn by two circumſtances; firſt, becauſe the lower parts of this compound tree will occaſionally put forth buds ſimilar to the original ſtock. And ſecondly, becauſe in ſome ingrafted trees, where a quick-growing ſcion has been inſerted into a ſtock of ſlower growth, as is often ſeen in old cherry-trees, the upper part of the trunk of the tree has become of almoſt double the diameter of the lower part; both which occurrences ſhew, that the lower part of the trunk of the tree continues to be of the ſame kind, though it muſt have been ſo repeatedly covered over with new circles of wood, bark, and cuticle.

Now as the caudex of each bud, which paſſes the whole length of the trunk of the tree, and forms a communication from the upper part, or plumula, to the lower part, or radicle, muſt conſiſt in theſe doubly ingrafted trees of three different kinds of caudexes, reſembling thoſe of the different ſtocks or ſcions; we acquire a knowledge of what may be termed a lateral or paternal mule, in contradiſtinction

to a ſexual mule. For as in theſe trees thus combined by ingraftment every bud has the upper parts of its caudex that of a golden pippin, the middle part of it that of a nonpareil, of the lower part of it that of a crab; if theſe caudexes, which conſtitute the filaments of the bark, could be ſeparated intire from the tree with their plumules and radicles, they would exhibit ſo many lateral or paternal mules, conſiſting of the connected parts of their three parents; the plumula belonging to the upper parent, and the radicle to the lower one, and the triple caudex to them all.

A ſeparation of theſe buds from the parent plant is ſaid to have been obſerved by Mr. Blumenback in the conferva fontinalis, a vegetable which conſiſts of ſmall ſhort ſlender threads, which grow in our fountains, and fix their roots in the mud. He obſerved by magnifying glaſſes, that the extremities of the threads ſwell, and from ſmall tubera, or heads, which gradually ſeparate from the parent threads, attach themſelves to the ground, and become perfect vegetables; the whole progreſs of their formation can be obſerved in forty-eight hours. Obſervations on Plants, by Von Uſlar, Creech, Edinb.

2. The lateral propagation of the polypus found in our ditches in July, but more particularly that of the hydra ſtentorea, is wonderfully analagous to the above idea of the lateral generation of vegetables. The hydra ſtentorea, according to the account of monſieur Trembley, multiplies itſelf by ſplitting lengthwiſe; and in twenty-four hours theſe diviſions, which adhere to a common pedicle, reſplit, and form four diſtinct animals. Theſe four in an equal time ſplit again, and thus double their number daily, till they acquire a figure ſomewhat reſembling a noſegay. The young animals afterwards ſeparate from the parent, attach themſelves to aquatic plants, and give riſe to new colonies.

Another curious animal fact is related by Blumenback in his treatiſe on generation, concerning the freſh water polypus. He cut two of them in half, which were of different colours, and applying the upper

part of one to the lower part of the other, by means of a glaſs-tube, and retaining them thus for ſome time in contact with each other, the two divided extremities united, and became one animal.

The attentive reader has already anticipated me in applying theſe wonderful modes of lateral animal reproduction and conjunction to the lateral propagation and ingraftment of vegetables. The junction of the head-part of one polypus to the tail-part of another is exactly repreſented by the ingraftment of a ſcion on the ſtock of another tree. The plumula, or apex of each bud, with the upper part of its caudex, joins to the long caudex of the ſtock, which paſſing down the trunk terminates in the radicles of it. And if this compound vegetable could be ſeparated longitudinally from the other long filaments of the bark in its vicinity, like the fibres of the bark of the mulberry-tree prepared at Otaheite, or as the bark of hemp and flax are prepared in this country, as the young ones of the hydra ſtentorea ſeparate from their parents, it might claim the name of a lateral or paternal mule, as above mentioned.

3. It hence appears, that every new bud of a tree, where two ſcions have been inſerted over each other on a ſtock, if it could be ſeparated from the plume to the radicle, muſt conſiſt of three different kinds of caudex, and might therefore be called a triple lateral mule. And that hence it follows, that every part of this new triple caudex, muſt have been ſeparated or ſecreted laterally from the adjoining part of the trunk of the tree; and that it could not be formed, as I formerly believed, from the roots of the plume of the bud deſcending from the upper part of the caudex of it to the earth. A circumſtance of great importance in the inveſtigation of the curious ſubject of the lateral generation of vegetables, and of inſects.

One might hence ſuſpect, that if Blumenback had attended to the propagation of the polypus, which he had compoſed of two half polypi, that the young progeny might have poſſeſſed two colours reſembling

ſembling the compound parent, like the different caudexes of ingrafted trees; an experiment well worthy repeated obſervation.

4. Another animal fact ought alſo to be here mentioned, that many inſects, as common earth-worms as well as the polypus, are ſaid to poſſeſs ſo much life throughout a great part of their ſyſtem, that they may be cut into two or more pieces without deſtroying them, as each piece will acquire a new head, or a new tail, or both; and the inſect will thus become multiplied. How exactly this is reſembled by the long caudex of the buds of trees, which poſſeſs ſuch vegetable life from one extremity to the other, that when the head or plume is lopped off, it can produce a new plume; and when the lower part is cut off, it can produce new radicles; and may be thus wonderfully multiplied.

5. Hence we acquire ſome new and important ideas concerning the lateral generation of vegetables, and which may probably contribute to elucidate their ſexual generation. Theſe are, firſt, that the parts of the long caudex of each new bud of an ingrafted tree, and conſequently of all trees, are ſeparated or ſecreted from the correſpondent or adjoining parts of the long caudex of the laſt year's bud, which was its parent; and not that it conſiſts of the roots of each new bud ſhot down from the plumula or apex of it, as I formerly ſuppoſed; and that thoſe various molecules, or fibrils, ſecreted from the caudex of the laſt year's buds, adjoin and grow together beneath the cuticle of the trunk of the tree, the upper ones forming the plumula of the new bud, which is its leaf or lungs, to acquire oxygen from the atmoſphere; and the lower ones forming the radicles of it, which are abſorbent veſſels to acquire nutriment from the earth.

Secondly, that every part of the caudex of an ingrafted tree, and conſequently of all trees, can generate or produce a new bud, when the upper part of it is ſtrangulated with a wire or cut off, or otherwiſe when it is ſupplied more abundantly with nutriment, ventilation, and light. And that each of theſe new buds thus produced

reſembles that part of the ſtock in compound trees, where it ariſes. Thus in the triple tree above mentioned a bud from the upper part of the long caudexes, which form the filaments of the bark, would become a golden pippin branch; a bud from the middle part of them would become a nonpareil branch; and a bud from the lower part a crab branch.

Thirdly, another wonderful property of this lateral mule progeny of trees compounded by ingraftment conſiſts in this, that the new mule may conſiſt of parts from three, or four, or many parents, when ſo many different ſcions are ingrafted on each other; whence a queſtion may ariſe, whether a mixture of two kinds of anther-duſt previous to its application to the ſtigma of flowers might not produce a threefold mule, partaking of the likeneſs of both the males?

6. On this nice ſubject of reproduction ſo far removed from common apprehenſion the patient reader will excuſe a more prolix inveſtigation. The attraction of all matter to the centres of the planets, or of the ſun, is termed gravitation; that of particular bodies to each other is generally called chemical affinity; to which the attractions belonging to electricity and magnetiſm appear to be allied.

In theſe latter kinds of attraction two circumſtances ſeem to be required; firſt, the power to attract poſſeſſed by one of the bodies, and ſecondly, the aptitude to be attracted poſſeſſed by the other. Thus when a magnet attracts iron, it may be ſaid to poſſeſs a ſpecific tendency to unite with the iron; and the iron may be ſaid to poſſeſs a ſpecific aptitude to be united with the magnet. The former appears to reſide in the magnet, becauſe it can be deprived of its attractive power, which can alſo be reſtored to it; and the iron appears to poſſeſs a ſpecific aptitude to be united with the magnet, becauſe no other metal will approach it. In the ſame manner a rubbed ſtick of ſealing-wax may be ſaid to poſſeſs a ſpecific tendency to unite with a light ſtraw, but not with a glaſs bead. Here the ſtraw ſeems to poſſeſs a ſpecific aptitude to unite with the rubbed ſealing-wax, becauſe

many

many other bodies refuſe to do ſo, as glaſs, ſilk, air; and laſtly, the ſpecific attraction of the rubbed ſealing-wax can be withdrawn or reſtored; to which may be added, that ſome chemical combinations may ariſe from the ſingle attraction of one body, and the aptitude to be attracted of another; or they may be owing to reciprocal attractions of the two bodies, as in what is termed by the chemiſts double affinity, which is known to be ſo powerful as to ſeparate thoſe bodies, which are held together by the ſingle attraction probably of one of them to the other, which other poſſeſſes only an aptitude to be attracted by the former.

7. The above account of the tendencies to union by unorganized or inanimate matter is not given as a philoſophical analogy, but to facilitate our conception of the adjunctions or concretions obſervable in organized or animated bodies, which conſtitute their formation, their nutrition, and their growth. Theſe may be divided into two kinds; firſt the junction or union of animated bodies with inanimate matter, as when fruit or fleſh is ſwallowed into the ſtomach, and becomes abſorbed by the lacteals; and the ſecond, where living particles coaleſce or concrete together, as in the formation, nutrition, or conjunction of the parts of living animals.

In reſpect to the former, the animal parts, as the noſtrils and palate, poſſeſs an appetency, when ſtimulated by the ſcent and flavour of agreeable food, to unite themſelves with it; and the inanimate material poſſeſſes an aptitude to be thus united with the animal organ. The ſame occurs when the food is ſwallowed into the ſtomach; the mouths of the lacteal veſſels being agreeably ſtimulated poſſeſs an appetency to abſorb the particles of the digeſting maſs, which is in a ſituation of undergoing chemical changes, and poſſeſſes at ſome period of them an aptitude to be united with the mouths of the abſorbent lacteals.

But when theſe abſorbed particles of inanimate matter have been circulated in the blood, they ſeem gradually to obtain a kind of vi-

tality; whence Mr. John Hunter, and I believe ſome ancient philoſophers, and the divine Moſes, aſſerted, that the blood is alive; that is, that it poſſeſſes ſome degree of organization, or other properties different from thoſe of inanimate matter, which are not producible by any chemical proceſs, and which ceaſe to exiſt along with the life of the animal. Hence for the purpoſe of nutrition there is reaſon to ſuſpect, that two circumſtances are neceſſary, both dependent upon life, and conſequent activity; theſe are firſt an appetency of the fibrils of the fixed organization, which wants nutrition; and ſecondly, a propenſity of the fluid molecules exiſting in the blood, or ſecreted from it, to unite with the organ now ſtimulated into action. So that nutrition may be ſaid to be affected by the embrace or coheſion of the fibrils, which poſſeſs nutritive appetencies, with the molecules, which poſſeſs nutritive propenſities.

8. If the philoſopher, who thinks on this ſubject, ſhould not be inclined to believe that the whole of the blood is alive; he can not eaſily deny life to that part of it which is ſecreted by the organs of generation, and conveys vitality to the new embryon, which it produces. Hence though in the proceſs of nutrition the activity of two kinds of fibrils or molecules may be ſuſpected, yet in the proceſs of the generation of a new vegetable or animal, there ſeems great reaſon to believe, that both the combining and combined particles are endued with vitality; that is, with ſome degree of organization or other properties not exiſting in inanimate matter, which we beg leave to denominate fibrils with formative appetencies, and molecules with formative propenſities, as the former may ſeem to poſſeſs a greater degree of organization than the latter.

And thus it appears, that though nutrition may be conceived to be produced by the animated fibrils of an organized part being ſtimulated into action by inanimate molecules, which they then embrace, and may thus be popularly compared to the ſimple attractions of chemiſtry; yet that in the production of a new embryon, whether

ther vegetable or animal, both the fibrils with formative appetencies, and the molecules with formative propenſities, recriprocally ſtimulate and embrace each other, and inſtantly coaleſce, and may thus popularly be compared to the double affinities of chemiſtry. But there are animal facts, which reſemble both theſe, and are thence more philoſophically analogous to them; and theſe are the two great ſupports of animated nature, the paſſions of hunger and of love. In the former the appetency reſides only in the ſtomach, or perhaps in the cardia ventriculi, but the object conſiſts of inanimate matter; in the latter reciprocal appetencies and propenſities exiſt in the male and female, which mutually excite them to embrace each other. Two other animal facts are equally analogous; the thirſt, which reſides at the upper end of the eſophagus, and though it poſſeſſes appetency itſelf, its object is inanimate matter; but in lacteſcent females, when they give ſuck to their young, there exiſts a reciprocal appetency in the mother to part with her milk, and in the young offspring to receive it.

This then finally I conceive to be the manner of the production of the lateral progeny of vegetables. The long caudex of an exiſting bud of a tree, which conſtitutes a ſingle filament of the preſent bark, is furniſhed with glands numerous as the perſpirative or mucous glands of animal bodies; and that theſe are of two kinds, the one ſecreting from the vegetable blood the fibrils with formative appetencies, correſpondent to the maſculine ſecretion of animals; and the other ſecreting from the vegetable blood the molecules with formative propenſities, correſpondent to the feminine ſecretion of animals; and then that both theſe kinds of formative particles are depoſited beneath the cuticle of the bark along the whole courſe of it, and nearly at the ſame time by the ſympathy of the ſecreting organs, and inſtantly embrace and coaleſce, forming a new caudex along the ſide of its parent with vegetable life, and with the additional powers of nutrition, and of growth.

9. This then is the great ſecret of nature; more living particles are produced by the powers of vitality in the fabrication of the vegetable blood, than are neceſſary for nutrition or reſtoration of decompoſing organs. Theſe are ſecreted, and detruded externally, and produce by their combination a new vital organization beneath the cuticles of trees over the old one. Theſe new combinations of vital fibrils and molecules acquire new appetencies, or fabricate molecules with new propenſities, and thus poſſeſs the power of forming the leaf or lungs at one extremity of the new caudex; and the radicles, or abſorbent veſſels at the other end; and ſome of them, as in the central buds which terminate the branches, finally form the ſexual organs of reproduction, which conſtitute the flower.

That new organizations of the growing ſyſtem acquire new appetencies appears from the production of the paſſion for generation, as ſoon as the adapted organs are complete; and from the deſire of lacteſcent females to ſuckle their offſpring, and alſo from the variation of the palate, or deſire for particular kinds of food, as we advance in life, as from milk to fleſh. Thus as a popular alluſion, and not as a philoſophical analogy, we may again be allowed to apply to the combinations of chemiſtry; where two different kinds of particles unite, as acids and alkalies, a third ſomething is produced, which poſſeſſes attractions diſſimilar to thoſe of either of them; and that new organizations form new molecules appears from the ſecretions of the ſeminal and uterine glands, when they have acquired their maturity; and from the breaſts of lacteſcent females.

10. In the lateral propagation of vegetable buds as the ſuperfluous fibrils or molecules, which were fabricated in the blood, or detached from living organs, and poſſeſs nutritive or formative appetencies and propenſities, and which were more abundant than were required for the nutrition of the parent vegetable bud, when it had obtained its full growth, were ſecreted by innumerable glands on the various parts of its ſurface beneath the general cuticle of the tree, and there embracing

bracing and coaleſcing, form a new embryon caudex, which gradually produces a new plumula and radicles. And as the different parts of the new caudex of a compound tree reſemble the parts of the parent caudex, to which it adheres, it was ſhewn, beyond all doubt, that different fibrils or molecules were detached from different parts of the parent caudex to form the filial one.

So in the ſexual propagation of vegetables the ſuperfluous living fibrils, or molecules, floating in the blood, appear to be ſecreted from it by two kinds of glands only; thoſe which conſtitute the anthers, and thoſe which conſtitute the pericarp of flowers. By the former I ſuppoſe the fibrils, with formative appetencies and with nutritive appetencies, to be ſecreted; and by the latter the molecules, with formative and with nutritive propenſities. Afterwards that theſe fibrils with formative and nutritive appetencies, become mixed in the pericarp or uterus of the flower, with the correſpondent molecules with formative and nutritive propenſities; and that a new embryon is inſtantly produced by their reciprocal embrace and coaleſcence. And that parts of this new organization afterwards acquire new appetencies, and form molecules with new propenſities, and thus gradually produce other parts of the growing ſeed, which do not at firſt appear, as the plumula, radicles, cuticle, and the glands of reproduction in the pericarp and anthers, which correſpond in the animal fetus to the lungs, inteſtines, cuticle, and the organs, which diſtinguiſh the ſexes.

11. From this new doctrine of a threefold vegetable mule by lateral propagation, as the new bud on the ſummit of a tree, which has had two ſcions ingrafted on it one above another, in which it is inconteſtibly ſhewn, that different fibrils, or molecules, are detached from different parts of the parent caudex to form the filial one, which adheres to it; and that it then acquires the power of producing new radicles, or a new plumula; we may ſafely conclude, as it is deducible from the ſtrongeſt analogy, that in the production of ſexual

mules, whether vegetable or animal, ſome parts of the new embryon were produced by, or detached from, ſimilar parts of the parent, which they reſemble. And that as theſe fibrils, or molecules, floated in the circulating blood of their parents, they were collected ſeparately by appropriated glands of the male or female; and that finally, on their mixture in the matrix the new embryon was immediately generated, reſembling in ſome parts the form of the father, and in other parts the form of the mother, according to the quantity or activity of the fibrils or molecules at the time of their conjunction.

And laſtly, that various parts of the new organizations afterwards acquired new appetencies, and formed molecules with new propenſities, and thus gradually produced other parts of the growing fetus, as the ſkin, nails, hair, and the organs which diſtinguiſh the ſexes.

If the molecules ſecreted by the female organ into the pericarp of flowers, or into the ovary of animals, were ſuppoſed to conſiſt of only unorganized or inanimate particles; and the fibrils ſecreted by the male organ only to poſſeſs formative appetencies to ſelect and combine with them; the new embryon muſt probably have always reſembled the father, and no mules could have had exiſtence.

But by the theory above delivered it appears, that the new offſpring, both in vegetable and animal reproduction, whether it be a mule or not, muſt ſometimes more reſemble the male parent, and ſometimes the female one, and ſometimes appear to be a combination of them both, as the epigram of Martial:

> Dum dubitat natura gravis puerum faceretne puellam,
> Factus es, O pulcher, pene puella, puer.

12. The certain proof above given, that ſome parts of the triple caudex of the new bud of a tree, which has been compounded by ingraftment, are formed from ſimilar parts of the triple caudex of the parent bud, carries us one ſtep further back into the myſterious proceſs

ceſs of reproduction, and ſomewhat countenances the ingenious conjectures of monſieur Buffon. And the analogy here obſerved, that as in chemical union there muſt be ſome particles of inanimate matter with attractions, and others with aptitudes to be attracted; ſo in the conjunctions of animated particles in the nutrition or formation of organized beings, there muſt exiſt fibrils or molecules with formative or nutritive appetencies, and others with formative or nutritive aptitudes or propenſities, one of which may be ſecreted by the male, and the other by the female parent, may facilitate our reaſoning upon this dark ſubject, which will be reſumed and enlarged upon in the next edition of Zoonomia, in the ſection on generation.

SECT. VIII.

1. THE MUSCLES, NERVES, AND BRAIN OF VEGETABLES.

1. *Vegetable muſcles evinced by their cloſing their corols, and calyxes, and moving their leaves in conſequence of ſtimulus. Hence alſo vegetable nerves both of ſenſe and motion. When one part of a leaf of mimoſa is touched the whole leaf falls. Hence alſo a vegetable brain or common ſenſorium.* 2. *Their irritability ſhewn by the abſorption, and circulation of their fluids. By electric ſhocks. By the aſcent of ſap-juice.* 3. *Their ſenſibility ſhewn by the collaps of mimoſa. By cloſing their petals from defect of ſtimulus, as in darkneſs and cold. By the males and females bending to each other.* 4. *Their volition ſhewn from hedyſarum gyrans. From polymorpha marchantia. From tendrils of vines. From their ſleep.* 5. *Their aſſociations of motion ſhewn by their cloſing their petals, performing abſorption and circulation of fluids. Their acquired habits. Grains and roots from the ſouth vegetate ſooner. Apple-trees. Senſitive plant. Berberry.* 6. *Vegetables poſſeſs a ſenſe of heat, of light, and of moiſture, and conſequently poſſeſs a brain or common ſenſorium.* 7. *They poſſeſs a ſenſe of touch and a common ſenſorium.* 8. *How do the anthers and ſtigmas find each other? by a ſenſe of ſmell. Adultery of collinſonia.* 9. *From their abſorptions, ſecretions, ſenſes, love and ſleep, they muſt poſſeſs a brain. Does this reſide in the pith of each individual bud?*

1. THE various motions of peculiar parts of vegetables evince the exiſtence of muſcles and nerves in thoſe parts, ſuch as the cloſing of their petals, and calyxes, at the approach of night, or in cold or wet weather; though the fibres and nerves, which conſtitute theſe muſcles, are too fine for anatomical demonſtration.

Some vegetables fold the older leaves over the new buds at the extremity of their ſtalks during the night, as alſine, chickweed; others, as the mimoſa, ſenſitive plant, fold the upper or poliſhed ſides of their

their leaves together during their ſleep. The hedyſarum gyrans whirls its leaves in various directions, when the air is ſtill, by an apparently voluntary effort, probably for the purpoſe of reſpiration. The dionœa muſcipula, Venus's fly-trap, cloſes its leaves from the ſtimulus of inſects, which crawl upon them, and pierces them with its prickles. And the apocynum androſemifolium contracts its petals or nectaries round the proboſcis of the flies, which ſtimulate it, and holds them till they die, or till the ſleep of the plant releaſes them by the relaxation of its muſcular action.

From theſe circumſtances it appears, that there are not only muſcles about the moving foot-ſtalks or claws of the leaves and petals above mentioned; but that theſe muſcles muſt be endued with nerves of ſenſe as well as of motion. Now, as when one part of a leaf of mimoſa is touched, the whole leaf falls, it follows, that there muſt be a common ſenſorium, or brain, where the nerves communicate, belonging to this one leaf-bud. To evince this further another leaflet was ſlit with ſharp ſciſſars, and ſome ſeconds of time elapſed, before the plant ſeemed ſenſible of the injury; and then the whole plant collapſed as far as the principal ſtem. Afterwards a ſmall drop of oil of vitriol was put on the bud in the boſom of a leaf of another ſenſitive plant; and, after about half a minute, when the brain of this bud could be ſuppoſed to be deſtroyed, the whole leaf fell, and roſe no more. If the individual buds of plants poſſeſs muſcles and nerves with a brain, or common ſenſorium; the following queſtions conſequently occur, and ſhould be anſwered in the affirmative. Have vegetable buds irritability? have they ſenſation? have they volition? have they aſſociations of motion? I am perſuaded they poſſeſs them all, though in a much inferior degree even than the cold blooded animals.

2. The irritability of vegetable fibres is demonſtrated by the abſorption and circulation of their fluids in their roots, leaves, and petals; which can not be explained by any mechanic law, and exactly

correſponds

correſponds with the abſorption of the aliment, and the circulation of the blood in animals; which Phyſiologiſts have demonſtrated to depend on the muſcular motions of the veſſels themſelves, which poſſeſs irritability, and are excited into action by the ſtimulus of the fluids, which they acquire or contain.

The irritability of vegetable veſſels is ſhewn by a curious experiment of Von Uſlar, who paſſed ſtrong electric ſhocks through a plant of euphorbia, ſo as to deſtroy the life of the plant; and he then obſerved on cutting off a branch, that it did not bleed; though a ſimilar branch cut off before the death of the plant effuſed much milky juice; whence he juſtly concludes, that the electric percuſſion had deſtroyed the irritability of the plant.

Mr. Cavallo aſſerts in his Treatiſe on Electricity, that he found by repeated experiments, that the plant balſam (impatiens) was deſtroyed by leſs quantities of electricity than any other vegetables, which he ſubjected to it; and that on examining the plant afterwards no injury on the external or internal parts of it could be diſcovered; whence it may be concluded that the irritability ſimply, and not the organization of the plant, was deſtroyed by the unnatural quantity of ſtimulus. He adds, that not only ſhocks from ſo ſmall a coated ſurface as ſix or eight ſquare inches, but even ſtrong ſparks from a large conductor deſtroyed theſe plants, which ſometimes recovered in a day or two, but not frequently. See Sect. XIII. 3. and Sect. XIV. 2. 3. of this work.

The aſcent of the ſap-juice during the vernal months in the experiments both of Hales and Walker, being retarded or quite ſtopped during the cold parts of the day, and in the night; and on the north ſide of the tree in cool days, when it continued to flow on the ſouth ſide, can only be aſcribed to the irritability of the vegetable veſſels being decreaſed by the deficient ſtimulus of heat. See this ſubject further treated of in Sect. XIV. 1. 10. of this work.

3. The ſenſibility of fibres is diſtinguiſhed from their irritability by

by the pain or pleaſure, which precedes or attends any animal action; and therefore ſuppoſes the exiſtence of a common ſenſorium; now when one diviſion of a leaf of mimoſa is injured by a wound or touch, in a ſhort time the whole leaf cloſes, which is owing to the actions of the diſtant muſcles about the footſtalks of the ſubdiviſions of the leaf. Does not this prove, that there is a brain or common ſenſorium, where the nerves communicate in ſome part of this bud or leaf, as the injury of one diſtant part of it thus affects the whole? or in other words, that the diſagreeable ſenſation is propagated from a part to the whole, and cauſes the actions of ſome diſtant muſcles, in the ſame manner as I draw away my hand when my finger is hurt?

There are muſcles placed about the foot-ſtalks of the leaves or leaflets of many plants, for the purpoſe of cloſing their upper ſurfaces together, or of bending them down ſo as to ſhoot off the ſhowers or dew-drops, as in ſenſitive plant, mimoſa; kidney-bean, phaſeolus; and many trees. The claws of the petals, or of the diviſions of the calyx of many flowers, are furniſhed in a ſimilar manner with muſcles, which are exerted to open or cloſe the corol and calyx of the flower, as in tragopogon, anemone. This action of opening and cloſing the leaves or flowers does not appear to be produced ſimply by irritation on the muſcles themſelves, but by the connexion of thoſe muſcles with a ſenſitive ſenſorium, or brain, exiſting in each individual bud or flower. 1ſt. Becauſe many flowers cloſe from defect of ſtimulus, not by the exceſs of it, as by darkneſs, which is the abſence of the ſtimulus of light; or by cold, which is the abſence of the ſtimulus of heat. Now the defect of heat, like the abſence of food, or of drink, affects our ſenſes with pain, which had been previouſly accuſtomed to a greater quantity of them, and a cutaneous ſhivering may be excited in conſequence of the pain; but a muſcle cannot be ſaid to be ſtimulated into action by a defect of ſtimulus, though ſome modern writers on medicine have called cold a ſtimulus to animal fibres, which it always renders torpid or inactive; a theory

derived from Galen, and which muſt have originated in his total ignorance of chemiſtry and natural philoſophy.

In ſome flowers the males bend into contact with the females, as in ciſtus, kalmia, fritillaria perſica, lithrum ſalicaria; in others the female bends to the males, as in collinſonia, glorioſa, geniſta, epilobium; which ſhews a ſenſibility to the paſſion of reproduction. In *irritation* the ſtimulated muſcles only are brought into action, without being perceived by the other parts of the ſyſtem; but in *ſenſation* the whole ſyſtem is affected by means of the brain or common ſenſorium, and thence very diſtant muſcles are brought into action to acquire an agreeable object, or to repel or withdraw from a diſagreeable one. See Zoonomia, Vol. I. Sect. XIII. 2.

4. That plants poſſeſs in ſome degree the power of volition would appear firſt from the hedyſarum gyrans, which moves its leaves in circular directions when the air is too ſtill. Secondly, from the marchantia polymorpha, in which ſome yellow wool advances from the flower-bearing anthers, while it drops its duſt like atoms. Murray's Syſtem of Vegetables. Thirdly, from the tendrils of vines, and the ſtems of other climbing vegetables, which continue to move round, till they find ſomething to adhere to, or till they have rolled themſelves up in a ſpiral line like a cork-ſcrew. And laſtly, from the efforts of almoſt all plants to turn the upper ſurface of their leaves, or their flowers, to the light.

But there is an indubitable proof of plants poſſeſſing ſome degree of voluntarity, and that is deduced from their ſleep. In animal bodies ſleep conſiſts in a ſuſpenſion or temporary abolition of voluntary power; the organs of ſenſe being at the ſame time cloſed, or by ſome other means rendered unfit for the perception of external bodies. Now the ſleep of plants is proved by the hanging down or cloſing of the leaves of many plants, and of ſhutting the petals and calyxes of many flowers in the dark, and their again opening or expanding them in the light, or at certain hours of the day.

5. In

5. In reſpect to vegetables acquiring aſſociations of motion, or habits of action, the former is ſeen in the abſorptions and circulations of their fluids, and in the various movements above deſcribed; which whirl their leaves or tendrils, and cloſe or open their corols and calyxes, which could not be performed without the ſynchronous and aſſociated actions of many muſcles; as in the abſorptions and circulations of animal bodies, and the movements of their limbs.

Other acquired habits of vegetable actions appear from the grains and roots brought from more ſouthern latitudes, which germinate here ſooner than thoſe which are brought from more northern ones, owing to their acquired habits. Fordyce on Agriculture. And from the apple trees ſent from hence to New York, which bloſſomed for a few years too early for the climate, and bore no fruit; but afterwards learnt to accommodate themſelves to their new ſituation. Travels in New York by Profeſſor Kalm.

The diviſions of the leaves of the ſenſitive plant have been accuſtomed to contract at the ſame time from the abſence of light; hence if by any other circumſtance, as a ſlight ſtroke or injury, one diviſion is irritated into contraction; the neighbouring ones contract alſo, from their motions being aſſociated with thoſe of the irritated part. So the various ſtamina of the barberry have been accuſtomed to contract together in the evening; and thence, if you ſtimulate one of them with a pin, according to the experiment of Dr. Smith, they all contract from their acquired aſſociations.

6. This leads us to a curious inquiry, whether vegetables poſſeſs any organs of ſenſe? Certain it is, that they poſſeſs a ſenſe of heat and cold, another of moiſture and dryneſs, and another of light and darkneſs; for they cloſe their petals occaſionally from the preſence of cold, moiſture, or darkneſs. And it has been already ſhewn, that theſe actions cannot be performed ſimply from irritation, becauſe cold and darkneſs are defective quantities of our uſual ſtimuli; and that on that account ſenſation or volition are employed; and in conſe-

quence a ſenſorium or union of the nerves muſt exiſt. So when we go into the light, we contract the iris, not from any ſtimulus of the light on the fine muſcles of the iris, but from its motions being aſſociated with the ſenſation of too much light on the retina, which could not take place without a ſenſorium or center of union of the nerves of the iris with thoſe of viſion.

7. Beſides theſe organs of ſenſe, which diſtinguiſh cold, moiſture, and darkneſs, the leaves of mimoſa, and of dionæa, and of droſera, and the ſtamens of many flowers, as of the barberry, and of the numerous claſs of ſyngeneſia, are ſenſible to mechanic impact; that is, they poſſeſs a ſenſe of touch; and as many of their diſtant muſcles are in conſequence excited into action, this alſo evinces, that they poſſeſs a common ſenſorium, by which this ſenſation is communicated to the whole, and volition occaſionally exerted.

8. Laſtly, in many flowers the anthers when mature approach the ſtigma, in others the female organ approaches to the male. I aſk, by what means are the anthers in many flowers, and ſtigmas in other flowers, directed to find their paramours? Is this curious kind of ſtorge produced by mechanic attraction, or by the ſenſation of love? The latter opinion is ſupported by the ſtrongeſt analogy, becauſe a reproduction of the ſpecies is the conſequence; and then another organ of ſenſe muſt be wanted to direct theſe vegetable amourettes to find each other; one probably analagous to our ſenſe of ſmell, which in the animal world directs the new-born infant to its ſource of nouriſhment; and in ſome animals directs the male to the female; and they may thus poſſeſs a faculty of perceiving as well as of producing odours.

A moſt curious example of the exiſtence of ſome kind of ſenſe, which may direct the piſtils, or female parts of the flowers of collinſonia, which way to bend for the purpoſe of finding the mature males, is related in Botanic Garden, Vol. I. Canto IV. l. 460, where ſome of the piſtils miſtake the males, or ſtamens, of the neighbouring flowers

flowers for their own huſbands; and bending into contact with them become guilty of adultery. See Sect. VII. 2. 2. of this work.

9. Thus, beſides a kind of taſte or appetency at the extremities of their roots, ſimilar to that of the extremities of our lacteal veſſels, for the purpoſe of ſelecting their proper food; and beſides different kinds of irritability or appetency reſiding in the various glands, which ſeparate honey, wax, reſin, and other juices from their blood; vegetable life ſeems to poſſeſs an organ of ſenſe to diſtinguiſh the variations of heat, another to diſtinguiſh the varying degrees of moiſture, another of light, another of touch, and probably another analogous to our ſenſe of ſmell. To theſe muſt be added the indubitable evidence of their paſſion of love, and of their neceſſity to ſleep; and I think we may truly conclude, that they are furniſhed with a brain or common ſenſorium belonging to each bud.

But whether this brain, or common ſenſorium, reſides in the medulla, or pith, which occupies the central parts of every bud and leaf, like the ſpinal marrow of animals, has not yet been certainly determined. By this medulla is meant only the pith of each individual bud, not that which is ſeen in the center of a tree, which, like the wood which ſurrounds it, has long ceaſed to have vegetable life.

The pith, or medulla of each bud, is ſuppoſed by its elaſticity to puſh out the central part of the bud; as the veſicular productions on the inſide of young quills are ſuppoſed to puſh forwards their early growth, and in ſome birds are ſaid by Mr. Hunter to receive air from the lungs. It is more probable that this pith, or medulla oblongata of plants, ſupplies the ſpirit of vegetation, ſince it exiſts in all buds in their moſt early ſtate, and does not communicate from one bud to another, and thus diſtinguiſh them from each other, and evinces their individuality. See Sect. I. 8. and IX. 2. 4.

PHYTOLOGIA.

PART THE SECOND.

ECONOMY OF VEGETATION.

SECT. IX.

THE GROWTH OF SEEDS, BUDS, AND BULBS.

I. 1. SEEDS *resemble eggs.* 2. *The embryon is of different maturity. The leaves visible in some seeds.* 3. *Why the plumula ascends and the root descends. Is nourished by the seed-lobes, by the fruit. Becomes a dwarf if deprived of them. Melons and cucumbers are too luxuriant. Turnep-seed should be new.* 4. *Seeds have hard shells, have acrid rinds with bitter or narcotic juices, but pure starch may be procured from them.* 5. *Umbilical vessels, and roots of seeds. Annual, biennial, and perennial plants. Reservoirs of nutriment in their roots. All plants are biennials. Bulbs and buds succeed each other many times before they flower.* 6. *Wheat. Stems and roots round the first joint. Has no nectary. Is greatly increased by transplanting.* II. 1. BUDS *are a viviparous progeny. Protected by scales and varnish. Grow by piping with more heat and moisture as they exhale less. Are individual, annual, or biennial plants.* 2. *Buds of herbs. Evergreens have no bleeding season.* 3. *Buds of deciduous trees are in different states of maturity, as in hepatica, daphne, osmunda. Some buds are invisible.* 4. *Importance of the pith like the spinal marrow; it lines hollow stalks.* 5. *Reservoir of nutriment for buds. Their umbilical vessels.* 6. *A bud contains many embryons. The first leaf-buds often destroyed by insects. The flower-buds only injured by them.* 7. *Vigorous branches produce leaf-buds, weak ones flower-buds. Why seedling apples are long before they bear. Why pears bear only at their extremities.* 8. *New buds may be made either leaf-buds by lopping a part of the branch, or flower-buds by bending the branch down, or cutting a ring in the bark, or strangulating*

it with a wire. Debarked oaks pullulate. Sap-juice in the alburnum. 9. *A pauſe in vegetation about midſummer. Trees then ſecrete nutriment in their roots and ſap-wood for the new buds. Are then beſt tranſplanted without lopping their branches.* 10. *Caudexes of the buds form the bark, whoſe veſſels inoſculate. Heart-wood dies. Sap-wood acts as umbilical veſſels, and afterwards as capillary tubes, or as capillary ſyphons.* 11. *Flower-buds periſh without increaſing the bark by new caudexes. Are convertible into leaf-buds. Vegetable monſters.* 12. *Central part of an adult bud.* III. 1. BULBS. *Leaf-bulbs precede flower-bulbs in the tulip as leaf-buds in apple-trees, as joints in the ſtalk of wheat. Solitary generation of inſects.* 2. *Bulbs of onions. Orchis. Tulip. Hyacinth. Ranunculus. Iris.* 3. *Roots of potatoes. Wires of ſtrawberries. Seeds of orchis. Flowers of potatoes.* 4. *Stem-bulbs on magical onions are ſimilar to root-bulbs.* 5. *Root-grafting. Root-inoculation. Root-propagation. Suckers of trees. Root-buds of herbaceous plants. Internal parts of which decay.* 6. *Tuberous roots of turnep and carrot are reſervoirs of nutriment for the ſucceeding flower-ſtem. No flower-bud is ever produced from a ſeed without previous leaf-buds. Why ſeedling apple-trees are ten or twelve years before they bear fruit. Magazines of aliment in almoſt all roots.* 7. *Uſe of the horſe-hoe to accumulate earth round the wheat-plants. Wheat dropped on the ſoil ſhoots up but one ſtem. Covered with the ſoil it ſhoots up many. And tranſplanted deeper in the ſoil many more. Potatoes, vines, and figs, produce lateral roots from their joints. So does the bark if wounded circularly. Uſe of eating down forward wheat with ſheep.*

I. 1. HAVING treated of the phyſiology, we now ſtep forwards to conſider the economy of vegetation, as far as it may ſerve the purpoſes of agriculture and gardening.

After the production of the ſeed, or vegetable egg in the pericarp of flowers, and its enſuing impregnation by the farina of the anthers ſhed upon the ſtigma, a coagulated point appears on the ſeed-lobes according to the obſervations of Spallanzani, like the cicatricula on the yolk of the egg.

The ſeed continues to grow in the pericarp ſuſtained by adapted ſecretions from the vegetable blood, which is previouſly oxygenated in

the bractes or floral-leaves of many plants; in others the ſeed is itſelf incloſed in an air-veſſel probably for that purpoſe, as in ſtaphylea, bladder nut, and tagetes, African marygold. At the ſame time a reſervoir of nutriment is ſecreted, and depoſited in the ſeed-lobes or cotyledons, which are ſingle ones in the ſeeds of palms, graſſes, and lilies; though twofold in thoſe of moſt other herbs and trees; whence the ſtricteſt analogy exiſts between ſeeds and eggs.

2. In ſome ſeeds, when they leave the vegetable uterus, this embryon is much more mature than in others. In the ſeeds of the nymphæa nelumbo the leaves of the future plant were ſeen ſo diſtinctly by Mr. Ferber, that he found out by them to what plant the ſeeds belonged. The ſame in the ſeeds of the tulip-tree, liriodendron tulipiferum. Amæn. Acad. V. VI. No. 120. And Mr. Baker aſſerts, that on diſſecting a ſeed of trembling graſs, he diſcovered by the microſcope a perfect plant with roots ſending forth two branches, from each of which ſeveral leaves or blades of graſs proceeded. Microſc. Vol. I. p. 252. While in other ſeeds the corculum, or heart only of the ſeed, is diſtinctly viſible, as in the kernel of the walnut, and the ſeed of the garden-bean. So in the animal kingdom the young of ſome birds are much more mature at their birth than thoſe of others. The chickens of pheaſants, quails, and partridges, can uſe their eyes, run after their mothers, and peck their food, almoſt as ſoon as they leave their ſhell; but thoſe of the linnet, thruſh, and blackbird, continue many days totally blind, and can only open their callow mouths for the offered morſel.

3. When the ſeed falls naturally upon the earth, or is buried artificially in ſhallow trenches beneath the ſoil, the firſt three things neceſſary to its growth are heat, water, and air. Heat is the general cauſe of fluidity, without which no motion can exiſt; water is the menſtruum, in which the nutriment of vegetable and animal bodies is conveyed to their various organs; and the oxygen of the atmoſphere is believed to afford the principle of excitability ſo perpetually

neceſſary

neceſſary to all organic life; and which renders the living fibres both of the vegetable and animal world obedient to the ſtimuli, which are naturally applied to them.

Whence we may in ſome meaſure comprehend a difficult queſtion; why the plume of a ſeed ſowed upon, or in the earth, ſhould aſcend, and the root deſcend, which has been aſcribed to a myſterious inſtinct; the plumula is ſtimulated by the air into action, and elongates itſelf, where it is thus moſt excited; and the radicle is ſtimulated by moiſture, and elongates itſelf thus, where it is moſt excited, whence one of them grows upwards in queſt of its adapted object, and the other downward.

The firſt ſource of nutriment ſupplied to the ſeminal embryon, after it falls from the parent plant, exiſts in the ſeed-lobes, or cotyledons, which either remain beneath the earth, and are permeated by the umbilical veſſels of the embryon plant, which abſorb the mucilaginous, farinaceous, or oily matter depoſited in them, as in the bean, piſum; or the ſeed-lobes riſe up into the air along with the young plant, as in the kidney-bean, phaſeolus, become ſeed-leaves, and ſerve both as a nutritive and reſpiratory organ. Theſe cotyledons or ſeed-lobes generally contain mucilage, as in quince-ſeed; or ſtarch, as in wheat; or oil, as in line-ſeed. Some of theſe nutritive materials are probably abſorbed unchanged, or diſſolved only by the moiſture of the earth; others are converted into ſugar partly by a chemical proceſs, and partly by the digeſtive powers of the young plant, as appears in the proceſs of germinating barley, and converting it into malt; theſe reſervoirs of nutriment are hence perfectly analogous to the white of the egg, a part of which is probably abſorbed unchanged by the lymphatics of the young embryon, and a part of it converted into a ſweet chyle for the nouriſhment of the chick, when it has acquired a ſtomach.

If the ſeed be deprived of theſe cotyledons, ſoon after the root appears, it will continue to grow, but with leſs vigour, and is ſaid to produce

duce a dwarf plant from three to nine times leſs than the parent. Hence the ſeeds of plants, which are liable to produce too vigorous roots, and thence have not time to ripen their fruits in the ſhort ſummers of this climate, or which fill our hot-beds with too luxuriant foliage, as melons, and cucumbers, ſhould in this climate be kept three or four years; by which part of the mucilaginous, or farinaceous, or oily matter of the cotyledons becomes injured or decayed, and the new plant grows leſs luxuriantly.

Another ſource of nutriment for the ſeminal embryon of many plants exiſts in the fruit, which envelopes the ſtone or ſeed-veſſel, after the growing fetus has burſt its confinement, and ſo far reſembles the yolk of the egg, which becomes a nutriment to the chick, after it has conſumed the white, and eloped from its ſhell.

When mature fruit, as an apple or a cucumber, falls upon the ground, it ſupplies, as it ripens or decays, a ſecond ſource of nouriſhment, which enables the incloſed ſeeds to ſhoot their roots into the earth, and to elevate their ſtems with greater vigour. Hence fruits generally contain a ſaccharine matter, or juices capable of being converted into ſugar, either by a ſpontaneous chemical proceſs, as in baking ſour apples; or by a vegetable proceſs, as in thoſe ſour pears, which continue to ripen for many months both before and after they are plucked from the tree, as long as life remains in them; that is, till they ferment or putrify; and laſtly, by the digeſtive power of the young embryon, as above mentioned.

If the ſeed be deprived of the fruit, it will indeed vegetate, but with leſs vigour. Hence thoſe ſeeds which are liable to produce too vigorous ſhoots for this climate, as the ſeeds of melons and cucumbers, ſhould be waſhed clean from their pulp, before they are hoarded, and preſerved three or four years before they are ſown in hot beds. But thoſe ſeeds, which are ſown late in the ſeaſon for the purpoſe of producing winter fodder, as the ſeeds of turneps, ſhould be collected and preſerved with every poſſible advantage; and on this

account new ſeed is much to be preferred to that which has been long kept.

4. Many ſeeds when mature are diſperſed far from the parent tree, for the purpoſe of their growth, by various contrivances, as mentioned in Sect. VII. 2. 5. Some of theſe are ſurrounded with hard ſhells, which are impenetrable by inſects, as they lie on the earth to take root, as peaches, nectarines, nuts, cocoa-nuts. Other ſeeds are furniſhed with an acrid covering to prevent the depredation of inſects, as the peel of oranges and lemons, the outward huſk and inward rind of walnuts, and of caſhew-nuts, and the ſkin of muſtard-ſeed, and rape-ſeed; other ſeeds for the ſame purpoſe abound with bitter or narcotic juices, as the horſe-cheſnut, acorn, apricot, cherry, many of which ſupply materials to the ſhops of medicine, and may ſupply nutriment in times of ſcarcity; as the ſtarch, which they contain, may be procured by grating them into cold water, and waſhing away the mucilage, and the poiſonous material, which adheres to it, or which is ſoluble in water.

5. The plumula of the ſeed, or embryon plant, abſorbs the nutriment laid up for it in the ſeed-lobes by veſſels, which permeate them for that purpoſe, and have been termed umbilical veſſels; and afterwards ſhoots its roots down into the fruit, or into the earth, in ſearch of other nouriſhment; and expands its leaves in the air as an organ of reſpiration.

Thoſe plants, which are uſually termed annuals, produce their flowers and die in the ſame year in which their ſeeds are ſown; as barley, oats, and a variety of garden flowers. Theſe nevertheleſs in accurate language ſhould be termed biennials, becauſe the ſeed in this climate is produced in one ſummer; and the embryon plant becomes mature in the next; as the ſeed is generally preſerved in our granaries, or ſeed-boxes, and not committed to the ground till the enſuing ſpring; for many of theſe vegetables are not natives of this climate,

climate, and would periſh if the ſeeds were ſown in autumn, when it is naturally ſcattered on the earth.

Thoſe which are uſually termed biennial plants, differ from the former, firſt in the time of ſowing the ſeed, which is generally in the early autumn, as ſoon as it is ripe, as of turneps, carrots, wheat; and thus theſe produce their flowers in the ſecond year after the ſeed is ſown, which has given them the name of biennials. Many of theſe plants, perhaps all of them, lay up a reſervoir of nutritious matter during the ſummer or autumn in their roots. This nutriment is ſecreted from the vegetable blood, which is previouſly oxygenated for that purpoſe in the large leaves, which generally ſurround the caudex of the plant, as in turneps and carrots. Theſe leaves ſurvive the winter in many plants, which the more ſucculent ſtems probably would not; and the nutriment depoſited in the root is expended in the growth of the ſtem and the production of ſeed in the enſuing ſpring. As in theſe vegetables one of our ſummers is too ſhort for their growth from the ſeed to the fructification; and it is for this reſervoir of nutriment that theſe plants are generally cultivated.

But thoſe plants, which are termed perennial, when firſt raiſed from ſeed, are many of them ſome years before they produce flowers. Some of them form bulbous roots, as the tulip, hyacinth, onion, which are three or four years before they flower, during which time I believe all the bulbs die annually, producing one larger than that of the preceding year, and perhaps ſome ſmaller ones, all which annually increaſe in ſize till they flower. The ſame occurs in potatoe-roots raiſed from ſeed, which do not flower as I am informed till the third year, and then only thoſe which ſeemed of ſtronger or forwarder growth.

Other perennial plants have palmated or branching roots; in ſome of theſe, as in ſeedling apple-trees, the flower is ſaid not to appear till ten or twelve years after the ſeed is ſown; the buds nevertheleſs annually dying and producing other buds over them, perhaps more

perfect ones, as they acquire after a few years the power of producing ſexual organs, and in conſequence a ſeminal progeny. In theſe perennial herbaceous plants and trees a magazine of nutriment is provided in their roots or ſap-wood, to ſupply the new buds, which are to grow in the enſuing ſpring.

Whence it appears, that all the vegetables of this climate may be termed biennial plants; as the ſeeds of ſome, and the buds or bulbs of others, are produced in one ſummer, and flouriſh and die in the next; thoſe which are called annuals or biennials leaving behind them a future progeny of ſeeds only; thoſe, which are termed perennial herbaceous plants, leaving behind them the firſt year or two a progeny of bulbs or root-buds only, and afterwards a progeny of ſeeds alſo; while the perennial arboreſcent vegetables leave behind them a progeny of buds only for ſeveral ſucceſſive years, and afterwards a progeny of both buds and ſeeds.

Thus the bulb from a tulip-ſeed produces a more perfect bulb annually, till it flowers, I believe, on the fifth year. It then produces a flower, and alſo one perfect bulb, which flowers the next year; and ſome other leſs perfect bulbs, which are ſucceeded by more perfect ones annually, till they alſo flower. Whence I conclude, that no tulip bulb flowers till the fourth or fifth generation.

It is probable, that a ſimilar circumſtance occurs in other vegetables, as in apple-trees; and that the buds of theſe do not produce ſexual organs, and a conſequent ſeminal progeny, till the twelfth or fourteenth generation of the bud from the ſeed; each of thoſe buds nevertheleſs producing one principal bud annually more perfect than itſelf, and many lateral buds leſs perfect than itſelf; that is, at a greater diſtance from that ſtate of maturity which enables it to form a flower. This art of diſtinguiſhing the greater or leſs maturity of buds is a matter of great importance in the management of fruit-trees, as in many of them the central bud becomes a ſpur one year, and flowers the

the next; and the lateral buds one or two years afterwards, as will be mentioned in Sect. XV. on the production of fruit.

6. In wheat there exists about the caudex a reservoir of nutritious juices deposited in the autumn for the purpose of raising the stem in the ensuing spring like that of turneps and carrots; but which is attended with other circumstances peculiar I suppose to the grasses, and other plants, which possess only one cotyledon or seed-lobe. The early leaf, which surrounds the first joint of the stem, withers, as the spring advances; in which joint it had previously deposited a saccharine juice, and probably some new embryon buds were at the same time generated in the caudex; for through this withered leaf, which surrounds the first joint of the stem within the earth, a circular set of new stems issue adhering to it, and a circle of roots below them adhering to the caudex or base of it. These new buds rise into air, and shoot their roots into the earth; and in this manner many stems are produced in the spring from one seed sowed in the autumn preceding; though in some kinds of wheat the whole process of the seed rising from earth, and producing other stems round the principal one, and of ripening its seeds, may be performed in one summer even in this northern climate.

Another peculiarity attends the growth of wheat and other grasses; the leaf, which surrounds and strengthens the stem by its foot-stalk, deposits at every lower joint a saccharine matter for the purpose of nourishing the ascending part of the young stem; and in the uppermost joint, I suppose, to serve instead of honey for the stamens and stigmas, as their flowers have no visible nectary; and as the scales of the flower may with good reason be esteemed a calyx rather than a corol, according to the opinion of Mr. Milne; as these scales attend the seed-vessel to its maturity, which the corol does not. Milne's Botanical Dict. Art. Gramina.

Owing to this secretion of saccharine matter at the foot-stalk of every leaf, and its collection round the joints of grasses, it happens that

that when theſe joints are ſurrounded with moiſt earth, and are placed but a certain depth from the air, that new buds will put forth round theſe joints, and ſtrike their roots into the ſoil. Whence the agrarian huſbandman may derive great advantage from tranſplanting his wheat, after it has produced a circle of new ſtems from the firſt joint of the ſtraw; for if he then parts and replants them an inch or two deeper in the ground, ſo as to cover the firſt joint of each of theſe additional ſtems, he may multiply every one of them four or ſix times, and thus obtain twenty or thirty ſtems from one original ſeed. See No. III. 1. and 7. of this ſection.

II. 1. Other vegetable embryons are produced in the buds on the ſtems or branches of trees, which may be termed the viviparous progeny of plants, in contradiſtinction to thoſe from ſeeds, which may be termed their oviparous progeny. Theſe buds are either leaf-buds or flower-buds, or both in one covering; the bud is termed hybernaculum, or winter-cradle, of the embryon ſhoot, and is covered with ſcales, and often with a reſinous varniſh, as in tacamahacca, to protect it from the cold and moiſture of the enſuing winter, and from the depredation of inſects.

Theſe by inoculation or ingrafting on other ſtems of trees, or by being planted in the earth, become plants exactly ſimilar to their parents. A ſmall glaſs inverted over theſe buds, when ſet in the earth, contributes to inſure their growth by preventing too great an exhalation; otherwiſe they are liable to perſpire more than they can abſorb, before they have acquired roots; this the gardeners call piping a ſlip, or a cutting, of a plant. In this ſituation a greater heat may be given them, as in hothouſes, without increaſing their quantity of perſpiration, which ceaſes as ſoon as the air in the glaſs is ſaturated with moiſture; and the increaſe of heat much contributes to the protruſion of their roots and new buds, as they can at the ſame time bear to be ſupplied with a greater quantity of moiſture.

Every bud of moſt of the deciduous trees of this climate may there-

fore be conſidered as an individual biennial plant, as diſtinctly ſo as a ſeed; that is, the bud like a ſeed is formed in one ſummer, grows to maturity in the next, and then dies. In ſome trees nevertheleſs of this climate, as the mock orange, philadelphus, acacia, viburnum; and in the evergreen ſhrubs or trees, as holly, laurel, vinca, heath, and rue; and in all thoſe herbs commonly called annuals; and in moſt of the trees of warmer climates; the buds appear to be formed in the vernal months, and to arrive at their maturity during the ſame year; and may therefore properly be called annual plants.

2. The bud of theſe herbs, which are commonly called annuals, riſes in the boſom of a leaf; and, as it adheres to its parent, requires no female apparatus to nouriſh it, but gradually ſtrikes down roots from its caudex into the ground, which caudex forms a part of the bark of the increaſing plant. This occurs in thoſe herbaceous vegetables, which have juſt riſen from ſeeds; the buds of which are properly individual annual plants, which grow to maturity adhering to the parent, and do not therefore reſemble a ſeed or egg, as there is no reſervoir of nutriment laid up for them.

This circumſtance alſo happens, I ſuppoſe, to the evergreen ſhrubs and trees of this climate, as to heath, rue, box, pine, laurel; for in theſe vegetables, as the leaf does not die in the autumn, it continues to oxygenate the blood, and to ſupply nouriſhment to the bud in its boſom during the fine days of winter, and in the ſpring, and ſurvives till near midſummer; that is, till the new bud has expanded a leaf of its own. Whence I ſuppoſe theſe evergreens lay up in ſummer no ſtore of nutriment in their roots or alburnum for the ſuſtenance of their enſuing vernal buds; and have thence probably no bleeding ſeaſon like deciduous trees.

But the embryon in a bud of a deciduous plant leaves in the ſpring of the year its winter cradle, or hybernaculum, like the embryon in a ſeed, or a chick in the egg; and like theſe the young plants of different vegetables have previouſly arrived at different ſtates of maturity.

rity. Thus Mr. Ferber aſſerts, that he was delighted in obſerving in the buds of hepatica, and pedicularis hirſuta, yet lying in the earth, and in the gems of the ſhrub daphne mezereon, and at the baſe of oſmunda lunaria, a perfect plant of the future year diſcernible in all its parts; thus alſo in horſe-cheſnut the leaves, and in cornel-tree the flowers, are each diſtinctly viſible during the winter in their reſpective buds. Amœn. Acad. Vol. VI. No. CXX. Milne's Dict. Art. Gemma.

While in buds of many other trees, and probably in all the more backward buds, which are formed late in the ſummer on the lower parts of branches, and much deprived of light and air, the embryon is not ſo forward as to be eaſily diſcernible; and in thoſe ſhrubs or trees, which are deciduous in this climate, and yet have no apparent buds in winter, as the philadelphus, mock orange, viburnum, and many ſhrubs. I ſuſpect there is nevertheleſs an embryon ſecreted from the blood at the foot-ſtalk of each leaf, though it is not ſo forward as to protrude through the bark, and produce a prominent bud, or hybernaculum. The ſame I ſuſpect to occur in reſpect to trees, which loſe their leaves in winter, in warmer climates, in which they are ſaid not to produce autumnal buds; as I can not conceive by what means freſh leaf-buds can be generated in the ſpring, when the leaves, which conſtitute the lungs of the mature living part of the tree, are dead; and the whole of that mature living part, or laſt year's bud, conſequently dead along with them. But if the caudex of the new bud be generated without the plumula, or viſible bud, it can certainly produce a plumula for itſelf in the enſuing ſpring, as is ſeen by the production of new buds, when a branch is cut off, round the remaining trunk, as is done frequently to the ſtems of willows.

In ſimilar manner the viviparous offſpring of different animals arrive at different ſtates of perfection before they are born, as calves and foals can ſtand erect in an hour, and quickly learn to uſe their eyes, and to run after their mothers; while the blind puppy, and kitten,

and the downleſs rabbit, are long before they can leave the neſt which the parent has provided for them.

4. The preſence of the pith or medulla is of great importance to the growth of the new bud, as may be obſerved by gradually ſlicing a ſhoot of a horſe-cheſnut in autumn, or in the early ſpring. The rudiments of the ſeven ſeparate ribs of the late parent-leaf, and the central pith of the bud in its boſom, are ſeen to ariſe or terminate near the pith of the parent ſhoot, where the embryon plumula is probably ſecreted by a gland at the bottom of the parent leaf-ſtalk, finds there its firſt reception and nouriſhment, and is gradually protruded and elongated by the pith, which exiſts in its center, as the bud proceeds, and thus conſtitutes the aſcending caudex or uterus of the new bud; which is reſembled by the wires of ſtrawberries, and other creeping vegetables; whereas the deſcending caudexes of the new buds, which form the filaments of the bark of trees, are ſecreted from the various parts of the old bark in their vicinity; all which probably occur at the ſame time by ſympathy, as ſhewn in Sect. VII.

The pith thus appears to be the firſt or moſt eſſential rudiment of the new plant, like the brain or ſpinal marrow, medulla oblongata, which is the firſt viſible part of the figure, I believe, of every animal fetus, from the tadpole to mankind.

In thoſe plants which have hollow ſtems, this central cavity, though not filled with the pith or medulla, appears to be lined with it; as in picris and tragopogon; in the former the ſtem is not only lined with the pith, but wherever a new bud is generated on the ſummit of the aſcending ſtem, or in the boſom of a leaf, a membranous diaphragm divides the cavity, and is covered with this medullary ſubſtance, which diviſion thus diſtinguiſhes one bud from another; and in ſlicing away the part of the ſtem of tragopogon, where the new lateral bud adheres, the medulla or pith in the center of the bud is ſeen to commence near that membrane which lines the ſtem, and to paſs through the circle of arterial, venal, and abſorbent veſſels, which conſtitute

the aſcending caudex, or uterus, of the new bud, while the deſcending caudex of it is ſecreted from the various parts of the older bark in its vicinity.

Something ſimilar to this mode of the production of the buds of trees had not eſcaped the ingenious Mr. Bradley, who aſſerts, "that buds have their firſt riſe in the pith; they are there framed, and furniſhed with every part of vegetation, and forced forwards to meet the air through the tender bark, and would drop on the ground, if they were not reſtrained by veſſels, which ſerve as roots to nouriſh them; and thus as a ſeed takes root in the earth, a bud takes root in the tree; but with this difference, that the ſeed has lobes to ſupply it with nouriſhment, till it can ſelect juices from the earth; but the bud has no occaſion for lobes, becauſe it takes root immediately in the body of the tree, where the proper juices are already prepared for it." Diſcourſes on Growth of Plants, 1727, p. 56.

5. As the ſeed was nouriſhed in the pericarp by an adapted ſecretion from the vegetable blood oxygenated in the bractes or floral-leaves; and as a reſervoir of nutriment was alſo prepared for it afterwards in the ſeed-lobes and fruit: ſo the bud is at firſt nouriſhed in the boſom of its parent-leaf by an adapted ſecretion from the vegetable blood; and continues to be ſo nouriſhed in annual herbs and evergreen trees, till it protrudes and expands its own leaf; but if it be a bud of a deciduous plant, which muſt loſe its parent-leaf in winter, a reſervoir of nutriment is prepared for it in the roots of ſome plants, as in carrots, turneps, liquorice, fern; and probably both in the roots and alburnum, or ſap-wood, of trees.

Thus in the ſpring the umbilical veſſels belonging to each individual biennial plant, or bud of a tree, abſorb moiſture from the earth, and propel it upwards through the roots and alburnum, where it is mixed with a nutritious material, and carried upwards in ſome trees with a power equal to the preſſure of the atmoſphere, as in the vine,

vitis;

vitis; the birch, betula; and the maple, acer; which at that ſeaſon bleed at every wound, as treated of in Sect. III.

6. At this time the buds begin to ſwell, and to ſhoot roots downwards from their caudexes into the earth; the intertexture of theſe caudexes conſtitutes a new bark over the old one, conſiſting of arteries, veins, and abſorbents, as deſcribed in Sect. I. 3. Each bud then alſo puts forth a leaf, which is a reſpiratory organ, and reſembles in many reſpects the lungs of animals, as deſcribed in Sect. IV. but differs from them in this circumſtance, that the leaf requires light as well as air for the purpoſe of perfect reſpiration, as will be treated of in the Section on Light.

Each embryon of a leaf-bud is thus furniſhed with its proper reſpiratory organ; and as many new embryons were generated during the ſummer in each leaf-bud, they now pullulate in ſucceſſion; each of which has like the firſt its appropriate leaf, which, as they ſucceſſively advance, compoſe the annual ſhoots or ſprigs of trees; which in ſome plants become of great length, as in vines, and willows, conſiſting of twenty or thirty new leaves. Hence if the firſt ſet of leaves be deſtroyed by vernal froſts, as frequently happens to aſh-trees, fraxinus, and to the weeping willow, ſalix babylonica; or by the depredation of inſects, which often injures our fruit-trees; and perpetually occurs in this climate to the ſpindle-tree, euonymus; and in Italy to the white mulberry-tree, which has its firſt leaves plucked off for the food of ſilk-worms, and to the tea-tree in China; a ſecond ſet of leaves ſucceeds, which belong to the ſecond embryons of the ſame bud.

But when the bractes or floral-leaves are deſtroyed by inſects, as ſometimes happens to currant-trees, and apple-trees; the fruit in the pericap does not periſh, like the firſt embryon of the leaf-bud above mentioned; becauſe it is ſtill ſupplied by the abſorbent ſyſtem of the caudex and roots of the flower-bud, which compoſe a part of the bark, and paſs into the ground; but the fruit becomes ſour and leſs per-

fect from the want of a due oxygenation of the juices, from which it is ſecreted; though its glands may probably alſo receive ſome oxygenated blood by the inoſculation of the veſſels of different buds, whether flower-buds or leaf-buds, with each other in the bark, on ſuppoſition that they are not all of them totally deſtroyed.

7. In the axilla of each leaf is generally produced about midſummer either a new leaf-bud or a flower-bud; if it be a leaf-bud, it becomes a branch the next year, producing many other leaves, and many other buds; if it be a flower-bud, the growth ceaſes, terminating in the ſeed. During the greater vigour of the plant the leaf-buds are ſolely or principally produced, as in young healthy trees; but when the veſſels of the bark become further elongated, as the plant grows taller, the nutritive juices are leſs copiouſly ſupplied, or the buds are become more mature, and the production of flower-buds ſucceeds as in Mr. Walker's experiments the ſap of the birch-tree in the ſpring was two or three weeks later in aſcending to the top of a high tree, than to the lower branches. Edinb. Tranſact. Vol. I.

Hence it happens, that the grafts from ſtrong ſeedling apple-trees do not bear fruit, till they are twelve or twenty years old; while the grafts from old weak trees will bear copiouſly in two or three years, and hence very vigorous trees, as pears, produce fruit only at their extremities; but if you decorticate about an inch of a branch of a vigorous pear-tree, and thus weaken it; that branch will flower, and bear fruit at every bud like trees of leſs vigour.

It ſhould be here obſerved, that the words ſtrength and weakneſs, when applied to the growth of vegetables, are in reality metaphorical terms; or expreſs the effect or conſequence of their producing leaf-buds or flower-buds, rather than the cauſe of it, whereas it is the facility with which the long caudexes of the new buds, which form the new filaments of bark, can be generated, which increaſes the number of leaf-buds, and gives the tree a luxuriant or vigorous appearance; and the difficulty of generating theſe new caudexes which

increaſes

increaſes the flower-buds, and thus gives a leſs vigorous appearance to the tree.

The generation of buds ſeems to require a leſs perfect apparatus than the generation of ſeeds; as that of buds always precedes that of ſeeds, both in trees and herbs; and becauſe the caterpillar is converted into a butterfly ſolely for the purpoſe of ſeminal propagation; whereas the polypus can only propagate laterally, or by buds. Hence the age of the plant is another neceſſary circumſtance to the production of flowers, fruit, and ſeeds, as appears in tulips, and hyacinths, as well as in apple-trees and pear-trees.

8. About midſummer the new buds are formed; but it is believed by ſome of the Linnean ſchool, that theſe buds may in their early ſtate be either converted into flower-buds or leaf-buds, according to the vigour of the vegetating branch. Thus if the upper part of a branch be cut away, the buds near the extremity of the remaining ſtem, having a greater proportional ſupply of nutriment, and poſſeſſing a greater facility of producing their new caudexes along the bark, will become leaf-buds; which might otherwiſe have been flower-buds; and on the contrary, if a vigorous branch of a wall-tree, which was expected to bear only leaf-buds, be bent down to the horizon or lower, it will bear flower-buds with weaker leaf-buds, as is much exemplified by Mr. Hitt in his Treatiſe on Fruit Trees.

The theory of this curious vegetable fact has been eſteemed difficult, but receives great light from the foregoing account of the individuality of buds. Both the flower-buds and leaf-buds die in the autumn; but the leaf-buds, as they advance, produce during the ſummer other leaf-buds or flower-buds in the axilla of every leaf; which new buds require new caudexes extending down the bark, and thus thicken as well as elongate the branch; whereas the flower-buds ſhed their ſeed, when they periſh in the autumn, and thus require no place on the bark for new caudexes. Hence when the ſummit of a branch is lopped off, the buds near the extremity of the remaining

ſtem produce new leaf-buds with greater facility, as there is more room for their new caudexes to be generated along the deſcending bark. But if a vigorous branch be bent down to the horizon, or below it, the bark is compreſſed beneath the curve, and extended above it, and thus the production of new caudexes along the bark is impeded, and in conſequence leſs leaf-buds and more flower-buds will be generated, or the former converted into the latter; which require no new caudexes. And on this circumſtance principally depends the management of wall-fruit trees, and of eſpalliers.

For the purpoſe of thus converting leaf-buds into flower-buds Mr. Whitmill adviſed to bind ſome of the moſt vigorous ſhoots with ſtrong wire, and even ſome of the large roots; and Mr. Warner cuts, what he calls, a wild-worm about the body of the tree; or ſcores the bark quite to the wood like a ſcrew with a ſharp knife. Bradley on Gardening, Vol. II. p. 155. Mr. Fitzgerald produced flowers and fruit on ſtandards and wall-trees by cutting off a cylinder of the bark, three or four inches long, and replacing it with proper bandage, (Philoſ. Tranſ. Ann. 1761) as deſcribed in Sect. XV. 1. 3. of this work. M. Buffon produced the ſame effect by a ſtraight bandage put round a branch, Act Paris, Ann. 1738; and concludes that an ingrafted branch bears better from its veſſels being compreſſed by the callus produced, where the grafted ſcion joins the ſtock.

It is cuſtomary to debark oak-trees in the ſpring, which are intended to be felled in the enſuing autumn; becauſe the bark comes off eaſier at this ſeaſon, and the ſap-wood, or alburnum, is believed to become more durable, if the trees remain till the end of ſummer from their expending their ſaccharine ſap-juice in the enſuing foliage, and thus being leſs liable to ferment and putrify. The trees thus ſtripped of their bark put forth ſhoots as uſual with acorns on, the ſixth, ſeventh, and eighth joint, like vines; but in the branches I examined the joints of the debarked trees were much ſhorter than thoſe of other oak-trees; the acorns were more numerous; and no

new

new buds were produced above the joints which bore acorns. From hence it appears that the branches of debarked oak-trees produce fewer leaf-buds, and more flower-buds; which muſt be owing to the impoſſibility of their producing new caudexes down the naked branches and ſtem for the embryon progeny of leaf-buds.

The pullulation of leaves on debarked oaks demonſtrates, that the reſervoirs of nutriment depoſited in the preceding ſummer for the uſe of the vernal buds muſt be in this alburnum; and that it is this ſaccharine matter which induces the alburnum to ferment and rot ſooner than the internal wood. Thus Dr. Walker found on nice inſpection the ſap-juice to flow from the ligneous circles of the alburnum as well as between them, when a freſh piece was cut off from a cicatrized part, and alſo between the wood and the bark. Edinb. Tranſact. Vol. I. He alſo obſerved that oak, aſh, elm, aſpen, hazel, and hawthorn, do not bleed; and that the birch, plane, and maple bleed the moſt, and that the grey willow, ſalix caprea, does not bleed, but the ſap-juice riſes viſibly between the wood and the bark, ſo as to make the bark ſeparate eaſily from the wood. From all theſe facts it may be inferred, that the ſaccharine matter, which is diſſolved in the ſap-juice, is depoſited in the autumn in the roots of ſome trees, and in the alburnum of others, or in both; as manna is found in the wood of the manna-aſh; and ſugar in the joints of many graſſes and of the ſugar-cane, and in the roots of liquorice, beets, and many other herbaceous vegetables.

9. About Midſummer, after the new buds appear in the boſom of every leaf, many authors have remarked that there ſeems to be a kind of pauſe in vegetation for about a fortnight, which they have aſcribed to different cauſes. At this time I ſuſpect the reſervoir of nouriſhment for the new buds is forming about the roots or in the alburnum of the tree; and that the caudexes and umbilical veſſels of the new buds are alſo at this time forming down the bark, and terminate in thoſe nutritious reſervoirs in the roots or new alburnum like the

umbilical

umbilical veſſels called ſeminal roots, which are viſible in many ſeeds.

That this ſyſtem of umbilical veſſels is poſſeſſed of a great power of abſorption in the roots of trees is certain from the force, with which the ſap-juice was propelled upward from a vine-ſtump in Dr. Hales' experiment. That the ſap-juice thus propelled upwards nouriſhes or expands the leaf of each new bud appears from the experiments of Dr. Walker; as the leaves began to unfold at the ſame height, as the wounded wood began to bleed, and that theſe veſſels paſs through or conſtitute the ſap-wood is evinced by the growth of the buds on oak-trees, after the bark is almoſt totally taken off.

The roots of trees are at this time protruded with greater vigour, as obſerved by the ingenious Mr. Bradley, who on that account prefers the midſummer ſeaſon for tranſplanting trees, if they are not to be removed to any great diſtance; and adds, that the new ſhoots in the following ſpring will put forth with much greater force, and the tree will thence be almoſt a year forwarder in its growth, than if it remains untranſplanted till the winter. Diſcourſes on Earth and Water. This ſeems to be owing to the deſtruction of much of the nutritious matter depoſited in the roots for the uſe of the new buds, which is torn off in tranſplanting, and which can only be replaced about Midſummer or ſoon after.

Mr. Bradley further adds, that when trees are thus tranſplanted at Midſummer, no part of the top or branches, or foliage, ſhould at that time be cut off; which well accords with the theory above delivered; as it is from the vegetable blood, which is oxygenated by its expoſure to the air through the thin moiſt pellicle on the upper ſmooth ſurfaces of theſe leaves, that the nutriment for the expanſion of the buds in the ſucceeding ſpring is ſecreted or produced; and hence if theſe leaves are prematurely deſtroyed, the vernal growth of the buds muſt receive injury; as the reſervoir of future nutriment for them will be leſs in quantity; but if ſome of the branches are lopped

lopped during the winter, the remainder will protrude more vigorous ſhoots, as their ſhare of the reſerved nutriment will be greater.

10. The umbilical veſſels of the new buds of deciduous trees, which are analogous to thoſe which permeate the lobes of the ſeed, are extended downward in the bark about midſummer, and terminate in certain reſervoirs of nutriment, which are at this time ſecreted from the vegetable blood oxygenated in the leaves. This bark now conſiſts of an intertexture of the caudexes of the preſent leaves, which were buds in the laſt ſummer, and are now adult vegetable beings; and of the embryon caudexes of the new buds; and of the umbilical veſſels of the new buds; it will become alburnum or ſap-wood during the autumn or enſuing ſpring, and will be gradually covered over with a new bark conſiſting of the mature caudexes of the new buds, while that, which was the alburnum in the preceding ſpring, will become a circle of lifeleſs timber, interior to the circle of alburnum.

The veſſels of this new bark, though they conſiſt of the caudexes of the individual adult leaves, and the umbilical veſſels of the individual young buds, evidently inoſculate; becauſe, when ſome buds are rubbed off or deſtroyed, thoſe in their vicinity grow with greater vigour; as the daily experience of pruning all kinds of trees evinces. The facility with which the ruptured veſſels of vegetables inoſculate into each other, or grow together, correſponds with that of animal veſſels in their inflamed ſtate. Thus a bud taken from one tree, and inſerted into any part of the bark of another tree of the ſame genus, or ingrafted on it, preſently receives nutriment, and grows to it by the reciprocal inoſculation of the wounded veſſels, in the ſame manner as a tranſplanted tooth; or as the fingers are liable to grow together after having been excoriated by a burn; or as the inflamed lungs and pleura are liable to adhere, and intermix their blood-veſſels. See Sect. III. 2. 7.

During the winter, when the leaves die and fall off, the arterial and venous ſyſtems, which belonged to them, and which compoſed the

greateſt part of the bark, ſeem to loſe their vegetable life at the ſame time, and to coaleſce, and form the alburnum, or ſap-wood; but the umbilical veſſels belonging to the new buds, which are intermixed with this alburnum, remain alive; and at the returning ſpring act with aſtoniſhing vigour; as deſcribed in Sect. III. 2. 2.

As the ſpring advances, the umbilical veſſels, after having drank up the reſervoirs of nutriment, which were depoſited about the roots, and having thus nouriſhed and expanded the new leaves, ceaſe to act; and the alburnum gradually changes into hard wood, called the heart of the tree; which no longer poſſeſſes vegetative life; and is now only uſeful to elevate and ſuſtain aloft the ſwarm of biennial plants, which cover it; and was probably originally produced for this purpoſe in the conteſt of all vegetables for light and air.

This inert or lifeleſs ſtate of the central parts of trees, called the heart-wood, is evident from thoſe old oaks and willows, which have loſt their internal hard wood, and are become quite hollow, conſiſting only of their bark and alburnum, and yet are furniſhed with many healthy branches. But the umbilical veſſels of the alburnum poſſeſs the properties of capillary tubes, or of a ſponge, after they are extinct, and ceaſe to act as umbilical veſſels; and thus may occaſionally attract moiſture, or ſuffer it to paſs through them mechanically; whilſt the new bark, which conſiſts of an intertexture of the caudexes of each bud with their radicles, may occaſionally abſorb this moiſture from the capillary veſſels of the alburnum, which may be compared to the upper ſtratum of the ſoil attracting by capillary power the moiſture from the ſoil immediately beneath it, which may exhale into the atmoſphere, or be imbibed by the roots of vegetables by the ſuperior living power of their abſorbent mouths.

That the veſſels of the alburnum in their living ſtate poſſeſs the property of conveying the ſap-juice, which is propelled upwards in the early ſpring by the abſorbent terminations of the roots, is viſible in decorticated oaks; the branches of which expand their buds, like

thoſe of the birch and vine in the bleeding ſeaſon. That the veſſels of the alburnum in their living ſtate occaſionally act as capillary ſyphons, through which the ſap-juice is firſt puſhed upwards by the abſorbent extremities of the roots, and afterwards returns downwards partly by its gravitation in branches bent below the horizon, appears from an experiment of Dr. Walker, mentioned in Sect. III. 2. 4.

Laſtly, that the veſſels of the alburnum after their vegetable life is extinct, poſſeſs a power of capillary attraction of the ſap-juice, or of permitting it to paſs through them occaſionally, appears from the following experiments. Firſt, a branch of a young apple-tree was ſo cankered, that the bark for about an inch quite round it was totally deſtroyed. To prevent the alburnum from becoming too dry by exhalation, this decayed part was covered with thick white paint; in a few days the painting was repeated, and this three or four times, ſo as to produce a thick coat of paint over the decayed part, or naked alburnum, extending to the aſcending and deſcending lips of the wound; this was in ſpring, and the branch bloſſomed and ripened ſeveral apples.

In a garden in Lichfield about four years ago a complete cylinder of bark about an inch long was cut from a branch of a pear-tree nailed againſt a wall; the circumciſed part is now not more than half the diameter of the ſame branch above and below it; yet this branch has been full of fruit every year ſince, when the other branches of the tree have borne only ſparingly. I lately obſerved, that the leaves of this wounded branch were ſmaller and paler, and the fruit leſs in ſize, and ripened a fortnight ſooner, than on the other parts of the tree. Another branch of the ſame tree has a part of the bark taken off about an inch long, but not quite all round it, with much the ſame effect.

The exiſtence of capillary tubes in dead ſap-wood is viſible in a piece of dry cane, which permit water or ſmoke to paſs through them; and in the exhauſted receiver of an air-pump both water and

quickſilver may be made readily to paſs through pieces of the dry alburnum of wood by the preſſure of the atmoſphere.

11. The flower-buds of many trees ariſe immediately from the laſt year's terminal ſhoots, or ſpurs, either accompanied with leaf-buds, or ſeparately, as in apple and pear-trees. Other flower-buds ariſe from the ſhoots of the preſent year alternately with leaf-buds, as thoſe of vines, and form the third or fourth buds of the new ſhoots. They differ from leaf-buds in this circumſtance, that they periſh when their ſeeds are ripe, without producing any addition or increaſe to the tree; whereas when the leaf-buds periſh in the autumn, their caudexes, the intertexture of which conſtitutes the bark of the tree, gradually become converted into alburnum, or ſap-wood; over which the new leaf-buds ſhoot forth their caudexes and radicles, or inſert them into it, and gradually fabricate the new bark and root-fibres.

It was before mentioned, that it is believed by ſome diſciples of the Linnean ſchool, that about Midſummer leaf-buds may be changed into flower-buds, or flower-buds into leaf-buds; and that even after the vegetable embryons are generated. And that this may be effected by weakening or ſtrengthening the growth of the laſt year's buds, which ſecrete theſe new ones from the vegetable blood, and nouriſh them in their infant ſtate. Thus if ſome inches of the extremity of a branch be lopped off at Midſummer, as is ſometimes done by unſkilful gardeners, the remaining few buds will become more vigorous, and conſequently produce leaf-buds inſtead of flower-buds; or perhaps the embryons already formed may be converted from one kind to the other. The contrary may occur, if a vigorous branch of a wall-tree be bent down beneath the horizon, or ſo much as to impede the generation of new caudexes; or if the leaf of the parent-bud be taken off, ſoon after the plumula or apex of the new bud is generated; and thus the new caudex along the bark may be prevented by deficiency of nutriment.

The probability of this idea of tranſmuting flower-buds and leaf-

buds

buds into each other is confirmed by the curious converſion of the parts of the flowers of ſome vegetable monſters into green leaves; if they be too well nouriſhed, after they are ſo far advanced as to be unchangeable into leaf-buds. Thus in the plantago roſea, roſe-plantain, the diviſions of the ſpike become wonderfully enlarged, and are converted into leaves; the chaffy ſcales of the calyx in xeranthemum, everlaſting, and in a ſpecies of dianthus, pink, and the glume of ſome alpine graſſes, and the ſcales in the ament of the ſalix roſea, roſe-willow, grow into leaves, and produce other kinds of vegetable monſters.

Add to this, that the petals of the helleborus niger, or chriſtmas-roſe, are beautifully white till the ſeed is impregnated; and then they change into green leaves, forming a calyx. And laſtly, in other flowers a bud or bulb ſucceeds the impregnation inſtead of a ſeed, as in polygonum viviparum, viviparous biſtort; and in allium magicum, magical onion; the ſame occurs in many of the alpine graſſes, and in the feſtuca dumetorum, feſcue graſs; all which are in ſome degree analogous to the ſuppoſed converſion of early flower-buds into leaf-buds; for in theſe magical onions, and other bulbiferous flowers, the bractes or floral-leaves, which at firſt ſecrete nouriſhment for the pericarp and ſeeds of the plant, aſſume a new office, and ſecrete a magazine of nouriſhment for the new bulb, as appears in the concentric fleſhy membranes, which ſurround the new ſummit-bulbs of the allium magicum, and the cloves of garlic.

12. The central part of an adult bud therefore conſiſts firſt of a conjunction of the blood-veſſels from above and below, which exiſts in the caudex of the bud between the beginning of the leaf-veſſels and the beginning of the root-veſſels; the circulation reſembling that of many inſects, of fiſh, and in the livers of quadrupeds, as ſhewn in Sect. V. 2. Secondly, there is probably at the ſame place a conjunction of the abſorbent veſſels correſpondent to the receptaculum chyli of animals. Thirdly, there exiſts in each bud an organ

of

of reproduction, which in a leaf-bud produces the lateral or paternal offspring, and in a flower-bud the ſeminal or amatorial one. Fourthly, a center of nervous influence, as a brain, or ſpinal marrow, or common ſenſorium, exiſts in each bud; and probably reſides near this junction of the blood-veſſels of the leaf and root, and of the abſorbent ſyſtem, along with the organ of reproduction in the caudex gemmæ.

III. 1. THE BULBOUS ROOTS of ſome perennial herbaceous plants, and the root-ſcions of other perennial herbaceous plants, are ſimilar in this reſpect, which diſtinguiſhes them from buds; that they are generated on the broad caudex of the plant within the ground, or in contact with it, and immediately ſhoot down their new roots into the earth. Whereas buds are formed above the ſoil on the long caudexes, which conſtitute the filaments of the bark of trees, and ſhoot down new roots into the earth from the lower end of theſe elongated caudexes.

Bulbs have not improperly been called ſubterraneous buds; and like them they may be divided into leaf-bulbs and flower-bulbs. When a tulip-ſeed is ſown, it produces a ſmall plant the firſt ſummer, which in the autumn dies, and leaves in its place one or more bulbs. Theſe are leaf-bulbs, which in the enſuing ſpring riſe into ſtronger plants than thoſe of the firſt year, but no flowers are yet generated; in the autumn theſe periſh like the former, and leave in their places other leaf-bulbs ſtronger, or more perfect, than their preceding parents. This ſucceſſion of leaf-bulbs continues for four or five years, till at length the bulb acquires a greater perfection or maturity, neceſſary for ſeminal generation, and produces in its place a large flower-bulb in the centre with ſeveral ſmall leaf-bulbs around it.

This ſucceſſive formation of leaf-bulbs in bulbous rooted plants previous to the formation of a flower-bulb is curiouſly analogous to the production of leaf-buds on many trees for ſeveral years before the production of flower-buds; thus the apple-trees, pyrus malus, which are raiſed from ſeeds, generate only leaf-buds for ten or twelve years, and

and afterwards annually generate both flower-buds and leaf-buds. From whence it would ſeem, that the adherent lateral or paternal progeny is the moſt ſimple, and eaſieſt, and conſequently the firſt mode of reproduction; and that the amatorial or ſeminal progeny is on this account not generated till the maturer age or more perfect ſtate of the parent-bud.

A ſtill more curious analogy to this circumſtance of a ſucceſſion of leaf-buds and leaf-bulbs preceding the formation of flower-buds and flower-bulbs exiſts in the growth of wheat, triticum, and other graſſes; but with this difference, that a ſucceſſion of leaf-buds, as of two, or three, or four, are produced in the ſame year previous to the flower-bud. At the firſt joint of the ſtem of wheat, on or within the ſurface of the earth, a leaf is produced; from which riſes the principal or central bud, and around it many new buds, which ſtrike their roots into the ſoil. After this central bud, and thoſe around it, have ariſen ſix or eight inches, a new leaf and a new leaf-bud riſes on each of them, producing a ſecond joint of the ſtem; and laſtly, a flower-bud is generated at the ſummit, which are all evidently diſtinct vegetable beings, as there is a diviſion acroſs the ſtem at each joint, which ſhews there is no connexion of the pith, or brain, or ſpinal marrow, between the lower and upper joints, as mentioned in Sect. I. 8.

That a new bud thus conſtitutes each joint of the ſtem of wheat, and other graſſes, is further evinced; firſt, by the exiſtence of a leaf at each joint without a lateral bud in its axilla, as occurs in other vegetables. Secondly, becauſe for the nouriſhment of this new leaf-bud a reſervoir of ſweet-juice is prepared in the new joint; as in the bulbs of many plants. And thirdly, becauſe the lower leaf dies, and the ſweet juice is abſorbed, as the upper leaf becomes vegete. Hence we acquire the knowledge of the uſe of this reſervoir of ſugar in the vegetable economy, which ſupplies ſo much agreeable and ſalu-

tary

tary nouriſhment to mankind from the cultivation of the ſugar-cane. See No. 1. 6. and No. 3. 7. of this Section.

The analogy between the buds of plants and the adherent lateral progeny of ſome inſects, as of the polypus, and tenia, or tape-worm, and volvox, was mentioned in Sect. VII. 1. 4. But the circumſtance of the ſucceſſive production of leaf-buds and leaf-bulbs previous to the production of flower-buds or flower-bulbs is wonderfully analogous to the generation of the aphis, which riſing from an egg in the ſpring after caſting its ſkin once or twice produces a living progeny without amatorial copulation; and this offspring produces others by this ſolitary propagation till the tenth generation; then a ſexual progeny of males and females is produced, and eggs are laid in the autumn from their amatorial intercourſe. Encycloped. Britan. Amœnitat. Academ. Vol. VII. by A. T. Bladh. See Sect. XIV. 3. 2. Thus this inſect from the egg requires to be reproduced many times by ſolitary propagation before it becomes ſufficiently perfect to generate a ſexual offspring like the buds and bulbs from ſeeds above mentioned. And it is probable, that the polypus of our ſtagnant waters, which produces a lateral offspring in the ſummer, I ſuppoſe by ſolitary propagation, may produce males and females, and generate eggs in conſequence in the autumn for their reproduction in the enſuing ſpring.

To this may be added the great change, which many inſects and even larger animals undergo either in ſtrength or form, before they acquire the power of ſeminal reproduction. As the ſilk-worm changes into a butterfly apparently for the purpoſe of generation only, as it then performs this office and dies. Other caterpillars change their form likewiſe into butterflies, and at the ſame time change their kind of food, which was the green foliage of vegetables before this tranſformation; but now conſiſts ſolely of honey. And laſtly, the gnat and muſqueto change at the ſame time both their forms, their food, and their element; and thus acquire higher animation apparently for the purpoſe of ſexual reproduction.

2. The

2. The manner of the production of herbaceous plants from their various perennial roots wants further inveſtigation, as their analogy is not yet clearly aſcertained. I this autumn diſſected two large roots of the onion or leek kind, which were in full flower; the ſtem of each of them was embraced by the cylindrical pedicles of ſix or ſeven concentric leaves; but the ſtem itſelf aroſe from the center between three large new bulbs in one of them, and between two in the other. All of which grew from the ſame caudex, but the central flower-ſtem was wrapped at its bottom in one membrane only, which ſeparated it from the new bulbs in its vicinity.

A large root of a young onion, which grew from ſeed ſown in the ſpring, was at the ſame time diſſected by ſtripping off the leaves, and their fleſhy baſes, one after another, till two buds were viſible in the center of the fleſhy baſes of the concentric leaves, which formed the bulb. Theſe two bulbs were evidently formed and nouriſhed on the caudex by the ſtem, and its ſix or ſeven concentric cylindrical leaves; and will, I ſuppoſe, ſeparate in the ſpring, as they riſe up, and produce each of them a flower with two or three new bulbs at the baſe of it, as deſcribed in the above paragraph.

Or from the different ſize and apparent greater maturity of the central bulb, and the ſecondary bulb being between the innermoſt and the ſecond circular fleſhy membrane, I ſuppoſe in theſe roots of onion, like the tulip-roots before ſpoken of, that the central bulb alone may produce a flower in the next ſummer; and that the lateral bulb or bulbs will produce only ſtronger and more mature leaf-bulbs, which will in the ſucceeding ſummer bear a flower or ſexual progeny.

The caudex, or central part of the bulb, from which the root-fibres deſcend, and the leaves aſcend, lies above the knot in the orchis morio; and the parent-root ſhrivels up and dies, as the young one increaſes. The flower of this plant does not ripen its ſeeds in this climate; it might be otherwiſe worth cultivation for the uſe of the

new roots; which when ſcalded and peeled, are ſaid to be the ſalep of the ſhops. It is aſſerted by one of the Linnean ſchool in the Amœn. Academ. that if the new root be pinched off, the ſeeds on the old one will ripen, and become prolific.

In the tulip the caudex lies below the bulb, from whence proceed the fibrous roots and the new bulbs; the root after it has flowered dies like the orchis root; for the ſtem of the laſt year's tulip lies on the outſide, and not in the center of the new bulb. In the tulip-root, diſſected in the early ſpring, juſt before it begins to ſhoot, a perfect flower is ſeen in its center; and between the firſt and ſecond coat the large next year's bulb is, I believe, produced; between the ſecond and third coat, and between this and the fourth coat, and perhaps further, other leſs and leſs bulbs are viſible, all adjoining to the caudex at the bottom of the mother bulb; and which I am told, require as many years, before they will flower, as the number of the coats with which they are covered; and that the ſame different ſtates of maturity probably obtain in the buds round the ſhoots of many fruit-trees, the central one of which will produce flowers the next year as on the ſpurs of apple-trees; while thoſe beneath it require more or fewer years, before they become ſufficiently mature to produce organs of ſexual generation; an important ſecret in the management of fruit-trees.

The hyacinth-root differs from the tulip-root; for, as I am informed, the ſtem of the laſt year's flower is always found in the center of the root, as in the onions above deſcribed; and that the new offſets ariſe from the caudex below this bulb, and not between any of the concentric coats of it, except the two external ones. On this account the central part is liable by its decay to deſtroy the flower-bud, if not taken out of the earth, when the leaves die; and hence ſome floriſts believe, that theſe roots periſh naturally in five or ſeven years, after they have flowered, but that the tulip-root never dies from age.

In

In a few roots of hyacinths, which I this day examined, September 1, the ſtem of one, which had apparently flowered in the ſummer, was perfectly decayed in the center of many new bulbs. In another bulb of leſs ſize and compact, which I ſuppoſed had not born a flower, I found a central flower-bud incloſed in many concentric fleſhy baſes of former leaves, like an onion in the autumn, which had been ſown in the preceding ſpring. And concluded from hence, that the hyacinth-root dies annually or biennially like the onion, leaving behind it a ſucceſſion of leaf-bulbs or of flower-bulbs.

The caudex and claw-like roots of the ranunculus cultivated by floriſts dies I believe annually, after having put forth a circle of new claws from the upper part of it round the bottom of the periſhing flower-ſtem. Hence the claws of the old root, which became ſhrivelled, as the flower advanced, in the autumn diſappear; and the decayed part of the old caudex is ſeen beneath the new claw-like roots, which I ſuppoſe has given occaſion to ſome inaccurate obſervers to believe, that the old ſtem in this and ſome other perennial herbaceous plants was drawn downwards by the new root fibres; while the bulbs of the iris have been ſuppoſed to have been puſhed upwards, like the lamb-like barometz, by the reſiſtance of the ſoil to the elongation of the root-fibres; which laſt ſeems to be a much more probable idea than the former.

From theſe obſervations it appears, that the concentric leaves, which incircle the ſtems of bulb-rooted plants, are the lungs to the caudex, as one or more leaves are to the bud of a tree; and that the caudex with theſe leaves, and the root-fibres, conſtitute a vegetable being; which produces a viviparous progeny of new leaf-bulbs, or a ſeminiferous progeny in flower-bulbs, with a magazine of nutriment in the fleſhy baſe of each leaf; and that the tulip produces only leaf-bulbs for four or five years from the ſeed, and then but one flower-bulb with many leaf-bulbs annually. But that the onion-kind, allium, generates two or three flower-bulbs in the firſt ſummer from

the ſeed; which produce flowers and other leaf-bulbs in the ſecond ſummer from the ſeed. And laſtly, that it is probable, that all bulbous roots, like the buds of deciduous trees, and perhaps of evergreen ones alſo, are properly ſpeaking biennial plants, as they riſe in one ſummer and periſh in the next.

3. In tulip-roots, which have been planted too deep in the earth, and in onion-roots, a vegetable cord, or proceſs, is ſometimes ſeen about an inch long to ariſe from the caudex beneath the baſes of the cylindrical leaves, and to form a new bulb. Similar to this appears the natural growth of the roots of potatoes; a ſpermatic cord ariſes from the old root, after the leaves are expanded in the air, to oxygenate the vegetable blood, and a new tuberous or bulbous root is thus generated.

This mode of producing diſtant roots is exactly reſembled above ground by the wires of ſtrawberries; which may be called ſpermatic cords, which depoſit a new vegetable being on the earth, and ſupport it like a bud on a tree, till it can ſtrike roots into the ſoil, and elevate leaves into the air. The final cauſe of the length of theſe ſubterraneous and aerial ſpermatic cords is evidently the deſign of placing their roots at a convenient diſtance from their parent plants; that they may not incommode each other, but may both of them more readily acquire nutritious juices from the earth, and the ventilation and ſunſhine of the atmoſphere.

Theſe embryon vegetables in the various bulbous and tuberous roots are in very different ſtates of maturity, as in the buds of different trees; thus in the potatoe the corculum or plumula of the new plant only is viſible, ſurrounded with a farinaceous nutriment, as in many ſeeds; whereas in the tulip and hyacinth the flower of the ſucceeding year is diſcernible, as in the bud of the horſe-cheſnut.

As the ripening of the ſeed of ſome bulbous-rooted plants is forwarded by deſtroying the new bulbs, as in orchis; and the flowering bulbs of other plants are made ſtronger by raiſing them out of the earth,

earth, and taking away the leaf-bulbs, which ſurround them on the ſame caudex; as in the cuſtomary management of tulip-roots, and hyacinth-roots by the floriſts; I was led to ſuſpect, that pinching off the flowers of potatoes two or three times might increaſe the ſize or quantity of the roots; as the nouriſhment derived from the vegetable blood to the flowers and ſeeds might thus be directed to enlarge the roots, and thus lay up more nutriment for the future plants. This idea I mentioned to an ingenious Lady, who acquainted me a few months afterwards, that on a few roots ſhe had made this experiment with apparent advantage.

4. The bulbous and tuberous roots of plants are a lateral or paternal progeny like the buds of trees, and therefore exactly reſemble the parent plant, as mentioned in Sect. III. 2. 1. and on this account may be liable to be affected by hereditary diſeaſes, and thus to become unhealthy; whence the canker is ſuppoſed to ariſe in thoſe apple-trees, which have for a century or two been propagated by grafting; and the curled leaf in potatoes, which have been too long propagated by their bulbs; and the barrenneſs of hautbois ſtrawberries, which have too long been propagated by wires; all which diſeaſes are believed not to happen in theſe plants, if they have recently been raiſed from ſeed, but want further obſervations to authenticate the facts.

But there exiſts a ſet of bulbs, which ſeem to be formed by amatorial or ſeminal generation, and not by the lateral or paternal generation, and would therefore ſeem to be a viviparous ſexual progeny. Theſe are produced on the flower-ſtem in the place of ſeeds; and in proceſs of time fall off, and take root in the earth, as is agreeably ſeen in the polygonum viviparum, viviparous biſtort, and the magical onion, allium magicum, and the leek, allium ſativum. A curious queſtion here occurs, whether the plants from theſe bulbs are liable exactly to reſemble their parents? and whether they would be liable to hereditary diſeaſes from a long cultivation of them in ſucceſſion, as is ſuppoſed to happen to thoſe mentioned above?

Though

Though a perfect flower precedes the product of ſome ſummit-bulbs, as I believe in the lower part of the ſpike of the polygonum viviparum; yet I ſuſpect, that the ſummit-bulbs of allium magicum, are exactly ſimilar to the bulbs, which are produced at their roots; becauſe on cutting one of them horizontally into two hemiſpheres this morning, September 10, I obſerved three young bulbs incloſed in the concentric fleſhy membranes of the ſummit-bulb in the following manner; five thick fleſhy concentric coats of the general ſummit-bulb being taken away, there appeared one ſingle naked ſmall bulb; and on the ſixth coat being removed, two other bulbs became viſible, which were included in it. Whence it ſeems, that theſe ſtem-bulbs are as forward as thoſe of the root, and probably are in every reſpect ſimilar; and that the bractes or floral-leaves, which in ſeed-bearing plants ſecrete or prepare a nouriſhment for the ſeed, and pericarp of the flower, acquire in theſe bulbiferous onions and leeks a new office, and prepare a magazine of nouriſhment in the concentric membranes, which ſurround their ſummit-bulbs; and theſe may be eſteemed therefore a ſexual viviparous progeny of vegetables, as buds are a lateral viviparous progeny.

5. The roots of trees ſo reſemble their branches, that ſubterraneous buds are frequently produced upon them, which reſemble the parent-tree. The bark of the root likewiſe ſo reſembles the bark of the branches, that it is not uncommon to ingraft with ſucceſs on roots taken out of the earth and replanted; as the robinia on the root of the acacia, and any other apples on the roots or the ſuckers of bur-apples or of codlings; which may be done earlier in the vernal months, as being leſs liable to injury from froſty nights; and it is probable, that budding or inoculating may be performed in the ſame manner on the roots at midſummer, as on the branches.

The roots of thoſe plants, which are otherwiſe not eaſily propagated, will ſhoot up buds, if a part of them next to the plant be half cut through, or raiſed out of the ground, and expoſed to the air; as

in pyramidal campanula, and geranium lobatum; and after a time the root may be ſeparated from the ſtock, and many new plants may be this way produced.

Theſe root-buds, or ſuckers, are generally produced near the trunk of the tree, before the root deſcends much beneath the ſoil; but in ſome trees, as the elm, ulmus, and acer, maple, whoſe roots ſpread far horizontally, and near the ſurface of the earth, they are generated at a great diſtance from the parent tree; becauſe the new ſcion can thus ſoon acquire the influence of the atmoſphere on its expanding foliage. Theſe root-ſcions from apple-trees are frequently uſed in vegetable nurſeries for the purpoſe of ingrafting upon, and are termed paradice-ſtocks by ſome gardeners; but are not liable to the canker like the grafts from thoſe old apple-trees, which have been in faſhion above a century; as theſe root-ſcions reſemble the trunk of the tree, which produces them, not the ingrafted head of it; and thus may not have been many years from the ſtate of a ſeedling vegetable.

Similar to theſe root-ſcions of trees it is probable, that the root-buds of perennial herbaceous plants are produced; which have divaricated, or fibrous-roots, and whoſe ſummits periſh in the winter. For many years the root thickens by an annual new bark being induced over the old one, exactly as in the trunks and roots of trees.

As theſe roots increaſe in ſize, the central part, I ſuppoſe, changes like the internal wood of a tree, and ceaſes to poſſeſs vegetable life; and in proceſs of time is liable to decay. On this account theſe perennial roots are not ſo valuable for the purpoſes of medicine or diet, or mechanic arts, either before or after they have paſſed a determinate age; as the bark of the root changes annually into a kind of alburnum, and then into a kind of wood, and laſtly, is liable to decay, as occurs in the roots of rheum palmatum, when they are ſeven or more years old. See Sect. XVII. 2. 1. This decay of the central part of the root, which happens annually to ſome plants, and is ſurrounded with new buds and their root-fibres, exhibits the appearance of the lower

lower end of the root having been chopped, or bitten off, to ſome fanciful botaniſts; as in plantago major, and valerian; and has hence given to ſcabioſa ſucciſa the name of devil's-bit, morſus diaboli.

6. The bulbs already mentioned, as thoſe of tulips, hyacinths, and onions, are properly the winter-cradles, or hybernacula, of the young plants, whether in their leaf-bulb or flower-bulb ſtate; and are furniſhed with a magazine or reſervoir of nouriſhment for the growing embryons, as appears in the ſquil, ſcilla maritima, which vegetates from this ſource of nutriment in the druggiſts ſhops. But there are other roots termed tuberous roots, as of turnep and carrot, which conſiſt ſolely of a large reſervoir of nutriment for the growth and nouriſhment of the riſing ſtem and future ſeeds; whether theſe are produced in the ſame year, as occurs, when the ſeeds are ſown early in the ſpring; or when their vegetation is ſtopped by the cold of winter, and proceeds again in the enſuing ſpring; as generally occurs to our turneps, the roots of which I am well informed may be much enlarged by tranſplantation. See Sect. XII. 6.

In theſe plants the leaves, by expoſing the vegetable blood to the influence of the air, prepare it for the ſecretion of nutriment in their knobby roots; in the ſame manner as nouriſhment is produced and reſerved in the concentric fleſhy baſes of the leaves of onions; and in theſe plants, as in the onion kind, the leaves, which ſurround the baſe of the new ſtems, wither and die; as the new buds, or bulbs, put forth leaves of their own for the purpoſe of oxygenating their blood. Thus it appears, that the ſtem and flower of the onion, or carrot, or turnep, is a new plant, not ariſing immediately from the ſeed which was ſown, but from the leaf-root or leaf-knob, if it may be ſo called, which preceded the production of the flower-bud, or flower-ſtem, exactly as the flower or ear of wheat, which was ſhewn in Sect. IX. 3. 1. to have three or four ſucceſſive leaf-buds preceding the flower-bud.

From theſe obſervations may we conclude, that no flower-bud or flower-

flower-bulb is ever produced from a ſeed, without the previous interpoſition of one or more leaf-buds or leaf-bulbs? and that thoſe flower-buds or flower-bulbs are either produced in one generation after ſowing the ſeed, as the flower-bulbs of onions, which are generated and nouriſhed at the baſes of the concentric cylindrical leaves of the preceding leaf-plant, which aroſe from the ſeed; or as the ſtems and flower-buds of the carrot and turnep, which are generated and nouriſhed at the baſe of the concentric leaves of the preceding leaf-plant. Or ſecondly, that they are produced in one ſummer, though after ſeveral generations from the ſeed; as the three or four joints of the ſtem of wheat, and other graſſes, which are generated and nouriſhed in ſucceſſion in the boſoms of four or five cylindrical leaves, one at each joint; which alſo probably obtains in all other vegetables, which are ſupported by hollow ſtems divided by joints, and furniſhed with leaves at theſe ſtem-joints with or without branches, as tragopogon or picris. In theſe plants, where there are no branches, there is ſimply a new central bud; and two or more lateral new buds beſide the central one, where there are branches.

Or laſtly, where the leaf-buds or leaf-bulbs, which are produced from ſeeds, ſucceed each other for ſome years, before they arrive at ſufficient maturity to produce ſexual organs, or generate a flower, as in the bulbs of tulips, and hyacinths, and the buds of trees. Whence we at length acquire a diſtinct idea, why ſeedling apple-trees are ten or twelve years before they bear fruit; though the buds or ſhoots taken from a tree, which already has born fruit, and ingrafted even on a young ſeedling-tree, ſhall produce flowers in the firſt or ſecond year; as theſe buds have already acquired that ſtate of perfection or maturity, which is neceſſary to the production of ſexual or ſeminal generation: and as it therefore poſſeſſes the age of puberty, or the maturity of the tree; we may ſuſpect, that it will ſooner acquire the hereditary diſeaſes conſequent to too long unmixed ſuc-

ceſſive generations, a piece of very important knowledge to the planters of orchards; which they owe to the obſervation of Mr. Knight, as mentioned in Sect. VII. 1. 3.

Hence in many plants produced from ſeeds, perhaps in all, one or more leaf-buds precede the flower-bud; and I ſuppoſe generally, if not always, a magazine of aliment is formed at the baſes of the leaves, or in the roots, for the nutriment of the ſucceeding leaf-bud or flower-bud, of which it is the parent.

Thus in the carrot and turnep the firſt leaves conſtitute the lungs of the new vegetable being, which generates the ſucceeding flower-ſtem, and ſecretes or depoſits for it a magazine of aliment, which forms the tuberous root: and then this firſt plant from the ſeed and its leaves or lungs periſh; and the root gradually ſhrivels up, as it is abſorbed by the new flower-ſtem. In many plants theſe firſt or root-leaves differ in form from thoſe of the ſucceeding ſtem, as in palmated rhubarb, and in campanula rotundifolia, which is ſo called from the round form of the leaves of this firſt leaf-bud, or root-plant, which precedes the flower-ſtem.

7. One great advantage of Mr. Tull's horſe-hoeing huſbandry, in which the earth near the rows of wheat is alternately turned from and to them during the vernal months, has been ſuppoſed to ariſe from ſome fibres of the roots being thus cut off, and new ſtems ſhooting up at the ends of thoſe which remain; but the real cauſe of the production of the new ſtems is from the accumulation of earth above the firſt joint of the young wheat-plant; from which the new buds ſpring out, generated and nouriſhed by the caudex of the leaf, which ſurrounds that joint, and which afterwards withers; this important circumſtance is ſhewn by the annexed delineation of a tranſplanted wheat-plant.

The plant of wheat was taken from a corn-field in the ſpring, and then conſiſted firſt of the root immediately proceeding from the

ſeed

ſeed *a*, which has been called the ſeminal root; and ſecondly, of the root, which was then near the ſurface of the ground *b*, which has been called the coronal root, was furniſhed with a ſtem and leaf, *c*, *d*, and with a ſecondary ſtem, or root-ſcion, *e*, *f*. This wheat-plant conſiſting of only two ſtems was replanted in my garden, and purpoſely buried ſo deep as to cover the two or three firſt joints of both the ſtems beneath the ſoil; that is as high as the letter *f*, where the ſecondary ſtem was purpoſely cut off.

On taking up this plant with ſome others on September 24, it had aſſumed the form here delineated. The primary ſtem, *c*, *g*, had ſhot out no new roots from the joint *g*, which I ſuppoſe to have happened from its being too far advanced when replanted; as many other ſtems of other wheat-plants, which had not been obtruncated, had nevertheleſs put forth one or more lateral ſtems or root-ſcions at the ſecond or third joints, which on tranſplantation had been covered with the ſoil.

But the obtruncated ſtem, *e*, *f*, had generated a new root-ſcion at *h*, like the firſt ſhoot from the ſeed at *a*; which had produced other new ſtems, as it approached nearer the ſurface of the earth at *i*; and as theſe advanced into the air, and formed their leaves, other new root-ſcions were generated at *k* and *l*. Whence it appears, that by decapitation, and a deeper immerſion in the ground, a ſecondary ſtem in this plant became multiplied into five; all which produced perfect ears of corn; and in other roots, which I had planted in a ſimilar manner, the increaſe was much greater: and eſpecially where one or more of the primary or ſecondary ſtems had been decapitated.

If a grain of wheat be dropped on the ſurface of the earth, and ſuffered to ſhoot down its roots, and to raiſe its ſtem, which is the proceſs of nature, I ſuppoſe but one ſtem would be produced; as the firſt knot or joint of it would not be covered with earth, and could

not therefore ſhoot down new roots; which are neceſſary in theſe plants to the production of new ſtems, which are not branches but ſuckers or root-ſcions.

But if the grain be buried an inch deep in the earth, a ſhoot riſes from the roots, which iſſue from the ſeed, which is an elongation of the caudex, and puts forth a leaf in contact with the ſurface of the earth; this leaf and ſtem conſtitute the primary plant, and generate new buds, which put forth new roots deſcending into the earth; and thus three or four or more ſuckers, or new plants, ariſe round the original one, which was contained in the ſeed: hence the appearance of two roots, which ſome authors have named the ſeminal and coronal roots. The ingenious Mr. Tull ſeems himſelf to have been aware of this circumſtance, as he ſays in his Huſbandry, "Late planted wheat ſends out no root above the grain before ſpring, but is nouriſhed all winter by a ſingle thread proceeding from the grain up to the ſurface."

This explains the prodigious multiplication of the ſtems of wheat, which may be produced by tranſplanting it three or four times in the ſummer, autumn, and enſuing ſpring; for if it be ſo managed, that a ſecond joint of each young ſtem be buried in the ſoil, or brought even into contact with it, ſo that new roots may ſtrike down into the earth; the caudex of the leaf, which ſurrounds this joint, will generate many new buds, which will thus become ſuckers, or root-ſcions, and rival their parent; and may be again tranſplanted or earthed up three or four times with wonderful increaſe. Mr. Charles Miller of Cambridge ſowed ſome wheat on the ſecond of June 1766, and on the eighth of Auguſt one plant was taken up and ſeparated into eighteen parts and replanted; theſe plants were again taken up and divided between the middle of September and the middle of October, and again planted ſeparately to ſtand the winter, and this ſecond diviſion produced ſixty-ſeven plants. They were again taken up, and divided between the middle of March and the middle of April, and

produced five hundred plants. The number of ears thus produced from one grain of wheat was 21109, which meaſured three pecks and three quarters of corn, weighed forty-ſeven pounds ſeven ounces, and were eſtimated at 576840 grains! Philoſ. Tranſ. Vol. LVIII. p. 203. See Sect. XII. 6.

Nor is this unſupported by the analogy of other vegetables, in which new roots are liable to ſhoot in great abundance from their joints either alone or along with new buds, if a proper degree of moiſture is preſented to them. Thus if the ſtem of a potatoe be laid down upon the earth, and covered with ſoil over the firſt joint, a new ſeries of roots will be protruded from that joint; and afterwards another ſeries of roots from the ſecond joint, if managed in the ſame manner; and it is aſſerted that this will occur even if the potatoe ſtems are taken out of the ground, when they are ſix or eight inches high, and deprived of all their young roots, and tranſplanted, ſo as to cover one or two joints, and that a great crop has been thus produced.

The rapid growth of ſome graſſes, and of ſome ſpecies of the convolvulus, and of colt's-foot, is well known, and very troubleſome in many ſituations. Of theſe very minute parts of the jointed root, when cut from the parent, elongate themſelves, and ſhoot up new plants. From the very numerous diviſions of the wheat-root deſcribed by Mr. Miller, it may be ſuſpected that ſomething ſimilar to this muſt have happened, which further obſervations muſt determine.

Vines alſo are thus liable to ſhoot out roots at their joints, and fig-trees, when covered only with a ſhred of cloth in nailing them to a wall, if it be accidentally kept moiſt. And there is an apple-tree, which is called a burr-apple, becauſe it puts out roundiſh protuberances or excreſcences of the bark like a burr, which if the branch be bent down, or even torn off, and ſet in the moiſt earth,

will

will immediately ſtrike out roots, as I am told, and become a tree ſimilar to the parent.

In the ſame manner I have been informed that if a circular ring of the bark be cut off from many trees and ſhrubs, which are otherwiſe difficult to propagate, and earth be put round the branch thus decorticated a few inches above and below the wounded part, by means of a garden-pot previouſly broken longitudinally, and bound together round the branch, that roots will ſhoot from the upper lip of the wound; and in a little time the branch may be ſafely cut off below the garden-pot, and planted with ſucceſs.

When a few inches of the end of a branch are cut off in the ſpring, as is common in pruning wall-trees, new buds are produced near the extremity, which remains; or thoſe, which did exiſt, grow with greater vigour; as they obtain ſome of that nouriſhment, which ſhould have ſupported the buds, which were cut off. The ſame occurs in reſpect to the ſuckers or root-ſcions of thoſe trees, which produce them, as of elm-trees, and of ſome apple-trees; if many of the branches be cut away, the ſuckers or root-ſcions become more numerous, or more vigorous.


This explains the uſe of a practice among many farmers of eating down a forward crop of wheat in the ſpring with ſheep. In this caſe the central or upright ſtem of the wheat is decapitated, and many lateral ones, or root-ſcions, as above deſcribed, become generated, or grow with greater vigour; acquiring additional nouriſhment from the joint, which was to have been expended in the growth of the central ſtem; and which appears ſo diſtinctly in the preceding figure of a tranſplanted wheat-plant, which nevertheleſs in crops, which are not too forward, may be very injurious, as ſpoken of in Sect. XVI. 2. 3.


Thus the figure above alluded to explains four important circumſtances in the cultivation of grains, that of earthing up the rows in

PLATE IV.

PLATE IV.

Repreſents a tranſplanted root of wheat deſcribed in Sect. IX. 3. 7. *a* the ſeminal root, *b* the coronal root, *a b* the elongated caudex, *c g* the firſt ſtem, *c d* the firſt leaf, *e f* a ſecondary ſtem. All theſe exiſted before tranſplantation. The ſecondary ſtem was then cut off at *f*, and the plant was buried in the ſoil as deep as the letter *f*, where it was cut off. Afterwards the ſtem, which was lopped, had put forth a new caudex or root-ſcion at *b*; which had produced three new ſtems at *i*; and other new ones, as it approached nearer the ſurface, at *k* and *l*. As theſe leaves advanced into the air, the latter new ſtems were produced by the caudexes of them.





London. Published Jan.y 1.st 1800, by J. Johnson, St.Paul's Church Yard.

ſpring by Mr. Tull's horſe-hoe; that of eating down the firſt ſtems of forward crops by ſheep; that of tranſplanting the roots deeper in the ſoil; and that of ſowing the ſeed an inch or two beneath the ſurface. For an account of the drill huſbandry now practiſed by Mr. Coke of Holkham in Norfolk, ſee Sect. XVI. 2. 2.

SECT.

SECT. X.

MANURES, OR THE FOOD OF PLANTS.

I. 1. *The* CHYLE *of all animals is ſimilar. It conſiſts of water, ſugar, mucilage, oil, with carbon, phoſphorus, and calcareous earth. The* SAP-JUICE *of vegetables conſiſts of water, ſugar, mucilage, with carbon, phoſphorus, and calcareous earth.* 2. *Food of young animals, of adult animals. Power of digeſtion. Production of ſugar by digeſtion.* 3. *Food of young vegetables. Production of ſugar by germination.* 4. *Food of adult plants from the ſpontaneous decompoſition of vegetable and animal bodies, or from water and air alone. They poſſeſs low heat and cold blood like winter-ſleeping animals. Diſtinction between animals and vegetables.* II. 1. AIR. *Oxygen in air, in water, united with heat, and light.* 2. *Forms all acids.* 3. *Metallic oxydes.* 4. *The baſes of all acids are inſoluble in water.* 5. *Carbonic acid gas from fermentation. In its fluid ſtate.* 6. *Aqueous acid.* 7. *Oxygen in vegetable perſpiration.* 8. *Plants ſprinkled with oxygenated water. Oxygen gas applied near their roots.* 9. *Azote or nitrogen is found in vegetables. Produces nitre and ammoniac.* III. 1. WATER. *Its large quantity in plants.* 2. *Uſe of their great perſpiration.* 3. *Water becomes decompoſed in plants, and is hyper-oxygenated.* 4. *Gives lubricity, fluidity, and ſolution.* 5. *Irrigation of the ſoil brings other manures.* 6. *Penetrability of the ſoil from irrigation. Sow and reap early in wet ſoils.* 7. *Haſty ſhowers are injurious. Hills ſhould be ploughed horizontally. Uſe of ridges and furrows. Surface of air greater.* 8. *Evaporation produces cold. Uſes of coping-ſtones on fruit-walls.* 9. *Production of foliage requires more moiſture than that of ſeeds. Froſt in Scotland ripens the corn.* 10. *Lime and dung-hills attract water. Steam uſed in hot-houſes. Much water in the atmoſphere.* IV. 1. CARBON *is an univerſal material in the atmoſphere.* 2. *In limeſtone.* 3. *In black earth, moraſſes, loam. Carbon combines with putrid exhalations.* 4. *United with oxygen is ſoluble in water. Lime combines with water. Emits heat. Is broken into powder by ſteam. Should be ſlaked before it is uſed in agriculture. Better ſlaked with hot water.*

Attracts

Attracts the carbonic acid, and in conſequence the water, of the atmoſphere. 5. *Carbonic acid ſubſides on the earth in the air.* 6. *United with calcareous earth is ſoluble in water, and abſorbed by vegetables.* 7. *An experiment in which carbon and lime form an hepar, and thus become ſoluble in water.* 8. *Vegetable roots abſorb carbonic acid from limeſtone in its fluid, not its gaſſeous ſtate.* 9. *Carbon exiſts in ſugar and mucilage, which are abſorbed undecompounded.* V. PHOSPHORUS *is a ſimple ſubſtance. Appears in rotten wood. In putreſcent fleſh and fiſh.* 2. *Exiſts in all vegetable and animal matter, as ſeen in Homberg's pyrophorus, and in Kunkel's phoſphorus.* 3. *And in all calcareous earth, as in oyſter-ſhells, limeſtone, gypſum, fluor.* 4. *Hence the uſe of calcareous earth in agriculture.* 5. *Shells become limeſtone by attracting carbonic acid from the air. Mountains of calcareous phoſphorus. Limeſtone ſhould be burnt in cloſe veſſels.* 6. *The hardneſs of bones owing to phoſphoric acid, and perhaps of ligneous fibres.* VI. 1. LIME *with carbon may make an hepar carbonis ſoluble in water.* 2. *Unites with carbonic acid, and renders it ſoluble in its fluid not its gaſſeous ſtate. Water from ſprings is preferable to that from rivers for flooding lands.* 3. *Lime unites with phoſphorus, and renders it ſoluble in water. Unites alſo with phoſphoric acid. Whence crab-fiſh renew their ſhells, and ſnails repair and enlarge theirs.* 4. *Lime unites with oil and mucilage, and may thence become nutritious. It decompoſes ſoap, and conſtitutes a part of animals and vegetables.* 5. *Lime deſtroys the coheſion of dead vegetables. Of recent ones by combuſtion. Attracts moiſture from the air and earth. Makes clay leſs adheſive. Unites with acids of vitriol and of nitre. Kills inſects.* 6. *One limeſtone twenty miles long and ten broad. Lime not of uſe on wet land, nor always on all calcareous ſoils.* 7. *Lime both forwards the ripening and meliorates and increaſes wheat and graſs by ſupplying nutriment.* 8. *Gypſum, fluor, bone aſhes. Breedon lime is half magneſia.* VII. 1. CLAY *is too adheſive. Becomes more ſolid by froſt.* 2. *Effervеſces in the air. Acquires oxygen. So iron, manganeſe, zinc. Raddle uſed as manure.* 3. *Granite acquires oxygen. Granites and dry clay have a ſmell when breathed on. Marl crumbles in the air. Burnt clay acquires oxygen and burnt lead.* 4. *Burnt clay promotes the generation of nitre. Uſe of paring and burning.* 5. *Burnt clay decompoſes marine ſalt. Uſe of ſea-ſalt in manure.* 6. *Would phoſphat of lime combine with clay, or bone-aſhes?* 7. *Coheſion of clay overcome by air. By roots of ſtrong plants. By carbonic acid from leaves in the ſhade. By dunghill water. By lime.* 8. *Aluminous clays how to correct. By wood-aſhes, ſoap-ſuds, lime, magneſia.* VIII. 1. SPON-

TANEOUS MANURES. *Saccharine fermentation is a chemical proceſs. Exiſts beneath the ſoil.* 2. *Vinous fermentation. Carbon and oxygen in a fluid ſtate. Heat of bark-beds. Hay-ſtacks take fire.* 3. *Putrefaction decompoſes water.* 4. *Produces nitre, whoſe looſe oxygen promotes vegetation.* 5. *Sow ſoon after the plough.* IX. CHEMICAL MANURES. 1. *Sugar and mucilage abſorbed undecompoſed.* 2. *Heat deſtroys life in ſeeds, fruits, roots. Potatoes dried on a malt-kiln. Cooked in ſteam hotter than boiling water. Papin's digeſter.* 4. *Trituration of wood, ſtraw, hay, for food in times of ſcarcity; of bones, chalk, bricks, ochres, calamy for manures.* X. INSECT-MANURE. *Cultivated countries increaſe in fertility. Some have decreaſed. Calcareous ſtrata from ſhells. Thoſe above them from vegetables and animals. The former can live on air and water, not the latter.* 2. *Crops ploughed in for manure.* 3. *Inſects increaſe manure. Water from dunghills.* 4. *Fiſh.* XI. PRESERVATION OF MANURES. *Rains waſh manure into the ſea. Snow floods leſs injurious. Hills ſhould be ploughed horizontally.* 2. *Common ſhores.* 3. *Burial grounds.* 4. *Wood-fuel.* 5. *Fermentation requires air, water, heat. Manure ſhould be turned over and mixed with lime.* 6. *Pig-troughs, ſoap-ſuds.* 7. *Weeds, leaves, water-plants.* 8. *Peat.* XII. APPLICATION OF MANURES. 1. *In powder for top-dreſſing. In ſtraw for clay-fields.* 2. *In fields when the corn is ſowed. On graſs-lands in the ſpring, not in the autumn.* 3. *Cover dung-heaps with ſoil. Gather cow-dung from the graſs.* 4. *What manures are moſt nutritive. Fleſh, horn, woollen rags, meal, ſugar, oil.*

I. 1. The various ſubſtances, which conſtitute animal bodies, or which are found in the cavities of them, are compoſed from ſimpler elements by the proceſſes of digeſtion, and ſanguification, and ſecretion; for it is well known, that even milk, which ſo much reſembles the chyle of animals, is not abſorbed by the lacteals without its being previouſly coagulated, and again diſſolved in the ſtomach by the power of digeſtion.

Hence it happens, that the chyle of all animals, and from every kind of food which they take into their ſtomachs, is very ſimilar; and like milk conſiſts of water, ſugar, mucilage, and oil; the laſt of which

which not being ſoluble in water, but only miſcible with it, gives it its opaque white colour.

But though the chyle from different kinds of aliment is ſo ſimilar, and all the various conſtituent parts of animal bodies are ultimately produced from the chyle by ſanguification and ſecretion, yet it happens, that ſome kinds of aliment poſſeſs a greater quantity of theſe particles, which make chyle, than other kinds of aliment. Such materials for inſtance as already contain much ſugar, mucilage, and oil, as the fleſh of dead animals, or the fruits and ſeeds of vegetables.

Beſides the water, ſugar, mucilage, and oil, which exiſt in chyle, there may be other materials, which are inviſible from their perfect ſolution in water, either alone or when converted into acids by the addition of oxygen; as carbon, phoſphorus, calcareous earth, marine and ammoniacal ſalts; though it is more probable, that the two laſt are formed and ſecreted by animal proceſſes, as well as ſelected by their abſorbent roots, as they are more compounded bodies than the former.

Similar to this chyle of animals the ſap-juice, which is abſorbed from the earth by the roots of plants, conſtitutes their nouriſhment, and conſiſts of water, ſugar, and mucilage, with other tranſparent ſolutions, as of carbon, phoſphorus, and calcareous earth. And though it has been proved by the experiments of ſome philoſophers, that vegetables can extract or compoſe all theſe ſubſtances from air and water alone; yet ſome materials contribute more to the production of this vegetable chyle or ſap-juice than others, ſuch as the recrements of dead vegetable and animal ſubſtances.

2. If any one ſhould aſk, what is the food of animals? I ſhould anſwer, that in the moſt early ſtate of animal life the embryon lives on a mucilaginous fluid, with which it is ſurrounded, whether in the egg or womb: that in its infant ſtate the young animal is ſuſtained by milk, which its ſtomach converts into chyle.

In their adult ſtate animals are ſuſtained by other vegetable or animal ſubſtances taken into their ſtomachs, which are there converted into chyle partly by a chemical, and partly by an animal proceſs; as by a mixture of gaſtric juice with water and heat, ſome of theſe recrements of organic nature are decompoſed, either into their ſimpler component parts, or ſometimes even into their elements; while other parts of them are only rendered ſoluble or miſcible with water; and are then drank up by the abſorbents of the ſtomach and inteſtines.

In this proceſs of digeſtion much ſugar is produced, which is probably immediately ſelected and drank up by the numerous mouths of the lacteals, or lymphatics; to which it is preſented by the vermicular or periſtaltic motions of the ſtomach and inteſtines. And as this ready ſelection and abſorption of the ſugar, as ſoon as it is formed, prevents it from paſſing into the vinous or acetous fermentation; it is probable that from the want of ſuch a means of ſeparating ſaccharine matter, as ſoon as it is formed, chemiſtry has not yet been able to produce ſugar from its elements without the aſſiſtance of animal digeſtion, or vegetable germination; as further ſpoken of in No. 8. 1. of this ſection.

In this proceſs of digeſtion, I believe, a great part of the water, ſugar, mucilage, and oil, which exiſt in vegetable and animal recrements, are not decompoſed into their elements, but abſorbed by being ſoluble or miſcible with water; the carbon, and the phoſphorus, and the hydrogen, are alſo I ſuppoſe diſſolved in the other fluids by means of oxygen, and form a part of the chyle, without their being converted into gaſſes; for when this happens to any exceſs in reſpect to carbon, it eſcapes from the ſtomach in eructations; and the ſame occurs to the inflammable air or hydrogen, if a part of the water becomes decompoſed in the inteſtines; which, if it be not abſorbed by its ſolution in other fluids, but acquires a gaſſeous ſtate, is liable to eſcape below; though both theſe gaſſes ſeem occaſionally

to

to revert to a fluid ſtate from their aerial one in the ſtomach or inteſtines, and to be then abſorbable by the lacteals or lymphatics.

3. What then is the food of vegetables? the embryon plant in the ſeed or fruit is ſurrounded with ſaccharine, mucilaginous, and oily materials, like the animal fetus in the egg or uterus, which it abſorbs, and converts into nutriment; while the embryon buds of deciduous trees, which is another infantine ſtate of vegetables, are ſupplied with a ſaccharine and mucilaginous juice prepared for them at the time of their production, and depoſited in the roots or ſap-wood of their parent-trees; as in the vine, maple, and birch; which ſaccharine matter is ſoluble and miſcible with the water of the ſurrounding earth in the ſubſequent ſpring, and is forcibly abſorbed by their root-veſſels, and expands their naſcent foliage.

In their infantine ſtate therefore there is a wonderful analogy between plants and animals; and it is particularly curious to obſerve in the proceſs of converting barley into malt by the germination of the ſeed, that the meal of the barley is in part converted into ſugar by the digeſtion of the young plant exactly as in the animal ſtomach. The wonderful effect of vegetable digeſtion in producing ſugar may be deduced from the great product of the ſugar-cane, and of the maple-tree in America, mentioned in Sect. III. 2. 3. and the wonderful effect of animal digeſtion in producing ſugar appears in patients, who labour under diabetes. A man in the Infirmary of Stafford, who drank daily an immoderate quantity of beer, and who eat above twice the quantity of food that thoſe in health conſume, voided ſixteen or eighteen pounds of water daily, from each pound of which above an ounce of coarſe ſugar was extracted by evaporation. Zoonomia, Vol. I. Sect. XXIX. 4. 9.

4. We now come to conſider the food of adult plants; and in this conſiſts the great and eſſential difference between the nutritive proceſſes of animals and vegetables. The former are poſſeſſed of a ſtomach, by which they can in a few hours decompoſe the tender parts of

of vegetable and animal ſubſtances by a chemical proceſs within themſelves, conducted in the heat of ninety-eight degrees, with a due quantity of water, and a perpetual agitation of the ingredients; which both mixes them, and applies them to the mouths of the abſorbent veſſels, which ſurround them. Whereas a vegetable being having no ſtomach is neceſſitated to wait for the ſpontaneous decompoſition of animal or vegetable recrements; which is indeed continually going on in thoſe ſoils, and climates, and in thoſe ſeaſons of the year, which are moſt friendly to vegetation; but is in other ſituations, and in other ſeaſons, a ſlow proceſs in a degree of heat often as low as forty of Farenheit, (in which the reindeer moſs, moſchus rangiferinus, vegetates beneath the ſnow in Siberia,) and often without an adapted quantity of water to give a due fluidity, or any mechanical locomotion to preſent them to the abſorbent mouths of their roots; or in ſtill worſe ſituations adult vegetables are neceſſitated ſtill more ſlowly to acquire or produce their nutritive juices from the ſimpler elements of air and water, with perhaps the ſolutions of carbonic acid and calcareous earth, and perhaps of ſome other matters, with which one or more of them abound.

But M. Haſſenfratz found, that the vegetation of thoſe plants was imperfect, which had not been ſuffered to grow in contact with the earth; as they never arrived at ſuch maturity as to produce fruit; and were found on analyſis to contain a leſs portion of carbon, than other plants of the ſame kind. The experiments were tried on hyacinths, kidney-beans, and creſſes.

Hence the other great difference, which exiſts between theſe two extenſive kingdoms of nature, is, that the larger and warmer blooded animals certainly, and I ſuppoſe all the tribes of inſects, and of colder blooded creatures alſo, can not exiſt long on air and water alone, except in their ſtate of hibernal torpor. The neareſt approach to this is however ſeen in ſome fevers, where water alone has been taken for a week or two, and yet the patient has recovered; and there is a well

atteſted

atteſted account of a numerous caravan, which having loſt their rout, or their proviſions, are affirmed to have lived ſome weeks on gum arabic and water alone.

Vegetables on the contrary, as above mentioned, can exiſt, though in a feebler ſtate, on water and air alone, with the carbonic acid, and perhaps other inviſible ſolvends, which thoſe elements unavoidably contain. This I ſuppoſe to be owing to the low degree of heat, which they produce internally, and to the ſlow circulation of their blood; from both which circumſtances leſs nutriment is expended, as by animals which ſleep in winter.

For the purpoſe of ſupplying adult vegetables with nouriſhment, we ſhould firſt conſider what kinds of matter are moſt prevalent or moſt neceſſary in their compoſition. Secondly, what of theſe ſubſtances they can abſorb without previous decompoſition. Laſtly, how to expedite the decompoſition of vegetable and animal ſubſtances on or in the ſoil, like the digeſtive proceſſes in the ſtomachs of animals; we may thus become acquainted with the ſources and the management of manures.

II. AIR.

1. Oxygen combined with heat conſtitutes that part of the atmoſphere, which is perpetually neceſſary to animal and vegetable reſpiration; and a greater part of that water, which forms a principal portion of their organization; a few words may be therefore premiſed on theſe moſt important diſcoveries of modern chemiſtry.

This vital air, called oxygen gas, conſtitutes twenty-ſeven hundredth parts of the atmoſphere; it is indiſpenſably neceſſary to the exiſtence of life, and of combuſtion, and forms the principal part of all acids; whence its name. The other ſeventy-three hundredth parts of the atmoſphere conſiſt of azote, which takes its name from its inutility to life in animal reſpiration; it is alſo called nitrogen, becauſe it conſtitutes the baſis of nitre.

Oxygen gas conſiſts of oxygen and heat; and when it unites with ſuch bodies, as are capable of uniting with it, the heat is ſet at liberty, as in reſpiration and in combuſtion; in both which proceſſes an acid is produced by the combination of oxygen with ſome inflammable baſe. Hence vital air conſiſts of oxygen diſſolved in the fluid matter of heat; but there is alſo another fluid, which ſeems to be combined with this ſolution of oxygen in heat, and that is light. For when oxygen becomes combined with charcoal, or with ſulphur, or with phoſphorus, both heat or light are ſet at liberty from theſe new combinations of oxygen; which thus produce the carbonic, ſulphuric, and phoſphoric acids.

When theſe new combinations of oxygen are performed very ſlowly, the light is ſometimes not viſible, as in the heating of a dunghill; in which proceſs the oxygen in the cells or cavities of the hotbed unites ſlowly with the carbon and phoſphorus of the decompoſing vegetable and animal matters; but though much heat is given out, no light is ſeen. While on the contrary from rotten wood alone, or putreſcent fiſh, when expoſed to the atmoſphere, much light is emitted, but not much ſenſible heat, owing perhaps ſimply to the combuſtion of the phoſphorus, which they contain.

2. The products of theſe combinations of oxygen with other bodies may all of them be termed acids; though in ſome the heat or light ſet at liberty converts theſe acid productions into gaſſes, as oxygen and charcoal form carbonic acid gas; and in others it converts the new product into ſteam, which is condenſible by cold, as the ſulphuric acid from the combination of oxygen and ſulphur; and the phoſphoric acid from oxygen and phoſphorus.

3. Other combinations of oxygen with heavier ſubſtances are produced in the atmoſphere without the ſeparation of either ſenſible heat, or viſible light; as the union of oxygen with metallic bodies, as with that of manganeſe, with zinc, lead, iron, as in common ore of manganeſe, in lapis calaminaris, white calciform lead-ore, and the

red ochre of iron; which have not obtained the name of acids, but are termed oxydes of thoſe minerals.

4. Now it happens, that none of theſe baſes, which can combine with oxygen alone, are ſoluble in water, and therefore can not be imbibed by the abſorbent veſſels of vegetable roots, until they become acids; and are perhaps then all of them in greater or leſs quantities ſoluble in water; and are thence capable of being drank up by the abſorbent veſſels of vegetable roots, and conſtitute a part of the food of plants.

5. When vegetable ſubſtances are decompoſed by fermentation, there is a quick union of oxygen and carbon; and this carbonic acid gas, called formerly fixed air, riſes up in vapour, and flies away. But where this proceſs goes on more ſlowly, as in a dung-hill lately turned over, or in black garden mould lately turned over, and thus expoſed to the air; much of which remains in the cells or cavities of the hotbed, or border; this carbonic acid is ſlowly produced, and is abſorbed by vegetable roots, I ſuppoſe in its fluid ſtate, or diſſolved in water, before it acquires ſo much heat as to riſe in the atmoſphere in the form of gas.

This carbonic gas in its fluid ſtate, or diſſolved in water, not in its aerial or gaſſeous ſtate, is the principal food of plants; as appears, becauſe their ſolid fibres conſiſt principally of carbon, and their fluids of water.

6. Next to carbonic acid the aqueous acid, if it may be ſo called, or water, ſeems to afford the principal food of vegetables; as water conſiſts of oxygen and hydrogen, it is properly an acid, like all other combinations of oxygen; and when abſorbed by vegetable roots becomes in part decompoſed in the circulation or ſecretion of their juices; the oxygen diſappears, or contributes to form the vegetable acids; and the hydrogen produces ammonia by its union with azote; which may contribute to vegetable nutriment by its mixture with oils, and thus producing ſoaps, which become diffuſible in water; and alſo by

decompoſing inſoluble ſaline earths, as gypſum, or metallic ſalts, as vitriol of iron, and thus producing more ſoluble or innocuous ſalts. And which laſtly forms a part of the various vegetable productions of ſugar, honey, wax, reſin, and other ſecretions.

7. There is a curious evolution of oxygen attends the perſpiration of the leaves of plants, which is not known to attend that of animal lungs; and that is, that when vegetable leaves are expoſed to the ſun's light, they ſeem to give up oxygen gas; but in the dark they give up carbonic acid gas, like the breath of animals. It is probable that animal lungs might do the ſame, if they were expoſed to the light; as perhaps might be ſubjected to experiment in the gills of fiſh, or by breathing through a tube into water in the ſunſhine.

In reſpiration as well as in combuſtion ſome light may poſſibly be given out as well as ſome heat from the combination of oxygen with ſome phlogiſtic baſe, as carbon or phoſphorus; whence the production of carbonic and phoſphoric acids in both animal and vegetable reſpiration. In moſt animals this quantity of light is probably too ſmall to be perceived, if their bodies were tranſparent; but in the glow-worm of this country, and in the more luminous fire-flies of the tropical climates, I ſuſpect the light to be emitted from their lungs in the act of reſpiration, which is a ſlow combuſtion.

8. Beſides the uſe of oxygen in the reſpiration of vegetables, when applied to their leaves, as it is mixed in the atmoſphere; it is believed by many to contribute much to their growth and nouriſhment in its combined ſtate, when abſorbed by their roots; and that by the decompoſition of water in the vegetable ſyſtem, when the hydrogen unites with carbon and produces oil, the oxygen becomes ſuperfluous, and is in part exhaled, as further ſpoken of in Sect. XIII. 1. 2. Hence alſo ſome calciform ores, or metallic oxydes, as raddle, and calamine, and burnt clay, are ſuppoſed to be uſeful as manures, becauſe they contain much oxygen, as mentioned in No. 7. 1. of this Section.

Mr.

Mr. Humboldt aſſerts, that on putting creſſes, lepidium ſativum, into oxygenated muriatic acid gas mixed with water, they produced germs in ſix hours; while thoſe in common water were thirty-ſix hours before they produced germs. Jacquin at Vienna put many old ſeeds, which had been in vain tried if they would vegetate, into ſuch a ſolution of oxygenated muriatic acid, and found great numbers of them quickly to vegetate. Journal de Phyſique, 1798. See Sect. XIV. 2. 5.

In the experiments of ſir Francis Ford many plants, which were ſprinkled with water previouſly impregnated with oxygen gas, are ſaid to have grown more vigorouſly, and to have diſplayed more beautiful tints, than thoſe nouriſhed with common water. Other experiments are ſaid to have been made by inverting bottles filled with oxygen gas, and burying their open mouths beneath the ſoil near the roots of vegetables, which are ſaid to have grown more healthy and beautiful, as the oxygen became abſorbed, and was ſucceeded by air like the common atmoſphere. Philoſ. Magaz. 1798, p. 224. Further experiments are required on this ſubject, ſince the fluids of vegetables would in general appear to be hyperoxygenated from the oxygen emitted from the perſpiration of their leaves in the ſunſhine, and which is believed to ariſe from the decompoſition of water in their arteries or glands.

9. We now come to the other ingredient, which conſtitutes a much greater part of the atmoſphere than the oxygen, and this is the azote, or nitrogen; which alſo ſeems much to contribute to the food or ſuſtenance of vegetables; for though azote, or nitrogen, enters into animal bodies in much greater quantities perhaps than into vegetables, ſo as to conſtitute according to ſome chemical philoſophers the principal difference between theſe two great claſſes of organized nature; yet it enters alſo into the vegetable ſyſtem, and is given out by their putrefaction; and alſo when lime is applied to moiſt vegetables it diſengages from them both hydrogen and azote forming

volatile alkali, as aſſerted in the ingenious work of Lord Dundonald on the Connection of Agriculture with Chemiſtry.

The azote of the atmoſphere, when air is confined in the interſtices of the ſoil newly turned over by the plough or ſpade, contributes to the production of the nitrous acid by its union with the oxygen of the atmoſphere, with which it was before only diffuſed, or with the much greater ſource of oxygen from the decompoſing water of the ſoil. At the ſame time another part of the abundant azote combines with the hydrogen of the decompoſing water of the ſoil, and produces ammonia or volatile alkali; which contributes to the growth of vegetables many ways, as already deſcribed in No. 2. 6. of this Section.

III. WATER.

1. The neceſſity of much water in the progreſs of vegetation appears from the great quantity, which exiſts naturally in all parts of plants; inſomuch that many roots, as ſquill and rhubarb, are known to loſe about ſix parts out of ſeven of their original weight ſimply by drying them before the fire; which quantity of moiſture nevertheleſs does not exhale in the common heat of the atmoſphere during the life of the root; as is ſeen in the growth of ſquills in the ſhops of the druggiſts, and of onions on the floors of our ſtore-rooms.

2. A ſecond neceſſity of much water in the economy of vegetation may be deduced from the great perſpiration of plants, which appears from the experiments of Hales and others; who like Sanctorius have eſtimated the quantity of their perſpiration from their daily loſs of weight; which however is not an accurate concluſion either in reſpect to plants or animals, as they both abſorb moiſture from the atmoſphere, as well as perſpire it.

This great perſpiration of vegetables, like that from the ſkin and lungs of animals, does not appear to conſiſt of excrementitious matter, becauſe it has in general no putreſcent ſmell or taſte; but ſeems

to

to be ſecreted firſt for the purpoſe of keeping the external ſurface of the leaves from becoming dry, which would prevent the oxygen of the atmoſphere from entering into the vegetable blood through them; ſince according to the experiments of Dr. Prieſtley on animal membranes the oxygen will only paſs through them, when they are moiſt. A ſecond uſe of this great perſpiration is to keep the bark ſupple by its moiſture, and thus to prevent its being cracked by the motion of the branches in the wind. And though a great part of this perſpirable matter is probably abſorbed, as on the ſkins of animals; yet as it exiſts on ſo large a ſurface of leaves and twigs, much of it muſt neceſſarily evaporate on dry and windy days.

3. One of the great diſcoveries of modern chemiſtry is the decompoſition of water, which is ſhewn both by analyſis and ſyntheſis to conſiſt of eighty-five hundredth parts of oxygen, and fifteen of hydrogen. Hence a third great uſe of water in the vegetable economy is probably owing to its ready decompoſition by their organs of digeſtion, ſanguification, and ſecretion. This is evinced firſt by the great quantity of hydrogen, which exiſts in the compoſition of many of their inflammable parts. And ſecondly, from the curious circumſtance, which was firſt diſcovered by the ingenious Dr. Prieſtley, that the water, which they perſpire, is hyperoxygenated; and in conſequence always ready to part with its ſuperabundance of oxygen, when expoſed to the ſun's light; from whence it may be concluded, that part of the hydrogen, which was previouſly an ingredient of this water, had been ſeparated from it, and uſed in the vegetable economy, as is further treated of in Section XIII. 1. 2.

Add to this, that from the decompoſition of water, when confined in contact with air beneath the ſoil, the nitrous acid ſeems to be produced and ammonia, both which are believed uſeful to vegetation, as mentioned in No. 2. 6. of this Section.

4. Beſides the peculiar uſes of a great quantity of water, as above deſcribed, the more common uſes of it both to vegetable and animal life,

life, along with the matter of heat, are to produce or preſerve a due ſuppleneſs or lubricity of the ſolids, and a due degree of fluidity of the liquids, which they contain or circulate. And laſtly, for the purpoſe of diſſolving or diffuſing in it other ſolid or fluid ſubſtances, and thus rendering them capable of abſorption, circulation, and ſecretion.

5. The due irrigation of the ſoil is much attended to in drier and warmer countries, as in Italy, Egypt, and ſome parts of China; where numerous canals, and aqueducts, have been dug through hills, and carried over vallies, for the purpoſe of watering the ſoil; and even in this colder and moiſter climate the practice of flooding land is coming daily into greater repute. For this occaſional ſuffuſion of water over land not only ſupplies ſimple moiſture for the purpoſes above mentioned in the drier parts of the ſeaſons, but brings along with it calcareous earth and azotic air from the neighbouring ſprings, or other manures from the rivers. Calcareous earth may be detected in the water of all thoſe ſprings which paſs under or over ſtrata of marle or limeſtone, by dropping into them a ſolution of ſalt of tartar; or of ſugar of lead in water, or of ſoap in ſpirits of wine; and a portion of azotic gas was diſcovered in Bath-water by Dr. Prieſtley, and in Buxton-water by Dr. Pierſon. See Section XI. 3. 1. Dr. Home thinks he diſcovered nitrat of lime in hard water, and found by his experiments that it promoted the growth of plants in a much greater degree than ſoft water.

6. Another demand for water in agriculture is to give a due penetrability to the ſoil, which otherwiſe in moſt ſituations becomes ſo hard as to ſtop the elongation of the tender roots of plants; but the coheſion of the ſoil may nevertheleſs be too much diminiſhed by great and perpetual moiſture, ſo as not to give ſufficient firmneſs to the roots of trees. And beſides this too much as well as too little water may be ſupplied to the generality of vegetables, which grow upon the land; though there are aquatic and amphibious plants as well as

aquatic and amphibious animals, and which differ from each other as fiſh and ſeals from quadrupeds.

Where land abounds too much with moiſture, the art of making ſubterraneous or ſuperficial drains deſcribed in Sect. XI. 1. muſt be had recourſe to. But where theſe are not executed, in lands not very moiſt it is thought advantageous to ſow the crops early before the wet ſeaſon, ſince corn will bear much more moiſture after it has ſhot from the ſeed, than the ſeed will bear; as the ſeed is leſs tenacious of life, and in conſequence more liable to putrify. The crops ſhould likewiſe be ſown or planted thinner, and be reaped early in the ſeaſon, as the excluſion of the air by thick foliage, and the greater dampneſs of the autumn, are liable to generate mildew in moiſt ſituations. Perhaps it ſhould be added, that ſowing early, and the conſequent reaping early, has ſo many advantages in all ſeaſons on all lands, that it may in general be univerſally recommended; and that in wet lands it might be very advantageous to cultivate crops by tranſplantation in the vernal months, having previouſly ſowed the ſeed in drier or warmer ſituations. See Sect. XVI. 8. 1.

7. Another injury in this climate occaſioned by too great a quantity of water ariſes from haſty ſhowers; which waſh off much of the decompoſing animal and vegetable recrements, which are ſoluble or diffuſible in water, and carry them down the rivers into the ſea. From the ſides of hills this damage is accompliſhed by ſmall ſhowers, on which account all ſloping grounds when applied to agriculture ſhould be ploughed horizontally, as by the ridges and furrows thus produced the ſmaller ſhowers of rain will not paſs ſo haſtily off, as when they are ploughed vertically.

A queſtion here occurs, whether it be advantageous to plough level plains into ridges and furrows? the Chineſe are ſaid never to divide their fields into ridges and furrows, but to plant their grain on an even ſurface. Embaſſy to China by ſir G. Staunton, Vol. III. p. 197, 8vo. edit. Some think it an error to ſuppoſe, that any increaſe of crop

crop can be thus obtained, as no more plants can riſe perpendicularly from the ground; but in the ripening of grain the ſurface of air to which the ears are expoſed is alſo to be conſidered; which correſponds with the ſurface of the ground, and is increaſed by its being laid in hill and dale. But there is a ſerious objection to this mode of ploughing in moiſt ſituations without ſufficient declivity, as the corn in the furrows appears weak and backward owing to the rain lying on it too long; and alſo to the beſt part of ſhallow ſoils being frequently taken from them to conſtruct the ridges. See Sect. XVI. 2. 2.

8. Add to this, that the evaporation of moiſture from the ſurface of the earth produces ſo much cold as to injure thoſe terreſtrial plants, which are too long covered with it. On this account thoſe parts of wall-trees, which are ſheltered from the deſcending dews by a coping ſtone on the wall, are not ſo liable to be injured by froſty nights on two accounts; both as they are not made colder by the evaporation of the dew, and alſo have leſs water to be congealed in their veſſels, and by its expanſion to burſt them.

9. Laſtly, the foliage on buds of plants, which conſtitute one part of their progeny, requires more moiſture for its vigorous growth, than their flowers or organs of ſexual generation. Hence in warm countries the rice-grounds are flooded only till the ſeaſon of flowering commences, and are laid dry again for the purpoſe of maturating the ſeed; and in our climate continued rains are liable not only to waſh off the farina from the burſting anthers, and thus prevent the impregnation of the piſtillum, but alſo to delay the ripening of the fruit or ſeeds from the want of a due evaporation of their perſpirable matter, as well as from the leſs ſolar light in cloudy ſeaſons; whence in the north of Scotland the oats are ſaid ſeldom to ripen till the froſt commences with the dry ſeaſon, which accompanies it.

10. There are methods of procuring or preſerving the ſalutary moiſture of the ſoil beſides thoſe of canals and aqueducts, which

ſhould

ſhould be here mentioned. Theſe are by uſing as manures ſuch ſubſtances as perpetually attract moiſture from the lower part of the ſoil, or from the atmoſphere; as quick-lime, and vegetable and animal recrements in the act of putrefaction.

In hot-houſes ſome have already employed ſteam as a means both of giving warmth and moiſture to the included plants, or to the ſoil in which they grow; and a great variety of forcing pumps have been conſtructed for the purpoſe of moiſtening the foliage of wall-trees; but there is a hope from the preſent great progreſs of chemical reſearch, that a means may ſometime be diſcovered of precipitating the water of the atmoſphere, which the ingenious biſhop Watſon thinks always exiſts in it in ſuch quantity as, if it was ſuddenly precipitated, might again deluge the world.

IV. CARBON.

1. When animal and vegetable bodies are burnt without the acceſs of air, that is, when their volatile parts are ſublimed; there remains a great quantity of charcoal, a much greater in vegetable bodies than in animal ones; this is termed carbon by the French ſchool, when it is quite pure; and is now known to be one of the moſt univerſal materials of nature. And as vegetable bodies contain ſo much of it in their compoſition, they may be ſuppoſed to abſorb it intire, where they grow vigorouſly; eſpecially as it is a ſimple material; but they may poſſibly form it alſo occaſionally from water and air within their own veſſels, when they are ſecluded from acceſs to it externally.

The whole atmoſphere contains always a quantity of it in the form of carbonic acid, or fixed air; as is known by the ſcum, which preſently becomes viſible on lime-water, when expoſed to the air; and which conſiſts of a reunion of the lime with carbonic acid; which may therefore be ſaid to encompaſs the earth.

The ſimplicity of carbon, as an elementary ſubſtance, was diſputed by Dr. Auſtin, who believed he had decompounded it. But Mr. Henry, by accurately repeating his experiments, has ſhewn the fallacy or inconcluſiveneſs of them. Philoſ. Tranſact. 1797.

2. Another great reſervoir of carbon exiſts in limeſtone in the form of carbonic acid; which when a ſtronger acid is poured on the calcareous earth becomes a gas, acquiring its neceſſary addition of heat from that, which is given out in the combination of the ſtronger acid with the lime. It alſo acquires its neceſſary heat, when limeſtone is burnt, from the conſuming fuel, riſes in the form of gas, and is diſſipated in the air; and probably ſoon ſettles on the earth, as it cools, as it is ten times heavier than the common atmoſphere.

3. But the great ſource of carbon exiſts in the black earth, which has lately been left by the decompoſition of vegetable and animal bodies; and is then in a ſtate fit to combine with azote or nitrogen, and with oxygen, when expoſed to thoſe two gaſſes, as they exiſt in the atmoſphere; and is thus adapted either to promote the generation of nitrous acid, or to form carbonic acid, and thus to aſſiſt vegetation.

Moraſſes conſiſt principally of the carbonic recrements of vegetable matters, which are gradually decompoſed in great length of time into clay, with argillaceous ſand, ſuch as is found over coal-beds, and ſome calcareous earth, as in marl; and laſtly, with ſome iron, and foſſile coal. Theſe by elutriation are ſeparated from each other, and form the ſtrata of coal countries. In other places they remain intermixed, as they were probably produced from the decompoſition of vegetables and terreſtrial animals; and form what in books of practical agriculture is called a *loamy* ſoil, conſiſting of carbonic matter, ſand, and clay, with a portion of iron.

It has always been obſerved, that this black garden mould, or earth produced from the recrements of vegetables, is capable of abſorbing a much greater quantity of putrid effluvia than either air or water, and

probably of combining with its ammonia, and producing a kind of hepar carbonis, and thus facilitating vegetation. The practice of burying dead bodies ſo few feet below the ſurface is a proof of this; as the putrid exhalations from the carcaſs are retained, and do not penetrate to the ſurface. On the ſame account the air over new ploughed fields has long been eſteemed ſalutary to invalids, or convaleſcents, as it probably purifies the ſupernatent atmoſphere. But it was not till lately known that carbon, or charcoal, abſorbs with ſuch great avidity all putrid exhalations; if it has been recently burnt, and has not been already ſaturated with them, inſomuch that putrid fleſh is ſaid to be much ſweetened by being covered a few inches with the powder of charcoal; or even by being buried for a time in black garden mould; as putrid exhalations conſiſt chiefly of ammonia, hydrogen, and carbonic acid, and are the immediate products of the diſſolution of animal or vegetable bodies, they are believed much to contribute to vegetation; as whatever materials have conſtituted an organic body, may again after a certain degree of diſſolution form a part of another organic body. The hydrogen and azote produce ammonia, which combining with carbon may form an hepar carbonis, and by thus rendering carbon ſoluble in water may much contribute to the growth of vegetables.

It has been ſaid, that ſome moraſſes have prevented the animal bodies, which have been buried in them, from putrefaction; which may in part have been owing to the great attraction of the carbon of the moraſs to putrid effluvia, and in part perhaps to the vitriolic acid, which ſome moraſſes are ſaid to contain.

4. Here occurs an important queſtion, by what other means is this ſolid carbon rendered fluid, ſo as to be capable of entering the fine mouths of vegetable abſorbents? The carbon, which exiſts in the atmoſphere, and in limeſtone, is united with oxygen, and thence becomes ſoluble or diffuſible in water; and may thus be abſorbed by the living action of vegetable veſſels; or may be again combined by

chemical attraction with the lime, which has been deprived of it by calcination.

When mild calcareous earth, as limeſtone, chalk, marble, has been deprived of its water and of its carbonic acid by calcination, it becomes lime. Afterwards when it is cold, if water be ſprinkled on it, a conſiderable heat is inſtantly perceived; which is preſſed out by the combination of a part of the water with the lime; as all bodies, when they change from a fluid ſtate to a ſolid one, give out the heat, which before kept them fluid. At the ſame time another part of the water, which was added, is raiſed into ſteam by the great heat given out as above mentioned; and the expanſion of this ſteam breaks the lime into fine powder, which otherwiſe retains the form of the lumps of limeſtone before calcination. But if too great a quantity of cold water be ſuddenly added, no ſteam is raiſed; and the lump of lime retains its form; whence it happens, that ſome kinds of lime fall into finer powder, and are ſaid to make better mortar, if ſlaked with boiling water than with cold.

On this account the lime, which is deſigned to be ſpread on land, ſhould previouſly be laid on a heap, and either ſuffered to become moiſt by the water of the atmoſphere, or ſlaked by a proper quantity of water; otherwiſe if it be ſpread on wet ground, or when ſo ſpread is expoſed to much rain, the heat generated will be diſſipated without breaking the lumps of lime into powder; which will then gradually harden again into limeſtone, diſappoint the expectation of the agricultor, and afflict him with the loſs of much labour and expence.

When the powder of ſlaked lime mixed with ſand and water is ſpread on a wall, that part of the water which is not neceſſary for its imperfect cryſtallization, evaporates into the air; and the lime then gradually attracts the carbonic acid, which is diffuſed in the atmoſphere; but as I ſuppoſe this carbonic acid is diſſolved in the water, which is alſo diffuſed in the atmoſphere; the lime is perpetually moiſtened

moiſtened by this new acquiſition of water from the air; as that, which before adhered to it, and had parted with its carbonic acid, evaporates. On which account new built walls are months, and even years, in drying, as they continue to attract water along with the carbonic acid from the air, which ſtands upon them in drops, till the lime regains its original quantity of carbonic acid, and again hardens into ſtone, or forms a ſpar by its more perfect or leſs diſturbed cryſtallization.

5. The earth I ſuppoſe acquires carbon, both in a manner ſimilar to the above by its attracting either the carbonic acid, or the water in which it is diffuſed, from the atmoſphere; and alſo by the ſpecific gravity of carbonic acid gas being ten times greater than that of common air; whence there muſt be conſtantly a great ſediment of it on the ſurface of the earth; which in its ſtate of ſolution in oxygen and water may be readily drank up by the roots of vegetables.

6. Another means by which vegetables acquire carbon in great quantity may be from limeſtone diſſolved in water; which though a ſlow proceſs occurs in innumerable ſprings of water, which paſs through the calcareous or marly ſtrata of the earth; as thoſe of Matlock and Briſtol in paſſing through limeſtone; and thoſe about Derby in paſſing through marl; and is brought to the roots of vegetables by the ſhowers, which fall on ſoils, where marl, chalk, limeſtone, marble, alabaſter, fluor, exiſt; which includes almoſt the whole of this iſland. By this ſolution of mild calcareous earth in water not only the carbon in the form of carbonic acid not yet made into gas, but the lime alſo, with which it is united, becomes abſorbed into the vegetable ſyſtem, and thus contributes to the nutriment of plants both as ſo much calcareous earth, and as ſo much carbon.

7. Another mode by which vegetables acquire carbon, may be by the union of this ſimple ſubſtance, with which all garden-mould abounds, with pure calcareous earth into a kind of hepar, analogous to the hepar of ſulphur made with lime, which abounds in ſome mineral

neral waters. And this I ſuppoſe to be the great uſe of lime in agriculture.

For the purpoſe of aſcertaining the probability of this mode of ſolution of carbon I made the following experiment. About two ounces of lime in powder were mixed with about as much charcoal in powder, put into a crucible, and covered with an inch or two of ſiliceous ſand. The crucible was kept red hot for an hour or longer, and then ſuffered to cool. On the next day water was poured on the lime and charcoal, which then ſtood a day or two in an open cup, and acquired a calcareous ſcum on its ſurface. And though it had not much taſte, except of the cauſticity of the lime, yet on dropping one drop of marine acid into a tea-ſpoonful of the clear ſolution a ſtrong ſmell like that of hepar ſulphuris was perceived, or like that of Harrogate water; which evinced, that the carbon was thus rendered ſoluble in water.

Perhaps the ſulphureous ſmell of Harrogate and Kedleſton waters, and other ſimilar ſprings, may be owing to the union of the alkali of decompoſing marine ſalt with the carbon of the earth, they run through? and this kind of water might thus poſſibly be uſed as a profitable manure?

8. Another mode by which vegetable roots acquire carbon, I ſuſpect to be by their diſuniting carbonic acid from limeſtone in its fluid not its gaſſeous ſtate; which the limeſtone again attracts from the atmoſphere and conſolidates, or from other matters included in the ſoil. Firſt, becauſe lime is believed by ſome agricultors, who much employ it, to do more ſervice in the ſecond year than in the firſt; that is in its mild ſtate, when it abounds with carbonic acid, than in its cauſtic ſtate, when it is deprived of it.

Secondly, that the uſe of burning lime ſeems hence to be ſimply to reduce it to an impalpable powder, almoſt approaching to fluidity; which muſt facilitate the application of the innumerable extremities of vegetable fibres to this uncalculable increaſe of its ſurface; which

may

may thence acquire by their abſorbent power the carbonic acid from theſe minute particles of lime, as faſt as they can recover it by chemical attraction from the air, or water, or from other inanimate ſubſtances in their vicinity.

Thirdly, the hyper-oxygenation of the perſpirable matter of plants, which thence gives up oxygen gas in the ſunſhine, would induce us to believe, that a great part of the carbon, which furniſhes ſo principal a part of vegetable nutriment, was received by their roots in the form of carbonic acid; and that it becomes in part decompoſed in their circulation, giving up its oxygen; which thus abounds in the ſecreted fluids of vegetables from this ſource, as well as from decompoſed water.

9. Another way by which carbon is received into the vegetable ſyſtem is by its exiſtence in ſugar and in mucilage; both which are taken up undecompounded, as appears by their preſence in the vernal ſap-juice, which is obtained from the maple and the birch; which like the chyle of animals, is abſorbed in its undecompounded ſtate.

V. PHOSPHORUS.

1. Another material which exiſts, I believe, univerſally in vegetables, and has not yet been ſufficiently attended to, is phoſphorus. This like the carbon, nitrogen, hydrogen, and ſulphur, is probably a ſimple ſubſtance; as our preſent chemiſtry has not yet certainly analyſed any of them; and therefore I ſuppoſe it is taken up intire by the abſorbent veſſels of vegetables, when it can be met with in a ſtate of ſolution; though it may alſo be occaſionally formed and ſecreted by them; and may hence be regiſtered among the articles of their food or ſuſtenance.

When wood is decompoſed by putrefaction in a certain degree of warmth and moiſture, it is often ſeen to emit much light in dark evenings, when recently broken and expoſed to the oxygen of the atmoſphere,

atmoſphere, ſo as to alarm benighted paſſengers; which is undoubtedly owing to the phoſphorus, which it contains, and which is at this time converted into phoſphoric acid. Such a light frequently is ſeen on putreſcent veal, when kept in a certain degree of warmth and moiſture; and on the ſea-weed placed on the oyſters packed in barrels, and ſent into the country; and in the ſtreets of Edinburgh, where the heads of the fiſh called whitings or haddies are frequently thrown out by the people, I have on a dark night eaſily ſeen the hour by holding one of them to my watch.

2. The exiſtence of phoſphorus in vegetables was detected by Margraaf; who found, that many vegetable matters, particularly farinaceous grains, contain enough of the phoſphoric acid to produce phoſphorus, when they are expoſed to great heat in cloſe veſſels. Macquer's Chemical Dictionary tranſlated by Mr. Keir, Vol. II. p. 535, Art. Phoſphorus. Phoſphorus has been detected in gum arabic, ſugar, honey, flour, and in every kind of vegetable or animal ſubſtance by the proceſs of making the phoſphorus of Homberg. And the exiſtence of phoſphorus in greater quantity in all the parts and recrements of animals, as in their fleſh, dung, urine, and bone-aſhes, and moſt copiouſly in the two latter, is evinced in the fabrication of Kunkel's phoſphorus. Whence its univerſal exiſtence is diſcovered in theſe two great kingdoms of nature. See the above Dict. Art. Pyrophorus.

The moſt eaſy proceſs for producing Homberg's phoſphorus conſiſts in mixing three parts of alum with one of ſugar, which are to be expoſed to a great heat in a covered crucible, till a bluiſh flame has appeared for ſome time. It muſt then be ſuffered to cool a little, and be put into a dry hot bottle, and cloſely ſtopped from the air. A drachm of this powder will afterwards, when poured from the bottle into the open air on paper, quickly kindle, become red like burning coals, and burn the paper, which it lies upon.

Hence we may conclude, that vegetable bodies, as well as animal ones,

ones, contain acid of phoſphorus; and that in this experiment the acid of the alum takes the fixed alkaline ſalt from the vegetable aſhes, and the calcareous earth, if ſuch there be, and that the carbon unites with the oxygen of the phoſphoric acid; and the vegetable phoſphorus is left mingled with the earth of alum; exactly in the ſame manner as the animal phoſphorus is obtained from the aſhes of bones, or the ſalt of urine, by calcining them in cloſe veſſels with charcoal.

3. An important queſtion now occurs; if this ſimple material of phoſphorus be not generally made in the veſſels of vegetables, whence do they acquire it? They may probably obtain it in conſiderable quantity from the recrements of decaying vegetable and animal bodies; as it appears in rotten wood, and in putrefying fiſh, and exiſts in ſuch large quantities in bone-aſhes, and in the ſalt of urine. But I ſuppoſe there is another great ſource of phoſphorus, I mean in calcareous earth, which alſo has been of animal origin in the early ages of the world.

If an oyſter-ſhell be calcined for about half an hour in a common fire, and is then kept from the air in a cold place; when it is afterwards expoſed for a while to the ſunſhine, and brought into a dark room, it will appear luminous like the calcined Bolognian ſtone; which is owing to the phoſphoric acid thus deprived of its oxygen by the carbon of the fire-coals, and intermingled with the pure calcareous earth or lime of the ſhell; and which again combining with the oxygen of the air, both light and heat are emitted in the reproduction of phoſphoric acid. See Wilſon on Phoſphori, Dodſley, London, 1795.

The Bolognian ſtone is a ſelenite or gypſum, which conſiſts of vitriolic acid and calcareous earth, and I ſuppoſe of acid of phoſphorus; ſince on mixing the powder of this ſtone with gum arabic, and calcining it ſome time, a kind of phoſphorus is produced ſimilar to the above, owing I ſuppoſe to the carbon of the fire coals, or of the gum arabic, carrying off the oxygen from the phoſphoric acid; which previouſly

viouſly exiſted both in the calcareous earth of the ſelenite, and in the aſhes of the gum arabic.

Mr. Canton, in the Philoſ. Tranſact. Vol. LVIII. p. 337, publiſhed his making a pyrophorus by calcining oyſter-ſhells, and then mixing them reduced to powder with ſulphur, and recalcining them in cloſe veſſels. This powder after being expoſed to light, or heated by other means, became luminous in the dark for many minutes. By this proceſs the acid of phoſphorus exiſting in the animal ſhell had been decompoſed by the red hot ſulphur having robbed it of its oxygen; and thus the phoſphorus remained united with the calcareous earth.

M. Du Fay, in a memoir publiſhed in the year 1730, aſſerts from experiments, that all calcareous ſtones, whether they contain vitriolic acid or not, are capable of becoming luminous by calcination; with this difference only, that the pure calcareous ſtones require a ſtronger or repeated calcination; whereas thoſe, which contain an acid, as ſelenites, or gypſum, become phoſphoric by ſlighter calcination. M. Margraaf alſo aſſerts, that all kinds of calcareous ſtones may by calcination be rendered phoſphoric; but thinks, that the pure ones ſhould be previouſly ſaturated with an acid. Keir's Dict. Art. Phoſphorus. And laſtly, ſome kinds of fluor, which is known to conſiſt of calcareous earth and the fluor-acid, emit phoſphoric light on being heated ſlowly, but looſe it, when much ignited. (Kirwan's Mineralogy.) This material might probably as well as gypſum become uſeful in agriculture.

4. Theſe experiments, which ſhew that all common calcareous ſtones, which contain only carbonic acid, were rendered phoſphoric by calcination; but that thoſe which did contain a fixed acid, as gypſum, and fluor, were rendered phoſphoric with leſs difficulty, acquaint us firſt with perhaps one very important uſe of lime in agriculture. Secondly, with that alſo of gypſum, or alabaſter, which has lately been uſed in America and in Germany without previous calcination; but

but which might probably be more ſucceſsful after calcination. And thirdly, with the probable uſe of fluor ſpar in its recent or calcined ſtate. As there is reaſon to believe, that the vegetable ſyſtem may abſorb phoſphorus from any of theſe materials; which phoſphorus may originally have been of animal origin, as well as that which exiſts in feces and urine. And laſtly, the uſe of recent ſhells or bones ground into powder, or of bone-aſhes, ſpread on land may be deduced; as they conſiſt almoſt entirely of phoſphorus and calcareous earth.

5. In the converſion of ſhells into limeſtone there ſeems to have been either ſimply an additional quantity of carbonic acid attracted from the air or from water during the proceſſion of ages, and added to the calcareous earth, or alſo a diminution of the phoſphoric acid. But an union of phoſphoric acid only with lime has lately been found to compoſe whole mountains in Spain, which is mentioned by Fourcroy, and is now termed phoſphate of lime, reſembling bone-aſhes. And M. Brumaire lately received from Spain a yellowiſh tranſlucent ſtone, called chryſolite by the jewellers, which he found to contain nearly equal parts of phoſphoric acid and calcareous earth, and to be a ſpar or cryſtallization of the phoſphate of lime. And as the limeſtone at Breedon has lately been diſcovered to contain equal parts of magneſia and lime, we may hope by greater attention to diſcover a mountain of phoſphate of lime in our own country. See Nicholſon's Journal 1798, p. 414.

From hence it would appear, that the immenſe quantities of limeſtone in the world, which was originally formed from the ſhells of ſubmarine animals, has during the long lapſe of time loſt more or leſs of its original phoſphoric acid, and acquired more or leſs carbonic acid. The carbon diſſolved in the atmoſphere or in the ocean having thus ſlowly decompoſed the phoſphoric acid in the elaboratory of nature without great heat, as it does in our crucibles in a ſhort time by the aſſiſtance of great heat.

It is probable that much phoſphorus may be conſumed in our inartificial mode of burning lime, which might be preſerved by calcining limeſtone in cloſe veſſels, and thus detaching the carbonic acid without admitting the aerial oxygen to the phoſphorus; but the advantage to agriculture of ſuch a proceſs can only be determined by experiment.

There are many inſtances given by Mr. Anderſon, and by Lord Kaims, of ſoils which are ſaid to have been for ages uncommonly fertile without addition of manures or culture. Theſe are plains near the ſhore in the county of Caithneſs, and in the Hebrides, and are ſaid to conſiſt almoſt entirely of ſhells broken into very ſmall particles, without almoſt any mixture of other ſoil. See Encyclop. Britan. Art. Agricult. Now the ſoil of an extenſive country called Lincoln Heath I obſerved ſome years ago to conſiſt in a great degree of powdered limeſtone, which like the Ketton limeſtone appeared in ſmall rounded particles, which I ſuppoſe had in remote times been diſſolved in water, and again precipitated; which ſhews a probable difference between this lime and recent ſhells in reſpect to their antiquity, and conſequently that the former muſt contain much of the original phoſphoric acid, and the latter only carbonic acid. And as Lincoln Heath was then eſteemed a very unproductive ſoil, there is reaſon to infer that the phoſphoric acid in recent ſhells is of greatly more ſervice to agriculture than the carbonic acid of alluvial limeſtone, or than calcined lime alone.

Hence it is probable, that a greater quantity of phoſphoric acid may exiſt in ſome marles than in others, as well as in ſome limeſtones; thus the appearance of recent ſhells exiſts in the lime near Loughborough in Leiceſterſhire, in the road to Nottingham, and in ſome marles called ſhell-marle; which muſt therefore probably contain much more phoſphoric acid, ſo as almoſt to reſemble the bones of animals; and may thus be more friendly to vegetation. A piece of land is mentioned by Mr. Anderſon, that, after a thick coat of marle

laid on it, bore crops for thirty years without additional improvement, and I think it was called ſhell-marle. See Encyclop. Britan. Agricult.

6. A medical philoſopher, M. Bonhomme, has endeavoured to ſhew, that the hardneſs of animal bones depends on the quantity of phoſphoric acid united to calcareous earth, which they contain; and that the rickets, a diſeaſe in which the bones become too ſoft, is ſolely owing to the want of it, or to the exiſtence of the vegetable acid inſtead of it. Annales de Chemie, Vol. XVII. May we not conclude, that the preſence of phoſphoric acid in the vegetable ſyſtem muſt be of importance; becauſe it ſo univerſally exiſts in them, and may probably give firmneſs to liqueous as well as to oſſeous fibres? To which may be added, that M. Fourcroy believes, that the aſhes of burnt vegetables, which have been ſuppoſed to conſiſt of earth or clay, when the fixed alkali is waſhed from them, are principally calcareous phoſphorus, like thoſe of animal bones. The ſame is aſſerted by Lord Dundonald in his Connection of Agriculture and Chemiſtry, p 25, who calls the inſoluble part of vegetable aſhes a phoſphat of lime. This ſubject is worthy further inveſtigation.

VI. LIME.

Many of the principal uſes of calcareous earth in promoting the growth of vegetables have been already mentioned in this ſection, which we ſhall recapitulate with additions.

1. One great uſe of calcareous earth I ſuſpect to conſiſt in its uniting with the carbon of the ſoil in its pure or cauſtic ſtate, or with that of vegetable or animal recrements during ſome part of the proceſs of putrefaction; and thus rendering it ſoluble in water by forming an hepar carbonis, ſomewhat like an hepar ſulphuris produced by lime and ſulphur, as mentioned in No. 4. 7. of this Sect.; by which proceſs

ceſs I ſuppoſe the carbon is rendered capable of being abſorbed by the lacteal veſſels of vegetable roots.

The black liquor, which flows from dunghills, is probably a fluid of this kind; but I mean to ſpeak hypothetically, as I have not verified it by experiment; and the carbon may be ſimply ſupported in the water by mucilage, like the coffee drank at our tea-tables; or may be converted into an hepar carbonis by its union with the fixed alkali of decaying vegetable matter, or by the volatile alkali, which accompanies ſome ſtages of putrefaction. See No. 10. 3. of this Section.

2. A ſecond mode of its ſerving the purpoſes of vegetation I believe to be by its union with carbonic acid, and rendering it thus ſoluble in water in its fluid ſtate inſtead of its being expanded into a gas; and that thus a great quantity of carbon may be drank up by vegetable abſorbent veſſels.

In the practice newly introduced of watering lands by deriving ſtreams over them for many weeks together, I am informed that water from ſprings is generally more effectual in promoting vegetation than that from rivers; which though it may in part be owing to the azotic gas, or nitrogen, contained in ſome ſprings, as thoſe of Buxton and of Bath, according to the analyſis of Dr. Prieſtley, and of Dr. Pearſon; yet I ſuppoſe it to be principally owing to the calcareous earth, which abounds in all ſprings, which paſs over marly ſoils, or through calcareous ſtrata; and which does not exiſt in rivers, as the ſalts waſhed into rivers from the ſoil all ſeem to decompoſe each other, except the marine ſalt, and ſome magneſian ſalt, which are carried down into the ocean. The calcareous earth likewiſe, which is waſhed into rivers, enters into new combinations, as into gypſum, or perhaps into ſiliceous ſand, and ſubſides. Theſe ſolutions of calcareous earth in thoſe waters, which are termed hard waters, and which incruſt the ſides of our tea-kettles, may poſſibly alſo contribute

tribute to the nutriment of animals, as mentioned in Zconomia, Part III. Article I. 2. 4. 2.

3. A third mode, by which lime promotes vegetation, I ſuppoſe may be aſcribed to its containing phoſphorus; which by its union with it may be converted into an hepar, and thus rendered ſoluble in water, without its becoming an acid by the addition of oxygen. Phoſphorus is probably as neceſſary an ingredient in vegetable as in animal bodies; which appears by the phoſphoric light viſible on rotten wood during ſome ſtages of putrefaction; in which I ſuppoſe the phoſphorus is ſet at liberty from the calcareous earth, or from the fixed alkali, or from the carbon of the decompoſing wood, and acquires oxygen from the atmoſphere; and both warmth and light are emitted during their union. But phoſphorus may perhaps more frequently exiſt in the form of phoſphoric acid in vegetables, and may thus be readily united with their calcareous earth, as mentioned in No. 5. 6. of this Section, and may be ſeparated from its acid by the carbon of the vegetable during calcination, and alſo during putrefaction, which may be conſidered as a ſlow combuſtion.

The exiſtence of a ſolution of phoſphoric acid and calcareous earth in the veſſels of animals is proved by the annual renovation of the ſhells of crab-fiſh, and by the fabrication of the egg-ſhells in female birds; and is occaſionally ſecreted, where it cements the wounds made on ſnail-ſhells; or where it joins the preſent year's growth of a ſnail-ſhell to the part, where a membranous cover had been attached for the protection of the animal during its ſtate of hibernation. And laſtly, it is evident from the growth of the bones of quadrupeds, and from the depoſition of callus to join them where they have been broken.

4. Lime in its pure ſtate is ſoluble in about 600 times its weight of water; and by a greater quantity of carbonic acid than is neceſſary for its cryſtallization, it is ſoluble in water in much greater quantities, as appears by the calcareous depoſition of the water at Matlock;

lock; and may I ſuppoſe ſupply a nutritious ſubſtance by uniting with mucilage or oil, either in the earth at the roots of vegetables, or on the ſurface of the ſoil, which may be gradually waſhed down to them.

If a ſolution of ſoap be poured into lime-water, the oil of the ſoap combines with the calcareous earth, and the cauſtic alkali is ſet at liberty, according to the experiments of Mr. Bertholet; (ſee Nicholſon's Journal, Vol. I. p. 170,) who concludes, that oil has a ſtronger affinity to calcareous earth than it has to fixed alkali. At the ſame time it appeared, that a ſolution of the mild or effervescent fixed alkali poured on this calcareous ſoap would decompoſe it by twofold elective attraction; as the carbonic acid of the mild fixed alkali unites with the calcareous earth of the calcareous ſoap, and the oil unites with the pure or cauſtic alkali.

Many arguments may be adduced to ſhew, that calcareous earth either alone, or in ſome of the ſtates of combination above mentioned, may contribute to the nouriſhment both of animals and vegetables. Firſt, becauſe calcareous earth conſtitutes a conſiderable part of them, and muſt therefore either be received from without, or formed by them, or both. Secondly, becauſe from the analogy of all organic life, whatever has compoſed a part of a vegetable or animal, may again after its chemical ſolution become a part of another vegetable or animal; ſuch is the general tranſmigration of matter!

5. There are other uſes of lime in agriculture, which may not be aſcribed to it as a nutritive food for vegetables, but from its producing ſome chemical or mechanical effects upon the ſoil, or upon other manures, with which it is mixed; as firſt, from its deſtroying in a ſhort time the coheſion of dead vegetable fibres, and thus reducing them to earth; which otherwiſe is effected by a ſlow proceſs, either by the conſumption of inſects, or by a gradual putrefaction. This is ſaid to be performed both by mild and by cauſtic calcareous earth, as in the experiments both of Pringle and Macbride. It is ſaid that unburnt

unburnt calcareous earth forwards the putrefaction of a mixture of animal and vegetable matter. But that pure lime, though it ſeemed to prevent putrefaction, deſtroyed or diſſolved the texture of the fleſh. Thus I am informed, that a mixture of lime with oak-bark, after the tanner has extracted from it whatever is ſoluble in water, will in two or three months reduce it to a fine black earth; which if only laid in heaps, would require as many years to effect by its own ſpontaneous fermentation or putrefaction. This effect of lime muſt be particularly advantageous to newly encloſed commons when firſt broken up.

Mr. Davis, in the papers of the Society of Arts, Vol. XVI. p. 122, aſſerts, that on a common, which had been previouſly covered with heath, but was otherwiſe very barren, the effect of lime was very advantageous for about ten years, during which time the vegetable roots might be ſuppoſed to have been diſſolved and expended; but that a ſecond liming he obſerved produced no good effect. It is probable the good effect might not be ſo great, but I ſhould doubt the circumſtance of its producing no good effect at all.

Mr. Browne of Derby has alſo an ingenious paper in the tranſactions of the Society of Arts, in which he aſſerts, that recent vegetables, as clover, laid on heaps and ſtratified with freſh lime, are quickly decompoſed, even in a few days. The heat occaſioned by the moiſture of the vegetables uniting with the lime I ſuppoſe quickens the fermentation of the vegetable juices, and produces charcoal in conſequence of combuſtion, ſimilar to that frequently produced in new hayſtacks, which if air be admitted burſt into flame.

Secondly, lime for many months continues to attract moiſture from the air or earth; which it deprives I ſuppoſe of carbonic acid, and then ſuffers it to exhale again, as is ſeen on the plaſtered walls of new houſes. On this account it muſt be advantageous when mixed with dry or ſandy ſoils, as it attracts moiſture from the air above, or

the earth beneath; and this moiſture is then abſorbed by the lymphatics of the roots of vegetables.

Thirdly, by mixing lime with clays it is believed to make them leſs coheſive; and thus to admit of their being more eaſily penetrated by vegetable fibres.

Fourthly, a mixture of lime with clay deſtroys its ſuperabundancy of acid, if ſuch exiſts; and by uniting with it converts it into gypſum, or alabaſter.

Fifthly, when lime is mixed with a compoſt of ſoil and manure, which is in the ſtate of generating nitrous acid, it arreſts the acid as it forms, and produces a calcareous nitre, and thus prevents both its exhalation and its eaſy elutriation.

And laſtly, freſh lime deſtroys worms, ſnails, and other inſects, with which it happens to come in contact, and with which almoſt every ſoil abounds.

6. The various properties of lime above deſcribed account for the great uſes of it on almoſt all lands; except perhaps ſome of thoſe which already abound with calcareous earth.

On riding from Beckingham to Sleaford, and from thence to Lincoln, I was informed by three or four farmers, that lime had been tried, but was believed to be of no ſervice in that country. Nor was I ſurpriſed at this obſervation, as I had ſeen fragments of alluvial limeſtone thrown out of every ditch on the road, which was of a looſe texture, conſiſting of calcareous ſand, like the Ketton limeſtone, rounded by friction, before it was conſolidated into a maſs, the upper ſurface of which was broken into fragments, when it was raiſed from the ſea by ſubterraneous fires, or by its cooling from a hot ſtate or its drying from a moiſt one.

Thus, as I had ridden over one ſingle alluvial limeſtone above ten miles broad and above twenty long, the broken ſurface of which appeared in the bottom of almoſt every ditch, I concluded, that the ſoil muſt be calcareous earth mixed only with ſome animal and vegetable

getable recrements, and that an addition of pure lime could probably not be of much advantage to the vegetables it ſupported. And the ſame I ſuppoſe muſt occur in thoſe ſituations, where the ſurface of the ſoil conſiſts almoſt totally of chalk, which is another kind of alluvial limeſtone; that is, which has been diſſolved in water in the early ages of the world, and again depoſited.

Yet even in ſome ſoils, which abound in calcareous earth, lime is eſteemed to be of ſervice; which may be owing both to its cauſtic quality, and to its being ſo finely pulverized. For a part of the water, which combines with it after calcination, gives out ſo much heat as to convert another part of it into ſteam; which breaks the calcined lime-lumps into a moſt ſubtile and impalpable powder, approaching even to fluidity, as mentioned in No. 4. 4. of this Section.

In the pariſh of Hartington in Derbyſhire there is a ſtratum of hard limeſtone, or marble, as I am informed, immediately beneath a ſhallow ſoil, and which in many places peeps through it; yet on ſome of this land an ingenious active agricultor has laid lime on the graſs in great quantity with prodigious advantage; and that he continues annually to improve by this means a conſiderable extent of land.

The difference between the hard limeſtone of this part of Derbyſhire, and the ſoft ſand-formed limeſtone about Lincoln Heath and Sleaford, may render the incumbent ſoil to be more or leſs mixed with calcareous earth; or they may abound more or leſs with phoſphoric acid, as mentioned in No. 5. 5. of this Section. But it may have happened, that ſome prejudices of the farmers, who gave me the information, might have led them to condemn the uſe of lime about Sleaford and Lincoln; and I ſhould again recommend it to their ſerious attention.

Another improper ſituation for the uſe of lime is ſaid to be on thoſe lands, which are too wet, and which therefore ſhould be previouſly drained; otherwiſe the lime is ſaid to coaleſce into a kind of mortar,

and become ſo hard, that the tender plumula of growing ſeeds, or the fine extremities of their roots, can not eaſily penetrate it. This may occur more certainly in that kind of lime, which contains manganeſe, and is therefore capable of ſetting under water, as, I ſuppoſe, the barrow lime of Leiceſterſhire, and agnes lime near Aſhbourn in Derbyſhire.

7. The great and general advantage of lime in all ſoils and all ſituations, except ſome of thoſe which are already replete with calcareous earth, or are too moiſt, can only be underſtood from the idea already mentioned of its ſupplying actual nutrition to vegetables; and this ſeems more probable, as it contributes ſo much to the melioration of the crops, as well as to their increaſe in quantity. Wheat from land well limed is believed by farmers, millers, and bakers, to be, as they ſuppoſe, thinner ſkinned; that is, it turns out more and better flour; which I ſuppoſe is owing to its containing more ſtarch and leſs mucilage.

Hence we perceive another very important uſe of lime in cultivation of land may be owing to its forwarding the converſion of mucilage into ſtarch, that is to its forwarding the ripening of the ſeed; which is a matter of great conſequence in this climate of ſhort and cold ſummers. See Sect. VI. 3. and XVI. 3.

In reſpect to graſs-ground I am informed, that if a ſpadeful of lime be thrown on a tuſſock, which horſes or cattle have refuſed to eat for years, they will for many ſucceeding ſeaſons eat it quite cloſe to the ground; which is owing, I ſuſpect, to the graſs containing more ſugar in its joints; or to the leſs acidity of all its juices.

8. There are not only ſome other bodies, which poſſeſs a calcareous baſe, beſides the common limeſtone, as gypſum, fluor, bone-aſhes, and perhaps vegetable aſhes; but there are others which are occaſionally united with carbonic acid, and may be detached from it by calcination, as the aerated barytes and magneſia. The laſt in its calcined ſtate may poſſibly be as uſeful in agriculture as the lime of

calcareous

calcareous earth, with which I believe it is frequently mixed. For Mr. Tennant aſſured me a few days ago, that he had analyſed the limeſtone of Breedon in Leiceſterſhire, and found it to contain nearly as much magneſia as calcareous earth, beſides ſome manganeſe; which is nevertheleſs a lime much eſteemed in this country both for architecture and agriculture. As magneſia exiſts in ſea-water, and in ſalt ſprings, it may render theſe waters uſeful as a manure as well as the marine ſalt, which they contain. As ſteatites or ſoap-ſtone conſiſts principally of magneſia, perhaps this limeſtone of Breedon may be worth the attention of the porcelain manufactory.

This magneſian lime of Breedon is further worthy attention in the cultivation of land, and particularly where a ſoil abounds with vitriol of iron, or where it abounds with gypſum, as about Chelaſton on the banks of the Derwent, and from Nottingham to Newark on the banks of the Trent, as the magneſian earth would unite with the vitriolic acid, and leave an ochre of iron in one caſe, and lime in the other; at the ſame time a ſoluble ſalt, called Epſom ſalt, would be formed, which, according to the experiments of Dr. Home, promotes rapid vegetation. To ſow a few pecks of gypſum reduced to powder on graſs land, as is done in America; and then to ſow upon this twice or thrice as much Breedon lime, might be an experiment which might be advantageous in the part of Derbyſhire next to Leiceſterſhire, where both of them are to be obtained at no great expence.

VII. CLAY, METALLIC OXYDES, NITRE, SEA-SALT.

1. The too great adheſion of the particles of argillaceous earth or clay renders it in its pure ſtate unfit for vegetation; as the tender fibrils of roots can with difficulty penetrate it, whence it becomes much improved for the purpoſes of agriculture, when it is mixed with calcareous earth and with ſiliceous ſand, as in marle.

It is commonly believed that lumps of clay become meliorated by being

being expoſed to froſt in its moiſt ſtate, which by expanding the water, which it contains, by converting it into ice is ſuppoſed to leave the particles of the clay further from each other. This however ſeems in general to be a miſtaken idea, ſince if the act of freezing be not very ſuddenly performed, a contrary effect ſeems to occur, as noticed by Mr. Kirwan; who obſerves, "that clay in its uſual ſtate of dryneſs can abſorb two and a half times its weight of water without ſuffering any to drop out, and retains it in the open air more pertinaciouſly than other earths; but that in a freezing cold clay contracts more than other earths ſqueezing out its water, and thus parting with more of it than other earths." Mineralogy, Vol. I. p. 9.

This curious circumſtance, that water, as it cryſtallizes, detrudes the clay, which is diffuſed in it, correſponds with other facts of congelation. Thus when wine, or vinegar, or common ſalt and water, or a ſolution of blue vitriol in water, are expoſed to froſty air; the alcohol, the acetous acid, the marine ſalt, and the calx of copper, are all of them detruded from the aqueous cryſtals, and retreat to the central part of the fluid, or to that laſt frozen, or into numerous cells ſurrounded with partitions of ice, as I have frequently obſerved; whence it appears, that wet clay is in general rendered more ſolid and tenacious by being frozen, as well as when it is dried, and its moiſture exhaled by too warm a ſun; and by both thoſe circumcumſtances becomes leſs adapted to the purpoſes of agriculture.

2. In moſt clays a kind of effervеſcence occurs, after they are turned over, and thrown on heaps, and thus acquire air into their inteſtines, which renders them much fitter for the purpoſes of vitrification; and thus forwards the proceſſes of the brick-kiln and pottery. This greater facility to vitrify is probably effected by the union of oxygen with the iron, which moſt clays contain; as oxydes of lead and manganeſe are uſed in the more perfect vitrifications.

The calciform ores, or oxydes, of iron, manganeſe, and zinc, are frequently found near the ſurface of the earth, where they have been

united with oxygen by the paſſing currents of the atmoſphere; and have been ſuppoſed to have originated from the decompoſition of vegetables and animal bodies, as mentioned in Botanic Garden, Vol. I. additional note 18. Iron has been detected in all vegetable and animal matters, manganeſe in ſome of them; and, if we poſſeſſed a teſt for diſcovering ſuch minute particles of zinc, as the magnet diſcovers of iron, it is probable, that zinc alſo would be detected in the vegetables, which grow over its beds.

As ſome philoſophers have lately contended for the great utility of oxygen in vegetation, as Humboldt and Von Uſlar; who affirm from their experiments, that hyper-oxygenated muriatic acid uſed in ſmall quantities promotes both the growth and irritability of plants; there is reaſon to ſuſpect, that the calciform ores of iron, manganeſe, and zinc, as well as minium, and other calces or oxydes of metals made by fire, and even burnt clays, when ſtrewed on the ground, may contribute to vegetation by their parting with their abundant oxygen in a fluid, not in a gaſſeous form; which uniting with carbon, or phoſphorus, or nitrogen, without emitting perceptible heat or light, might ſupply nutritious fluids to the roots of vegetables; further experiments are wanted on this ſubject. But I am well informed, that a red ocher of iron, called raddle, has been uſed on ſome lands with advantage in the north of Staffordſhire; and ſhould recommend a trial of manganeſe in thoſe countries, where it abounds, as near Kingſbury, and near Atherſtone in Warwickſhire; and a trial of lapis calaminaris, where it abounds, as near Matlock in Derbyſhire; and even of the calciform ore of lead, which is found in Angleſey, and on the top of ſome other lead mines.

M. Humbold aſſerts, that he mixed many ſeeds into a kind of paſte with the black oxyde of manganeſe, and poured over it the muriatic acid diluted with water, in the proportion of about ſix of water to one of acid; and that much oxygen was thus diſengaged, and occaſioned

ed quick vegetation. Journal de Phyſique, 1798. See No. 2. 8. of this Section.

3. When clays are turned up with the ſpade, as is uſual in preparing them for the brick kiln, a kind of efferveſcence occurs, as mentioned above; which is probably owing to the eſcape of the azote of the air impriſoned in the interſtices, as the oxygen unites with ſome metallic particles in the clay; or to ſteam raiſed from the water in the clay by the heat ſet at liberty from the combination of the oxygen and the iron. This union of oxygen with iron is curiouſly almoſt viſible in many granates or porphyries; which I have ſeen thinly ſcattered in large nodules near Cannock in Staffordſhire, in the road from Lichfield to Shrewſbury; and on breaking them have obſerved no appearance of iron on the newly divided ſurfaces; but which in a few days acquired an ochery appearance on them, which penetrated nearly half an inch. This can not but be aſcribed to the oxygen of the atmoſphere having united with the iron in theſe ſtones, which by their ſmell, when breathed upon, contain indurated clay, and having converted into an oxyde either the clay itſelf, or ſome metallic particles included in it.

There is nevertheleſs an exhalation from clay, and perhaps from moſt ſoils, when they have been previouſly dried, and then ſprinkled with water, as after a ſhower in ſummer, which has been ſuppoſed to be ſalubrious to invalids and convaleſcents. This remarkably occurs, when dry clay is breathed upon even in its moſt indurated ſtate, as in granites and porphyries, by which criterion theſe ſtones are immediately diſtinguiſhed from the ſiliceous and calcareous ones. This I imagine is produced by the heat ſet at liberty by the combination of dry clay and water, like that produced in ſo much greater degree by the combination of lime and water; and that this heat raiſes a part of the acquired moiſture into ſteam, in which are diſſolved the odorous particles; both which probably cauſe the quick vegetation on clayey ſoils after the ſhowers in ſummer.

When

When marl, which conſiſts of clay, calcareous earth, and ſand, which are frequently coloured red by iron, or blue probably by manganeſe, is expoſed in ſmall lumps to the atmoſphere; it is liable to crumble into powder, which I ſuppoſe to ariſe from a ſimilar circumſtance; that the oxygen of the atmoſphere uniting with the clay, or the metallic particles it poſſeſſes, lets at liberty the ſame gas, or ſteam, which is ſeen to riſe from clay, when thrown on heaps for the brick kiln or pottery; which breaks the lumps into powder, as the lumps of lime are broken into powder by the ſteam, which is generated when water is thrown on them, by the heat ſet at liberty by the combination of the lime and water.

This union of oxygen with the clay, or with the metallic particles mingled with it, I ſuppoſe to be much facilitated by expoſing it to a red heat, as in burning bricks; while a greater heat may unite ſo much oxygen with it as to turn it into glaſs. Exactly ſuch a proceſs occurs in the production of minium; a certain quantity of heat with the contact of air combines ſo much oxygen with the melted lead, as to form an oxyde; a greater quantity of heat converts it into glaſs.

4. When clay is united with ſo much oxygen by fire as to form a ſoft or imperfect brick, it poſſeſſes the power of promoting the generation of the nitrous acid in certain ſituations; which is frequently ſeen like an efflorescence on mouldering walls, having become by the addition of lime a calcareous nitre. The uſe of theſe ſoft bricks in the production of nitre is well known in Paris, where the rubbiſh of old houſes is regularly purchaſed for that purpoſe; which before the revolution was a royal manufacture.

As theſe ſoft efflorescent bricks from old houſes are known powerfully to promote vegetation, when pulverized and mixed with the ſoil; at the ſame time that they are capable of producing the nitrous acid; I imagine, that the uſe of paring and burning the turf of ſome newly encloſed commons depends on this circumſtance. That is,

that the heat emitted from the burning vegetable fibres unites oxygen with the clay; which latter forms more than half of the ſlices of turf, as they are dug from the ground. In other reſpects the paring and burning of graſs grounds would certainly be a waſteful procedure; as much carbon is converted into carbonic acid, and diſperſed along with the uninflamed ſmoke or ſoot, and nothing left but the vegetable aſhes. From theſe conſiderations it would probably be worthy experiment in farms, where coal and clay abound, to burn the latter to a certain degree; which might ſupply an exhauſtleſs ſource of profitable manure.

5. I have ſuſpected alſo, that this calcined clay, as it exiſts in ſoft bricks, has a power of decompoſing marine ſalt, as I once obſerved in a cellar, where beef had been long ſalted on one ſide of a nine-inch wall, the wooden ſalting-tub for which was attached to it; that a great effloreſcence appeared on the other ſide of the wall, which I believed to be foſſile alkali or natron. If this idea be juſt, the ſoft bricks from old buildings, or clays ſo far purpoſely burnt, may in this manner be ſerviceable to vegetation, by ſeparating the foſſile alkali from the ſea-ſalt, which is waſhed from decompoſing animal and vegetable ſubſtances; which by converting carbon into an hepar carbonis, as lime is ſuppoſed to do in No. 6. 1. of this Section, might render it ſoluble in water, and capable of being abſorbed by the lymphatic veſſels of the roots of plants.

If clay calcined to a certain degree, and thus united with oxygen, poſſeſſes the power of decompoſing marine ſalt, there is reaſon to believe, when it is more ſlowly united with oxygen by its expoſure to the atmoſphere by the ſpade or plough, that it may poſſeſs the ſame property; and that this may have given riſe to the very contradictory reports concerning the uſe of ſea-ſalt in agriculture; as it may probably be of great advantage to clayey ſoils, but perhaps not ſo to other ſoils. See Sect. XIV. 2. 8.

6. Another ſaline body, which readily unites with argillaceous earth

earth in the fire, is ſalt of urine, commonly called microcoſmic ſalt, which acts as a flux diſſolving clay with conſiderable efferveſcence. Kirwan's Mineralogy, Vol. I. p. 9. This microcoſmic ſalt conſiſts of phoſphoric acid united with an ammonical, or with a calcareous baſe; and muſt in the latter caſe reſemble the phoſphat of lime, of which there are whole mountains diſcovered in Spain, as mentioned in No. 5. 5. of this Section; and of which many may probably be diſcovered in our own country. Now as the ſame combinations of matter, which are quickly formed by the heat of the chemiſt's furnaces, are often performed, though more ſlowly, in the elaboratory of nature; it is probable, that if this calcareous phoſphorus could be procured in this country, reduced to powder, and ſpread on our clay lands, that it might more than any other calcareous matter render them friendly to vegetation, like the aſhes of burnt bones; which experiment alone can determine.

7. As clay is leſs adapted to the growth of the roots of plants by the too great coheſion of its particles, this may be in ſome degree corrected by frequently expoſing it to air impriſoned in its interſtices, as by turning it over by the plough or ſpade. Another method is by planting on it ſuch vegetables firſt as are known to grow well in clay, as beans, and as their roots are afterwards left in the clay, they not only thus form tubes in it, ſo as to render the maſs leſs coheſive; but add to it ſo much carbon, and thus rather enrich than impoveriſh it. Add to this that the lower leaves of the denſe foliage of theſe vigorous vegetables are believed to give out much carbonic acid by their reſpiration in the ſhade ſimilar to the reſpiration of animals; which perpetually ſinking down upon the ſurface of the ſoil is believed to ſupply it with carbon; and thus alſo to render it more nutritive to other vegetables, which may afterwards grow upon it.

Lord Kaimes, who allows that clay, if it be moiſtened after it has been pulverized, becomes on drying as indurated and coheſive as

before, aſſerts, that this does not happen, if it be moiſtened with the fluid, which eſcapes from dunghills; which may be owing both to the carbon, and to the fixed vegetable alkali, which that fluid contains. And alſo adds, that lime will prevent the coheſion or induration of clay, and therefore greatly improves argillaceous ſoils for all the purpoſes of agriculture.

8. When clay abounds with vitriolic acid ſo as to be converted into alum, it becomes very unfriendly to vegetation. In this ſtate it is believed much to counteract the proceſs of putrefaction in animal bodies, as is ſaid to have happened in ſome burying grounds. This it may effect by uniting with the ammonia generated by putrefaction the moment it is formed, or by preventing its production; as when the ſalt of Neville Holt water in Leiceſterſhire, which I ſuppoſe is alum, is mixed with very putrid blood, as I once witneſſed, the putrid ſcent was inſtantly deſtroyed, as I ſuppoſe the argillaceous earth was precipitated.

Where this acid or aluminous clay abounds, it is believed to check the vegetation of trees as well as of herbaceous plants by eroding the fine extremities of their roots, as mentioned in Sect. II. 9. which is perhaps beſt to be remedied in gardens by wood-aſhes or ſoap-ſuds, and in larger fields by mixing lime, or chalk in powder, or the ſweepings from roads, which are repaired by limeſtone, with theſe aluminous clays. Or laſtly, where it can be procured, by mixing with them ſuch lime as that of Breedon in Leiceſterſhire, which conſiſts of equal parts of magneſia and calcareous earth, which would thus fabricate what has been termed Epſom ſalt, which is ſaid to be friendly to vegetation.

VIII. MANURES BY SPONTANEOUS DECOMPOSITION.

We ſhall now conſider more generally the decompoſition of organized matter, which vegetable and animal bodies ſpontaneouſly undergo,

dergo, when they ceaſe to live. The proceſſes of this decompoſition have commonly been divided into the vinous, acetous, and putrefactive fermentations; which have been ſuppoſed uniformly to ſucceed each other. But it is more probable, that different kinds or parts of dead organized matter may be ſubject to many different kinds of chemical changes, and that theſe may vary with the degrees of heat, and the quantity of water, and of air, with which they are ſurrounded.

1. In the ſtomachs of animals a ſaccharine proceſs precedes the vinous fermentation; which laſt only occurs, when the animal power of digeſtion or abſorption is for a time ſuſpended. A ſimilar proceſs occurs in the germination of vegetable roots, whereby meal is converted into ſugar, as in the malt-houſe; and in the gradual ripening of apples and pears, after they are plucked from the tree; but all theſe may be ſaid to be ſtill alive; and this change of meal or of mucilage into ſugar may thus be eſteemed a vegetable rather than a chemical proceſs.

The art of cookery, by expoſing vegetable and animal ſubſtances to heat, has contributed to increaſe the quantity of the food of mankind by converting the acerb juices of ſome fruits into ſugar, as in the baking of unripe pears, and the bruiſing of unripe apples; in both which ſituations the life of the vegetable is deſtroyed, and the converſion of the harſh juice into a ſweet one muſt be performed by a chemical proceſs; and not by a vegetable one only, as the germination of barley in making malt has generally been ſuppoſed.

Some large round auſtere pears were yeſterday, November 20, ſhewn me after having been nine hours in the oven behind a kitchen fire covered ſome inches with water in a ſteam-pot. On taſting them they were ſweet, and ſoft, and appeared to have had at leaſt the heat of boiling water. They were replaced in the oven, and kept in it twelve hours longer; and then became nearly as ſweet as ſyrup or treacle; which might in part have been occaſioned by the

evaporation of half the water. From this curious circumſtance there ſeems reaſon to conclude, that in a degree of heat about that of boiling water the ſaccharine proceſs may ſucceed; and at the ſame time that the proceſs of fermentation may be prevented from exiſting; which I hope may induce ſome chemical philoſopher to inveſtigate by experiments this curious and important ſubject.

Some circumſtances, which ſeem to injure the life of ſeveral fruits, ſeem to forward the ſaccharine proceſs of their juices. Thus if ſome kinds of pears are gathered a week before they would ripen on the tree, and are laid on a heap and covered, their juice becomes ſweet many days ſooner. The taking off a circular piece of the bark from a branch of a pear-tree cauſes the fruit of that branch to ripen ſooner by a fortnight, as I have more than once obſerved. The wounds made in apples by inſects occaſion thoſe apples to ripen ſooner; caprification, or the piercing of figs, in the iſland of Malta, is ſaid to ripen them ſooner; and I am well informed, that when bunches of grapes in this country have acquired their expected ſize, that if the ſtalk of each bunch be cut half through, they will ſooner ripen.

The germinating barley in the malt-houſe I believe acquires not half its ſweetneſs, till the life of the ſeed is deſtroyed; and the ſaccharine proceſs then continued or advanced by the heat in drying it; though I have lately been informed that ſome grains of malt will vegetate after having been dried in the uſual manner, which however may have been owing to their not having been previouſly ſuffered perfectly to germinate. Thus in animal digeſtion the ſugar produced in the ſtomach is abſorbed by the lacteals, as faſt as it is made; otherwiſe it ferments and produces flatulency; ſo in the germination of barley in the malt-houſe ſo long as the new plant lives, the ſugar I ſuppoſe is abſorbed, as faſt as it is made; but that which we uſe in making beer is the ſugar produced by a chemical proceſs after the death of the young plant, or which is made more expeditiouſly than the plant can abſorb it.

It is probably this ſaccharine proceſs, which obtains in new hay-ſtacks too haſtily; and which by immediately running into fermentation produces ſo much heat as to ſet them on fire. The greateſt part of the grain, or ſeeds, or roots, uſed in the diſtilleries, as wheat, canary ſeed, potatoes, are not I believe previouſly ſubjected to germination; but are in part by a chemical proceſs converted into ſugar, and immediately ſubjected to vinous fermentation. And it is probable, a proceſs may ſometime be diſcovered of producing ſugar from ſtarch or meal; and of ſeparating it from them for domeſtic purpoſes by alcohol; which diſſolves ſugar but not mucilage; or by other means.

This then may be termed the ſaccharine fermentation, and may exiſt I ſuppoſe beneath or upon the earth in the beginning of ſome ſpontaneous vegetable decompoſitions, previous to the vinous fermentation; and may ſupply thus a very nutritive material to vegetation; ſimilar to that which the embryon plants in the ſeeds of many fruit-trees acquire from their fruits; and to that, which the embryons in many farinaceous ſeeds acquire from the ſpontaneous change of the meal in their cotyledons; though perhaps in leſs quantity and purity.

2. A ſecondary proceſs to this I ſuppoſe to be the vinous fermentation, in which much carbon becomes united to oxygen; and probably at the very inſtant of their combination, while they are yet in the form of a liquid, and not of a gas, they become abſorbed by the roots of plants. The heat, which is perceived in the hotbeds, which are uſed for the growth of cucumbers and melons, is produced by this union of oxygen and carbon, or by the generation of ſome other acids, as of phoſphorus, or nitre.

That this heat is owing to the atmoſpheric air combining with ſome inflammable baſe, and producing acidity of ſome kind, appears from the following experiment. A few years ago a gardener told me that a hot-bed, which he had made of tanner's bark with ſome horſe

horſe dung and ſtraw, was become too cold for the growth of his pots of cucumbers. He was deſired ſimply to turn over the bed, and ſhake every part of it in the air with his fork, as he lightly replaced it. This was complied with, and in a few days I obſerved by touching a ſtick, which had for ſome hours been inſerted into it, that it had acquired the uſual heat of a hot-bed.

This addition of heat was doubtleſs acquired from the air, which was recently included in the interſtices of the bed by its being turned over, broken into ſmall pieces, and expoſed to the atmoſphere; whence new acids ſeem to have been generated, and carbon, and perhaps phoſphorus and nitrogen, rendered ſoluble in water. Great heat is produced from the union of oxygen with thoſe baſes of acidity, which in large ſtacks of new hay is often known to excite real combuſtion; the violent fermentation of which may be partly owing to the ſugar, which is depoſited in the joints of graſs before the ſeeds are ripe for their nouriſhment, and partly to a chemical production of ſugar, as above deſcribed.

3. In the putrefactive proceſs carbon is not only converted into carbonic acid, as above related; but there appears to be a decompoſition of water, as is known by the ſmell of hydrogen; and it is probable, this inflammable body may unite with carbon, as in hydrocarbonate gas, and thus render them both ſoluble in water, and abſorbable by the veſſels of vegetable roots, without their paſſing into an acid or gaſſeous form, and may much contribute to the nutriment of vegetables.

4. There alſo appears at the end of the putrefactive proceſs to be a junction of azote with oxygen producing the acid of nitre, which probably may contribute much to promote vegetation. This appears from the mode of procuring that acid in France and Pruſſia, and which might be ſucceſsfully practiſed under every ſhed in our own farm-yards; as it conſiſts in a due mixture of vegetable and animal recrements with ſoil, frequently turned over to expoſe it to the air,

while

while it is defended by a ſhed from the ſunſhine and rain; which is thus at the ſame time adapted to produce the quickeſt vegetation, and to generate the nitrous acid.

The oxygen, which compoſes nitrous acid, is believed to adhere more weakly to its baſe the azote, than in the compoſition of other acids. On this account it ſo readily explodes by its junction with carbon in a given degree of heat. This looſe adherence of the oxygen in nitrous acid, like that of hyper-oxygenated marine acid, and of the oxygen in the ore of manganeſe, and of ſome other metallic oxydes, may adapt them to promote vegetation by their more readily parting with this material ſo eſſential in the compoſition of plants.

5. From the above obſervations it appears, that when the ſoil is turned over by the ſpade or plough, and thus acquires atmoſpheric air in its interſtices, and in conſequence becomes warm by the production of new acids, that the ſeeds or plants ſhould be inſerted as ſoon as convenient, for the purpoſe of their receiving the moſt ſalutary effect of thoſe operations. Nor ſhould this be obſerved only in black garden mould, or well manured glebes, where carbon or phoſphorus may be ſuppoſed to abound, and a proper diſpoſition for the production of the nitrous acid, but in thoſe clays alſo which are pure enough for the brick-kiln or the pottery.

IX. MANURES BY CHEMICAL DECOMPOSITION.

The uſe of fire and water contributes to increaſe the nouriſhment of mankind by rendering many vegetable materials innocuous, and others digeſtable in the animal ſtomach; and ſeems particularly efficacious in promoting the ſaccharine proceſs, and in producing mucilage from griſtles, horn, hair, and perhaps even from bones by means of Papin's digeſter. Whether this art could be advantageouſly uſed for the purpoſe of rendering manures capable of being abſorbed by

vegetable roots in a ſtate of leſs decompoſition, than by the ſlow proceſs of putrefaction, is a queſtion of curioſity and utility.

Sugar and mucilage are certainly abſorbed by vegetables without their being reſolved into the elements, from which they were compoſed; as appears in the ſap-juice which flows from the wounds of birch and maple trees in the vernal months; which I am informed will paſs into fermentation and produce wine; a proceſs which ſome modern chemiſt affirms cannot be effected by ſugar alone without the addition of mucilage. The abſorption of mucilage ſeems to occur in the germination of many ſeeds, as of barley; a part of the meal of the cotyledon is evidently converted into ſugar, but another part of it is probably abſorbed in the form of mucilage; ſome of which oozes on breaking the plumula; and in the growth of thoſe ſeeds, which contain oil, as in almond, hemp, rape, and line-ſeed, it is probable, a part of the undecompoſed oil may be abſorbed by the umbilical veſſels of the embryons in thoſe ſeeds.

It hence ſeems credible, that by the uſe of heat and water the art of cookery might furniſh mucilage, ſugar, and oil, from vegetable or animal materials; which might be converted into ſap-juice or chyle, without their being previouſly reduced into their elements; and might thus facilitate the more luxuriant growth of plants, as they contribute more to fatten animals, than materials of leſs combination.

2. To this might be added, that the putrefactive proceſs may be forwarded by heat in ſome materials by deſtroying the life of the material; as in roaſting apples and pears, and in killing the roots of potatoes, or the ſeeds of corn. Thus Mr. D——, a friend of mine, had twenty ſtrikes of potatoes, which he wiſhed to dry on a malt-kiln, hoping to render them more like the meal of wheat, and better to preſerve them during the ſummer-months. Whether they were ſufficiently dried he did not attend to; but they were carried into a granary, and laid on heaps; and in a week or two became ſo putrid, that

that the ſmell was inſufferable, his ſwine refuſed to eat them, and he was obliged to add them to the manure of the dunghill.

That potatoes, which have undergone a certain degree of heat, contribute more to fatten all kinds of animals, ariſes from the acrimony of their rinds being deſtroyed, and from their auſtere juices being converted into mucilage, and perhaps a part of their mucilage into ſtarch, and are hence ready for the ſaccharine and oily proceſſes of animal digeſtion. A very convenient method of expoſing them to ſteam is deſcribed in a late ingenious publication of the Agricultural Society. A ſmall boiler is ſet in brick work under a ſhed, ſo that the flame of wood or coal may paſs ſpirally round it. It ſhould be covered with a double lid of tin or wood to prevent much heat from eſcaping; and may have a ſand-joint to keep the ſteam in, or a little moiſt clay, or even a wet flannel put circularly round the cover may anſwer this purpoſe.

Near this furnace is to be fixed a large barrel on one of its ends, with a cover on the other end; which may be occaſionally opened to admit potatoes, and cloſed again ſo as to confine the ſteam, which is to be derived into it from the boiler by a double pipe one within the other, of tin or wood, about two inches in diameter. By theſe means a large quantity of potatoes may be rendered much more nutritive to animals, and I ſuppoſe to vegetables (if they were uſed as manure), as they may thus probably be abſorbed by their lacteals or lymphatics without being ſo much decompoſed as by the putrefactive proceſs; and thus produce nutriment in leſs time, and by leſs labour of digeſtion.

If the ſteam could be made hotter than boiling water, which it poſſibly may in the veſſel above deſcribed, if the water in it riſes but a few inches, and the ſteam after it is produced, is heated above 212 degrees by the ſides of the boiler above the water, round which the flame plays ſpirally, the ſteam thus made hotter might probably render the potatoes more mucilaginous or more ſtarchy.

3. A ſtill more effectual method of diſſolving hard vegetable and animal ſubſtances, and rendering them nutritive, might be by digeſting them for ſome time in water raiſed to a much greater heat than that of boiling. This is to be done in a cloſe veſſel, called Papin's digeſter; in which it is ſaid, that the confined water may be made red hot; and will then diſſolve hair, horns, hoofs, bones, tortoiſeſhell, and all animal, and perhaps many vegetable matters; which might thus facilitate their decompoſition for the purpoſes of manures, or for the nutriment of many animals; and might even contribute to the food of mankind in times of ſcarcity. This veſſel ſhould be made of iron, and ſhould have an oval opening at top, with an oval lid of iron larger than the aperture. This lid ſhould be ſlipped in endways, when the veſſel is filled, and then turned, and raiſed by a ſcrew above it into contact with the under edges of the aperture. There ſhould alſo be a ſmall tube or hole covered with a weighted valve to prevent the danger of burſting the digeſter.

4. Other materials might be rendered more eaſily digeſtible, and thence more nutritive to animals, and perhaps to plants, by mechanic trituration as well as by cookery; if the labour and expence were not too great; as the grinding of graſſes, ſtraws, and farinaceous ſeeds into powder between mill-ſtones; which have been called the artificial teeth of ſociety. It is probable, that ſome ſoft kinds of wood ground into powder, and eſpecially when they have undergone a kind of fermentation, and become of looſer texture, or boiled to deſtroy their acrimony, might be rendered uſeful food for ſwine or horſes, and even for mankind in times of famine.

Nor is it improbable, that hay, which has been kept in ſtacks, ſo as to undergo the ſaccharine proceſs, may be ſo managed by grinding and by fermentation with yeaſt like bread, as to ſerve in part for the ſuſtenance of mankind in times of great ſcarcity. Dr. Prieſtley gave to a cow for ſome time a ſtrong infuſion of hay in large quantity for her drink, and found, that ſhe produced during this treatment

above

above double the quantity of milk. Hence if bread cannot be made from ground hay, there is great reaſon to ſuſpect, that a nutritive beverage may be thus prepared either in its ſaccharine ſtate, or fermented into a kind of beer.

It may be here obſerved, that it is believed by ſome, that feeding horſes with ground corn, as with the flour of beans or oats, does not ſtrengthen them nearly ſo much as by giving them the ſame quantity of oats or beans whole. Parkinſon, Exper. Farmer, Vol. I. p. 227. It is aſſerted alſo that ſoup, with the fleſh-meat boiled down into a fluid maſs, will give much leſs ſtrength to a man, than he would acquire by eating the ſolid meat, of which the ſoup was made. The reaſon of both theſe ſeems to ariſe from the ſaliva being well mixed with the maſticated food, and in greater quantity; which therefore becomes more animalized aliment, than that diſſolved in water alone, and is more eaſily converted into nutriment.

In times of great ſcarcity there are other vegetables, which though not in common uſe, would moſt probably afford wholeſome nouriſhment, either by boiling them, or drying and grinding them, or by both thoſe proceſſes in ſucceſſion. Of theſe are perhaps the tops and the bark of all thoſe vegetables which are armed with thorns or prickles, as gooſeberry-trees, holly, gorſe, and perhaps hawthorn. The inner bark of the elm-tree makes a kind of gruel. And the roots of fern, and probably very many other roots, as of graſs and of clover, taken up in winter, might yield nouriſhment either by boiling or baking, and ſeparating the fibres from the pulp by beating them; or by getting only the ſtarch from thoſe which poſſeſs an acrid mucilage, as the white briony.

The grinding of bones to powder has already been applied to agriculture, and the chopping of woollen rags; and I ſuppoſe the trituration of alabaſter, and of chalk, and of ſoft bricks, and probably of iron ochres, manganeſe, and calamy, might well repay the labour;

after

after a few experiments had been inſtituted to determine the quantity, which ſhould be ſtrewed on different ſoils.

X. MANURES BY INSECT PROPAGATION.

1. That the continual growth and decay of animal and vegetable nature increaſes the quantity of ſuch matter, as is fit for the reproduction of organized bodies, is evinced by the increaſing fertility of cultivated countries; ſince even in theſe a great quantity of the annual recrements of decompoſed animals and vegetables are waſhed by rains from the ſoil, and carried down the rivers into the ocean; and in many ſituations of ſoil in Africa and America, which have been but lately cultivated, there exiſts a wonderful fertility from the aggregate remains of vegetable and animal bodies; which have for uncounted ages ariſen and periſhed there; and which have either left moraſſes, where they could not part with their ſuperabundant water; or a fertile earth, ſuch as in our gardens and church-yards, where the declination of the ground was more favourable.

Some countries on the contrary once highly cultivated and very populous are in proceſs of time become deſerts of ſand; as many parts of Syria, and the diſtricts about Palmira, and Balbec. This has probably been owing to the want of the neceſſary moiſture in thoſe warm and ſandy regions; which was formerly ſupplied by artificial derivations of water; but which ceaſed, after their inhabitants were deſtroyed by war and tyranny; and ſecondly to the rapid ſtreams occaſionally poured over them by the monſoon floods; ſimilar to thoſe which impoveriſh Abyſſinia and Nubia, while they fertilize the flat and ſhowerleſs provinces of Egypt.

We might add, that all calcareous ſtrata are now believed to have been produced by ſhells depoſited by aquatic animals in the early ages of the world; and that the materials, which conſtitute the ſtrata above

them, have afterwards been formed by the recrements of terreſtrial animal and vegetable bodies. Whence it may be concluded, that vegetables and animals during their growth increaſe the quantity of matter fit for the more nutritive food of organized bodies, or of that which is leſs decompounded; while they muſt at the ſame time occaſionally form or elaborate a part of the materials, of which they conſiſt, from the ſimple elements of hydrogen, nitrogen, carbon, phoſphorus, ſulphur, and oxygen; into which modern chemiſtry has reſolved them by analyſis.

And laſtly, that vegetables can acquire nutrition from water and air alone with the carbonic acid, which floats in them, appears by the experiments of thoſe philoſophers, who have nicely encloſed the roots of ſome plants in pots, and moiſtened them with diſtilled water; and from hence we learn an eſſential diſtinction between vegetable and animal nature; the former can elaborate the two univerſal elements of water and air into nutritive juices, whereas the latter is neceſſitated to ſeek more compound nutriment, and to live upon the vegetables, which have produced it.

2. One method therefore of increaſing manures may be by repeatedly propagating and deſtroying vegetable crops; as by raiſing thoſe of quick growth, and ploughing them again into the ſoil during their ſaccharine and mucilaginous ſtate, before they ripen their ſeeds; as of vetches, and buck-wheat; vicia and polygonum; and thus producing a ſucceſſion of crops by the partial decompoſition of the preceding ones. And it is probable that this proceſs might be much improved by ſtrewing lime over the recent vegetables, at the time of ploughing them in, as is ſhewn in No. 6. 5. of this Section.

3. Another mode by which vegetable matter may be decompoſed in the ſummer months, and at the ſame time the quantity of manure increaſed, is by the depredation of inſects, as is ſeen in wood, which is ſo far decompoſing as to become tender, and is then conſumed by various kinds of inſects, whether it be buried beneath the ſoil, or ex-

poſed

poſed to the air. And I ſuſpect, that the excrement and the bodies of ſuch inſects would ſupply more nutriment to vegetable roots, than if the vegetable recrements were left to their ſpontaneous or chemical diſſolution; as I ſuppoſe the bitter excrementitious powder in a filbert, and the well fed maggot, before it erodes its way out, would fertilize more barren ſoil than an emulſion of the kernel.

An ingenious obſerver of nature conveyed water on a dunghill in the ſummer months in ſuch quantity, as to make a kind of ſemi-fluid chaos, for the purpoſe of animating the whole maſs. It became full of inſects, and was uſed in the autumn as manure, and he believed with much greater powers, than it would have otherwiſe poſſeſſed.

Hence in the ſummer months a manure-heap may be advantageouſly ſupplied with water for the purpoſe of encouraging the propagation and nouriſhment of myriads of inſects; but in the winter ſeaſon it ſhould not be expoſed to much moiſture; or that which drains from it ſhould be derived ſpontaneouſly on lower grounds, or conveyed to higher ones by pumps or water carts; as it probably conſiſts of a ſolution of carbon by means of vegetable alkali; or of a mixture of it in water by mucilage; and is thought to fertilize the ground more than the other parts of the manure heap. In the tranſactions of ſome provincial Society there is an account of much fixed vegetable alkali having been obtained from the evaporation of the water, which oozed from dunghills; and M. Rouelle has obſerved, that fixed alkali diſſolves a conſiderable quantity of charcoal by fuſion. Fourcroy's Elem. of Chemiſt. Vol. IV. p. 125.

4. Another great ſource of inſect-manure may be obtained from the myriads of ſmall fiſh, by thoſe who live near the ocean; which by mixing them with ſoil ſo as to make what is termed a compoſt, will much add to the fertility of the land, on which it is afterwards ſpread, more ſo perhaps than any other material except the fleſh of land-animals. In China it is ſaid that the ſpawn of fiſh in the proper ſeaſon

is

brought to market, and purchaſed for the purpoſe of peopling the floods on their rice grounds with fiſh, part of which becomes large enough to be fried and eaten by the land cultivator; and the reſt ſerves the purpoſe of fertilizing the ſoil, when the floods are drawn off, by their death and conſequent decompoſition.

XI. PRESERVATION OF MANURES.

1. The fertility of all countries depends on the ſaving and uſing thoſe kinds of matter, which are fit for the reproduction of organized bodies. There is a proverb in China, that for this purpoſe a wiſe man ſaves even the parings of his nails, and the clippings of his hair.

One great waſte of manure in this country, and in moſt others, is from the frequent rains waſhing down the diffuſible and ſoluble parts of the ſoil into the muddy rivers; ſo that every flood from ſudden ſhowers carries into the ſea many thouſand pounds worth of the matter of fertility; and thus diminiſhes ſo much the food of terreſtrial animals, however it may add to the ſuſtenance of marine ones. The Delta of Egypt, and a diſtrict in South America near the foot of the Andes mentioned by Ulloa, are ſaid by the ſituation of the ſurrounding country to be free from rain, though they have frequent dews; and to this circumſtance they may in part owe their increaſing fertility.

In this country the ſnow-floods, which occur after a continued froſt, are leſs injurious than thoſe from rains; as the ſtreams of water from the upper ſurface of the diſſolving ice flows over the under ſurface of it not yet diſſolved; and the ſoil is not agitated as in rain by the percuſſion of the deſcending drops; inſomuch that in ſnow-floods the rivers are ſcarcely muddy; whence theſe floods may be readily diſtinguiſhed from land-floods by the eye, and are much leſs injurious.

Great attention ſhould therefore be ſhewn to the preventing ſmall

ſhowers from waſhing away the ſoluble parts of good ſoil. For this purpoſe all hills ſhould be ploughed horizontally, and not in aſcending and deſcending furrows. Deſcending plains of graſs-ground might alſo be laid with horizontal ridges and depreſſions; by which management ſhowers will lie a few hours in the horizontal furrows or depreſſions, and either exhale or ſoak into the ground; and in very wet ſeaſons theſe may eaſily by the ſpade be opened into each other, if the water is found to lie too long upon them, ſo as to produce too much cold by its evaporation, or too great ſoftneſs by its abſorption into the ſoil.

2. Secondly, the manures of towns and cities, which are all now left buried in deep wells, or carried away by ſoughs into the rivers, ſhould be removed by a police, which is ſaid to exiſt in China; and carried out of towns at ſtated intervals of time for the purpoſes of agriculture; which might be performed in the night, as is done in Edinburgh; or by means of large baſons or reſervoirs at the extremities of the common ſhores, or ſoughs for the reception of the manure, before it is waſhed into rivers. See Embaſſy to China by ſir G. Staunton, Vol. III. p. 308, 8vo. edit.

It has been believed by ſome writers in the American Medical Repoſitory, that the peſtilential fever, which has of late infeſted that country, was in part produced or propagated by the filth of the ſtreets of New York. Dr. S. L. Mitchill adds to his chemical remarks on manures, "it muſt be welcome intelligence, that the collected maſs of nuiſance, which we are now with ſuch happy ſucceſs engaged in removing from the city of New York, is convertible by the powers of vegetation from poiſon to wholeſome articles of food; and thus the purity and healthineſs of the towns may contribute to the thriftineſs and wealth of the ſurrounding country." Medical Journal, No. I.

3. Thirdly, there ſhould be no burial places in churches or in church-yards, where the monuments of departed ſinners ſhoulder God's

God's altar, pollute his holy places with dead men's bones, and produce by putrid exhalations contagious diſeaſes among thoſe who frequent his worſhip. But proper burial grounds ſhould be conſecrated out of towns, and divided into two compartments, the earth from one of which, ſaturated with animal decompoſition, ſhould be taken away once in ten or twenty years, for the purpoſes of agriculture; and ſand or clay, or leſs fertile ſoil, brought into its place.

A great riſe of the ſoil, from the remains of the bodies entombed in it, is ſeen round the churches of almoſt all populous towns; ſo as to have rendered it neceſſary to deſcend by ſeveral ſteps into thoſe churches, which were originally built ſo as to require ſteps to aſcend into them; as may frequently be ſeen by the baſe of the architecture. Nor would the removal of this earth, if the few bones, which might be found, were again buried for a further decompoſition, be likely to ſhock the relations of the deceaſed; as the ſuperſtition concerning the earth, from which we roſe, and into which we return, has gradually vaniſhed before the light of reaſon; as occurred about thirty years ago in removing much rich earth from the cloſe of the cathedral at Lichfield, and more lately in changing a burying ground at Shrewſbury; both which were executed without ſuperſtitious terror, or popular commotion.

4. Fourthly, a great waſte of the materials of fertility occurs in all countries, and cannot eaſily be avoided, in the conſumption by fire of ſo much wood inſtead of coal. Whence the mucilage, and other nutritious juices, which exiſt in the fire-wood, are decompoſed into their elements; and the carbon united with oxygen is diffuſed in the atmoſphere, and in part carried by the winds into the ſurrounding ocean; inſtead of the manures occaſioned by the ſlow decompoſition of it upon or beneath the ſoil, or by the depredation of inſects; which might ſupply leſs decompoſed nutriment to the abſorbent roots of plants.

This may be more eaſy to conceive, if we compare the little vege-

table nutriment, which could be derived from the ſmall quantity of aſhes left from a cart-load of burnt-ſtraw, with that which would ariſe from the ſame quantity of ſtraw mixed with ſome animal recrements, and made into a manure heap. A ſtill greater diminution of uſeful manure would be made by burning ſhavings or raſpings of horn, or woollen rags, or hair, or fleſh; as a nutritive mucilage would be thus decompoſed into its elements, which might otherwiſe have been gradually diſſolved beneath the ſoil, and abſorbed by the roots of vegetables nearly in an unaltered ſtate; as jellies and mucilage are known to be drank up by the lacteals of animals; and, when drank in too great abundance, to appear almoſt unchanged in their urine.

It muſt hence appear, that the numerous fires of a great city, if ſupplied with wood inſtead of coals, as in Paris, muſt very much impoveriſh a great part of the country which ſupplies it; not only in the neceſſity of uſing large tracts of land for the growth of fire-wood, but alſo becauſe ſo ſmall a part of it returns as manure. There is a provident adage of general benevolence, "Burn nothing which any animal will eat;" that is, "Burn nothing which may nouriſh animals by its digeſtion in their ſtomachs." May not the ſame benevolent idea be extended to the vegetable world, and ſay, "Burn nothing which may nouriſh vegetables by its ſlow decompoſition beneath the ſoil, which conſtitutes their ſtomachs."

5. It may be a matter of uſe as well as of curioſity to aſcertain the ſituations and circumſtances moſt favourable for promoting the ſpontaneous decompoſition of vegetable ſubſtances; which may conſiſt perhaps in the due quantity of air, water, and heat, with a ſufficient proportion of animal ſubſtances, and finally an admixture of lime toward the end of the proceſs.

1. In a cellar covered with an arch of bricks, and cloſed with a very ſtrong door, I once obſerved, that a deal ſhelf two inches in thickneſs was decayed, ſo as to fall down with ſome wine bottles on it,

it, in about four years. This ſudden decay I believed to have been owing to the unchanging moiſture of the board, and at the ſame time to its expoſure to unchanged air without the power of much exhalation; by which a ſlow fermentation was induced, and a conſequent ſlow putrefaction, unchecked by the extremes either of heat or cold.

For the ſame reaſon I ſuppoſe the wooden ſupporters of bridges decay firſt juſt above the ſurface of the water; and pieces of timber buried but a few inches under ground, which are there expoſed to the influence both of water and air, go quicker into fermentation, and conſequent putrefaction, than thoſe pieces of timber, which are many feet buried beneath the ſoil, or immerſed deep in water; which in that ſituation continue unchanged for ages. The ſame ſeems to occur in the vinous fermentation, which is inſtantly checked, if not totally ſtopped, by bunging the barrel, or corking the bottle, which contains it, and thus precluding the acceſs of atmoſpheric air.

2. From hence it may be concluded, firſt, that the vegetable and animal ſubſtances, which we wiſh ſoon to become decompoſed by the fermentative and putrefactive proceſſes, ſhould be expoſed to an uniform moiſture, though not covered deep with water; as is generally practiſed in the firſt part of the preparation of hemp or flax, which is deſigned to diſſolve the mucilage, and the cellular membrane of thoſe vegetables, without injuring the ligneous fibres. And that they ſhould be ſo far accumulated as not too much to exhale; yet not to lie in ſuch large heaps, as entirely to preclude the acceſs of air from the interior parts of them.

The manures of great farms ſhould therefore be occaſionally removed from the fold-yards, or large reſervoirs of it, and laid in ſmall heaps not only to increaſe its ſurface expoſed to the external atmoſphere, for the purpoſe of exciting greater fermentation, which is a ſlow combuſtion; but alſo that air may be impriſoned in the interſtices of theſe manure-heaps, as mentioned in No. 8. 2. of this Section.

It

It ſhould then be uſed on or in the ſoil, as it afterward loſes much of its nutritive qualities by evaporation, or ſinking into the ground, or draining away.

3. A due degree of heat is neceſſary for the commencement of fermentation and putrefaction, as both vegetable and animal materials, as fruit or fleſh, may be preſerved for years if kept in an ice-houſe below the freezing point of 32. And alſo, I am told, if they could be kept in an uniform degree of heat above the boiling point of 212. After the commencement of either of theſe proceſſes a quantity of heat is evolved from the combination of the oxygen and carbon, which contributes to forward the proceſſes by promoting the union of the next particles of oxygen and carbon; which may thence be compared to a ſlow combuſtion, or to a gradual exploſion of gunpowder.

This heat therefore ſhould be managed with ſome addreſs, as a great quantity of it would calcine or evaporate too much of the materials, and leave the remainder a leſs profitable maſs; as happens, I am informed, to ſome parts of thoſe heaps of manure, which are uſed in the manufactory of white lead; while on the contrary, when the heat is too ſmall, as in ſevere froſt, theſe proceſſes of decompoſition will not commence, or may be ſtopped in their progreſs. In the former caſe, where the heat is too great, it may be checked by covering the whole manure-heap with ſoil and turf, and thus preventing the acceſs of air. And when the heat is too ſmall, as in old hot beds, it may be renewed or promoted by turning the heap over with the ſpade, and thus confining a new quantity of air in its interſtices. On theſe accounts it appears, that in the vernal and autumnal months theſe proceſſes muſt ſucceed better than in the winter or the ſummer ones.

4. Toward the end of the putrefactive proceſs the materials ſhould be repeatedly turned over with the ſpade, not only for the purpoſe of ſimply expoſing their interior parts to the atmoſphere, but alſo of in-

cluding air in the interſtices; as the union of carbon with oxygen, and probably of azote with hydrogen, ſeems thus to be occaſioned; by which the three laſt of theſe elements may change from a gaſſeous ſtate into a fluid one, and thus become abſorbed by vegetable roots.

Laſtly, I conclude that in general the manure heap before ſtables, or in the fold-yard, ſhould be placed on a gently riſing eminence, with a baſon beneath it, that the ſuperfluous water, which would otherwiſe prevent the fermentation of the ſtraw, may drain off and be there received; and that into this baſon, as often as a fluid appears in it, ſome earth, or weeds, or leaves, or ſaw-duſt, or other vegetable or animal recrements ſhould be thrown; the fermentation and putrefaction of which will be thus forwarded, and the carbonic draining from the manure-heap will not be loſt.

5. The admixture of lime with this carbonic ſoil is found by daily experience to produce the moſt fertile compoſitions for the growth of vegetables, and for the production of nitre. The great uſe of nitrous acid in vegetation has long been acknowledged, and that of hyper-oxygenated marine acid appears probable from recent experiments; and would ſeem to be occaſioned by the more looſe adheſion of the oxygen in thoſe acids to their reſpective baſes; which may therefore in its fluid ſtate be more readily abſorbed by vegetable roots. One uſe therefore of the admixture of lime in ſuch a compoſt of ſoil and manure is to arreſt the nitrous acid, as it is formed, and by making a calcareous nitre, prevent its exhalation, or its eaſy elutriation from the other materials.

6. A principal circumſtance for the quicker and more perfect decompoſition of vegetable recrements is a due quantity of animal matter, and their being properly mixed together; as appears from the early experiments of ſir John Pringle and Macbride, and by daily experience. There is nevertheleſs great neglect in this reſpect in all thoſe farm-yards, where the ſwine have their food in fixed ſtone-troughs,

troughs, from which the refuſe is occaſionally waſhed or ſwept. Whereas if wooden moveable ſwine-troughs were always placed on the ſummit of the heaps of dry ſtraw, the quantity of their ſwill, conſiſting of broth, whey, and other vegetable and animal matter, which theſe animals waſte in their contention for it, would generate early putrefactive proceſſes; beſides their mixing the ſubſtances well together with their feet, and adding to it their urine and ordure.

Beſides this inattention to the manure-heap in many houſes the waſhings of boilers, and milk-pans, and diſhes, as well as the ſoap-ſuds, which are all of them manures of the moſt productive kind, are thrown into the common ſewer, inſtead of being derived or carried to the garden or the ſtraw-yard.

7. Another inattention to the production of manures concerns the heaps of common weeds, and of dock-roots, and of cabbage-ſtalks, and the roots of twitch-graſs; which improvident farmers and gardeners frequently throw into the high roads, or conſume with fire; and which if laid on heaps, and occaſionally turned over, and covered with ſoil, will quickly die, and paſs into ſpeedy fermentation from the ſugar and mucilage, which they contain; and if to theſe a portion of lime be added, I am informed by one who made the experiment, that the whole was decompoſed in a ſhort time, and manure of the beſt kind was the product.

The ſame ſhould be practiſed with the leaves which fall in autumn on graſs land, eſpecially from thoſe orchards, or hedges, or from gooſeberry-trees, which have been infeſted with caterpillars; ſince I am told the eggs of a future race of theſe inſects are frequently depoſited on the leaves, and hatched on or beneath the ſoil in the enſuing ſpring. Theſe therefore ſhould be removed from the roots of ſuch trees, and converted into manure by the proceſs above mentioned.

Along with the weeds and leaves above mentioned I ſhould ſtrongly recommend to the induſtrious agricultor to collect the water-plants

which

which grow in great abundance in lakes and rivers, for the purpoſe of manure; which at preſent are employed to no advantage. Theſe might be moved twice a year, as it is probable that theſe vegetables in their younger ſtate, as the typha, or cat's-tail; the butomus, or flowering-ruſh; nymphæa and aliſma, as well as many other aquatic plants, would give better manure, or ſooner become ſufficiently decompoſed, during their more ſaccharine and mucilaginous ſtate, than when they have acquired more fibrous leaves, and more woody ſtems.

By thus expoſing the roots and tops of weeds to fermentation, their ſeeds would alſo be deſtroyed as well as the vegetative power of their roots; and on this account the hay-ſeeds collected from ſtacks, which have fermented too violently, ſo as to become black by this ſlow combuſtion, are frequently ſo much injured as not to vegetate, to the great diſappointment of the ſower, a circumſtance which alſo ſometimes occurs in ſtacks of wheat, as mentioned in Sect. XVI. 7. 1.

8. Laſtly, peat, ſo well underſtood and ſo ſtrongly recommended by Lord Dundonald, is too much neglected in agriculture. The peat or turf, which conſtitutes the ſolid parts of moraſſes, as it conſiſts of vegetable fibres in different ſtates of decompoſition, may be laid on clayey or ſandy ſoils with the greateſt advantage; and ought to be conſidered as an ineſtimable treaſure to the farms in its vicinity. Or it may previouſly be laid on heaps, and thus mixed with air and drained from water for further decompoſition, with or without the addition of lime.

XII. APPLICATION OF MANURES.

Two queſtions of importance here preſent themſelves. As the ſpontaneous or chemical changes of manure-heaps in farm-yards gradually progrede from the ſaccharine and mucilaginous commence-

ment through a great variety of other fermentations; which can only be named from the principal material, which each of them produces, as carbonic acid, alcohol, vinegar, volatile alkali, hydrogen, nitrous acid, and finally carbonic earth. At what era or ſtage of this decompoſition of vegetable and animal ſubſtances can they be moſt advantageouſly applied to the purpoſes of agriculture? and ſecondly, at what time of the year?

1. In reſpect to the era of the progreſs of the decompoſition in manure-heaps, in which they may be moſt advantageouſly applied in agriculture, the particular purpoſe of that application muſt be attended to. Where they are deſigned to be ſpread on the ſurface of graſs lands, as a top-dreſſing, the accumulations of vegetable and animal recrements ſhould be permitted to go through the various ſpontaneous proceſſes of decompoſition, which begin with the ſaccharine and mucilaginous ſtate, and end with the production of carbonic earth, with many kinds of intermediate fermentations, if they may be ſo called, which accompany or ſucceed each other, and which I believe to be more in number than have had names applied to them.

But that leſs of the fertilizing materials, whether of ſoluble ſolids, or of fluids, or of gaſſes, may be loſt in theſe ſeries of fermentations; it is a very advantageous management to cover them with ſoil, when the firſt fermentation is advanced, as is known by the production of conſiderable heat; or when the putrefactive one has commenced, which is known by the ſmell of volatile alkali, or of hydrogen. By this method the too great rapidity of theſe fermentations is checked, and the fluid part of the manure is retained by the addition of the ſoil below, and the gaſſeous part by that above; and if to this be afterwards added a proportion of lime, which by uniting with the nitrous acid may retain it from exhalation or from alluviation, every thing is preſerved that art can accompliſh.

Where manure-heaps are to be ploughed into clayey ſoils, which are liable to become too ſolid and impenetrable to the root-fibres of ſeeds,

ſeeds, as of wheat; or where knobby or bulbous roots are to be inſerted to produce other knobs or bulbs beneath the ſoil, as potatoes; it is probably more advantageous to bury the manure in a leſs decompoſed ſtate, while ſome of the ſtraw retains its form; as ſuch parts by their ſlower decompoſition will longer prevent the ſuper-incumbent ſoil from becoming too ſolid; and though they will in this ſituation require ſome time before they will be perfectly decompoſed, and reduced to the black carbonic earth; yet they will in the end totally decay, and give the ſame quantity of nutriment to the roots, though it may be more gradually applied.

2. In reſpect to the time of year thoſe manures, which are to be ploughed or dug into the ground, ſhould be uſed immediately before ſowing the ſeeds or ſetting the roots, which they are deſigned to nurture; becauſe the atmoſpheric air, which is buried along with the manure in the interſtices of the earth, and which for many weeks, or even months, renders the ſoil looſe, and eaſily impreſſed by the foot on walking on it, gradually evolves by its union with carbon a genial heat very friendly to vegetation in this climate, as well as the immediate production of much fluid carbonic acid, and probably of a fluid mixture of nitrogen with hydrogen, which are believed to ſupply much nutriment to plants.

But thoſe manures, which are deſigned to be ſpread on the ſurface of graſs-land, which is called the top-dreſſing, are beſt applied, I ſuſpect, in the early ſpring; and ſhould be diſperſed over the ſoil almoſt in a ſtate of powder, or in lumps of very looſe coheſion; as at this time the vernal ſhowers waſh them into the ſoil; and they are applied to the roots of the graſs, before their eſſential parts are diminiſhed by winter rains or by ſummer exhalation. There are ſome in Derbyſhire, who ſpread manure even on the meadows, which are annually overflowed by the Trent or Derwent, at the end of ſummer, or as ſoon as the graſs is mowed and removed; which appears to be an improvident management, ſince the aftermath, or autumnal graſs,

is thus rendered unpalatable to the cattle; and the winter rains, or the vernal floods, which generally occur with the return of the ſouth-weſt winds, after the ſeaſon of froſt ceaſes, muſt waſh away a great part of it.

In reſpect to the moſt economical manner of uſing manures in agriculture Mr. Parkinſon aſſerts, that one great advantage of the drill-huſbandry conſiſts in putting the manure into drills, which he directs to be made at two feet diſtance from each other. He ſows wheat, beans, peas, cabbages, on this manure, and affirms, that four loads of manure on an acre in this kind of huſbandry is equal to ſixteen loads in the uſual way of ſpreading it over the whole of the field. Experienced Farmer, Vol. I. p. 32.

3. A third queſtion here preſents itſelf, if the recrements of vegetable and animal bodies buried a few inches beneath the ſoil undergo the ſame decompoſition, as when laid on heaps in farm-yards. And though this is accompliſhed more ſlowly, yet it is attended with leſs loſs of carbonic acid, and of volatile alkali, and of hyrogen, and of the fluid matter of heat; all which are emitted in great quantity during the rapid fermentations of large heaps of manure, and are waſted in the atmoſphere, or on unprolific ground; would it not in general be more economical to bury ſuch vegetable and animal matters beneath the ſoil without a previous fermentation and putrefaction?

In anſwer to this it muſt be obſerved, that in ſome caſes the uſe of recent vegetables ploughed into the earth is found of advantage, as in ſandy ſoils buck-wheat, or vetches, are ſown, and the crop ploughed in, before it ripens its ſeeds. In this circumſtance the recent crop is buried in its ſaccharine and mucilaginous ſtate, which muſt undergo indeed a ſlower fermentation, without being mixed with animal ſubſtances, but no part of the organic matter, nor of the fluid heat, is loſt to the purpoſes of new organization.

So in the cultivation of clayey lands, whoſe tenacity is too great;

or

or where knobby roots, as potatoes, are to be inſerted for the production of other knobby roots beneath the ſoil; long muck, as it is called, or ſuch which is only ſo far decompoſed as to diſſolve the mucilage or more tender veſſels or membranes, but in which the form of the fibrous or ligneous parts of the ſtraw remains, is recommended above; and may in theſe ſituations perhaps be ploughed into the ground even in their moſt early ſtate, when rejected from the ſtable or cowhouſe, before the commencement of their ſpontaneous diſſolution.

So alſo in gardens, which are already fertile, and do not want the immediate aſſiſtance of mature manure, it may be more economical to bury the weeds, as the ground is dug, than to convey them to a manure-heap, and replace them after a twelvemonth's decompoſition.

But where a luxuriant crop is immediately wanted, a manure-heap towards the end of the putrefactive proceſs by being recently interred in the ſoil, which is immediately to be ſown or planted, has this great advantage; that the carbonic acid is preſently formed by the mixture of atmoſpheric air with the carbon of the manure; which exiſts therefore in its fluid, not its gaſſeous ſtate, and is thence more readily abſorbed. Secondly, ammoniac is produced, and nitre, and hydrogen probably is mixed with nitrogen; and theſe alſo, I ſuppoſe, exiſt at firſt in their fluid, not in their gaſſeous ſtate. And thirdly, from theſe combinations a genial degree of heat is evolved, which ſo much aſſiſts the vernal growth of vegetation.

And where manure is to be uſed as a top-dreſſing, it is neceſſary, that it ſhould be in a ſtate of powder, or in ſmall lumps of looſe coheſion, as mentioned above; that it may be eaſily waſhed by rains to the roots of the graſs, or that the young ſtems of graſs may readily ſhoot themſelves through it; whence mature heaps of manure are for this purpoſe neceſſary; and on this account any adheſive manure,

nure, as cow-dung itſelf, ſhould be weekly gathered from graſs-ground, where cattle are nouriſhed, and laid on heaps with ſoil, or ſtraw, or weeds, to ferment or putrefy; till it becomes leſs tenacious, and can be profitably replaced in the enſuing ſpring.

Finally, I ſuſpect the moſt economical method of diſpoſing of the ſtraw and dung from the farm-yard would be, as ſoon as a dark coloured water drains from the heap, by which much loſs is ſuſtained, to carry the refuſe of the ſtable and cow-houſe, as frequently as convenient, to the ground, where it is deſigned to be employed; and there to mix it with earth in heaps of proper ſize, and to cover them likewiſe with ſoil; and by theſe means I ſuppoſe the whole proceſs of decompoſition may be carried on with very little loſs; and by the addition of a greater or leſs quantity of ſoil that the era of complete or moſt profitable decompoſition of the compoſt may be managed, ſo as to coincide nearly with the time it may be wanted.

4. Fourthly, it may be aſked, what kinds of manure contribute moſt to the luxuriant growth of vegetables? In anſwer to this it may be ſaid, that as plants are inferior animals, and are furniſhed with abſorbent veſſels in their roots correſpondent to the lacteals in the ſtomach; that the ſame organic matters, which by their quick ſolution in the ſtomach ſupply the nutritive chyle to animals, will by their ſlow ſolution in or near the ſurface of the earth ſupply the nutritive ſap-juice to vegetables. Hence all kinds of animal and vegetable ſubſtances, which will undergo a digeſtive proceſs, or ſpontaneous ſolution, as the fleſh, fat, ſkin, and bones, of animals; with their ſecretions of bile, ſaliva, mucus; and their excretions of urine, and ordure; and alſo the fruit, meal, oil, leaves, wood, of vegetables, when properly decompoſed on or beneath the ſoil, ſupply the moſt nutritive food to plants.

Secondly, the chyle of all animals is ſimilar to the ſap-juice of all vegetables in this circumſtance, that they both contain mucilage and

ſugar, and ſeem only to differ in this reſpect, that the chyle of animals alſo contains oil, which being mixed with the mucilage gives it its whiteneſs like milk. Hence thoſe matters muſt ſupply nutriment moſt expeditiouſly to vegetables, which contain mucilage and ſugar, or produce them with the leaſt decompoſition, as the jellies from the ſhavings of horns, from hair, woollen rags, and the ſaccharine matter of ſweet fruits, roots, kernels, ſeeds; and in the ſame manner theſe things with the addition of oil are moſt expeditiouſly nutritive to animals.

Thirdly, ſuch materials as contain in ſolution thoſe ſimple ſubſtances, which conſtitute a great part of vegetable bodies, as carbon, which is found in moſt earths; and oxygen, hydrogen, and nitrogen, which are found in water and in air; and from hence we may conclude, that whatever material has conſtituted a part of living organic bodies, may again conſtitute a part of them; and that with more expedition, if they can be uſed without being decompoſed into their primary elements.

Mr. Bewley, the Norfolk philoſopher, ſaid to a friend, who was riding by his ſide, that when he wanted a whip, he habitually looked for a dead ſtick in the hedge, unwilling to pluck off a leafy branch, and deſtroy ſo many living buds. He might have added, that to burn a hair or a ſtraw unneceſſarily diminiſhes the ſum of matter fit for quick nutrition by decompoſing it nearly into its elements, and ſhould therefore give ſome compunctions to a mind of univerſal ſympathy.

It would ſeem therefore, that long roots fixed into the earth, and leaves innumerable waving in the air, were neceſſary for the decompoſition and new combinations of water and air, and the converſion of them into ſaccharine and mucilaginous matter; which would have been not only cumbrous but totally incompatible with the locomotions of animal bodies; for how could a man or quadruped have

have carried on his head or back a foreſt of leaves, or have trailed after him long branching lacteals terminating on the ſurface of the earth? Animals therefore ſubſiſt on vegetables; that is, they take the matter ſo far prepared, and poſſeſs organs to prepare it further for the purpoſes of greater ſenſibility, and of higher animation.

SECT.

SECT. XI.

OF DRAINING AND WATERING LANDS.

I. 1. *Moraſſes are in high or low ſituations.* 2. *Springs riſe from the ſummits of mountains, paſs between the ſtrata.* 3. *Strata of the earth about Derby, and at Lichfield, and the ſprings.* 4. *Plains formed in vallies.* 5 *Wall-ſprings intercepted by ditches, ſunk perpendicular to the ſides of the hills.* 6. *By boring holes at the bottom of ſuch ditches.* 7. *Uſe of ditches, where the wall-ſprings cannot be intercepted.* 8. *Holes through clay into a ſand ſtone beneath.* 9. *Deep ſprings riſe higheſt, when bored into.* 10. *Many ſprings may be raiſed higher than their ſources.* 11. *Enlarging the bottom of wells increaſes the water in them.* 12. *Springs diſcovered on one ſide only of ſome mountains. Diſcovered by evening miſts. By morning rime. By aquatic plants. Warm ſprings.* II. 1. *Draining moraſſes, where there is no fall.* 2. *In the craters of ancient volcanoes.* 3. *In countries of marble, granite, or quartz.* 4. *Fens below the level of the ſea. Should be ſurrounded with dikes.* 5. *Uſes of aquatic plants.* III. 1. *Of flooding lands.* 2. *Ice preſerves the graſs beneath. The French bored holes in the ice.* 3. *Advantages of flooding recapitulated. It deſtroys ruſhes. Saves manure.* 4. *Cautions to be obſerved. Flooding not injurious to health. Vicinity of running water wholeſome.* 5. *Flooding lands might be performed to a great extent. By rivers, ſprings, land-floods, and machinery. Hiero's fountain. Horizontal wind-mill, and centrifugal pump.*

I. 1. THE great quantity of water required for healthy vegetation is treated of in Sect. X. 3. 1. But as all extremes are injurious, too much water becomes pernicious to all except aquatic plants. Whence the neceſſity of draining thoſe lands, which too much abound with moiſture; the art of which is better underſtood, ſince the knowledge

of geology has been ſtudied, and in ſome meaſure diffuſed amongſt the people.

Lands in reſpect to the method of draining them may be divided into two ſituations; thoſe which lie ſo high, that the water can deſcend from them, if it be properly collected and conducted; and thoſe which lie ſo low as to command no fall, ſome of which are even below the level of the ſea.

2. In regard to the former it generally happens, that the waters from the ſprings beneath the ſoil have not a free paſſage to the rivers in their vicinity; the nature of ſprings ſhould therefore be previouſly underſtood. Many modern philoſophers have endeavoured to ſhew, that all the continents and iſlands of the world, as well as the hills, which emboſs their ſurfaces, have been raiſed out of the primeval ocean by ſubterraneous fires. This appears from the quantity of ſea-ſhells, which form innumerable mountains; and from the fiſſures in the rocks, of which they conſiſt; the quantity of volcanic productions all over the world; and the numerous remains of craters of volcanoes in mountainous countries.

Hence the ſtrata, which compoſe the ſides of mountains, lie ſlanting downwards; and one or two or more of the external ſtrata not reaching to the ſummit, when the mountain was raiſed up, the ſecond or third ſtratum, or a more inferior one, is there expoſed to day. This may be well repreſented by forcibly thruſting a very blunt inſtrument through ſome folds of paper, a bur will be raiſed with the lowermoſt leaf ſtanding higheſt in the center of it. Or if at the original elevation of an extenſive mountain the loweſt ſtratum ſhould not at firſt ſtand higher in the center of the ſummit, it would in time become ſo by ſome of the upper ſtrata of the mountain being gradually waſhed away by rains into the valleys or rivers. On this uppermoſt ſtratum, which is colder, as it is more elevated, the dews are condenſed in large quantities; and ſliding down paſs under the firſt, or ſecond, or third ſtratum, which compoſe the ſides of the hill;

hill; and either form a moraſs below, or a weeping rock by oozing out in numerous places; or many of theſe leſs currents meeting together burſt out in a more copious rill.

The immediate cauſe of ſprings conſiſts therefore in the condenſation of the atmoſpheric moiſture, during the night principally, by the greater coldneſs of the ſummits of hills, which is explained in detail in the Botanic Garden, Vol. I. additional note 26. The water thus condenſed on the ſummits of hills deſcends between the ſtrata of the incumbent ſoil, ſometimes for many miles together; but generally from the neareſt eminences into the adjoining vallies.

3. Thus there is a ſtratum of marl, which I have obſerved on the ſurface of the lands about Derby, which extends many miles in moſt directions. This ſtratum of marl is of various thickneſs from 10 to 150 feet, and beneath it lies a ſtratum of ſand, which is alſo of various thickneſs from a few inches to ſix or eight feet, and of various degrees of induration; and beneath this lies another ſtratum of marl to an unknown depth. On the top of Radborne common, about five miles north-weſt from Derby, the ſandy ſtratum is quite looſe, and riſes above the ſtratum of marl, which is deficient at the ſummit of the hill. Three or four ſtrong ſprings of water burſt out on the ſides of this hill, which thus originate from the moiſture of the atmoſphere condenſed on the cold ſummit, and paſſing through the ſandy ſtratum between the two ſtrata of marl.

In the road to Duffield, about two miles north of Derby, the ſand-ſtratum is cemented into ſtone, as well as in ſome ſituations near Radborne-common above mentioned. This ſtratum of ſand-ſtone is ſome feet in thickneſs, and lies four or five yards deep, beneath the upper ſtratum of marl, dividing it from the lower one. At Normanton, about two miles ſouth from Derby, the ſand-ſtratum conſiſts of a looſe ſand, ſo white and pure, that I imagine it might be uſed in the manufacture of flint-glaſs, and lies about twelve feet deep, beneath the upper ſtratum of marl, dividing it from the

under one. In the town of Derby on boring with deſign to ſink a well, after having paſſed about thirteen yards through marl, ſome ſand was brought up by the auger, and water followed, as related in the Philoſ. Tranſact. Vol. LXXV.

The dews therefore, which are perpetually condenſing on the ſummits of theſe hills, deſcend beneath the upper and under ſtrata of marl, through the thin ſtratum of ſand, which divides them, and form St. Alkmund's well, and many other ſprings in the vicinity of Derby; and probably all thoſe which ſupply the wells within the town.

But there is a ſituation, where the manner of the production of ſprings is moſt agreeably viſible; it is about a mile from the city of Lichfield, near the cold bath erected by ſir John Floyer, in a beautiful piece of ground, which was formerly Dr. Darwin's botanic garden.

In this place a grotto about ſix yards wide and ten long has been excavated on the ſide of a hill conſiſting of ſiliceous ſand-ſtone with this peculiar circumſtance; that the upper ſtratum of the ſand-rock, which is there about five feet thick, is divided from the lower ſtratum of it by a ſheet of clay not more than three or four inches in thickneſs; on the upper ſurface of this ſheet of clay, between the lips of theſe rocks, a perpetual dribbling of water oozes quite round the grotto, like a ſhower from a weeping rock. Such ſheets of water having been often obſerved to ſlide between the ſtrata of the earth almoſt horizontally, like the horizontal joints of a ſtone-wall, have, I ſuppoſe, given the name of wall-ſprings to them, to diſtinguiſh them from pipe-ſprings, or ſuch as burſt out in a ſingle rill.

Thus this thin ſheet of clay prevents the water from ſinking into the lower ſtratum of ſand-ſtone; and produces other copious ſprings, which are collected at about half a mile's diſtance, and conveyed by leaden pipes to the cathedral cloſe of Lichfield, which is thus ſupplied with water of uncommon purity, which contains no calcare-

ous

ous earth, owing to its paſſing through ſiliceous ſand over a ſtratum of clay, and which would be a treaſure to the paper-mill or the bleach-yard.

4. One other circumſtance in the preſent conformation of the earth is neceſſary to be mentioned; which is, that at the time when the mountains were raiſed all over the world by deep volcanoes, or by central fires, ſome parts of the ſummits of many of them, and of their ſteeper ſides, rolled down again into the new formed vallies. And ſecondly, that ſince that remote time the recrements of vegetable and animal bodies have continually been waſhed down from the eminences by ſhowers, and have contributed gradually to accumulate in the vallies, and to form the plains, which exiſt on the ſides of rivers. This appears from the tin ores found in the vallies in Cornwall in looſe pieces ſimilar to thoſe in the proximate mountains; and from the black carbonic ſoil, or moraſs-turf, found in moſt vallies.

5. From theſe clear ideas of the ſtrata of the earth, and of the ſtreams of water, which ſlide between them, and form what are termed wall-ſprings, it is eaſy to conceive, that the beſt method of preventing the vallies at the bottom of hills from being too moiſt muſt be by cutting a long horizontal ditch into the ſide of the mountain to intercept the water, juſt before the level land of the valley commences; and thus to carry away the water before it comes upon the plain beneath.

For this purpoſe at the foot of the hill where the plain, which is too moiſt, commences, ſome auger-holes ſhould be bored to find the depth of the ſprings, that is to find the thickneſs of the upper ſtratum of the ſoil. If this be only four or ſix feet, an horizontal ditch ſhould be cut along the bottom of the mountain to intercept the water; which muſt then be carried away by one or more other ditches opening into this, and conducting the water ſo collected into the neighbouring rivulet.

As the ſtrata, between which the water deſcends in forming theſe

ſprings,

ſprings, have generally the ſame inclination as the ſurface of the hill, or nearly ſo; it follows, that the holes ſhould be bored, and the ditch cut, not vertically downwards, as is the common practice, but perpendicular to the ſurface of the mountain; as by that means the ſecond ſtratum will ſooner be arrived at; as ſhewn in Plate V. at the end of this Section.

6. But if on cutting a ditch five or ſix feet along the bottom of the hill perpendicular to the riſing plain, which forms the ſide of it, the upper ſtratum be not cut through; and in conſequence no water oozes into the bottom of the ditch; it is then proper to bore other holes at the bottom of this ditch ſome yards deeper, or till water riſes up through them into the ditch, if it can be ſo diſcovered. Where this ſucceeds, many holes ſhould be bored, and the water received into the ditches, and conducted into the adjacent river; for the water will then riſe into the bottom of this ditch ſix feet below the wet ſurface of the valley, and thus flow away, rather than riſe up from the lower wall-ſprings, or apertures of the ſtratum, through the incumbent ſoil to the ſurface of the valley, which is ſo many feet higher. This well underſtood is the great ſecret for draining thoſe grounds, where the ſprings can not be cut into ſimply by a ditch.

This method has been ſome years practiſed with ſucceſs by Mr. Elkington, but was previouſly uſed and explained by Mr. Anderſon, as he aſſerts in his introduction to Vol. III. of his Eſſays on Agriculture, who ſunk a hole into the earth at the bottom of a ditch in the year 1764, and the water roſe ſix feet above the ſurface of the ground, and has continued to flow with leſs violence ever ſince that time.

It ſhould here be noticed, that where the water riſes with great force through holes thus bored into a deep ſtratum, it is liable to bring up along with it much ſand, ſo as ſometimes to obſtruct its paſſage; which ſand in this caſe muſt frequently be removed for a few days by the reapplication of the auger. Of this a remarkable in-

ſtance is publiſhed in a late volume of the Phil. Tranſ. by Mr. Wulliamy, who ſunk a well 236 feet deep and four feet wide; and, on then boring a few feet lower with a five-inch borer, ſo much ſand aroſe with a violent ſtream of water, as to fill up the whole well; which was repeatedly cleared away by buckets in its fluid ſtate, and at laſt the water ran over the ſurface to the amount of forty-ſix gallons in a minute.

The manner of making theſe ditches narrower, as they deſcend, by ſpades of an adapted breadth; and of making the loweſt part narrower than any other part, ſo that the ſhoulders or edges of it may ſupport ſtones, or faggots, to cover the whole at a ſmall expence without obſtructing the currents of water, are obvious to the workmen. In many ſituations hollow bricks, or ridge-tiles, or old pieces of plaſter-floors, may be worth the aditional expence of providing them.

7. There may nevertheleſs be found ſituations, where the firſt ſtratum of earth may be too thick to be eaſily penetrated; or where the water, condenſed from the atmoſphere on the ſummits of the hills, may ſlide between the ſecond and third, or between the third and fourth ſtrata, which form the ſides of thoſe hills, owing to a deficiency of ſo many of the ſtrata at the ſummits of them; and hence that it may lie too deep to be eaſily arreſted by a ditch, or by boring; and yet by its being dammed up by the materials, which form the level plain of the valley, may riſe up through thoſe materials to the ſurface, and form boggy or moraſſy ground.

In theſe ſituations the common unſkilful method of draining may be uſefully employed; which conſiſts in cutting many ditches four or ſix feet deep acroſs the bog or moraſs; and covering them, ſo that the water may have no obſtruction in paſſing along them; which may thus, as it riſes from below, be in part collected and conveyed away; though leſs advantageouſly than where the ſprings can be intercepted.

Another

Another method of draining moiſt meadows has been by making or opening drains almoſt annually by a large plough with two converging coulters, and other adapted parts, for the purpoſe of cutting both the ſides of a ditch at the ſame time, and turning out the intervening turf and ſoil. Theſe large ploughs have been kept in ſome pariſhes, and drawn over moiſt commons by twelve or twenty horſes, to form parallel ditches.

Mr. Adam Scott has invented for the ſame purpoſe what he terms a mole-plough, which conſiſts of a coulter fifteen inches long, and two and a half wide, to cut the ſward; and behind this an horizontal cone of caſt iron twenty inches long, and two and a half diameter at the baſe, to the middle of which is fixed an upright bar two feet long, and three inches and a half broad, with a ſharp edge. As this caſt iron cone is drawn along ſix or eight inches beneath the turf in moiſt lands, either in the ſpring or autumn, in many parallel lines, the water for a conſiderable time is conveyed away, and no injury done to the ſurface; which thus ſeems to be an uſeful machine, and may be well managed, I am informed, by ſix or eight horſes. In very moiſt lands, or at very moiſt ſeaſons, if more horſes be uſed, their feet will not ſink ſo deep into the turf, as each horſe will draw leſs; or a contrivance of adding broader ſhoes of wood to the horſes like the ſnow-ſhoes of higher latitudes, might anſwer this purpoſe. See Tranſact. of Society of Arts, Vol. XV.

8. There are nevertheleſs ſome ſituations, where the water is conveyed beneath the firſt ſtratum on a thin bed of clay over a porus ſand-ſtone beneath it; as in the grotto at Lichfield above deſcribed. In theſe ſituations by boring many auger-holes, or by ſinking wells, through the ſtratum of clay the water will penetrate the ſand-ſtone beneath it; and either paſs away by the poroſity of this kind of ſtone, or by the cracks or joints which are always found in it; of which the horizontal joints were formed at the time of the production or accumulation of the ſand beneath the ſea, which was then formed in horizontal

horizontal ſtrata; but the vertical cracks were made at the time of its elevation by ſubterraneous fires. In theſe vertical fiſſures the ores of lead, ponderous earth, and calcareous ſpars, are found in the limeſtone rocks of Derbyſhire; and thoſe of tin, and quartz, in the granite rocks of Cornwall.

9. The knowledge of this part of geology concerning the formation of ſprings may be employed for many uſeful purpoſes; thus where the wall-ſprings, or water-conducting ſtrata, lie ſo deep as not to be acceſſible at a ſmall expence; they generally exiſt between the ſecond and third, or between the third and fourth ſtrata; which riſe into day higher on the ſummits of the adjacent mountains than the firſt ſtratum; and hence, when they are bored into, the water will riſe higher, than when it is found beneath the firſt ſtratum only; which generally becomes deficient on lower parts of the adjacent eminences of the country.

Thus where water, deſcending in high columns between the ſtrata of mountains, is dammed up below by the materials, which fill up the vallies; if a hole be bored in the valley deep through the incumbent ſoil and ſtrata, it frequently riſes much above the ſource of the new aperture, and ſometimes above the ſurface of the ground. In ſinking the king's well at Sheerneſs the water roſe 300 feet above its ſource in the well, as related in Philoſ. Tranſact. Vol. LXXIV. And at Hartford in Connecticut there is a well, which was dug ſeventy feet before water was found; and then on boring an auger hole through a rock the water roſe ſo faſt, as to make it difficult to keep it dry by pumps, till the hole could be blown larger by gunpowder; which was no ſooner accompliſhed, than it filled, and run over, and has been a brook for near a century. Travels through America, Lond. 1789. Lane.

In the town of Richmond in Surry, and at Inſlip near Preſton, in Lancaſhire, I am informed, that it is uſual to bore for water to a certain depth; and that when it is found in both thoſe places, it riſes

ſo high as to flow over the ſurface. And there is reaſon to conclude, that if ſimilar experiments were made in many other places, ſuch artificial ſprings might be produced at ſmall expence, both for the common purpoſes of life, and for the great improvement of lands by watering them.

10. Another deduction, which may be made from this knowledge of geology, is, that many ſprings of water, which lie too low for ſerving a houſe, or ſtreet, or town, or for watering higher grounds for the purpoſes of agriculture or gardening, may in many ſituations be dammed up many feet with little or no loſs. Thus when the new bridge was building at Dublin, Mr. G. Semple found a ſpring in the bed of the river, where he meant to lay the foundation of a pier; which by fixing iron pipes into it he raiſed many feet; and in boring a hole near the Derwent in Derby about fifteen yards deep, the water roſe above the ſurface of the ground, and has continued to flow now for above twelve years in rather an increaſing quantity. From having obſerved a valley north-weſt of St. Alkmund's well near Derby, at the head of which that ſpring of water once probably exiſted, and by its current formed the valley, (which current in after times found its way out in its preſent lower ſituation), I ſuſpect, that St. Alkmond's well might by building round it be raiſed high enough to ſupply many ſtreets in Derby with ſpring water, which are now only ſupplied with river water.

11. A third deduction from the knowledge of this geology concerning the production of ſprings teaches, that by enlarging the bottom of a well, where the water oozes from between the ſurrounding ſtrata in too ſcanty a ſupply, a proportionally greater quantity of water may be procured. The hole near the river Derwent in Derby above mentioned, is about an inch and a half in diameter, and was bored about fifteen yards deep through the uppermoſt ſtratum of marl into the ſand beneath it, and ſupplies Dr. Darwin's houſe with two or three hogſheads of water a day. And Mr. Strutt near St. Peter's

ter's Bridge has ſunk a well for the uſe of his ſteam-engine about 200 yards from the former, which paſſes through the ſame upper ſtratum of marl, and is three feet in diameter at the bottom, and ſupplies, when required, a hundred hogſheads in a day.

12. The knowledge of this part of geology leads to another uſeful purpoſe, the diſcovery of ſprings; concerning which ſome have pretended to poſſeſs ſecret or myſtical intelligence both in England and in France. When the eminences of a country were raiſed out of the primeval ocean by ſubterraneous fires, ſome of them were raiſed nearly equally on all ſides, like the limeſtone mountain at Breedon in Leiceſterſhire; in which the central ſtratum may be ſeen to ſtand nearly erect or vertical, and thoſe on all ſides at conſiderable inclination. Other mountains were abruptly broken off on one ſide only from the adjoining earth, like thoſe which form the high torr at Matlock; which riſe with one of their ſides perpendicular as a wall by the Derwent ſide; ſo that the ſtrata of the former of theſe mountains may be repreſented, as before mentioned, by the bur, which would be made on ſome folds of paper, if a very hard blunt inſtrument was thruſt through them; and the latter by raiſing up one edge of ſuch folds of paper, ſo as to incline the whole of it at ſome angle with the horizon.

As the ſprings conſiſt of the water, which ſlides between theſe inclined ſtrata; it is evident, that in ſome eminences of ground they are only to be met with on one ſide of the mountain; and in other eminences of ground on all ſides of it. In ſearching for ſprings therefore attention ſhould be given to the inclination of the ſtrata of that part of the country, which may be often ſeen in marl-pits, gravel-pits, or in hollow lanes. But they may in general be found above any moiſt or moraſſy plain or valley; the moiſture of which ſhews, that ſprings exiſt in the ſtrata on that ſide of the mountain.

A ſecond obſervation for the purpoſe of detecting ſprings may be made on miſty evenings; as thoſe parts of the ground, where the

miſt commences, are moiſter than thoſe in their vicinity on the ſame level; and in conſequence may generally, if they are not hollow baſons, poſſeſs ſprings nearer the ſurface; for theſe moiſter parts of the ground, having evaporated more during the day, are become colder on their ſurfaces than the drier ground in their vicinity; and in miſty evenings, which are at the ſame time calm, the ſtationary air over theſe moiſt parts of the ground is alſo more loaded with the evaporated moiſture; and on both theſe accounts theſe moiſter ſituations are liable to ſhew a condenſation of aerial vapour ſooner than other places on the ſame level.

As mountains are colder in proportion to their height, which is explained in Botanic Garden, Vol. I. additional note 26, the evening miſt ſometimes commences ſooner on them than in the valleys; but is ſeen earlier in theſe ſituations over the moiſter places, if they are on the ſame level with the drier ones, exactly as on the plains or valleys; and may therefore indicate the exiſtence of ſprings, unleſs theſe moiſter places conſiſt of hollow baſons containing water, which if not attended to may in all ſituations deceive the obſerver.

Another obſervation for detecting ſprings may be made in rimy mornings; for as moiſt earth is a better conductor of heat than dry earth, the rime will ſooner melt on thoſe parts of the ſoil, which are kept moiſt by ſprings under it than on other parts; as the common heat of the earth, which is 48 in this country, will ſooner be conducted upwards in moiſt places to diſſolve the rime on the ſurface. On this account the rime is frequently ſeen on froſty mornings, when the heat of the air is not much above 32, to lie an hour longer on dry cakes of cow-dung, or on bridges, or planks of wood, than on the common moiſt ground; as the latter much better conducts the common heat of the earth to the incumbent rime, which is in contact with it.

But as the heat of the common ſprings in this country is 48, where they exiſt, the rime is ſooner diſſolved, than on the ſtagnant moiſ-

ture

ture of bogs or moraſſes. And as the ſprings about Buxton and Matlock, and at Bath and Briſtol, are ſo much warmer than common ſprings; it is highly probable, that where theſe waters approach the ſurface of the ſoil, they muſt much ſooner diſſolve the rime on froſty mornings; which may probably be obſerved in ſituations much higher than their preſent apparent ſources; as they ſlide down between the interior ſtrata of thoſe hills, beneath the ſummit of which they are condenſed from the ſteam of water boiling at great depths in the earth; which riſes up through thoſe perpendicular clefts of the rocks, which were formed at their original elevation, as explained in Botanic Garden, Vol. II. note on fucus; and in Pilkington's View of Derbyſhire, V. I. p. 256.

In the winter months the riſe of ſprings may be detected in moiſt ditches by the preſence of aquatic plants, as of water-creſs, water-parſnip, brook-lime; as in thoſe ditches, which become dry in the ſummer, theſe plants do not exiſt; and when thoſe ditches with ſprings in them are nearly dry, it may be diſcovered which way the current has formerly deſcended by the direction of the points of the leaves of the aquatic plants as certainly as by a level; an obſervation which I learnt from Mr. Brindley, the great canal-conductor of Staffordſhire.

Finally, theſe arts of detecting the ſituation of ſprings may be advantageous to the attentive agricultor both for the purpoſes of draining thoſe lands, which too much abound with water, and for the purpoſe of watering thoſe, which are too dry, and which lie beneath the level of the ſprings, or to which the water may be raiſed by wind-mills or water-engines to be explained hereafter.

II. 1. In reſpect to draining thoſe plains or moraſſes where no fall can be had, the water may in many ſituations be caught by cutting a long horizontal ditch into the adjoining mountain perpendicular to the inclined plane, which conſtitutes the ſide of the mountain, above the level of the moraſs, ſo as to intercept all the wall-ſprings; and

may

may then be conveyed away in wooden troughs or hollow bricks above the ſurface; and if ſome water ſtill finds its way into the moraſs, this leſs quantity may be conducted to one extremity of the ground in open drains or covered ſoughs, and raiſed by an horizontal windmill and centrifugal pump, as deſcribed at the end of this Section; and thus the moraſs may be converted into ſoil of the moſt productive kind.

2. There may be other ſituations, as in the Peak of Derbyſhire, where pools of water, or moraſſes, are collected on the hollow ſummits of hills; which have been the craters of volcanoes in the primeval ages of the world, as Elden-hole near Caſtleton, which ſeems to have been the ſhaft of ſuch a volcano. In many of theſe baſons on the ſummits of hills there ſtill exiſt what are called "Swallows," or cavities; where the water ſinks into the earth, as it collects, to paſs to ſome diſtant valley, as Elden-hole above mentioned, and as in the channels of the rivers Hamps and Manifold, between Aſhbourn and Leek. In others, as at the ſummit of a ſteep promontory called Axedge, near Buxton, and about Broke-houſe, are unfathomed moraſſes, which are ſaid in ſome places not to bear a ſheep to paſs over them; and that on the more tenacious parts of them it is neceſſary for the adventurer to ſtep from taſſock to taſſock, or to carry a long pole horizontally in his hand, like thoſe who ſkaite upon ſuſpected ice, to prevent his ſinking over head, if he ſhould chance to ſink at all.

It is probable, that by ſinking a well, or boring a hole, where ſuch moraſſes or lakes now exiſt, into the obſtructed ſhaft of the ancient volcano, the water might be let off from thoſe eminent moraſſes at leſs expence, than by excavating a paſſage for it ſome miles in a country of marble.

3. It is poſſible there may be ſituations in high countries of marble, or granite, or quartz, where the difficulty and expence of excavating the ground may be too great, as above; in which a ſyphon might be contrived for the purpoſe of raiſing the water from a mo-

raſs or lake, and conveying it away. Such an inſtrument might be conſtructed of bored Riga deals; but as air is liable to collect in the ſummit of a ſyphon from the water, which paſſes through it, it would be neceſſary to fix at the ſummit an air-veſſel with an air-pump at the top of it; which might be moved by a very ſmall horizontal windmill ſail, to be deſcribed at the end of this Section, or occaſionally by the hand of a labourer for a few minutes perhaps once or twice a day.

4. The draining of thoſe large plains, which lie beneath the level of the ſea, is a ſubject, which belongs to the public, rather than to the individual farmer; and is practiſed near Linn on the river Cam by locks to keep out the tide, and by windmills to lift or forward the otherwiſe ſtagnate water in the fen-dikes. Theſe windmills have vertical ſails of the common kind, which move a vertical water-wheel, by which the water is raiſed a foot or two; but it is probable even this might be done better by the horizontal ſail and centrifugal pump to be deſcribed at the end of this Section, as being a ſimpler machine, and requiring no attention to turn it to the wind.

It might be a noble work, worthy the attention of a government, that wiſhed to increaſe the quantity of nutriment, and conſequent population and happineſs of the country, to employ proper engineers with a number of labourers to environ with ditches every moraſſy diſtrict of whatever extent, which lies beneath the level of the tides, as the fens of Lincolnſhire and Cambridgeſhire. Theſe ditches ſhould be cut at the feet of the adjacent riſing grounds, or of eminences ſurrounded with fens, like iſlands in a lake, ſo as to intercept the wall-ſprings and land-floods, and convey the water thus collected above the level of the moraſs into the ocean.

But this, I fear, is an effort not to be expected in the preſent times, when the encloſure of foreſts and large commons is prevented by the intereſt of individuals, or by the difficulty of procuring expenſive acts of parliament for every minute diſtrict, inſtead of including them in a general

a general act, ſo meritoriouſly contended for by ſir John Sinclair, then Preſident of the Agricultural Society.

5. Where finally the draining of marſhy grounds can not be effected at a reſponſible expence, ſome plants may perhaps be cultivated with profit to the cultivator; as in ſome ſituations the feſtica fluitans, floating feſcue, callitriche, ſtar-graſs; or in others the orchis for the purpoſe of making ſaloop by drying the peeled roots in an oven. This might be better worth notice, if the ſeed could be ripened in this climate for its eaſier propagation, which probably may be accompliſhed either by cutting away the new root, as is affirmed in the Amœnitates Academicæ; or by planting them in a garden-pot ſo as to confine the roots in reſpect to ſpace, which is ſaid in the ſame work to ripen the ſeeds of convallaria, lily of the valley; and laſtly by cultivating a few on a hot-bed or in a green-houſe.

In other ſituations the menyanthes, bog-bean, would flouriſh abundantly, and might become a ſubſtitute for hops in the brewery, and be equally wholeſome and palatable. It is indeed much to be lamented, that we have no grain ſimilar to rice, that will grow in watery grounds in this cold climate, nor any eſculent roots or foliage except the water-creſs. There is reaſon to believe nevertheleſs, that the roots of nymphæa, water-lily, or of butomus, flowering-ruſh, may be eſculent by ſimple boiling; or that a wholeſome ſtarch might be obtained from them; or laſtly, that they might be fermentable into ardent ſpirit, like the roots of potatoes, or into vinegar.

The nymphæa nelumbo is much cultivated in China in their ſwampy grounds, and in their lakes. The ſeed is like an acorn, and of a taſte more delicate than that of almonds. The roots are ſliced and ſerved with ice in ſummer at their tables; and are preſerved in ſalt and vinegar for the winter. Embaſſy to China by ſir G. Staunton, Vol. III. p. 214, 8vo. ed. The nymphæa alba of our country produces a root of three or four inches in diameter. See Sect. XVII. 2. 3; and though the ſeed is very ſmall, and perhaps does not perfectly

fectly ripen, I have obſerved it to be agreeable to the palate both in its recent ſtate, and when dry.

If theſe ſhould not ſucceed, other quick-growing plants might be cultivated for manures, as typha, cat's-tail, caltha, and others; which ſhould be mowed twice a year, while they are young, and in conſequence abound with ſaccharine and mucilaginous matter ready to paſs into fermentation.

III. 1. The advantages reſulting from occaſionally covering lands with water have long been experienced in warmer countries, as in Egypt, Italy, and many parts of China; and have of late years been introduced into our own more northern climates. The great importance of much water to the progreſs of vegetation has already been ſpoken of in Section X. 3. And in the warm climates above mentioned, it is particularly uſeful in the cultivation of rice for the purpoſe perhaps of ſimply moiſtening the ground.

But the advantages of flooding meadow-lands in this country may be divided principally into three kinds, one of which conſiſts in ſimply moiſtening them, which ſeems to be the principal uſe of watering lands in warm countries, where the water is derived to them almoſt every evening from reſervoirs above them, or from water-wheels worked by aſſes, and which is ſometimes done in the gardens of this country by watering pans and human labour.

The ſecond and greater advantage of flooding lands in this climate conſiſts in deriving much water over them from rivers or from ſtrong ſprings, and by thus ſupplying them with the muddy ſediment brought down by rivers, after ſudden rains, or with the calcareous earth diſſolved in many ſprings. All thoſe ſprings, which paſs through marl, or chalk, or other limeſtone, are replete with calcareous earth; which they hold in ſolution, as thoſe about Derby and about Matlock, which earth they depoſit on ſtanding on the ſoil, or in ſlowly trickling over it. See Sect. X. 6. 2. And river

water in rainy ſeaſons is loaded with diffuſed as well as with diſſolved materials from the neighbouring country.

Both theſe therefore are of great ſervice in flooding meadow-lands, and perhaps almoſt all other lands. But thoſe ſprings, which paſs only through ſiliceous ſandſtone, as thoſe at Lichfield in Staffordſhire, have no calcareous earth diſſolved in them, as I have found by experiment; and the water of moſt rivers, when they are not ſwelled by rain, are alſo too pure for this purpoſe; as they have depoſited already in their courſe the calcareous earth, which might abound in the ſprings, which feed them; as I have obſerved by experiments on the water of the Derwent at Derby, which though it runs for many miles about Matlock through a bed of limeſtone, yet when clear of mud from rains, it contains no calcareous earth, as it paſſes by Derby, though the ſprings in the vicinity are replete with it. Neither of theſe ſources of water can therefore do much ſervice for this ſecond deſign of depoſiting limeſtone, or mud.

The third advantage of flooding lands in this climate is for the purpoſe of defending them from the cold of the winter or vernal months. For this advantage the water from ſtrong ſprings, which are always at 48 degrees of Farenheit in this country, is preferable to river water, where it can be had in ſufficient quantity; ſince the water of rivers is of the ſame degree of cold as the atmoſphere, till the thermometer ſinks to 32. But both of them, when they form a ſheet of thin ice, as they cover a meadow, defend the roots of the graſs from ſeverer degrees of cold; which are thus preſerved, and thoſe of ſome graſſes are believed even to vegetate beneath the ice, as the rein-deer moſs in Siberia vegetates beneath the ſnow in a degree of heat about 40, which is the medium between that of the under ſurface of the thawing ſnow, which is 32; and that of the common heat of the interior parts of the earth, which is 48; and thus the rops of graſs in this cold climate may be wonderfully forwarded; ſo as

as almoſt to double the product of the year, if well managed and carefully attended to.

The method of forming the channels to convey the water conſiſts in carrying the firſt or principal aqueduct along the higheſt part of the meadow, and deriving others on the ſummits of the lands; if the meadow has formerly been ploughed into ridges and furrows, theſe again are to be divaricated ſo as to paſs into the furrows; all theſe branches of the ſtream are again to be collected from the furrows, and diſcharged at the loweſt part of the ſurface.

Something ſimilar to this muſt be managed on more level grounds, ſo as to conduct the water over the whole meadow, and alſo to carry it off, that it may not ſtagnate; but that a moving ſheet of water about an inch in depth may continually flow over the whole for the purpoſe of depoſiting the materials diſſolved or diffuſed in it. The conſtruction and width of theſe channels, with many uſeful obſervations, are ſhewn in a pamphlet of Mr. T. Wright, on "the Art of Floating Land in Glouceſterſhire." Scatcherd. London.

2. Mr. Wright in the treatiſe above mentioned adviſes, that the aftermath of graſs land ſhould be eaten off bare by the beginning of November, and that the channels for conducting the water to and from the meadows ſhould be then cleanſed and repaired; and that the water ſhould be ſuffered to flow over the meadow for three weeks; and that then the land ought to be expoſed to the air for a few days; ſince ſome of the graſſes, and thoſe of the moſt nutritive kinds, he believes will not much longer exiſt under water. By this early preparation, he adds, that advantage is taken of the autumnal floods, which bring along with them a greater quantity of putreſcent matter than thoſe of winter.

In the months of December and January Mr. Wright adds, that the chief care of the floater conſiſts in keeping the land ſheltered by the water from the ſeverity of froſty nights; but adviſes through the whole of theſe months every ten or fourteen days to expoſe the land

to the air by laying it as dry as poſſible for a few days; and always to diſcontinue the flooding, when the land is covered with a ſheet of ice.

In the month of February greater attention is required; if the water be ſuffered to flow over the meadow for the ſpace of many days without intermiſſion, a white ſcum is generated, and the graſs is much injured. And he juſtly obſerves that, if you now take off the water, and expoſe the land in its wet ſtate to a ſevere froſty night, a great part of the graſs will be cut off.

Mr. Wright adds, that in Glouceſterſhire two methods of avoiding theſe injuries are practiſed: one is to take off the water by day to prevent the production of the ſcum, and to turn it over again at night to guard againſt the froſt. The other is to take off the water early in the morning; and, if the day be dry, to ſuffer it to remain off a few days and nights; for if the land experiences only one drying day, the froſt at night will do little injury. But the former of theſe practices, where it can be eaſily done, he thinks preferable to the latter.

In the beginning of March the graſs on well-flooded meadows will generally be ſo forward, as to afford abundant paſturage, and the water ſhould be taken off for about a week, that the land may become dry and firm; and the cattle ſhould for the firſt week be allowed a little hay in the evening, if the weather be cold and rainy.

In the month of April the graſs may be eaten off quite ſhort and cloſe, but not later; ſince if you treſpaſs but one week in the month of May, the crop of hay, which is to ſucceed, will be much impaired; and the graſs will become ſoft and woolly, and the hay have the appearance of lattermath hay, and be leſs valuable.

At the beginning of the month of May the water is again thrown over the meadows for a few days; which ſimply by moiſtening the land will in moſt ſeaſons, Mr. Wright obſerves, enſure a crop of hay of one ton and a half on an acre in the courſe of ſix or ſeven weeks.

The

The water is ſometimes again uſed, when the hay is carried off, but may render the lattermath, he thinks, unwholeſome to ſheep. But this is particularly ſerviceable, when the water is rendered turbid by ſuddens rains. Some have taken off two hay-crops in one year, but this Mr. Wright thinks is imprudent in this climate; which however I ſuppoſe might be accompliſhed, where the firſt growth is not eaten in April, and where much turbid river water or calcareous ſpring water can be uſed between them.

Mr. Wright further obſerves, that the hay on theſe flooded meadows is little inferior to upland hay, if it be cut at its proper age; but that ſome avaricious farmers have permitted it to remain uncut till it produces three tons on an acre, and that then it will become long and coarſe, and little better than ſtraw. But that when it is cut in June, and has been flooded well with muddy water in the winter, that it becomes little inferior to the beſt upland hay.

The hay, I ſhould ſuppoſe, which is cut before the graſs is in full flower, while the ſaccharine juice ſtill remains in part at the joints of the flower-ſtems, muſt contain the moſt nutritious matter; which is afterwards abſorbed as the flower expands, and as the ſeed ripens, and forms the meal or ſtarch of the ſeed-lobe, and is ſhed upon the ground, or conſumed by birds, and the graſs-ſtems and their leaves become ſimply like the ſtraw of ripened corn.

This will appear of more importance to any one, who attends to the difference of the pods or huſks of peas, or of kidney-beans, during the early ſtate of the encloſed ſeeds, and again after the ſeeds become ripe. The pod or capſule is at firſt ſweet and mucilaginous, ſo as to ſupply an agreeable and nutritive food, the latter of which, and ſometimes the former, are eaten at our tables; afterwards as the ſeeds, which are attached alternately to each ſide of the capſule, drink up by their vegetable life after impregnation the ſaccharine and mucilaginous matters there purpoſely depoſited for them; the capſule itſelf

becomes

becomes a mere fibrous membrane not better than the ſtraw of ripe grains above mentioned.

It may be here repeated, that one great uſe in this country of flooding graſs-grounds in winter, and in early ſpring, ſo as to let a thin ſheet of water perpetually flow ſlowly over them, is, that it will in froſty nights, when the cold is not much below the freezing point, produce a thin ſheet of ice, and thus prevent the cold from affecting the roots of the graſs beneath it; which may thus be two or three weeks forwarder than on other lands; for ice is ſo bad a conductor of heat, that water is not readily frozen beneath it; and eſpecially if it ſtands hollow, ſo as to encloſe a ſtratum of air between itſelf and the water beneath.

This ſeems to have been attended to by the philoſophers in the French army, when they paſſed over ice to ſubdue Holland; fearing leaſt the ice ſhould be too weak for the paſſage of their troops and artillery, they bored many holes through it every night; and then by preſſure on its ſurface the water was made to riſe through theſe holes, ſo as to ſtand an inch above the ſurface; which being thus expoſed to the cold air of the night, became frozen before morning; and thus in a few nights thickened and ſtrengthened the ice ten times more than would have been done naturally by the ſlower freezing beneath it.

3. To recapitulate the advantages of flooding, firſt, not only the common meadow grounds are enriched, but moraſſy ones are conſolidated, by the mud brought over them from river water; or the calcareous ſediment, and azotic or nitrogen air, from moſt ſpring waters, during thoſe ſeaſons when graſs does not naturally make much progreſs in its growth. 2. They are defended from froſt by the flowing water, or by the ice, when it is frozen; and thus a much forwarder crop of graſs is produced, as may frequently be ſeen over pieces of ground naturally moiſt; which look green in the ſpring, ſome

ſome weeks before that on drier land in their vicinity. 3. The ground is rendered more eaſily penetrable by the roots of graſs, both by its being kept ſofter, and alſo from its being ſeldomer frozen below the ſurface in the vernal months. 4. This early crop may be eaten off by cattle or ſheep, and a new flooding for a ſhort time will forward the growth of it ſo as to produce a good crop of hay. 5. After the hay is removed another flooding for a ſhort time enſures a luxuriant growth of autumnal graſs, or aftermath.

The difficulty of getting moiſt lands free from ruſhes is ſaid to be readily overcome by flooding them, and that eſpecially after previouſly mowing them, as their ſpongy pith will then abſorb ſo much water, as to cauſe them to putrify by its ſtagnation; or if this be done in autumn or ſpring, and a froſt ſupervenes, the water in their pith by expanding, as it becomes ice, burſts and deſtroys their organic ſtructure.

The following concluſion is copied from Parkinſon's Experienced Farmer. "Upon the whole, artificial watering of meadows is a moſt profitable improvement; it robs no dunghill, but raiſes one for the benefit of other lands; for if a farmer can water ten acres of land, cut the graſs and uſe it either in ſtall or fold-feeding, he might keep perhaps forty beaſts; and by working the manure made by them into a compoſt, and applying that compoſt to other lands, he might either have a great deal more hay for the winter, or feed more cattle in the ſummer." Vol. II. p. 68.

4. Two or three obſervations of importance ſhould be here inſerted. 1. That in flooding lands for a conſiderable time, the water ſhould only trickle over them from the canal, which leads it along the more elevated parts, and not ſtand on it like a fiſh-pond; as in the latter caſe the graſs roots will periſh in a few weeks in the early ſpring, to the great injury of the farmer, an example of which on ſeveral acres I once witneſſed.

As ſoon as any materials thus begin to putrefy beneath the water,

a ſcum of white froth ariſes owing to the air ſet at liberty by putrefaction; which is ſuppoſed by ſome to injure the graſs, whereas it is a conſequence rather than a cauſe of injury, and ſhews, that the water has ſtagnated too long; and ſhould either be immediately drawn off, or ſupplied by a running ſtream; but the former ſhould probably be preferred: if the ſtems of graſs are ſo tall as to riſe above the running water, it is probable, that their death and putrefaction do not ſo ſoon occur.

Secondly. It is obſerved by gardeners, that in dry ſeaſons, if you begin to water any kinds of plants, you muſt continue to repeat it; otherwiſe that they are ſooner injured by dry weather, than thoſe which have not been watered. This fact alſo I think I have obſerved, and it may depend on the circumſtance of the roots of annual vegetables ſhooting themſelves lower down in dry ſeaſons in ſearch of moiſture; but if this be given them in the commencement of their growth, they then ſhoot their roots more horizontally, and are afterwards in conſequence ſooner deſtroyed by the ſubſequent dry weather.

Thirdly. Much cold water given ſuddenly to plants, which were nearly periſhing with heat and dryneſs, will I believe ſometimes injure or deſtroy them, as I ſaw occur this year, 1798, in June to ſome rows of garden beans; which after being flooded for one night withered, and in part died, on the following day, which was probably cauſed, not by the exceſs of water, as plants of this genus would ſeem to bear much moiſture from an experiment of Lord Kaimes, who ſays in the Gentleman Farmer, that he planted a pea on ſome cotton-wool ſpread on water in a phial, and that it ſprung up, and ſhot roots through the cotton-wool into the water, and produced large pods full of ripe ſeeds. The death of theſe beans was more probably occaſioned by the torpor of the ſyſtem induced by cold, as occurs to thoſe who have injudiciouſly drank much cold water, or plunged into a cold bath, when they have been previouſly much weakened by the unneceſſary

unneceſſary activity of the ſyſtem occaſioned by continued heat, or great exerciſe. See Sect. XIV. 1. 1.

Nor is there reaſon to ſuppoſe that to whatever extent this mode of cultivation of graſs could be carried in this country, that any injurious effects in reſpect to the health of the inhabitants could be produced; as this mode of flooding is not by ſtagnant water, as in rice grounds; which D. A. J. Cavanilles, who has lately publiſhed a work on the cultivation of rice in the kingdom of Valencia, believes to be injurious to the health of the inhabitants. Magaz. Encyclop. T. 3.

In theſe cold climates the vicinity of running ſtreams may perhaps be rather ſalubrious than the contrary; as the air is cooled in hot weather, and warmed in cold weather, by its contact with their ever-changing ſurfaces, till they become frozen. I at this moment recollect many, who lived to an healthy old age in the valley of the Trent near the very edge of the water, whoſe names I could repeat. But ſtagnate waters, from which putrid exhalations ariſe, produce agues in cold countries, as in the fens of Lincolnſhire; and putrid fevers in hot ones; from which our armies ſuffered ſo much at St. Lucia both in the preſent and the laſt war.

5. This practice of flooding is capable of being extended to a wonderful degree in this country, not only by uſing the natural falls of brooks and ſprings, and by occaſionally damming them up to ſupply higher ſituations; and by effectually ſpreading the land-floods from accidental ſhowers over the inferior lands to a great extent. And laſtly, the water, which is now dammed up to ſupply the numerous mills, might be diffuſed in rills over a thouſand meadows, or part of it be raiſed by pumps to higher grounds; and thus fertilize and enrich the country; while the grinding of corn, ſpinning of cotton, rolling iron bars, and other mechanic purpoſes, might be effected by wind-mills, or ſteam-engines, in almoſt every part of the iſland.

For this purpoſe likewiſe the new method of raiſing water by the vis inertiæ or acquired momentum of moving ſtreams might be well

applied, which was formerly uſed by Mr. Whitehurſt of Derby on a ſmall ſcale at Oulton in Cheſhire, as deſcribed with a plate of the machine, to which an air-veſſel is ingeniouſly added, in the Philoſophical Tranſactions for the year 1775, Vol. LXV. p. 277, and which is now adapted to variety of ingenious machinery by M. Boulton, Eſq. of Soho near Birmingham; and is well explained with two prints in the Repertory of Arts and Manufactures, No. LI.

6. The following water machine, which is on the principle of Hiero's fountain, is deſigned to raiſe part of the water of a ſpring, or ſmall brook, where ſome feet of fall may be acquired, to a greater height for the purpoſe of watering higher levels of ground; and the horizontal windmill with centrifugal pump is deſigned for the ſame purpoſe, where no fall can be acquired. We ſhall then perhaps have ſatiated ſome of our readers with this ſubject of watering lands, and may conclude with the ſhepherds in Virgil's Eclogue,


Claudite jam rivos, Pueri, ſat prata biberunt.

SECT.

PLATE V.

PLATE V.

Repreſents the ſtrata of a hill. *a b* is the upper ſtratum, ſuppoſe of marle; *c d* is the ſecond ſtratum, ſuppoſe of ſand; *e f* repreſents the accumulated earth in the valley. It is deſigned to ſhew, that in boring holes through the upper ſtratum to find that beneath it, they ſhould be formed perpendicular to the ſide of the mountain, and not perpendicular to the horizon, as is the common practice, as by thoſe means the hole *y y* is much ſhorter than the hole *x x*. As explained in Sect. XI. 1. 5.



London, Published Jan.y 1.st 1800, by J. Johnson, St. Pauls Church Yard.


PLATE VI.


PLATE VI.

Is a ſection of a machine ſimilar to Hiero's fountain, but deſigned to raiſe water to a great perpendicular height, where there is the convenience of a ſmall fall.

a b the ſtream of water, *b c c* the height of the fall of it, ſuppoſe ten feet, *d e* two veſſels of lead or iron containing, ſuppoſe, four gallons each, *f g h i k l* are veſſels of lead containing, ſuppoſe, two quarts each, *o p* two cocks, each of which paſſes through two pipes opening one and cloſing the other, *q r* a water balance moving on its centre *s* and turning the two cocks *o* and *p*, alternately, *t u* and *w x* two air-pipes of lead one quarter or half an inch diameter within, *y z*, *y z*, *y z*, water-pipes one inch diameter.

The pipe *b c c* is always full from the ſtream *a b*, the ſmall ciſterns *g i l*, and the large one *d*, are ſuppoſed to have been previouſly full of water, then admit water by turning the cock *o* through the pipe *c e* into the large ciſtern *e*. This water will preſs the air, which was in this ciſtern *e* up the air-pipe *w x*, and will force the water from the ſmall ciſterns *g i l* into the ciſterns *h k* and great C. At the ſame time by opening B, the water and condenſed air, which previouſly exiſted in the large ciſtern *d*, and the ſmall ones *f h k*, is diſcharged at B. After a time the water balance *q r s* cloſes the cocks now open, and opens their antagoniſts, and the ciſterns *f h k* are emptied in their turn by the force of the condenſed air from the ciſtern *d*, as the water enters into it from the pipe *b c*.


c
z
l
y
k
u
x
z
i
y
h



London, Published Jan.y 1.st 1800, by J. Johnson, St. Paul's Church Yard.

PLATE VII.

PLATE VII.


Is a ſection of a machine for raiſing water a few feet high by the power of the wind for the purpoſe of draining moraſſes, or of watering lands on a higher level.


It conſiſts of a windmill ſail placed horizontally like that of a ſmoak-jack, ſurrounded by an octagon tower; the diverging rays of this tower, *a b*, *a b*, may conſiſt of two-inch deals only, if on a ſmall ſcale, or of brick-work if on a larger one. Theſe upright pillars are connected together by oblique horizontal boards as ſhewn at A B, by which boards placed horizontally from pillar to pillar, in reſpect to their length, but at an angle of about 45 degrees in reſpect to their breadth, ſo as to form a complete octagon including the horizontal windmill ſail near the top of it; the wind as it ſtrikes againſt any of them, from whatever quarter it comes, is bent upwards and then ſtrikes againſt the horizontal wind-ſail. Theſe horizontal boards, which form the ſides of the octagon, may either be fixed in their ſituations, or be made to turn upon an axis a little below their centres of gravity, ſo as to cloſe themſelves on that ſide of the octagon tower moſt diſtant from the wind.

It may be ſuppoſed that the wind thus reflected would loſe conſiderably of its power before it ſtrikes on the wind-ſail, but on fixing a model of ſuch a machine on the arm of a long whirling lever, with proper machinery to count the revolution of the wind ſail, when thus included in a tower and moving horizontally; and then when moved vertically as it was whirled on the arm of the lever with the ſame velocity, it was found on many trials by Mr. Edgeworth of Edgeworth Town in Ireland, and by myſelf, that the wind by being thus reverted upwards by a fixed planed board did not ſeem to loſe any of its power. And as the height of the tower may be made twice as great as the diameter of the ſail, there is reaſon to conclude that the power of this horizontal wind-ſail may be conſiderably greater, than if the ſame ſail was placed nearly vertically oppoſed to the wind in the uſual manner.

At the bottom of the ſhaft of the wind-ſail is placed a centrifugal pump with two arms at C D, which has been deſcribed in mechanical authors. It conſiſts ſimply of an upright bored trunk, or cylinder of lead, with two oppoſite arms with an adapted valve at the bottom to prevent the return of the water, and a valve at the extremity of each arm to prevent any ingreſs of air above the current of the water as it flows out.

c c c c is a circular trough to receive the ſtreams of water from C and D, to convey them where required.





London, Published Jan.y 1.st 1800, by J. Johnson, St. Paul's Church Yard.

SECT. XII.

AERATION AND PULVERIZATION OF THE SOIL.

I. *Soils contain inflammable matters and water. Air conſiſts of oxygen, nitrogen, and heat. Produces carbonic, nitrous, and phoſphoric acids, and volatile alkali with water when buried in the ſoil. Heat and light given out from the union of carbon and oxygen in a letter-wafer. Sow and ſet ſoon after the plough or ſpade.* 2. *Penetrability of the ſoil increaſed, and mixture of its ingredients. Retains the rains. Enlarges the ſurface.* 3. *Uſes of fallowing. Turnips ſaid not to impoveriſh the ſoil, why.* 4. *Fallowing injurious to rich lands, why.* 5. *The great advantages of Tull's drill huſbandry. Prefers horſe-hoeing to hand-hoeing. An improved drill machine.* 6. *Advantages of tranſplanting wheat.* 7. *Of harrowing wheat in ſpring.* 8. *Rolling wheat in ſpring.*

As almoſt all ſoils not only contain carbon, and other inflammable materials, which are capable of uniting with oxygen, and thus producing the carbonic and other acids; but alſo contain water, which by its decompoſition, when in contact with confined air, produces ammonia or volatile alkali by the union of its hydrogen with azote; and nitre by the union of its abundant oxygen with another part of the abundant azote or nitrogen of the atmoſpheric air; there is reaſon to conclude, that the great uſe of turning over the ſoil with the plough or ſpade depends principally in the production of theſe effects by the confinement of both the oxygen and the azote or nitrogen of the air in the interſtices of the ſoil; and on this account we have entitled this ſection the aeration of the ſoil rather than the oxygenation

of it, as the latter belongs to the reſpiration rather than to the nutrition of vegetables.

When atmoſpheric air is impriſoned in the cavities of the ſoil by turning over its ſurface, which muſt be in greater quantity, when the ſoil is reduced into the very ſmall fragments, which has been called pulverization; and when it is the leaſt preſſed down by animals trampling on it, it more readily unites, I believe, with the materials above mentioned than in its free ſtate; which is probably effected by double or triple chemical affinities.

For this atmoſpheric air conſiſts of oxygen, azote, and the fluid matter of heat; now if the heat, which occaſions the oxygen and azote of the atmoſphere to exiſt uncombined in the form of gaſſes, be attracted from them by any other material, as they are confined in the cavities of the ſoil, they may by their nearer approach to each other combine into nitrous acid; or the oxygen may in its fluid ſtate, not in its aerial one, more readily unite with carbon; and form a fluid, not an aerial, carbonic acid; which we believe to be of ſo much conſequence in the growth of plants, as ſhewn in Sect. X. 4.

Add to this, that if any putrefactive proceſs be proceeding, where atmoſpheric air is thus impriſoned in the cavities of the ſoil, and by the loſs of its heat is converted from a gas to a fluid; that the azote may unite with the hydrogen of the decompoſing water, or contribute to decompoſe it; and thus to form volatile alkali, which like the nitrous acid, may either during the proceſs of its formation, or after it is formed, be of effectual ſervice to vegetation, at the ſame time the oxygen given out from the decompoſing water may contribute like that of the atmoſphere to produce carbonic, nitrous, or phoſphoric acids; and thus to render carbon, phoſphorus, and the baſis of nitre, capable of being abſorbed by vegetable lacteals.

Where atmoſpheric air is confined along with water, I well remember from experiments I made long ago, by inverting a bottle filled with air in a jar of water, that the bulk of the air was in ſome days

days ſo much diminiſhed as to occupy only half the bottle, which probably occurs from the decompoſition of both the water and air; and the production of ammonia and nitrous acid, both which are believed to be ſo ſerviceable to vegetation, as mentioned in Sect. X. 2. 9.

That the heat of the atmoſpheric air is given out, when oxygen unites with carbon, is ſhewn by the heat of hot-beds; and of fermenting ſaccharine and mucilaginous fluids, as in the production of ardent ſpirit; and may be beautifully ſeen in the combination of oxygen with carbon in the burning of one of thoſe common letter-wafers, which conſiſt of the mucilage of flour, and red lead or minium; not one of thoſe, which are called Iriſh wafers, and which are coloured with vermilion. If one of theſe minium wafers be made to blaze in the flame of a candle, the oxygen contained in the minium unites with the carbon of the flour, and gives out a very luminous ſpark, and conſequent great heat, and at the ſame inſtant a ſmall globule of melted lead drops down, and may be agreeably ſeen, if received on a ſheet of white paper held under it. It is alſo probable, that heat is emitted during the production of nitrous and of phoſphoric acids.

From theſe obſervations it appears, that ſeeds ſhould be ſown, and roots planted, ſoon after the ſoil is turned over; while the production of the carbonic, nitrous, and phoſphoric acids, and of volatile alkali, and perhaps many other proceſſes, are proceeding, rather than after they are completed; and alſo while the fluid element of heat is paſſing from its combined ſtate, and permeating the ſoil, which in this cold climate in the vernal months muſt be highly conducive to vegetation.

2. By thus turning over the ſoil with the plough or ſpade the penetrability of it by the roots of plants is alſo much facilitated; and for this purpoſe, as well as for the admixture of atmoſpheric air, it can ſcarcely be reduced into too fine molecules, or a kind of wet powder;

der; for the moiſture of ſoil is as neceſſary for its being permeated by the young roots of plants, as its ſmall coheſion, as mentioned in Sect. X. 3. 6.

Secondly, a more intimate mixture of the various ingredients, which moſt ſoils poſſeſs, as carbon, calcareous, argillaceous, ſiliceous, and magneſian earths, with various metallic oxydes, as thoſe of iron, and ſometimes of manganeſe, and calamy, all which by frequent turning over the ſoil with the plough or ſpade, become mixed ſo as to act on each other or on the roots of vegetables in every minute part of the ſoil.

And thirdly, the vernal rains are retained by their ſinking more readily into the pores and cells of land recently turned over, and which ſtill poſſeſſes an uneven ſurface. Beſides a greater ſurface of it being continually expoſed to the paſſing air, and to the heavier impurities, which it perpetually contains, as carbonic acid, ſoot, odours of many kinds.

3. A recapitulation of theſe circumſtances leads us to the knowledge of the uſe of fallowing lands, by repeatedly turning them over much carbonic acid is produced in its fluid ſtate; and perhaps ſome of the nitrous and phoſphoric acids; theſe may remain united with the vegetable recrements, or with volatile alkali, or with calcareous earth. 2. The parts of the ſoil may become better mixed together, and thus either chemically affect each other to their mutual melioration; or they may more uniformly ſupply nutriment to the roots, which penetrate it. 3. The ſoil may become broken into a moiſt powder, and may thus be more eaſily permeated, and ſupply a greater ſurface of its cavities for the vegetable abſorbents to apply themſelves to. 4. Unprofitable plants, or weeds, not being permitted to grow on it, or their being perpetually ploughed under the ſoil in their early growth, much vegetable nutriment will be reſerved by not being expended; or it will be increaſed by the ſaccharine and mucilaginous matter of the young plants, which are thus buried in it.

It ſhould be added, that ſome plants are ſaid not to impoveriſh the ground, on which they have grown during their herbaceous ſtate, before the ſeed-ſtems have ariſen; as turnips, when drawn up and carried away to feed cattle or ſheep on other grounds. This has been aſcribed by ſome authors to the ſoil having been ſhaded by their thick foliage, and thus not having ſuffered ſo much by evaporation. Some have aſcribed this ſuppoſed melioration of the ſoil to its having been ſcreened or overſhadowed by the thicker foliage of ſuch crops; and that as the putrefactive proceſs of vegetable recrements proceeds beſt in damp and confined air, as wood decays ſooneſt in cellars, they ſuppoſe the ſoil may thus become improved. But Mr. Tull ſeems either to doubt the fact, or to attribute it to the ground, where ſuch plants are cultivated, being uſually once or twice hoed; and thus in effect to have been followed by the repeated aeration and pulverization of the ſoil, and the deſtruction of innumerable weeds.

If nevertheleſs the fact be true, not only all the circumſtances above mentioned may contribute to produce it, but alſo, as it appears by the experiments of Prieſtley and Ingenhouſe, that though the perſpirable matter of vegetable leaves gives out oxygen in the ſunſhine, yet that it gives out carbonic acid in the ſhade; which even in its aerial or gaſſeous form is much heavier than common air, and will therefore ſubſide on the earth in the ſhade of this perſpiring foliage, and contribute to enrich the ſoil by the hourly addition of carbon.

4. Nevertheleſs where the ſoil is already replete with manures, and theſe proceſſes productive of carbonic, nitrous, and phoſphoric acids, and of volatile alkali, are going on in proper abundance; ſuch ſoils muſt be injured by being too frequently turned over in ſummer fallowing; and thus by expoſing too great a ſurface, and that too frequently, to the air, the ſunſhine, and the rain; by which much of the fluid carbonic acid will be converted into aerial carbonic acid, and eſcape, as well as the phoſphorus and the ingredients in their ſtate previous to the production of nitrous acid, and of the volatile alkali. On

this account in the manufacture of nitre in France, Spain, and Pruſſia, it is directed to cover the compoſt of ſoil and animal recrements with a ſhed to prevent too great exhalation and ablution. Hence though a ſummer fallow may be of advantage to a poor ſoil, which has nothing to loſe; it muſt be diſadvantageous to a rich one, which has nothing to gain.

Lord Dundonald in his work on the Connection of Agriculture and Chemiſtry ingeniouſly ſuppoſes, that ſoils become injured, when much expoſed to the air by fallowing, from the carbon or other inflammable matters uniting with oxygen; and that then being again combined with other materials, they become inſoluble, producing limeſtone, calcareous nitre, and phoſphat of lime. But there is another injury to ſoil by frequent fallowing, which I ſuſpect to be more extenſive, from the eſcape of carbonic acid, or of nitrous acid, or of ammonia, into the atmoſphere in the form of gas, as above mentioned; or their being waſhed away by rains.

5. Hence the great advantages of Mr. Tull's ingenious diſcovery of the drill huſbandry are eaſily underſtood, 1. By ſowing the wheat in rows, ſcattered by a drill-plough at regular diſtances, and buried at a regular depth, the grain is neither crowded, nor too thinly diſperſed. 2. Nor are the roots buried either too deep in the ſoil, or too ſhallow. 3. By turning the ſoil firſt from the rows in the ſpring for a week or two, and then turning it up againſt the rows, the ſoil becomes newly aerated with all the good effects in conſequence. 4. It becomes more penetrable by the ſuperficial roots of the corn. 5. By raiſing it to the ſecond joint of the corn-ſtems, four or ſix new roots with new ſtems will ſhoot out, generated by the caudex of the ſecond leaf of the corn-ſtem; which is now within the ſoil, or in contact with it, as explained in Sect. IX. 3. 1. and 7. XVI. 2. 2.

Thus Mr. Tull's method of heaping ſoil againſt wheat-plants up to the ſecond joint anſwers in ſome degree the ſame purpoſe, as tranſplanting the roots, and ſetting them deeper in the ſoil with much

much leſs expence of labour. But for the more perfect pulverization of the ſoil, and the more complete aeration of it, he inſiſts much on the preference of horſe-hoeing to hand-hoeing; as the former paſſes deeper into the ſoil, and thus expoſes a greater quantity of it to the air; and eſpecially of that part of it, which before lay too much beneath the ſurface to be previouſly much affected by the incumbent atmoſphere. But the great objection to the uſe of the horſe-hoe is, that the alternate rows of corn muſt be placed at too great a diſtance, as will be again ſpoken of in Sect. XVI. 2. 2.

To the many advantages of the drill huſbandry above recited Mr. Tull adds, that "where the ſpring-turnips are uſed too late in the year, there is not time to bring the land into tilth for barley, and there is a loſs of the barley crop in conſequence; which he ſays is entirely remedied by the drilling method; for by that the land may be almoſt as well tilled before the turnips are eaten or taken off, as it can afterwards." Huſbandry, Chap. VIII. p. 89.

So many great advantages ſeem to accrue from Mr. Tull's method of drill-ſowing and horſe-hoeing, that a curious queſtion offers itſelf, Why it has not been more generally adopted? Firſt, I ſuppoſe, becauſe it is difficult to teach any thing new to adult ignorance, ſo that the maſter muſt for ſome time attend the proceſs with his own eye. Secondly, I believe the axle-tree of Mr. Tull's ſowing machine did not accurately emit the proper quantity of ſeed from the hopper, and was liable to bruiſe and deſtroy ſome of it in its paſſage. And thirdly, that the improved drill machine of Mr. Cook's patent is too expenſive for the purchaſe of ſmall farmers, who fear that it may not anſwer the expected advantages.

I have therefore given a print at the end of this work of a machine conſtructed on a cheaper plan, which is ſimply an improvement of that deſcribed in Mr. Tull's book, by enlarging that part of the axle-tree which delivers the grain, into a cylinder of ſome inches diameter

with excavations in the rim; which rim riſes above the ſurface of the corn in the ſeed-box, and lets drop again into the ſeed-box, whatever grains fill the holes above the level of the rim, as that ſide of the cylinder aſcends. Whence the quantity delivered is uniform, and no grains are in the way to be bruiſed or injured, as explained at large along with the print; and the whole machine is ſimple, and of ſmall expence.

6. The moſt effectual method of obtaining the great combined advantages of aeration and pulverization of the ſoil is by tranſplanting the roots of wheat, and parting them, as already ſpoken of in Sect. IX. 3. 7. By taking up the roots and replanting them in ſoil lately turned over, and conſequently expoſed to the air, which is now confined in its interſtices, all the advantages already mentioned are effectually received, from the new made fluid, carbonic, nitrous, and phoſphoric acids, and from the ammonia, and other unnamed combinations. Secondly, all the advantages ariſing from the eaſy penetrability of the looſe ſoil by the root-fibres, which are believed by Mr. Tull to put out more radicles with abſorbent mouths at every part, where they are diſſevered, like a bruſh or pencil of hairs. Thirdly, by parting the root-ſcions from each other they acquire greater ſpace of air for their reſpiring leaves, and of ſoil for their abſorbent roots. Whereas when too many ſtems ariſe from one root, or many ſeeds are ſown near together, a tuſſock is produced in a conical form riſing higheſt in the center; which ſeems to be occaſioned by the conteſt of the ſtems for air and light; their roots alſo muſt deſcend lower in their conteſt for moiſture, and for other advantages of the ſoil; whence many of theſe crowded ſtems become barren, producing no ears, or ill-corned ones.

Another benefit from tranſplanting corn is owing to the quicker tendency to fructification, and conſequent ſooner ripening of the grain. Thus tranſplanted garden beans and tranſplanted brocoli flower ſooner, and I ſuppoſe produce leſs ſtems or ſtraw, as mentioned

tioned in Sect. XVI. 1. 2. I am alſo well informed by the Rev. Mr. Pole of Radborne, that the roots of thoſe turnips, which were drawn out of the ground and tranſplanted, became conſiderably larger than thoſe, which were only hoed in the common manner; which I ſuppoſe to have been owing to many of the extremities of the roots having been torn off in drawing them out of the ground; and that thence the tendency to ſhoot up the new central ſtem is delayed, and the reſervoir of nouriſhment accumulated in the tuberous root is thus increaſed in quantity, as ſeveral of theſe turnips weighed ten and eleven pounds; and hence probably the tranſplanting turnips by means of a cylindrical ſpade deſcribed in Vol. IV. of the Bath Society, which tears the roots leſs, might not have been ſo advantageous. Something ſimilar occurs in tranſplanting fruit-trees. See Sect. XV. 2. 4.

But the great advantage of tranſplanting wheat above the drill-huſbandry conſiſts in being able at the ſame time to divide the root-ſcions from each other; and thus not only to prevent their crowding each other, but alſo wonderfully to increaſe the product from a ſingle grain, with many other advantages mentioned by Mr. Bogle in the works of the Bath Society, Vol. III. p. 494.

Another great advantage of tranſplanting wheat conſiſts in this, that it may be ſowed in a garden, one acre of which will produce ſets for one hundred acres, if they be divided and planted at nine inches diſtance from each other; and as they are not to be tranſplanted till the ſpring, wheat may be thus cultivated in moiſter ſituations than would otherwiſe be friendly to its growth.

And that a clean crop may be certainly thus procured; becauſe if the land be ploughed immediately before the plants are ſet out, the corn will ſpring much quicker from the plants, than the weeds from their ſeeds; and the corn will thence bear down the growth of the weeds.

For many other particulars the reader is referred to the ingenious paper of Mr. Bogle above mentioned, who thinks the tranſplanting

might be done by boys and girls at a ſmall expence; I ſhall only add, that rape-ſeed, which is generally ſown in Auguſt, and not reaped till the Auguſt following, might be profitably tranſplanted, as well as peas and beans. And laſtly, that it is probable, that ſome means of making the holes to receive the plants might be much expedited by a broad wheel to be drawn by a man or horſe with prominent pegs on its periphery two inches tall, and nine inches aſunder.

7. Another means of aeration and of pulverization has been uſed in reſpect to wheat crops by many with advantage, and that is by drawing a lightiſh harrow over a wheat-crop in the ſpring, which, where a crop is thin, is particularly recommended; and may alſo be of ſervice where it is too thick.

The harrow by breaking the clods, and by turning up the ſoil againſt the ſtems of many plants, earths them deeper as in hoeing; and thus by burying the ſecond joint occaſions it to tiller, or ſhoot out new root-ſcions; at the ſame time the earth is expoſed to the air, and many weeds are rooted up and covered, and ſome roots of the corn.

The drawing a ſharp harrow over a field of wheat in the ſpring muſt cut or tear many of the roots of thoſe ſtems, which it comes near, which according to Mr. Tull's theory would ſhoot out many new radicles, or pencils of fine roots, and thus acquire more nouriſhment. But I ſuſpect that tearing of many of the root-fibres prevents the too luxuriant growth of the ſtem and leaves, and thence ſooner produces the fructification, as in tranſplanting. At the ſame time the earth being looſened becomes more penetrable to the remaining roots, as well as more nutritive from its aeration.

Others have even ploughed a field at this ſeaſon with good effect, as Mr. Bogle aſſerts; but both of them appear to be only inferior kinds of drill huſbandry; and the former may ſo far be of conſiderable utility.

8. Another method of aerating and pulverizing the ſoil of a wheat field in ſpring is by rolling it, which may be done before or after the

uſe of the harrow, or without it. As the ſurface of a wheat field is generally left rough with clods or eminences, the preſſure of a heavyiſh roller will not only pulverize theſe, and thus expoſe their interior ſurface to the air, and raiſe the ſoil round the wheat-ſtems above the ſecond joint, and thus induce them to ſhoot out new root-ſcions, or tiller; but will alſo preſs down the wheat roots into the ſoil, and thus alſo promote the growth of new ſtems, as mentioned in Sect. XVI. 2. 5. if it be performed, when the ground is neither too wet nor too dry for ſuch an operation.

SECT.

SECT XIII.

OF LIGHT, HEAT, ELECTRICITY.

I. 1. LIGHT *and heat are different fluids. Light does not heat tranſparent bodies. A glaſs fire-ſcreen, combines with opake bodies, and heat is detruded.* 2. *Light combines with ſolid oxygen, and with heat converts it into gas. Perſpiration of plants is decompoſed by light. The hydrogen retained gives the green colour. Water hyper-oxygenated. Oxygenated marine acid. Colourleſs nitrous acid. A branch immerſed in carbonic acid and water.* 3. *Etiolation of vegetables. Bleaching owing to oxygen. Colour of plants to hydrogen, and the yellow tan of the ſkin. Pure air from dew. Perſpiration of plants oxygenated. Light tans living bodies, and bleaches dead ones, both vegetable and animal.* 4. *Uſe of light in vegetable reſpiration. Plants do not reſpire in the night. Truffles and fungi live without light.* 5. *Spring water frequently oxygenated. Air liberated by points.* 6. *Plants require oxygen. Fallacy of contrary experiments.* II. 1. HEAT *univerſal. Counteracts gravitation. Is the cauſe of fluidity, and of aeriform ſtate. Particles of matter do not touch. Heat becomes combined. Is ſet at liberty in production of acids. In freezing water.* 2. *Froſt deſtroys fluidity. Ice expands. Separates compound fluids from each other, and burſts the veſſels of plants. Not of evergreens. Rime froſts and black froſts. Low ſituations not proper for gardens. Uſe of coping ſtones on fruit-walls. Rows of young peas from S. E. to S. W. Bend fig-trees on the ground. Froſt erroneouſly believed to meliorate the ſoil, and to be wholeſome. Clay rendered denſer by froſt. Snow protects plants. Animals covered with ſnow are not wet or ſtarved. Lichen rangiferinus.* 3. *Cold deſtroys vegetable irritability. Heat is a ſtimulus. Acquired habits of plants.* 4. *Cold produced by evaporation. Plants not to be watered in the ſunſhine.* III. 1. ELECTRICITY *conſiſts of two fluids. Forwards the growth of plants whether poſitive or negative. Lightning deſtroys them.* 2. *It aſſiſts the decompoſition of water in vegetables.* 3. *Clouds*

are generally electriſed plus. Experiment on vapour. Rain from hydrogen and oxygen. Thunder ſhowers. 4. *Electric points to collect dew, and promote vegetation. Electric clock.*

I. 1. PHILOSOPHERS are not yet agreed, whether light and heat be the ſame fluid under different modifications, or two different fluids, which exiſt frequently together. The latter opinion ſeems to be more probable from the circumſtances related below, and alſo from the analogy of other aqueous, aerial, or ethereal fluids, which appear to conſiſt of two other fluids combined or diffuſed with each other. Thus water conſiſts of oxygen and hydrogen combined together. Atmoſpheric air of oxygen and nitrogen diffuſed together. Electricity probably conſiſts of two fluids, which may be termed vitreous and reſinous electricity. Magnetiſm alſo probably conſiſts of two fluids, which conſtitute northern and ſouthern polarity. The power of attraction ſeems to conſiſt of gravitation and of chemical affinity. And laſtly, the element of fire conſiſts I ſuppoſe of light and heat.

The diſſimilarity of light and heat is evinced by this ſimple circumſtance; that as light gives no heat to tranſparent bodies, which the emanations from a fire do, there is reaſon to believe them to be different fluids. Thus when ſmoke is blown near the focus of a large burning glaſs, it does not aſcend; which ſhews, that the air is not heated and rarified by it; though it would burn or vitrify in an inſtant any opake body, which might be oppoſed to it; but the emanations of heat from a fire ſoon rarify and warm the air in its vicinity, cauſing it to aſcend, as may be ſeen by a ſpiral card-vann placed over a chimney-piece, and which is agreeably ſeen in the uſe of the new glaſs fire-ſcreens of Pariſian invention, which placed before a parlour fire permit the rays of light to paſs, but intercept the emanations of fluid heat.

Whence it would ſeem, that light does not itſelf communicate heat to opake bodies, when it falls on them; but combines with them,

and

and by that union heat is detruded or given out; which heat may produce inflammation of the material, if it be of an inflammable nature, by uniting it with the oxygen of the atmoſphere; and thus producing an eduction of more heat from the oxygen, and greater inflammation of the burning body.

2. Another eſſential difference between light and heat conſiſts in the particular attraction of the former to oxygen; inſomuch that by their union the combined or ſolid oxygen becomes changed into an aerial, or gaſſeous ſtate; as conſtantly occurs, when the ſun ſhines on the hyper-oxygenated water, which is perſpired or exhaled from plants, as mentioned in Botanic Garden, Vol. I. Cant. IV. l. 25. But as an addition of heat ſeems neceſſary to the converſion of a ſolid or fluid body into an aerial or gaſſeous one, I ſuppoſe the ſun's light at the ſame time by combining alſo with the water ſets at liberty ſome latent heat from it, which gives wings to the oxygen.

The water perſpired by plants, when expoſed to the ſunſhine, is believed to be decompoſed, as it eſcapes from the fine extremities of the exhalent or perſpirative veſſels of plants; and that the hydrogen is reabſorbed by the mouths of thoſe veſſels, as explained in Botanic Garden, Vol. I. note 34. That this happens to a certain degree is evinced by etiolated or blanched vegetable leaves becoming green, when expoſed to the ſunſhine in a few days; which is, I believe, produced by their retaining the hydrogen of the water they perſpire, as it is decompoſed by the ſun's light.

But it is alſo probable, that the perſpired fluid of plants is previouſly hyper-oxygenated in the vegetable circulation. Firſt, becauſe there is never perceived any ſmell of hydrogen to attend this proceſs of liberating oxygen by the ſun's light. And ſecondly, becauſe the following productions of oxygen gas by the ſun's light are ſimilar phenomena; though I ſuppoſe the points or hairs on vegetable leaves may contribute to the eſcape of the oxygen, as explained in Botanic Garden, Vol. I. note 10.

Sir

Sir Benj. Thompſon, now Count Rumford, in a paper publiſhed in Philoſ. Tranſact. Vol. LXXVII. put thirty grains of raw ſilk previouſly waſhed into ſome ſpring water, and expoſing it ſome hours to the ſunſhine obtained from it very pure vital air, or oxygen gas. In that experiment the ſpring water ſeems to have been in a ſtate of hyper-oxygenation, and the points or fine edges of the raw ſilk to have aſſiſted its liberation from the water in the ſunſhine, as explained in Botanic Garden, Vol. II. note on fucus. 2. The hyper-oxygenated marine acid is known very haſtily to part with its ſuperabundant oxygen in the ſunſhine. 3. Mr. Scheele inverted a glaſs veſſel filled with colourleſs nitrous acid into another glaſs-veſſel containing the ſame acid; and on expoſing them to the ſun's light, the inverted glaſs became partly filled with pure air, and the acid at the ſame time became coloured. Crell's Annal. 1786.

As water contains 85 hundredth parts of oxygen to 15 of hydrogen, it may become much oxygenated occaſionally by a ſmall loſs of hydrogen in the vegetable ſyſtem; or by the carbonic acid being decompoſed in plants by the ſecretion of carbon, which conſtitutes ſo great a part of them; and that on both of theſe accounts they may yield oxygen gas, when expoſed to the ſun's light, as appears from the following experiment related from Von Uſlar by G. Schmeiſſer. Obſervat. on Plants. Creech, Edinburgh, p. 92.

If two branches of a plant are immerſed, one in common water, and the other in water impregnated with carbonic acid, we then find, that the branch immerſed in the latter yields a much greater quantity of oxygenous gas in the ſunſhine than the other. The difference in ſome experiments has been found in the proportion of 264 to 1. But the proportions vary when different plants are ſubjected to trial. Thus the carbonic acid, with which the water is impregnated, is decompoſed by the branch, the carbon apparently enters into the conſtitution of the plant, while the oxygen is ſet at liberty, and eſcapes

in the form of gas in the ſunſhine; but not in the night, as then the carbon is perſpired along with it.

3. A third circumſtance, in which the effects of light differ eſſentially from thoſe of heat, appears in the blanching or etiolation of vegetables; under whatever temperature of heat a plant is kept, it becomes white, if the light be excluded from it, and is ſo far diſeaſed, as mentioned in Sect. XIV. 2. 4. Whence all vegetables turn towards the window, if confined in a room, and in denſe woods grow taller, than in open grounds, for the purpoſe of acquiring acceſs to this neceſſary fluid. On this ſubject many experiments are related by M. Senebier on vegetables confined in a dark cavern.

From the experiment laſt related of the nitrous acid becoming coloured, when the ſuperabundant oxygen was volatilized by the ſun's light, or attracted from it; and from the experiments of bleaching cotton by the hyper-oxygenated marine acid, where the union of oxygen with the colouring matter ſeems to deſtroy the latter by forming a new acid, which is colourleſs, it appears, that the abſence of oxygen occaſions the colour of vegetable bodies, probably by the accumulation of hydrogen; and that on this account, when they are ſecluded from the light, they become white, or blanched, or etiolated, by their not being in a ſituation to part with ſo much oxygen, as when they are expoſed to the light.

Hence plants growing in the ſhade are white, and become green by being expoſed to the ſun's light; for their natural colour being blue, the addition of hydrogen adds yellow to this blue, and *tans* them green.

I ſuppoſe a ſimilar circumſtance takes place in animal bodies; their perſpirable matter is probably hyper-oxygenated; and, as it eſcapes in the ſunſhine, loſes its ſuperabundant oxygen; and by the hydrogen being retained the ſkin becomes *tanned* yellow. Though this muſt occur in leſs quantity in animals, as they perſpire ſo much leſs than

than vegetables; and the greateſt part of their perſpired matter, which exhales from the lungs, is not expoſed to the ſun's light. In proof of this it muſt be obſerved, that both vegetable and animal ſubſtances become bleached white by the ſun-beams and water, when they are dead, as cabbage-ſtalks, bones, ivory, tallow, bees-wax, linen and cotton cloth; and hence, I ſuppoſe, the copper coloured natives of ſunny countries might become etiolated, or blanched, by being kept from their infancy in the dark, or removed for a few generations to more northern climates.

It is probable, that on a ſunny morning much pure air becomes ſeparated from the dew by means of the points of vegetables, on which it adheres, and much inflammable air imbibed by the vegetable, or combined with it; and, by the ſun's light thus decompoſing water, the effects of it in bleaching linen ſeem to depend; the water is decompoſed by the light at the ends or points of the cotton or thread; and the vital air unites with the phlogiſtic or colouring matters of the cloth; and produces a new acid, which is either itſelf colourleſs, or waſhes out; at the ſame time the hydrogen or inflammable part of the water eſcapes. Hence there ſeems a reaſon, why cotton bleaches ſo much ſooner than linen; viz. becauſe its fibres are three or four times ſhorter, and therefore protrude ſo many more points; which ſeem to facilitate the liberation of the vital air from the inflammable part of the water.

A ſun-flower three feet and a half high, according to the experiment of Dr. Hales, perſpired two pints in one day, (vegetable ſtatics) which is many times as much in proportion to its ſurface, as is perſpired from the ſurface and lungs of animal bodies; it follows, that the vital air, liberated from the ſurface of plants by the ſunſhine, muſt much exceed the quantity of it abſorbed by their reſpiration; and that hence they improve the air, in which they live, during the light part of the day; and thus blanched vegetables will ſooner become

tanned into green by the ſun's light, than etiolated animal bodies will become *tanned* yellow by the ſame means.

Laſtly. This retention of the hydrogen on the ſkins of vegetables and animals, when their perſpirable matter is decompoſed by the ſun's light, and by which the former becomes green, and the latter yellow, is evidently owing to the power of life; becauſe when either of them are dead, the action of the ſunſhine on the water ſprinkled on them again blanches them, or bleaches them white.

It is hence evident, that the curious diſcovery of Dr. Prieſtley, that his green vegetable matter, and other aquatic plants, gave out vital air, when the ſun ſhone upon them; and the leaves of other plants did the ſame when immerſed in water, as obſerved by Mr. Ingenhouz, refer to the perſpiration of vegetables, not to their reſpiration. Becauſe Dr. Prieſtley obſerved the pure air to come from both ſides of the leaves, and even from the ſtalks of a water-flag, whereas one ſide of the leaf only ſerves the office of lungs, and certainly not the ſtalks. Exper. on Air, Vol. III. And thus in reſpect to the circumſtance, in which plants and animals ſeemed the fartheſt removed from each other, I mean in their ſuppoſed mode of reſpiration, by which one was believed to purify the air, which the other had injured, they ſeem to differ only in degree; and the analogy between them remains unbroken.

4. The conteſt for light, as well as for air, which is ſo viſible in the growth of vegetables, as deſcribed in Botanic Garden, Vol. II. note on cuſcuta, ſhews the former to be of great conſequence to their exiſtence as well as the latter. Thus many flowers follow the ſun during the courſe of the day by the nutation of the ſtalks, not by the rotation of them, as obſerved in the ſun-flower by Dr. Hales; and the leaves of all plants endeavour to turn their upper ſurface to the light, which is their reſpiratory organ, or lungs, as ſhewn in Sect. IV.

The

The great uſe of all plants turning their upper ſurfaces of their leaves to the light is thus intelligible ; the water perſpired from thoſe ſurfaces is hyper-oxygenated ; and, as it eſcapes from the ſharp edges of the mouths of the perſpiring veſſels, when acted upon by the ſun's light, gives out oxygen ; which oxygen, thus liberated from the perſpired water, and added to that of the common atmoſphere, preſents to the reſpiratory terminations of the pulmonary arteries on the upper ſurfaces of leaves an atmoſphere more replete with vital air.

This neceſſity of light to the reſpiration of vegetables is ſo great, that there is reaſon to believe, that many plants do not reſpire during the night, but exiſt in a torpid ſtate like winter ſleeping inſects. Thus the mimoſa, ſenſible plant, and many others, cloſe the upper ſurfaces of their oppoſite leaves together during the night, and thus preclude them both from the air and light. And the internal ſurfaces of innumerable flowers, which are their reſpiratory organs, are cloſed during the night, and thus unexpoſed both to light and air.

The fungi nevertheleſs, which are termed vegetables, becauſe they are fixed to the earth, or to the ſtones, or trees, or timber, where they are found, can exiſt without light or much air ; as appears in the truffle, which never appears above ground ; and by other fungi, which grow in dark cellars ; and in eſculent muſhrooms, which are cultivated beneath beds of ſtraw. From this circumſtance of their exiſting without light, and from their ſmell of volatile alkali, like burnt feathers, when they are burnt, and from their taſte when cooked and eaten, they ſeem to approximate to the animal kingdom.

5. Laſtly. It may nevertheleſs be ſuſpected, that in many of the experiments of Dr. Prieſtley and Dr. Ingenhouz, the production of vital air might be ſimply owing to the action of the ſun's light on the water, in which the vegetables were immerſed, like that from the ſilk in the experiment of Count Rumford ; and that the fine points, or ſharp edges of thoſe bodies, contributed only to facilitate the

the liberation of it, when expoſed to the ſunſhine, which thus diſoxygenate the water by their united effect.

This appears on immerſing a dry hairy leaf in water freſh from a pump, innumerable globules like quickſilver appear on almoſt every point; for the extremities of theſe points attract the particles of water leſs forcibly, than thoſe particles attract each other; hence the contained air, whoſe elaſticity was but juſt balanced by the attractive power of the ſurrounding particles of water to each other, finds at the point of each fibre a place, where the reſiſtance to its expanſion is leſs; and in conſequence it there expands, and becomes a bubble of air. It is eaſy to foreſee, that the rays of the ſunſhine, by being refracted and in part reflected by the two ſurfaces of theſe minute air-bubbles, muſt impart to them much more heat than to the tranſparent water; and thus facilitate their aſcent by further expanding them; and that the points of vegetables attract the particles of water leſs, than they attract each other, is ſeen by the ſpherical form of dew-drops on the points of graſs.

6. It may be added in this place, that there may alſo be a fallacy in the ſuppoſed reſults of thoſe experiments, where plants have been confined in hydrogen or azote mixed with atmoſpheric air; and have been believed to have vegetated more vigorouſly, and to have meliorated the air. In theſe experiments I ſuſpect, that the impure part of the air was attracted by the water, and taken up by the abſorbents of the roots of the plants from the water, rather than by the abſorbents of their leaves or ſtems in the air; and that the melioration of the air was occaſioned, as above deſcribed, by the action of the light on the water perſpired from the ſurface of the plant, or liberated by its points from the water, with which part of it was covered. This is rendered more probable, becauſe plants and ſeeds in the experiments of others ceaſed to vegetate in thoſe gaſſes, which were totally deprived of oxygen, as in M. Scheele's experiments on the growth of ſeeds.

II. 1. The

II. 1. The fluid matter of heat is one of the moſt extenſive elements in nature, perhaps next to that of gravitation; all other bodies are immerſed in it, and are preſerved in their preſent ſtate of ſolidity or fluidity by the different attraction of their particles to the matter of heat, which thus counteracts the powers of gravitation, and of chemical affinity, which would otherwiſe compreſs them into one ſolid chaotic maſs!

Since all known bodies are contractible into leſs ſpace by depriving them of ſome portion of their heat; and as there is no part of nature totally deprived of heat; there is reaſon to believe, that the particles of bodies do not touch, but are held towards each other by their ſelf-attraction, or recede from each other by their attraction to the maſs of heat, which ſurrounds them; and thus exiſt in an equilibrium between theſe two powers.

If more of the matter of heat be applied to them, they recede farther from each other, and become fluid; if ſtill more be applied, they take an aerial form, and are termed gaſſes; and it is probable, that the ethereal fluid of electricity may alſo be diffuſed with heat, as well as the ethereal fluid of light.

Thus when water is heated to a certain degree, it would inſtantly aſſume the form of ſteam, but for the preſſure of the atmoſphere; which prevents this change from taking place ſo eaſily; the ſame is true of quickſilver, diamonds, and of perhaps all other bodies in nature; they would firſt become fluid, and then aeriform, by appropriated degrees of heat. On the contrary, this elaſtic matter of heat, termed Calorique in the new nomenclature of the French academicians, is liable to become conſolidated itſelf in its combinations with ſome bodies, as certainly in nitre, and probably in combuſtible bodies, as ſulphur and charcoal.

This combined heat is univerſally ſet at liberty in the production of acids by the union of oxygen with all inflammable bodies, as ſhewn in Sect. XII. 1. It is alſo taken from ſome bodies by the vicinity of

very cold ones, as water when frozen loſes ſuddenly a part of its combined heat, at the moment it becomes ice.

2. It is evident, that without fluidity the blood or juices can not circulate in animal or in vegetable veſſels; whence ſo great a diminution of heat as to produce froſt on this account would deſtroy them if long continued; at the ſame time too great a deduction of heat is known to deſtroy the irritability of animal as well as of vegetable fibres, and muſt on this account alſo prevent the circulation of their fluids, and occaſion the mortification of parts of them, or the death of the whole. But when fluids are converted into ice, the bulk of them is enlarged to a conſiderable degree, and that with ſuch violence as to burſt iron veſſels, as bombs, which are filled with water. Whence in this manner alſo froſt deſtroys thoſe parts of vegetables, which are moſt ſucculent; as the early ſhoots of aſh trees, and other young plants, are frequently deſtroyed in the beginning of May by a froſty night.

The veſſels of theſe ſucculent parts of plants are diſtended and burſt by the expanſion of their frozen fluids; while the drier or more reſinous vegetables, as pines, yews, laurels, and other evergreens, are leſs liable to injury from cold. The trees in valleys are on this account more liable to injury by the vernal froſts, than thoſe on eminences; becauſe their early ſucculent ſhoots appear ſooner in the year.

Another method, by which the act of freezing may deſtroy vegetable life, may be by ſeparating ſome part of their fluids from other parts of them. Thus when wine, or vinegar, or ſalt and water, or clay diffuſed in water, and perhaps milk, are frozen; the watery part, as it congeals, protrudes from its forming cryſtals the ſpirit, the acid, the ſalt, the clay, and probably the opake particles of the milk; and by a ſimilar proceſs on vegetable and perhaps on animal fluids, when expoſed to great cold, they may be rendered unfit for future circulation or life. See Sect. XV. 4. 1.

The

The expanſion of ice nevertheleſs well accounts for the greater miſchief which is ſometimes done by vernal froſt, when preceded by much rain, or miſt, or dew, as by hoar-froſt, than by the dry froſts without rime, called black froſts; as the vegetable veſſels are then fuller of fluids. But when miſt or dew attends a froſty night, but has not preceded it, I ſuppoſe a hoar froſt may be leſs injurious than a black froſt; as the caſe of ice on the buds of trees, or on young graſs, being inſtantly produced, covers them with a bad conductor of heat, and prevents them from being expoſed to ſo great cold, as in the continuance of a black froſt without hoar or rime. See Sect. XV. 3. 5.

Mr. Laurence, in a letter to Mr. Bradley, complains, that the dale-miſt attended with a froſt on May-day had deſtroyed all his tender fruits; though there was a ſharper froſt the night before without a miſt, that did him no injury; and adds, that a garden not a ſtone's throw from his own on a higher ſituation, being above the dale-miſt, had received no damage. Bradley, V. II. p. 232. From this inſtructive fact it appears, that very low ſituations even in this cold climate are not proper for the purpoſes of a garden. And on the contrary, very high ſituations are equally improper on account of their greater cold, and the conſequent backwardneſs of their vegetable products. See Sect. XV. 3. 5.

Hence fruit trees againſt a wall, which are covered with coping ſtones projecting ſix inches over them, are leſs injured by the vernal froſts; becauſe their being thus ſheltered from the deſcending night-dews has prevented them from being moiſt at the time, they were frozen; which circumſtance has given riſe to a vulgar error amongſt gardeners, who ſuppoſe froſt to deſcend.

Hence as the freezing winds of this country are from the north-eaſt, a gardener ſhould extend his rows of young peas and beans from the ſouth-eaſt to the north-weſt, and raiſe a mound of earth behind them, and might ſhelter them occaſionally with ſtraw, placed on the

ground behind the young plants, and ſupported a few inches over them in front by poles placed horizontally over the rows; remembering the old proverb,

The wind from north-eaſt
Deſtroys man and beaſt;
The wind from ſouth-weſt
Is always the beſt.

The immediate cauſe of the coldneſs of the N. E. winds is, that they conſiſt of regions of air brought from the north over evaporating ice, and gain an apparent eaſterly direction, becauſe they arrive at a part of the ſurface of the earth, which moves with greater velocity, than the ſurface of the part of the earth, they come from. So on the contrary the S.W. winds are warm, as they conſiſt of regions of air brought from the ſouth, and gain an apparent weſterly direction, becauſe they arrive at a part of the earth's ſurface, which moves ſlower than the ſurface nearer the equator, whence they came, and of which they had previouſly acquired the velocity.

As the common heat of the earth in this climate is 48 degrees, thoſe tender trees, which will bear bending down, are eaſily ſecured from the froſt by ſpreading them upon the ground, and covering them with ſtraw or fern. This particularly ſuits fig-trees, as they are very flexible, and as they are furniſhed with an acrid juice, which defends them from inſects; but I have nevertheleſs found them in this ſituation much eaten by mice.

It has been believed by many, that froſt meliorates the ground; but it is now well known, that ice contains no nitrous particles, as was formerly ſuppoſed; and that though froſt by enlarging the bulk of ſome moiſt ſoils may leave them more porous for a time after the thaw; yet as the water exhales, the ſoil becomes as hard as before, being preſſed together by the incumbent atmoſphere. And from an obſervation of Mr. Kirwan's, mentioned in Section XV. 4. 1. it appears,

pears, that moiſt clay becomes denſer or more ſolid by being frozen; and if this ſhould not occur, yet it would quickly become as ſolid as before by the ſelf-attraction of its particles, called *ſetting* by the potters; as well as by the preſſure of the atmoſphere; as its water exhales, and leaves vacuities between its particles. Add to this, that on the coaſts of Africa, where froſt is unknown, the fertility of the ſoil is much ſuperior to our own.

In reſpect to the commonly ſuppoſed ſalubrity of froſty ſeaſons to mankind, and to other animals, the bills of mortality are an evidence in the negative in reſpect to mankind, as in long froſts many weakly and old people periſh from debility, occaſioned by the diminiſhed heat not being ſufficient to excite into action their veſſels previouſly too inirritable; and many birds, and other wild animals, and tender vegetables, periſh benumbed by the degree and continuance of the cold.

It ſhould however be obſerved, as froſty air is alway dry, except when frozen miſts diſſolve, as they adhere to the warmer ſkins of animals, that it does not generally affect us with ſo great a ſenſation of cold, as when air near the freezing point is loaded with moiſture; as the moiſture of ſuch air is perpetually evaporating from our ſkins, and produces on them a degree of cold greater than the ſimple contact of dry air produces, when it is but a little beneath the freezing point. Hence froſty air is more agreeable to thoſe young or ſtrong people, who can keep themſelves warm by exerciſe; that is, who can generate heat by increaſed ſecretions. But ſevere and continued froſts deſtroy the old and infirm, who cannot uſe much exertion; and the children of the poor, who want both food, fire, and clothing, in this harſh climate.

It may nevertheleſs be true, that ſnows of long duration in our winters may be leſs injurious to vegetation than great rains and ſhorter froſts. 1. Becauſe great rains carry down many thouſand pounds worth of the beſt manure into the ſea; whereas ſnow diſſolves gradually, the upper ſurface, as it thaws, ſliding over the under part,

which remains frozen, and thence carries away leſs from the land into the rivers; whence a ſnow flood may be diſtinguiſhed from a rain flood by the tranſparency of the water.

Secondly. Snow protects vegetables from the ſeverity of the froſt; ſince it is generally in a ſtate of thaw, where it is in contact with the earth; as the earth's heat is 48 degrees, and that of thawing ſnow is 32°. The plants between them are generally kept in a degree of heat about 40, by which many of them are preſerved. On this account ſome plants from Siberia were ſaid to periſh by the froſts at Upſal; becauſe the ſnows did not commence at the ſame time as in the colder climate, from which they were brought.

Thus the lichen rangiferinus, coral-moſs, vegetates beneath the ſnow in Siberia, where the degree of heat is always about 40; that is in the middle between the freezing point and the common heat of the earth. And as this vegetable is for many months of the winter the ſole food of the rein-deer, who digs furrows in the ſnow to find it; and as the milk and fleſh of this animal is almoſt the only ſuſtenance, which can be procured by the natives during the long winters of thoſe higher latitudes, this moſs may be ſaid to ſupport ſome millions of mankind.

Snow protects vegetables, that are covered by it, from cold, both becauſe it is a bad conductor of heat itſelf, and contains much air in its pores. When living animals are buried in ſnow, as ſheep, or hares, the water, which their warmth produces, becomes abſorbed into the ſurrounding ſnow by capillary attraction, and the creatures are not moiſtened by its dropping on them; but the cavity enlarges, as the ſnow diſſolves, affording them both a dry and a warm habitation. If this was generally known, many cold and weary travellers in ſnowy nights might be ſaved by covering themſelves with ſnow inſtead of endeavouring to proceed.

It ſhould be added that Haſſenfratz has endeavoured to ſhew by ingenious chemical experiments, that rain water and ſnow contain

both of them a redundancy of oxygen compared with river water, which they may have acquired in their deſcent through the atmoſphere; and that as oxygen is ſhewn by the experiments of Ingenhouz and Senebier to promote the growth of ſeeds and of plants, he concludes, that rain water and ſnow promote vegetation in a much greater degree than river water or ice, which ſeems to accord with the popular obſervations on this ſubject.

3. Mr. John Hunter by applying thermometers to the internal parts of vegetables newly opened diſcovered, that they poſſeſſed in froſty ſeaſons a degree of heat above that of the atmoſphere, though leſs than that of cold blooded animals. Whence another deleterious effect of cold on vegetable bodies muſt be by deſtroying their irritability, and by that means ſtopping the abſorption and circulation of their juices; in the ſame manner as is ſeen in the pale benumbed fingers of ſome people, when expoſed to the cold; and which is the immediate cauſe of death in thoſe, who periſh in the ſnow in winter, which occurs long before their fluids are frozen.

The neceſſity of a certain degree of heat to produce or to preſerve the activity of the abſorbent veſſels of vegetables is well evinced by the experiments of Hales and Duhamel on the riſing ſap of vines in the vernal months. On a froſty day, when the ſun ſhone on one of thoſe wounded trees, the ſap flowed on the ſouth ſide of the tree, but not on the north ſide. Phyſique des arbres, Vol. II. p. 258. M. Duhamel further obſerves, that the maples in Canada, where the froſt is long and ſevere, begin to bleed, when wounded with the firſt thaw, and ſtop again, when it freezes; and that this in froſty days occurs only on the ſouth ſide of the tree.

This acquaints us, that one of the principal properties of heat in reſpect to organic bodies, whether of vegetables or animals, conſiſts in its acting as a ſtimulus; and that in a greater quantity than that, which the organized being has been accuſtomed to, it acts as an exceſs of ſtimulus; and thus increaſes the activity of the ſyſtem in

in reſpect to the abſorption of its food, circulation of its juices, and quantity of its ſecretions, and conſequently to its more rapid growth; but all increaſe of ſtimulus becomes injurious by its exceſs, and is certainly followed by debility; as is ſeen in thoſe of our own ſpecies, who are habitually kept in too warm rooms, or are accuſtomed to drink intoxicating liquors.

Hence a wiſe gardener muſt regard the acquired habits of tender vegetables; the inhabitants of his green houſe, and thoſe plants, which have been expoſed to a greater heat for any length of time, ſhould be gradually cooled, and watered with ſubtepid water; ſince expoſing them to the cold of this climate is otherwiſe liable to deſtroy their irritability and occaſion their death.

4. The great cold produced by evaporation is now well underſtood. In all chemical proceſſes, where aerial or fluid bodies become conſolidated, a part of the heat, which was before latent, becomes preſſed out from the uniting particles; as in the inſtant that water freezes, or that water unites with quick lime. On the reverſe, when ſolid bodies become fluid, or fluid ones become aerial, heat is abſorbed by the ſolution; whence it may be ſaid in popular language, that all chemical combinations produce heat, and all chemical ſolutions produce cold. This ſhould teach the careful gardener not to water tender vegetables in the heat of the ſunſhine, or in a warm dry wind; leſt the haſty evaporation ſhould produce ſo much cold as to deſtroy them; and that more certainly from their having been previouſly too much ſtimulated by heat, and in conſequence their power of life, or irritability, having been already diminiſhed; as further ſpoken of in Sect. XIV. 2. 2.

III. 1. The mechanical theory of electricity invented by Dr. Franklin is believed by ſome philoſophers not ſo well to explain the various phenomena of electricity, as may be accompliſhed by an hypotheſis of the exiſtence of two electric fluids diffuſed together, and ſtrongly attracting each other, one of them to be called vitreous, and

the other reſinous, electricity. The latter opinion I am inclined to eſpouſe, but ſhall not here enter into a detail of the theory; but ſhall only obſerve, that the experiments on vegetation have been principally made with the accumulation of the vitreous electricity only, and the conſequent excluſion of the reſinous; that is, with what is commonly termed poſitive electricity, and not with what is termed negative electricity. It is therefore to be wiſhed, that ſome future experiments may be made with the reſinous or negative electricity in preference to the vitreous or poſitive electricity, or with both of them alternately or comparatively.

The influence of poſitive or vitreous electricity in forwarding the germination of plants and their growth ſeems to be pretty well eſtabliſhed; though Mr. Ingenhouz did not ſucceed in his experiments, and thence doubts the ſucceſs of thoſe of others; and though M. Rouland, from his new experiments believes, that neither poſitive nor negative electricity increaſes vegetation; both which philoſophers had previouſly been ſupporters of the contrary doctrine; for many other naturaliſts have ſince repeated their experiments relative to this object, and their new reſults have confirmed their former ones. Mr. D'Ormey and the two Roziers have found the ſame ſucceſs in numerous experiments, which they have made in the two laſt years; and Mr. Carmoy has ſhewn in a convincing manner, that electricity accelerates germination.

Mr. D'Ormey not only found various ſeeds to vegetate ſooner, and to grow taller, which were put upon his inſulated table, and ſupplied with electricity; but alſo that ſilk-worms began to ſpin much ſooner, which were kept electrified, than thoſe of the ſame hatch, which were kept in the ſame place and manner, except that they were not electrified. Theſe experiments of Mr. D'Ormoy are detailed at length in the Journal de Phyſique of Rozier, Tom. XXXV. p. 270.

Mr. Bartholon, who had before written a tract on this ſubject, and propoſed

propoſed ingenious methods for applying electricity to agriculture and gardening, has alſo repeated a numerous ſet of experiments; and ſhews, that natural electricity as well as the artificial increaſes the growth of plants, and the germination of ſeeds; and oppoſes Mr. Ingenhouz by very numerous and concluſive facts. Ib. Tom. XXXV. p. 401.

My friend Mr. D. Bilſborrow in June 1797 ſowed muſtard-ſeed in four garden pots at Mr. Hartop's at Dalby Hall in Leiceſterſhire. He ſubjected one of theſe to poſitive or vitreous electricity, and another to negative or reſinous electricity, and obſerved that the ſeeds in the pot ſubjected to the negative or reſinous electricity germinated a day before the pot ſubjected to poſitive or vitreous electricity, and both of them much before the two pots, which were not electriſed, but otherwiſe expoſed to the ſame circumſtances.

Nor do the injuries occaſionally received from lightning in its paſſage through trees or corn fields from or to the earth or clouds, which are mentioned in Sect. XIV. 2. 3. in the leaſt invalidate this opinion of its general utility as well as that of the fluid element of heat; for the exceſs of the moſt ſalutary ſtimuli become deleterious both to vegetable and animal bodies.

2. Since by the late diſcoveries in chemiſtry there is reaſon to believe, that water is decompoſed in the veſſels of vegetables; and that the hydrogene, or inflammable air, of which it in part conſiſts, contributes to the nouriſhment of the plant, and to the production of its oils, reſins, gums, ſugar, &c. And laſtly, as electricity has by late experiments been found to decompoſe water into the two airs, termed oxygen and hydrogen, there is a powerful analogy to induce us to believe, that it accelerates or contributes to the growth of vegetation; and like heat may poſſibly enter into combination with many bodies, or form the baſis of ſome yet unanalyſed acid.

3. The ſolution of water in air or in calorique ſeems to acquire electric matter at the ſame time, as appears from an experiment of Mr.

Mr. Bennet. He put ſome live coals into an inſulated funnel of metal, and throwing on them a little water, obſerved that the aſcending ſteam was electriſed plus; and the water, which deſcended through the funnel, was electriſed minus. Hence it appears, that though clouds by their change of form may ſometimes become electriſed minus, yet they have in general an accumulation of poſitive electricity. This accumulation of electric matter alſo evidently contributes to ſupport the atmoſpheric vapour, when it is condenſed into the form of clouds; becauſe it is ſeen to deſcend rapidly, after the flaſhes of lightning have diminiſhed its quantity.

According to the theory of Mr. Lavoiſier concerning the compoſition and decompoſition of water, there would ſeem another ſource of thunder-ſhowers; and that is, that the two gaſſes termed oxygen gas, or vital air, and hydrogen gas, or inflammable air, may exiſt in the ſummer atmoſphere in a ſtate of mixture, but not of combination; and that the electric ſpark, or flaſh of lightning, may combine them, and produce water inſtantaneouſly.

4. A profitable application of electricity by the gardener or agricultor to promote the growth of plants is not yet diſcovered; it is nevertheleſs probable, that in dry ſeaſons the erection of numerous metallic points on the ſurface of the ground, but a few feet high, might in the night time contribute to precipitate the dew by facilitating the paſſage of electricity from the air into the earth; and that an erection of ſuch points higher in the air by means of wires wrapped round tall rods, like angle rods, or elevated on buildings, might frequently precipitate ſhowers from the higher parts of the atmoſphere.

And laſtly, that ſuch points erected in gardens might promote a quicker vegetation of the plants in their vicinity by ſupplying them more abundantly with the electric ether; if the events of the experiments of the philoſophers above mentioned are to be depended upon, which may at leaſt be worth a further trial.

5. For the purpoſe of keeping a few flower-pots perpetually ſubject to more abundant electricity, Mr. Bennet of Wirkſworth in Derbyſhire affixed a ſmall apparatus to the pendulum of a clock, as deſcribed below with a plate; but has not yet ſufficiently attended to it to determine its effect on vegetation.

SECT.

PLATE VIII.

PLATE VIII.


Shews the ſtructure of Mr. Bennet's electric Doubler, applied to the pendulum of a clock, for the purpoſe of ſubjecting a flower pot to perpetual poſitive or negative electricity.

A the braſs plate, which is always inſulated by its glaſs pedeſtal, on which the electricity is accumulated. B the braſs plate, which becomes electrified by the influence of the moving plate C, which is alſo inſulated. D the pendulum wire. C is inſulated by the glaſs-tube E E. The wire F F is alſo inſulated by the ſame glaſs, being faſtened to the middle of it by a braſs ſocket at G. H H H H H are wires to connect the plates with each other, or with the earth. I I a ſtring to be carried from the plate A over inſulated hooks to any part of a room, or to an inſulated flower-pot.

Now if A be poſitive, and C moves, till it be parallel to it, and the wires at the bottom touch each other, then C becomes negative, and moving till it be parallel to B, and its wire touched by the uppermoſt H, then B becomes poſitive; and when C returns to A, the electricity of A and B becomes united by means of the inſulated wire F F touching H H. The longer end of F is bent ſo as not to touch the wire of B, till the end is brought to it. Thus the poſitive electricity of A is increaſed.

The wires are curled into ſeveral rings to make them more elaſtic, as otherwiſe they would ſoon be puſhed out of their places, and the proper contacts not occur. The plates A and B may be fixed on heavy pedeſtals, that they may be moved upon a ſhelf to a proper diſtance from the plate, which hangs by the pendulum wire. The heavier the pendulum and the larger the plates, the more electricity may be accumulated. With my ſmall apparatus fixed to a Dutch wooden clock ſparks are ſometimes produced between the plates, and ſometimes the clock has been ſtopped by their attraction to each other. Perhaps the plates ſhould not be circular, but ſomething like a lady's fan, when expanded, the bottom being a part of the curve deſcribed by the moving pendulum, with the ſides directed towards the point on which it moves.

This drawing and deſcription of his Pendulum Doubler was ſent me by Mr. Bennet of Wirkſworth, and is referred to at the end of Sect. XIII. of this work. If another inſulated flower-pot was connected with the plate B inſtead of the wire at the uppermoſt H, perhaps it might be kept in a ſtate of minus, or negative electricity, at the ſame time that the other flower-pot was kept in a ſtate of plus or poſitive electricity.



London, Published Jan.y 1.st 1800, by J.Johnson, St. Paul's Church Yard.

SECT. XIV.

DISEASES OF PLANTS.

I. Diſeaſes from internal cauſes. 1. *Diſeaſed irritability. Irritability derived from oxygen. Exhauſted by too great ſtimulus. Shade apricot flowers from the ſun. Much water after a hot day injurious. Irritability accumulated by leſs ſtimulus. Experiment on euphorbia. Habits of plants brought from the ſouth. Taken to America. In the bleeding ſeaſon. Vines in hot-houſes. Habits of plants. Irritability greater after being expoſed to much cold, leſs after much heat. Greateſt in the morning. Hybernating animals. Variation of heat contributes to health.* 2. *Eryſiphe mildew. A ſeſſile fungus. Give light and ventilation. Drain the land. Sow early. Rubigo, ruſt. Probably another fungus. Uredo frumenti. Blight.* 4. *Clavus, ergot. On rye, which it renders unwholeſome. Aſcribed to inſects by Duhamel.* 5. *Uſtilago, ſmut. Aſcribed to inſects by Linneus. Is probably owing to want of impregnation. How prevented.* 6. *Gangrena, canker. Affects apple-trees from old grafts. From wounds. Bind living bark on the wound. Or paint the alburnum.* 7. *Suffuſio mellita, honey-dew. If occaſioned by the aphis? Succeeded by a black powder.* 8. *Exſudatio miliaris, miliary ſweat. On vines in hot-houſes from too great heat in confined air.* 9. *Fluxus umbilicalis, ſap-flow. From wounds in ſpring, and after midſummer. Bind on ſponge. Strangulate with wire.* 10. *Secretio gummoſa, gum ſecretion. Bind on lead. Sponge, Indian rubber. Apply ſolution of green vitriol. Bind on a new bark.* II. Diſeaſes from external elements. 1. *Draught and moiſture.* 2. *Heat and cold. Shelter early bloſſoms from the ſunſhine.* 3. *Lightning. Injures trees and wheat fields. By deſtroying their irritability, like the ſtimulus of ſome poiſons. By burſting their veſſels. How to prevent.* 4. *Light. Etiolation of ſea-cale.* 5. *Of acid clay. Of ſterile ſand.* 6. *Noxious exhalations, from lead-works, and lime-kilns.* 7. *Poiſons of arſenic, muriatic acid.* 8. *Condiments. Alcohol. Opium. Sea-ſalt. Its uſe and effect on vegetables. Uſe in the worm of ſheep.* 9. *External injuries. Wound*

grape-ſtalks. Caprification. Pluck pears to ripen them. III. Diſeaſes from inſects. 1. *From their neſts and young. On roſes, on quince-bloſſoms, on aconite.* 2. *Aphis on peach trees. Slugs prefer withered leaves. Cows eat withered thiſtles. The poiſon of yew leaves. Hiſtory of the aphis. Means of deſtroying them. Aphidivorous larva and fly.* 3. *Caterpillars on apple-trees and gooſe-berries. Burn the leaves. Put a fringe round gooſeberry-trees. Deſtroy white butterflies. Cabbage caterpillars deſtroyed by ichneumon fly.* 4. *Inſects in hot-houſes. Smoke of ſulphur injurious to trees.* 5. *Beetles beneath the ſoil. Snails. Slugs. Roll turnips before ſun-riſe. Slugs prevented by lime or ſalt. Caught by a board. Fly on turnips. Roll them. Steep turnip ſeeds in liquid manure as in China.* 6. *Beetles. Fern-chaffer. Deſtroys crops of wheat. Sow wheat ſhallow. Roll it, or ſtrew ſalt in fine powder. Thrips phyſaphus on wheat. Corn butterfly. May-chaffers on hedges. Locuſt. Encourage hedge-birds, larks, rooks, hedge-hogs. Some caterpillars wholeſome to eat, others poiſonous. All very hardy and difficult to deſtroy.* IV. Deſtruction by vermin. 1. *Mice. Tuſſocks of wheat from their granaries. Encourage the breed of owls.* 2. *Water-rats like beavers, how driven from a fiſh-pond. They eat vegetables. Are attracted by ſcents. How to poiſon them. How to entrap them.* 3. *Moles never drink. Sometimes ſwim. Work before ſun-riſe. How to deſtroy them by traps.*

THE diſeaſes of vegetables may be divided into thoſe, which appear to originate from internal cauſes, thoſe from the external elements, and thoſe from the nidifications or depredations of inſects; to which may be added the depredations of other animals. We ſhall begin with diſeaſed irritability.

DISEASES FROM INTERNAL CAUSES.

I. 1. It has already been ſhewn, that the buds of vegetables are individual beings, and conſtitute an inferior order of animals; and that they poſſeſs irritability, and ſenſibility, and voluntarity, and have aſſociations of motion; as explained in Zoonomia, Vol. I. Sect. XIII. But as the three latter kinds of excitability are poſſeſſed in a ſo much leſs

leſs degree by vegetable buds, than by more perfect animals, we ſhall only conſider the diſeaſes of their irritability.

M. Girtannir endeavoured to ſhew, that animal irritability originates from the oxygen, which conſtitutes ſomewhat leſs than a third of the atmoſphere, which they breathe. And M. Van Uſlar has applied the ſame idea to vegetable life; and has endeavoured to ſhew, that their irritability alſo originates from the oxygen, which they acquire either by the reſpiration of their leaves, or by the abſorption of their roots. And indeed, as reſpiration is every minute neceſſary to animal life, there is reaſon to believe, that ſomething immediately neceſſary to the exiſtence of life is acquired by the lungs of animals from the atmoſphere rather than from the food, which they digeſt; and that this, which is believed to be the oxygen only, is mixed with the blood, and ſeparated again from it by the brain, and ſpinal marrow, after having undergone ſome change in the circulation or ſecretion of it.

In the ſame manner it is not improbable, but that the ſpirit of vegetation may have a ſimilar origin, probably from the uncombined oxygen of the air, reſpired by the upper ſurfaces of their leaves; and not from that, which is abſorbed by their roots in a more combined ſtate; and that this oxygen is again ſeparated from their juices by the ſenſorium, or brain, of each individual bud, after having undergone ſome change in the circulation or ſecretion of it. See Sect. IV. 1. 2.

The circumſtances attending vegetable irritability are ſimilar to thoſe belonging to the irritability of animals upon a leſs extenſive ſcale, as detailed in Zoonomia, Vol. I. Sect. XII.

When vegetable fibres have been long ſtimulated more than natural or uſual by increaſe of heat, the ſpirit of vegetation becomes exhauſted; and in conſequence a ſlighter degree of cold will deſtroy them; becauſe their fibres after having been long excited by a greater ſtimulus will ceaſe to act on the application of one, which is much

leſs; whence after hot days tender plants are more liable to be deſtroyed by the coldneſs of the night. Whence in more northern climates the gardeners ſhade their tender vegetables, as the flowers of apricots, in the ſpring-froſts from the meridian ſun, as well as from the coldneſs of the night; which is generally the greateſt about an hour before ſunriſe.

In the hot days of June 1798 I twice obſerved ſeveral rows of garden beans become quite ſickly, and many of them to die, from being flooded for an hour or two with water from a canal in the neighbourhood; which I aſcribed more to the ſudden application of too great cold, after being much enfeebled, or rendered inirritable, by the exceſſive heat of the ſeaſon, than to the too copious ſupply of water to the dry ground; to which ſhould be added, that ſome plants are more liable to be thus injured than others; as the ſtrawberries, young cabbage plants, and onions, which were in the ſame ſituation, received benefit and not deterioration by being thus occaſionally watered in that dry ſeaſon.

On the contrary, when plants have been long expoſed to a leſs ſtimulus of heat than natural or uſual, the ſpirit of vegetation becomes accumulated; and if they are too ſuddenly ſubjected to much greater heat, their too great increaſe of action induces inflammation, and conſequent mortification, and death; as occurs to thoſe people, who have had too much warmth applied to their frozen limbs. Experiments of this kind were inſtituted by Van Uſſar; he increaſed the irritability of euphorbia peplus and eſula by ſecluding light and heat from them; and, when he expoſed them to a meridian ſun, they became gangrenous, and died in a ſhort time.

This greater or leſs irritability of plants is to be aſcribed to their previous habits in reſpect to the ſtimulus of greater or leſs heat. Thus the times of the appearance of vegetables in the ſpring ſeem occaſionally to be influenced by their previouſly acquired habits, as well as by their preſent ſenſibility to heat. For the roots of potatoes, onions, will

will germinate with much leſs heat in the ſpring than in the autumn; as is eaſily obſervable, where theſe roots are ſtored for uſe; and hence malt is beſt made in the ſpring, as the barley will then germinate with a leſs degree of heat.

The grains and roots brought from more ſouthern latitudes germinate here ſooner than thoſe, which are brought from more northern ones, owing to their acquired habits. Fordyce on Agriculture. It was obſerved by one of the ſcholars of Linneus, that the apple trees ſent from hence to New England bloſſomed for a few years too early for that climate, and bore no fruit; but afterwards learnt to accommodate themſelves to their new ſituation. (Kalm's Travels.) Vines in grape houſes, which have been expoſed to the winter's cold, will become forwarder and more vigorous than thoſe, which have been kept during the winter in the houſe. (Kennedy on Gardening.) This accounts for the very rapid vegetation in the northern latitudes after the ſolution of the ſnows.

The increaſe of the irritability of plants in reſpect to heat, after having been previouſly expoſed to cold, is farther illuſtrated by an experiment of Dr. Walker's. He cut apertures into a birch-tree at different heights; and on the 26th of March ſome of theſe apertures bled, or oozed with the ſap-juice, when the thermometer was at 39; which ſame apertures did not bleed on the 13th of March, when the thermometer was at 44. The reaſon of this I apprehend was, becauſe on the night of the 25th of March the thermometer was as low as 34; whereas on the night of the 12th of March it was at 41; though the ingenious author aſcribes it to another cauſe. Tranſact. of the Royal Society of Edinburgh, V. I. p. 19.

There is an obſervation in Mr. Tull's work, which he ingeniouſly aſcribes to the acquired habits of plants. "By the extremely hard winter of the year 1708 or 1709, ſome lucern in Languedoc was killed, along with all the olive trees and walnut trees by the ſeverity of the ſeaſon; though I could not hear that one walnut tree was

killed in England. Perhaps thoſe in France having been accuſtomed to much hotter ſummers were unable to endure the rigour of the ſame winter, that did not deſtroy the ſame plants in England." Horſe-hoeing Huſbandry, Ch. XIII. p. 201.

By adapted experiments Medicus is ſaid to have found, that the irritability of plants is greater in the morning, leſs in the middle of the day, and much leſs in the evening. And Von Uſlar found, that their irritability in reſpect to their contractions was increaſed in cool and rainy weather. Obſerv. on Plants by Schmeiſſer. Edinb. So the parts of animals become more ſenſible to heat after having been previouſly expoſed to cold; as our hands glow on coming into the houſe after having for a while been immerſed in ſnow; and many inſects, and other animals, which hide themſelves in the earth, and ſleep during the winter, were obſerved by M. Spallanzani to diſappear at a ſeaſon, when the heat of the atmoſphere was much higher than in the ſpring, when they again made their appearance.

Hence it follows, that plants, which are kept in a warm room during winter, ſhould occaſionally be expoſed to cooler air to increaſe their irritability; as otherwiſe their growth in the ſpring is obſerved to be very tardy. Mankind for the ſame reaſon requires the perpetual variations of the heat of the atmoſphere to preſerve or reſtore the irritability, and conſequent activity, of the ſyſtem. Whence the health and energy of men are greater, and their lives longer, in this variable iſland, than in the tropical continents, which poſſeſs greater warmth, and leſs variation of weather.

2. Linneus in the Philoſophia Botanica has given names to but four internal diſeaſes, euriſiphe, mildew; rubigo, ruſt; clavus, ergot, or ſpur; and uſtilago, ſmut; to which may be added many others as deſcribed below.

Eryſiphe, a white mucor, or mould, or mildew, with ſeſſile tawny heads, with which the leaves are ſprinkled; this is frequent in humulus, hop; lamium, dead nettle; gallopſis, arch-angel; lithoſpermum,

thoſpermum, ſtone-ſeed; and acer, maple. This mucor is a plant of the fungus kind, which will grow without light, or change of air, like other funguſes; and with its roots penetrates the veſſels of the vegetables to which it adheres. But theſe veſſels are probably previouſly injured by internal diſeaſe. The methods of preventing or deſtroying it muſt conſiſt in thinning the plant, or removing thoſe in its vicinity, ſo as to admit more light, and greater ventilation, which may at the ſame time eradicate the mildew, and reſtore the internal vigour of the plant.

As the greater dampneſs of ſome land ſupplies one permanent cauſe of mildew, as well as its being too much overſhadowed by thick foliage, the methods of prevention muſt conſiſt in properly draining the land, and uſing drier kinds of manure, as coal-aſhes and bone-aſhes, as well as by thinning the crops. And laſtly, it is recommended to ſow early in the ſeaſon for the purpoſe of procuring forward crops; as this diſeaſe is ſaid more to injure late crops owing to the greater dampneſs of the ground in autumn.

3. Rubigo, ruſt, a ferruginous powder ſprinkled under the leaves, frequent in alchemilla, lady's mantle, rubus ſaxatilis, eſſula degener; and particularly in ſenecio or jacobæa; and eſpecially in a burnt woody ſoil.

This is probably another fungus ſimilar to the former, or to ſome kinds of lichen, which grows beneath the leaves of vegetables previouſly diſeaſed, and may probably be prevented or deſtroyed by expoſing the plant to more light, and greater ventilation, as in the mucor above mentioned.

An account is given by Mr. Lambert in the Tranſactions of the Linnean Society, Vol. IV. of a diſeaſe which may probably be ſomewhat ſimilar to the rubigo, which he calls uredo frumenti, or blight of wheat, and deſcribes it to be a fungus, which covers the ſtems of wheat in wet ſeaſons, when it is nearly ripe, ſo as to give the field an appearance of being covered with ſoot. The ſtem of the wheat is

ſaid to appear to be ſplit, and the growth of the plant to be much injured. He deſcribes the fungus to be linear-oblong, tawny-black.

4. Clavus, ergot, or ſpur, occurs when ſeeds grow out into large horns, black without, as in ſecale, rye, and in carex. This diſeaſe frequently affects the rye in France, and ſometimes in England, in moiſt ſeaſons, and is called ergot, ſpur, or horn-ſeed; the grain becomes conſiderably elongated, and is either ſtraight or crooked, containing black meal along with the white; and is ſaid to appear to be pierced by inſects, which are ſuppoſed to cauſe the diſeaſe.

Mr. Duhamel aſcribes it to this cauſe, and compares it to galls on oak-leaves; but this has not yet been eſtabliſhed by ſufficient obſervations. By the uſe of this bad grain amongſt the poor, diſeaſes have been produced, attended with great debility, and mortification of the extremities, both in France and England. Dict. Raiſon. Art. Siegle. Philoſ. Tranſact. Vol. LV. 106.

5. Uſtilago, ſmut, when the fruit inſtead of ſeed produces a black meal, as in wheat, barley, oats, ſcorzonera, tragopogon. Much is ſaid on this diſeaſe in the Dict. Raiſon of Bomare. Art. Bled, who recommends ſteeping the grain, before it is ſown, in brine; which is generally directed to have ſo much ſalt added to the water, as may increaſe its ſpecific gravity, till an egg will ſwim in it; or ſecondly, to ſteep the ſeed-wheat in lime water; or thirdly, which he thinks moſt efficacious, in an alkaline ley made by adding pot-aſh to lime-water.

In the ſyſtema naturæ of Linneus under the article Vermes, Zoophyta, Chaos uſtilago, there is a quotation from Munchhauſen, that the uſtilago is a black powder, which is found in the deſtroyed grains of barley, wheat, and other graſſes; and in the florets of tragopogon ſcorzonera. And that this powder being macerated in warm water for ſome days paſſes into oblong animalcules, hyaline in reſpect to colour, and playing about like fiſh, as may be ſeen by a microſcope; and

and are again mentioned in Linneus's diſſertation on the inviſible world.

There is an ingenious paper in the publications of the Bath Society, in which the author obſerves, that the ſmut in wheat only happens, when wet weather occurs at the time of the flowering of the wheat; which may burſt the anthers, and waſh away the farina. He thinks that ſteeping the wheat in brine or lime water is an ancient error, and can be of no uſe but to ſeparate light wheat from that which is good.

For he found ſmutty ears and good ones growing from the ſame root; and thence it could not depend on any contagious material, or inſects eggs, adhering to the ſeed; and in ſome even the ſame ear contained both ſound and ſmutty corns. And laſtly, that ſome of the corns had one end ſmutty, and the other ſound; and he concludes, that it muſt be owing to the want of impregnation from the defect of the farina fecundans; and that the putrefaction ſucceeded the death of the grain.

From the obſervations of Spallanzani on leguminous plants the probability of this opinion is much confirmed. He found that the ſeed was produced by the female organ of the plant, long before it was impregnated; which could not happen, till the flower was open, and the anther-duſt ripe. Whence it is eaſy to conceive, that for want of impregnation, or the vivifying principle, the wheat-corn muſt putrefy like the addle eggs of poultry, which are unimpregnated, and thence die, and in conſequence putrefy.

If this diſeaſe of ſmut ſhould become a ſerious evil, it might poſſibly be prevented by ſowing the grain in diſtant rows; and after ſome days ſowing other rows between them of the ſame, or of another kind of wheat; by which means, if wet weather ſhould deſtroy the anthers of one ſet of rows, the alternate ones might ſupply farina to their ſtigmas, if the weather became favourable. See Sect. XVI. 8. 2.

Wheat diſcoloured by ſmut may be waſhed, and readily dried on

a malt kiln, and may be thus eaſily made marketable and equally good; for the living grain will not abſorb much water in a ſhort time; or it may be mixed with clean ſand, and after being well agitated the ſand may be ſeparated by a riddle; and if neceſſary the ſame ſand may be waſhed and dried for repeated uſe.

6. Beſides the four internal diſeaſes above ſpoken of, as mentioned by Linneus; and the uredo of Mr. Lambert, there are probably many others, which have not yet been ſufficiently attended to, as the canker, gangrena; the honey-ſweat, exſudatio mellita; the miliary ſweat, exſudatio miliaris; the ſap-flow, fluxus umbilicalis; and the gum ſecretion, ſecretio gummoſa.

The canker, which may be termed gangrena vegetabilis, is a phagedenic ulcer of the bark; which is very deſtructive to apple-trees, and pear-trees, as it ſpreads round the trunk or branches, and deſtroys them.

Mr. Knight has obſerved this diſeaſe to be moſt frequent and fatal to thoſe trees, the fruit of which has been long in faſhion; as they have been perpetually propagated for a century or two by ingrafting; which he believes to be a continuation of the old tree, though nouriſhed by a new ſtock; and that the canker is thus a diſeaſe of old age, like the mortification of the limbs of elderly people, and ariſes from the irritability of a part of the ſyſtem.

But it ſeems more probably to be an hereditary diſeaſe, as the buds of trees being a lateral progeny, and more exactly reſembling their parents, muſt be more liable to the diſeaſes gradually acquired or increaſed by the influence of ſoil or climate; and have not the probability of improvement, which attends the progeny of ſexual generation.

It is nevertheleſs frequently produced on trees by external violence, as by a ſtroke with a ſpade by a careleſs labourer, who is digging near them; but this probably may more eaſily affect the old grafts above mentioned. When a deſtruction of the bark is thus produced by external

ternal violence, it may poſſibly be cured by the application of a piece of living bark from a leſs valuable tree, bound on as mentioned in the next article, and in Sect. XVII. 3. 10.

The edges of theſe gangrenous ulcers of the bark ſhould be nicely pared with a knife, ſo as to admit the air, and to prevent the depredations of inſects and the lodgment of moiſture, which might promote the putrefaction of the ſtagnant juices, and ſpread the gangrene; this ſhould be ſo managed as only to cut away the dead lips of the wound, but not ſo as in the leaſt to injure the living bark. Some thick white paint may then be ſmeared on the naked alburnum or ſap-wood on a dry day, which may prevent inſects from inſerting their eggs into it, and produce maggots, which erode and deſtroy the wood; and may alſo prevent the dews and rains from rotting it. The paint ſhould nevertheleſs be ſo ſpread, as not to touch the edges of the wound; as it might injure their growth by its poiſonous quality; a quarter of an ounce of ſublimate of mercury, hydrargyrus muriatus, rubbed with about a pound of white lead paint, might render it more noxious to inſects. See Sect. XVII. 3. 9. and 10.

7. The honey-dew, which may be called ſuffuſio mellita, conſiſts of a ſaccharine juice, which I have ſuppoſed to be exſuded from the tree by the retrograde motions of the cutaneous lymphatic veſſels, connected either with the common ſap-veſſels deſcribed in Sect. II. or with the umbilical veſſels deſcribed in Sect. III. 2. 8. inſtead of its being carried forwards to increaſe the growth of the preſent leaf-buds, or to lay up nutriment for the buds, which are in their embryon ſtate; and may thus be compared to the diabœtes mellitus, or to the ſweating ſickneſs of the laſt century.

The ſaccharine and nutritious quality of the honey-dew, ſimilar to that of the ſap-juice, which riſes in the vernal months from the birch and maple, is evident from its taſte; and from the number of bees and ants, which are ſaid to feed on it, when it appears on ſome trees;

trees; and which ſhews, that its exſudation muſt be conſiderably injurious to the tree, as before mentioned in Sect. VI. 6. 3.

In a paper written by the Abbé Boiſſier de Sauvages, he deſcribes two kinds of honey-dew; one of which he concludes to be an exſudation from the tree, and the other he aſſerts to be the excrement of one kind of aphis, which the animal projects to the diſtance of ſome inches from its body on the leaves and ground beneath it; and which he believes the animal acquires by piercing the ſap-veſſels of the leaf. This paper is detailed in Wildman's work on Bees, p. 46. The circumſtances are diſtinctly deſcribed, and by ſo great a philoſopher as Sauvages of Montpellier, that it is difficult to doubt the authenticity of the fact. But that a material ſo nutritive ſhould be produced as the excrement of an inſect is ſo totally contrary to the ſtrongeſt analogy, that it may nevertheleſs be ſuſpected to be a morbid exſudation from the tree; though theſe inſects might occaſionally prey upon it, and void it almoſt unchanged at thoſe ſeaſons, becauſe the inſects continued ſome months after the honey-dew ceaſed, and before it commenced, as mentioned below; and the upper ſurfaces of the leaves became covered with a black powder, which had before been covered with the honey-dew. And laſtly, becauſe on other trees, as on the peach and nectarine, at other ſeaſons of the year, no honey-dew is perceived, though the aphis much abounds to the great injury of the trees.

Early this morning, June 18, 1798, I obſerved a remarkable honey-dew on an extenſive row of nut-trees, corylus avellana, which grow by the ſide of a pond of water; the ſun ſhone bright, and the upper ſurface of every leaf, which was illumined by the ſun, was covered with a viſcid juice, which taſted as ſweet as diluted honey. From many of theſe leaves large drops hung from the point, and during that day and the following one much of this honey dropped down ſo as to moiſten the gravel walk beneath the branches of every tree, and ſeemed more fluid as the ſunſhine became warmer; and the leaves,

leaves, which were concealed from the ſun, appeared to have leſs of the honey-dew, and ſome of them none of it.

How long this honey-dew had continued before I obſerved it, I cannot tell, but probably many days, as the weather was then, and had been uncommonly dry and warm, and ſhining; and after two or three days, when the weather changed, the morbid exſudation, if ſuch it was, or the excrementitious depoſition of this viſcid honey, became checked and gradually diſappeared.

Beneath every leaf of this extenſive hedge of filberts I diſcerned fifty or a hundred aphiſes of all ſizes, and many of them had wings; but I could not perceive, that any of them had been on the upper ſurfaces of the leaves, where the honey only exiſted; nor were any bees, or butterflies, or ants, about theſe leaves; on which they muſt have adhered, if they had ſettled; which poſſibly they were aware of, as a hive of bees was at no great diſtance.

M. Duhamel obſerved a ſimilar ſweet juice drop in ſuch quantity from willows by the ſide of a river in very hot and dry weather, that children were buſy in catching or gathering it, and that it taſted like manna, but was more agreeable. He alſo mentions its dropping from nut-trees. Phyſique des arbres, Vol. I. p. 150. M. Reneaume, in the Memoires of the Academ. des Sciences, obſerved a ſimilar exſudation from the maple, and ſycamore; and adds, 1. That it was unctuous and ſweet. 2. That it was in the greateſt quantity on the leaves expoſed to the ſun, which appeared wet on their upper ſurfaces; and that it was not ſeen before ſun-riſe. 3. That bees collected it as anxiouſly as common honey. 4. And that ſome leaves died, whoſe diſcharge was very great. 5. That it exiſted in a very dry and hot ſeaſon. But neither of theſe philoſophers ſpeak of its being attended by the aphis.

The aphis this year was uncommonly numerous, the leaves of the peach and nectarine trees were half of them deſtroyed by this pernicious inſect, and became bliſtered and curled I ſuppoſe by their punc-

tures; which were made ſome weeks earlier in the year, and by an aphis without wings, and differing ſomewhat in their ſhape, but without any appearance of honey-dew on thoſe trees. But I could not diſcover any punctures or other diſeaſe of the leaves of theſe nut-trees, and therefore doubt whether theſe inſects, though ſo numerous on the under ſurface of every leaf, could be the cauſe of the morbid exſudation, if ſuch it was, on their upper ſurfaces; and the more as I could not diſtinguiſh, that they preyed upon the honey thus produced; and I afterwards obſerved that they continued in immenſe numbers under every leaf, when the weather became cooler, and moiſter, and the honey-dew ceaſed to be viſible. But after a few weeks I obſerved the upper ſurface of every leaf became covered with a black powder like ſoot; whether this was a new material, or remained after the exhalation of the honey-dew, I did not determine by experiment. But if both the honey-dew and this ſubſequent black powder on the upper ſurfaces of the leaves, were the excrement of the aphis on the under ſurfaces of the leaves over the former, or owing to an exſudation from the tree, muſt be determined by further obſervations.

But as a ſecond period of ſap-flow is believed to exiſt about midſummer, or a depoſition of vegetable nutriment for the new buds, as deſcribed in Sect. III. 2. 8. there is reaſon to ſuſpect, that the honey-dew is owing to the inverted action of the external lymphatics occaſioned by the debility induced by the continued heat, and perhaps to the moiſture of ſituation. Whence the nutritive fluid is thrown upon the external habit inſtead of being applied to nouriſh the new buds, or to be laid up as a reſervoir for their uſe. And that if it be voided by the aphis, it is owing to their puncturing the ſap-veſſels with the fine proboſcis, which they poſſeſs, at this ſeaſon only, or in a diſtempered ſtate of the tree, and drinking more of it than they are able to digeſt. For a further hiſtory of this inſect ſee No. 3. 2. of this Section.

8. Exſudatio

8. Exſudatio miliaris, miliary ſweat, appears to be produced by too great and continued heat, as it exiſts on vines in hot-houſes, which are kept too warm, or too cloſe in reſpect to their ventilation.

This ſecretion has not the ſweet taſte like that of the honey-dew, but conſiſts of mucilage; which, as the watery part evaporates by heat, remains on the plant in very ſmall round hard globules, like millet ſeeds, whence their name. I once witneſſed a very ſimilar appearance of minute hard round globules on the ſkin in a miliary fever, which eaſily were rubbed off with the finger; and were probably occaſioned, as in this vegetable diſeaſe, by too great heat, and the excluſion of air, as deſcribed in Zoonomia, Vol. II. Claſs 2. 1. 3. 12.

In the evaporation of perſpirable matter, which in its diſeaſed ſtate may be more mucilaginous than natural, in confined bed-rooms or hot-houſes, I ſuppoſe, the aqueous part only is exhaled, and the mucilaginous part remains in the form of a globule; in the ſame manner as ſtalactites are formed on the roofs of caverns from a ſolution of calcareous earth in water, ſimply by the evaporation of the water.

9. Fluxus umbilicalis, ſap-flow, this occurs, when the alburnum or ſap-wood of trees is wounded in the vernal months, as in birch and maple, deſcribed in Sect. III. 2. 2. and conſiſts of a ſaccharine and mucilaginous fluid ſimilar to the honey-dew, or ſuffuſio mellita; and is often very troubleſome, when vines in hot-houſes are pruned too late in the ſeaſon, as the whole branch is liable to bleed to death, owing thus to the loſs of the ſap-juice, which ought to be employed in nouriſhing the young buds, and expanding their leaves.

When ſome perennial plants have riſen but a certain height from the ground, if their ſtems are much wounded, or cut off, the roots are liable to bleed to death from this diſcharge of the umbilical fluid, or ſap-juice, which ought to have nouriſhed and expanded the new buds and foliage; as may be ſeen in cutting down the heracleum ſpondylium, cow parſnep, in April; and on this account it has been

recommended to mow down thiſtles, and other weeds, which are troubleſome from their numerous increaſe, early in the ſpring; as many of them will then die, and the reſt be much weakened by the ſap-flow, which attends their wounds at that ſeaſon.

In reſpect to trees another period of ſap-flow is ſaid to exiſt, when the new buds are forming after Midſummer, as ſpoken of in Sect. III. 2. 8. Whence wounds at this ſeaſon alſo muſt be injurious; where this loſs of ſap-juice occurs in hot-houſes various applications have been recommended by gardeners. I ſuſpect that a bit of ſponge bound upon the end of the cut branch, or on the wound, by means of ſome elaſtic bandage, muſt be the moſt certain application; or a wire twiſted round the end of the branch cut off, ſo tightly as to ſtrangulate the whole circulation of juices, and conſequently deſtroy the part above the ligature.

10. Secretio gummoſa, gum ſecretion, a morbid production of gum, which differs from the ſap-juice above deſcribed, as it contains no ſaccharine quality, though like the former it exſudes from the wounded alburnum of deciduous trees; whether the wound be originally cauſed by internal diſeaſe, or by external violence, as mentioned in the gangrene of the bark above deſcribed.

Where this happens to cherry-trees, prunus ceraſus, a gum exſudes like gum arabic; which in dry weather hardens, as it adheres, and thus prevents the further diſcharge of this nutritive material; otherwiſe the tree weeps away its life, periſhing from deficient nouriſhment. In ſimilar manner a reſin is emitted from the injuries or wounds of pine-trees, and ſome other evergreens, with great injury to the growth, or the deſtruction of the tree.

This exſudation of the gum or reſin of trees, as it happens chiefly in ſummer, is probably a part of nutritious fluid deſigned for the new buds, which in moſt deciduous trees are formed about this time, and ſhould be prevented from continuing to flow by binding on the part, previouſly made ſmooth by a knife, a metallic plate, as of the lead

in

in which tea is wrapped, ſo as to prevent rain or dew drops from diſſolving the indurated gum. A bit of ſponge, or of ſoft leather, or of Indian rubber, caoutchouc, might be bound on under the lead, till the wound is healed. Might not a ſtrong ſolution of green vitriol in water, or ſome ink, if applied to the extremities of theſe bleeding veſſels, ſtimulate them into contraction, and prevent the further effuſion of gum?

Another method might be worth trial, which is mentioned in Sect. XVII. 3. 10. A piece of bark from a ſimilar tree of inferior value might be cut out, ſo as nicely to fit the wounded part, after its edges were nicely ſmoothed, and might be tied on by a proper bandage, as the liſting cut from the edges of cloth, or flannel, ſo that its elaſticity might ſecure a perpetual preſſure without injury.

II. DISEASES FROM EXTERNAL ELEMENTS.

1. In climates liable to inceſſant rains or perpetual drought for a length of time many diſeaſes of vegetables muſt originate from the exceſs of moiſture, or to the want of it; which are not very frequent in this country. In moiſt ſeaſons the leaf-buds of plants, as of graſs and corn, as well as of trees and perennial vegetables, grow too luxuriantly; and the flowers and conſequent fruits or ſeeds are later, and contain more aqueous, and leſs mucilaginous and ſaccharine matter.

On the contrary, in dry ſeaſons the leaf-buds are leſs vigorous, and therefore in leſs quantity, as the crops of hay, and the quantity of ſtraw; but the fruits and ſeeds ripen earlier, and are of more grateful flavour, and more nutritious.

2. The effect of heat on vegetation is ſpoken of in Sect. XIII. 2. 2. The exceſs of that element is ſeldom much injurious to the vegetation of this country, unleſs it may contribute to increaſe the dryneſs of the ſoil, when there is a ſcarcity of moiſture. But the de-

fect of the element of heat, or in common language exceſs of cold, is frequently deſtructive to the early ſhoots of the aſh, fraxinus, and to the early bloſſoms of many fruit-trees, as apples, pears, apricots; as theſe are either more ſucculent, or have leſs irritability, or more ſenſibility; on both which accounts they are more liable to be diſeaſed by cold.

The blights occaſioned by froſt generally happen in the ſpring, when cold nights ſucceed to warm ſunny days, as the living power of the plant has then been previouſly exhauſted by the ſtimulus of heat, and is therefore leſs capable of being excited into the actions, which are neceſſary to vegetable life, by the greatly diminiſhed ſtimulus of a freezing atmoſphere.

In ſome northern climates, where the long ſunny days ſucceed the diſſolving of the ſnows, as in Denmark and in Ruſſia, the gardeners are ſaid to ſhelter their wall-trees from the meridian ſun in the vernal months; which preſerves them from the cold of the ſucceeding night; and by preventing them from flowering too early avoids the danger of the vernal froſts.

The deſtruction of the more ſucculent parts of vegetables, as their early ſhoots, and that eſpecially when expoſed to froſty nights, was ſpoken of in Sect. XIII. 2. 2. and can only be counteracted by covering them from the deſcending dews or rime by the coping-ſtones of a wall, or matts of ſtraw.

3. The blaſts occaſioned by lightning are more frequent, I believe, than is uſually ſuppoſed; as I am informed by thoſe, who purchaſe extenſive woods, that very many trees on being ſawed through are found cracked, and much injured by lightning. I had laſt year a ſtandard apple-tree, and a tall apricot-tree, in full leaf blaſted at the ſame time by lightning, as was believed. They both loſt all their leaves; the apple-tree nevertheleſs put out a new foliage, and recovered, and bore fruit this year; but the apricot, which was nailed to a high wall, never ſhewed any returning life.

Mr.

Mr. Tull aſcribes one injury to the health of wheat plants, and frequently their death, to lightning; the effects whereof, he ſays, may be obſerved by the blackiſh parts or patches viſible in a field of wheat, eſpecially in thoſe years which have more thunder-ſtorms than uſual, and adds that againſt this there is no remedy.

The erection of frequent metallic points could alone ſecure a garden or field from this misfortune; which probably occurs more frequently on damp ſituations, than on dry ones; as mentioned in the account of Fairy Rings in Botanic Garden, Vol. I. note XIII.

The manner in which lightning deſtroys the life of vegetables may be ſimilar to that, in which it deſtroys animal life; which is I ſuppoſe by its great ſtimulus exhauſting the ſenſorial power in the violent action it occaſions, and thus producing total inirritability to the common ſtimuli, which ought to excite the vital actions of the ſyſtem; ſimilar to which, though with leſs expedition, ſeems to be the effect of ſome poiſons on the animal ſyſtem, as the diſtilled water of lauro-ceraſus, a ſolution of arſenic, the contagious matter of fevers, and even a common emetic; all which by their ſtrong ſtimulus ſeem almoſt inſtantaneouſly to render the ſtomach, and other parts of the ſyſtem, nearly or entirely inirritable, or diſobedient to their natural ſtimuli.

It may alſo affect vegetables in another way ſimilar to that, which probably alſo happens, when their young ſucculent ſhoots are frozen; that is, by burſting their veſſels, as it paſſes through them, by its expanſive power; as happens to the large branches of ſome trees, and to ſtone-buildings, and other bad conductors of electricity, when they are ſtruck with lightning.

The expanſive power of electricity is not only ſhewn by trees and towers being rent by lightning, but by the ſound, which ſucceeds the paſſage of it through air; ſince a vacuum, or nearly a vacuum, in reſpect to air muſt previouſly be made by the preſence of the electric fluid; and the ſides of this vacuum ruſhing together, when the

ſtream has paſſed, occaſions the conſequent vibrations of the air, which conſtitute ſound, whether in the audible ſpark of electricity, or the tremendous craſh of thunder. See Sect. XIII. 3.

4. The element of light, as well as that of heat, is neceſſary to vegetation. In this climate they both ſeem in general to be injurious only by their defect, and ſeldom by their exceſs. But as light acts as a ſtimulus on the more irritative or ſenſitive parts of plants, which appears by the expanſion of many flowers, and of ſome leaves, when the ſun ſhines on them; and by the nutation of the whole flower, as of the ſun-flower, helianthus; and by the bending of the ſummits of all plants confined in houſes towards the light; there may be diſeaſes owing to the exceſs of this ſtimulus, which have not been attended to; to prevent which the flowers of tragapogon ſalſafi, and of other plants, cloſe about noon. Other unobſerved diſeaſes may be owing to a defect of the ſtimulus of light; as a mimoſa, ſenſitive plant, which I had confined in a dark room, did not open its foliage, though late in the day, till many minutes after it was expoſed to the light.

The exceſs of light has not been obſerved to be attended by vegetable diſeaſes in theſe more northern latitudes; but the diſeaſe produced by the deficiency of it, which is termed etiolation, or blanching, has been ſucceſsfully uſed to render ſome vegetable leaves and ſtalks eſculent by depriving them of much of their acrimony, and of their coheſion, as well as of their colour; as is ſeen in the blanching of celery, apium; endive, cichorium; cinara, cardoon; ſea-cale, crambe.

The following method of the growth and etiolation of ſea-cale is tranſcribed from the letter of a friend; to which ſhould be added, that the young heads of this vegetable without blanching are equal or ſuperior to moſt kinds of brocoli, braſſica. "Sea-cale ſeed ſhould be ſowed the latter end of March or beginning of April in drills, and then earthed up. In autumn it ſhould be tranſplanted into high beds, one row of roots in a bed, about a foot aſunder, and in the winter

winter it ſhould be covered up. It muſt be kept dry, that is, the beds made in the drieſt ground; it is not fit to be eaten till the third year after it is ſowed. The year before it is eaten it muſt be covered up in the beginning of winter, firſt with ſtable dung, which may be kept from preſſing on it by a few ſticks placed like a cone over each root; then with long litter two or three feet high; the higher the better, becauſe the more it is forced, the earlier it is fit to be gathered, and the whiter it will be. It is to be gathered about the beginning of January, and ſo on till May, one bed being kept under another. It ſhould be boiled and ſent up on toaſt like aſparagus, and is an excellent vegetable, and at an early ſeaſon."

5. The earth, on which vegetables inſert their roots, ſometimes preſents noxious materials to their abſorbent ſyſtem, as the acidity of ſome clays; into which when the roots of ſome fruit trees penetrate, they are ſaid to loſe their health, as mentioned in Sect. II. 9. by the death or decay or their root-fibres.

Pure ſiliceous ſands alſo prevent vegetation from their containing no carbonaceous matter, and by their ſo readily permitting the dews and rains to exhale from them, eſpecially in hotter climates, where they conſtitute a moving ſurface unfriendly to all organized life.

6. There are alſo noxious exhalations diffuſed in the atmoſphere in the neighbourhood of ſome manufactories; which are ſaid to injure the growth or deſtroy the life of vegetables; as the ſmoke from the furnaces, in which lead is ſmelted from the ore, from potteries, and from lime-kilns; to which may be added the marine ſalt, or marine acid, which abounds in the too great vicinity of the ſea.

To theſe belong the experiments of Dr. Peſchier of Geneva, who immerſed ſeveral plants in vapours of nitrous acid, of volatile alkali, and of ether, to the great injury or death of the plants. Journal de Phyſique par Delametherie, T. ii. p. 345.

7. Unwholeſome or poiſonous materials may be applied to vegetables ſo as to diſeaſe or deſtroy them; as their abſorbent ſyſtems like thoſe

thoſe of animals are liable to imbibe many noxious materials, as mentioned in Sect. II. 8. A ſlight ſolution of arſenic, ſprinkled on a peach-tree in the ſpring, deſtroyed the branches which received it. A ſolution of liver of ſulphur was equally fatal to the branches of a nectarine-tree, and alſo oil of turpentine.

Mr. Von Uſlar affirms, that watering plants with a due quantity of oxygenated muriatic acid will increaſe their irritability; and if carried beyond a certain degree will injure or deſtroy the vegetable by giving it too much oxygen; which is known in due quantity to be a ſalutary material, and the moſt neceſſary of all others to vegetable as well as to animal life.

8. There are materials called condiments, which are believed to poſſeſs ſtimulus without nutriment in reſpect to animal bodies, as ſpice, ſalt, bitters, as the hop, and probably opium and vinous ſpirit. Theſe when taken into the ſtomach increaſe its activity, and render the animal for a time fat, and even ſtrong; but as all increaſe of ſtimulus, beyond what is natural, is followed by debility; after a time the animal becomes weak, and emaciated; and enervated in mind as well as body; as is uniformly ſeen in thoſe who are addicted to the uſe of much beer and wine, or of opium; and in a leſs degree where ſpice, or ſalt, or bitters, are taken in too large quantity.

What then ſhall we ſay to the uſe of common ſalt in agriculture? as it is a ſtimulus, which poſſeſſes no nouriſhment, but may incite the vegetable abſorbent veſſels into greater action; it may in a certain quantity increaſe their growth by their taking up more nutriment in a given time, and performing their circulations and ſecretions with greater energy. In a greater quantity its ſtimulus may be ſo great as to act as an immediate poiſon on vegetables, and deſtroy the motions of the veſſels by exhauſting their irritability.

After a time I ſuſpect vegetables will always be liable to diſeaſe from this ſtimulating innutritive material; and that though it may increaſe the early growth of the plant, it will injure its flowering or

ſeed-

ſeed-bearing; and that hence, if it be uſed at all, it ſhould be a little before the time, that the plant would acquire that part of its growth, which is wanted. Thus if the herb or young ſtem only be wanted, as in ſpinage, mercury, aſparagus, apply ſalt early; if the flower be wanted, as in brocoli and artichoke, or in tulip or hyacinth, moiſten them with a ſlight ſolution of ſalt, when the flower-bud is formed. When the fruit or ſeed is wanted, as in melons or cucumbers, or peas and beans, apply the ſolution of ſalt ſtill later, and at all times with rather a parſimonious hand. See Sect. X. 7. 4.

Similar to this, where animals diſeaſed with ſuperabundancy of fat are required, it is cuſtomary, I am told, to feed poultry for the London markets by mixing gin and even opium with their food, and to keep them in the dark; but they muſt be killed as ſoon as their corpulency is formed, or they ſoon become weak, and emaciated like human drunkards. And in ſome countries, as in Languedoc in France, the livers of geeſe and ducks are required to be enlarged and diſeaſed; as they are reckoned a dainty by modern epicures, as well as by the ancient ones, who ſpeak of the tumidum jecur anſeris; and for this purpoſe the animals are kept in the dark, and crammed with more than their natural quantity of nutriment; but are ſaid to become lean, and to die, if not killed as ſoon as this diſeaſe is produced.

It is nevertheleſs to be obſerved, that ſea-ſalt as well as other ſtimulating condiments may be advantageouſly uſed as medicines, though injurious as common food. Thus it is aſſerted by Baron Schulz in the communications to the board of Agriculture, Vol. I. Part III. and IV. p. 318, that it deſtroys the faſciola hepatica, or flewk-worm in ſheep. Some have recommended one ounce of ſalt to be given every day diſſolved in water, but it is probable, it might be uſed with greater advantage, if hay was moiſtened with the ſolution, which would thus at the ſame time ſupply them with better nouriſh-

ment than generally falls to the lot of theſe diſeaſed ſheep, on ſuppoſition that they would eat it.

The rot of ſheep, I ſuſpect, ariſes from the inactivity of the abſorbent veſſels of the liver of that animal; whence the bile is too dilute, eſpecially in moiſt ſeaſons; whence the flewk-worm, as I have ſeen in the ſhambles, inhabits the common bile-duct, and at length erodes the liver, cauſing ulcers; which from the ſympathy of the lungs with the liver occaſions a cough, and a hectic fever from the abſorption of the matter. Hence the ſalt by its additional ſtimulus may render the bile leſs dilute by promoting a greater abſorption of its aqueous parts, as well as a greater ſecretion of it; which however I ſuſpect would be much more efficacious, if about ſixty grains of iron-filings made into a ball with flour was given every morning for a week along with the ſalt, as further explained in Zoonomia, Part III. Art. 4. 2. 6. 4.

Since writing the above account of common ſalt as a condiment, and the probable conſequences attending the uſe of it, I have met with ſome experiments publiſhed by Lord Kaimes in his Gentleman Farmer, which ſeem much to confirm the preceding account. He watered ſome Jeruſalem artichokes, helianthus tuberoſus, which were planted in ſeparate pots, with a ſolution of fixed vegetable alkali, others with volatile alkali, others with weak lime water, others with ſtrong lime water, others with putrid urine, and laſtly others with water impregnated with putrid animal and vegetable ſubſtances, I ſuppoſe as they exiſt in a dunghill. All theſe ſaline ſolutions at firſt encouraged the growth of the reſpective plants, ſo as much to ſurpaſs thoſe in the pot, which was moiſtened only with common water, as a ſtandard to compare the others to; but by additional quantities of the ſolutions, they all, except the laſt, gradually loſt their vigour, and periſhed in the end, as I ſuppoſe, by the exceſs of ſtimulus.

There

There is alſo an experiment in the works of Mr. Anderſon, which ſeems to ſhew, that common ſalt poſſeſſes no nutritive quality adapted to vegetable growth; and that in ſome ſoils, or to ſome vegetables, it would ſeem not even to act as a ſtimulus or condiment. He marked out a circle of ſix feet diameter in the middle of a graſs field, which he diſtinguiſhed by driving a ſtake in the centre; on this circle he ſtrewed common ſalt, ſo as to lie nearly an inch thick on the ground. The graſs ſprung up in this circle in the ſame manner as in the other parts of the ground, and the place could only be diſtinguiſhed by the ſtake, though it was left there for ſome years. Encycl. Britan. Art. Agriculture. See Sect. X. 7. 5. of this work. This experiment is worthy to be repeated, leſt there might have been ſome miſtake attending it; as ſo many authors have given experiments with contrary reſults; and as ſome other neutral ſalts were ſhewn to promote vegetation in the experiments of Dr. Home.

9. Some diſeaſes from external violence have been already mentioned in this Section, in which the injury is a remote rather than a proximate cauſe of the diſeaſe, as in the canker ſometimes, and the ſap-flow, and gum-ſecretion. But ſome other diſeaſes from external violence have been purpoſely produced, as well as that of etiolation, and turned to advantage; as the bunches of grapes, which have acquired their full ſize, are ſaid to ripen ſooner, if the ſtalk of the bunch be cut half through. Tournefort ſays, that the figs in Provence and about Paris ripen ſooner, if the buds be wounded with a ſtraw dipped in olive-oil. And laſtly, the figs in the iſland of Malta are made to ripen ſooner by caprification; as ſpoken of in Botanic Garden, Vol. II. note on Caprificus. And it may daily be remarked, that thoſe apples and plums ripen ſooner, which have been wounded by inſects; and that pears will ripen conſiderably ſooner, if they be immaturely plucked from the tree, which muſt be eſteemed injurious to the life of the pear; and as the converſion of auſtere acid juices of fruit into ſugar in the proceſs of ripening may be in part che-

mical, it may proceed more haſtily, when the life of the fruit is impaired or deſtroyed; as ſeems to occur in the drying of germinated barley, and in baking pears, as well as in bruiſing apples for the purpoſe of making cyder; which laſt effect might probably be much improved by the addition of warmth.

III. DISEASES OCCASIONED BY INSECTS.

1. Among the diſeaſes of plants Linneus adds in his Philoſophia Botanica the neſts of thoſe inſects, which depoſit their eggs in plants; whence a variety of excreſcences. Theſe are, 1. The galls of oak, of ground-ivy, ciſtus, trembling poplar, willow, and hawk-weed. 2. Bedequar of roſes, or briar-balls. 3. Follicles of piſtachia, and black poplar. 4. Contortions of ceraſtium, chick-weed, veronica, ſpeedwell, and lotus. 5. Scales of firs, willows, and roſes.

He then adds, that the duplicature and prolification of flowers is often occaſioned by inſects, as common chamomile, matricaria, is thus made proliferus; and that carduus caule criſpo bears larger florets, with the piſtils growing into leaves, by the wounds of inſects.

It muſt be obſerved, that theſe excreſcences on the leaves of ſome plants, or mutation of their manner of growth, are not always the conſequence of a ſimple wound or puncture of the inſects, but of the depoſition of their eggs, or young offspring; which afterwards continue to ſtimulate the growing plant into unnatural motions, and conſequently into unnatural growth; like the inflammation and conſequent new granulations of fleſh in the wounds of animal bodies; which, if the ſkin is prevented from ſpreading over them, will riſe into large ſubſtances of fungous fleſh; or beneath the ſkin, where it is looſe, as in wens.

Many flowers are deſtroyed or rendered unprolific by the depredation of inſects, as roſe-buds by the cynips; and I remember obſerving one dry ſummer, that every bloſſom of a large quince tree was

was pierced by a fly, and rendered unprolific before the bloſſoms had opened. I have alſo ſeen the hood of the aconite, ſo replete with an acrid juice, pierced by inſects to plunder it of its honey.

2. The curling of the leaves of nectarine, and peach, and cherry-trees, with the cells or bladders on their ſurfaces, are formed in conſequence of the wounds inflicted by the aphis; in the ſame manner as the galls and bedeguars on the oak and ſweet-briar by other inſects, but without their nidification or the depoſition of their eggs; though from the ſudden and general appearance of theſe injuries they have been aſcribed to blights from inclement weather.

Some obſervers have believed nevertheleſs, that theſe affected leaves were previouſly out of health; which occaſioned them to ſupply a proper ſituation for thoſe inſects, which moleſt them; as I have frequently obſerved, that ſnails or ſlugs eat thoſe leaves, which have been plucked from cucumber plants, and are beginning to wither; in preference to thoſe, which are growing in perfect health.

Mr. Lawrence relates, that in June the leaves of ſome of his wall-pear-trees were much injured by a hail-ſtorm, which leaves were afterwards blighted, and become full of tumours from inſects; and the pears, which were then as large as walnuts, all periſhed. On this Mr. Bradley remarks, that inſects generally lay their eggs on the dead or putrefying parts both of vegetable and animal bodies; and adds a conjecture, that the parent inſects may circulate in the juices of the plant, which however is not probable, as though microſcopic animals have been diſcovered in the ſtagnating juices of animal bodies, as in the puſtules of the itch, and in the fæces in the dyſentery, and even in the ſemen, which may have ſtagnated in the veſiculæ ſeminales; yet no ſuch animalculæ have, I believe, ever been detected in recent blood, or any recent ſecretions from it.

A predilection for ſome withered leaves appears alſo in larger animals as well as in inſects; cows will eat young thiſtles, a few hours after they are cut down, as their prickles become flaccid; and horſes

refuſe

refuſe the young ſhoots of yew-trees, as they grow; but will eat them when they are cut off, and begin to wither; and on that account loſe a part of their acrimony; though there is ſtill often ſufficient poiſon within them to deſtroy the animal. And it is even probable, that when the leaves of yew are withered to a greater degree, their poiſonous acrimony becomes ſo far deſtroyed, that they ceaſe to be deleterious to horſes; ſo that in Heſſe in Germany it is cuſtomary in the winter to crop the young ſhoots of yew-trees, and mixing them with other provender to give them as common food to horſes. See Anderſon on Agriculture, Vol. III. p. 590.

On this account if wall-trees are frequently watered by an engine, ſo as to moiſten their leaves or branches as well as the ground at their roots on the dry days in ſpring, by which they will be kept in vigorous growth, I was told, that they would totally or nearly eſcape the depredations of inſects; but I found by an experiment well conducted on three trees, that this management had no effect; and I alſo obſerved in the ſpring and ſummer of this year, 1798, which ſeems to have much favoured the production of the aphis, that they attacked the moſt healthy leaves of peach and nectarine trees, as well as the others; and that plums, cherries, black currants, and many other trees ſuffered by their depredations, though previouſly in perfect vigour. And laſtly, that on repeatedly having waſhed off many thouſands of aphiſes from peach and nectarine leaves by a ſtrong ſtream from a forcible water-engine, that they evidently crawled again up the ſtems of the trees, or on the wall to which they were nailed, as in another day the lowermoſt branches were thus more infeſted with them than the upper ones.

The hiſtory of the aphis, puceron, or vine-fretter, is ſo curious, the deſtruction it commits on the foliage of the peach and nectarine is in dry ſummers ſo irreſiſtible, and its exiſtence on other trees ſo extenſive, that it demands our particular attention. See No. 1. 7. of this Section. From the obſervations of Swammerden, Bonnet, Dr. Richardſon,

Richardſon, and of other philoſophers, this extraordinary inſect riſes in the ſpring from eggs, which are ſaid to be attached by the parent aphis to the twigs of trees in the autumn, and are believed to produce not a larva or caterpillar, but a progeny ſimilar to the parent; every one of which produces in about ten days not an egg, but another living progeny to the ninth generation, without being connected amatorially with each other. The ninth generation produces males and females, ſome of both kinds with wings, and others without them; and this tenth generation from thoſe, which were hatched from eggs, become amatorially connected, and produce eggs; which are laid on the new twigs of various trees for the next year's progeny to be hatched by the vernal ſun. Philoſ. Tranſact. Vol. LXI. p. 182.

In this uncommon circumſtance the eggs of the aphis reſemble the ſeeds of plants; which firſt produce ſome ſucceſſive generations of leaf-buds, which are a viviparous progeny, before they again produce ſeeds, which are their oviparous progeny, as mentioned in Sect. IX. 3. 1. of this work. Nor is this to be aſcribed to what has been termed equivocal generation, or to an impregnation of nine fetuſes encloſed within each other, as ſome have ſuppoſed. But this central production of the viviparous progeny of the aphis ſeems to reſemble the lateral production of a viviparous progeny from the polypus, which in time detach themſelves from their parents; like the buds of the polygonum viviparum, or the bulbs of the magical onion, allium magicum; which are produced from the flower-cup inſtead of ſeeds, and in time detach themſelves, and fall on the ground. So that theſe aphiſes are not, I ſuppoſe, to be eſteemed fecundated females, but proliferous males, as explained in Zoonomia, Vol. I. Sect. 39. on generation.

This double mode of reproduction, ſo exactly reſembling the buds and ſeeds of trees, accounts for the wonderful increaſe of this inſect; which according to Dr. Richardſon conſiſts of ten generations, and of fifty at an average in each generation; ſo that the ſum of fifty

multiplied

multiplied by fifty, and that product again multiplied by fifty nine times, would give the product of one egg only in countleſs millions; to which muſt be added the innumerable eggs laid by the tenth generation for the renovation of their progeny in the enſuing ſpring.

Their punctures of the leaves of peach and nectarine trees in the vernal months, and of cherry, plum, and currant trees in the ſummer, produce a ſwelling and elevation of the cuticle of the leaf on its upper ſide, and a conſequent curling of it with its upper ſurface outwards, which terminates in a deſtruction of it to the great injury of the tree, and frequently to the death of it; while the leaves of the nut-trees, mentioned above, in No. 1. 7. of this Section, appeared to be but little injured by them, though fifty or a hundred of theſe inſects were ſeen under every leaf about Midſummer, both before and after their affuſion with the honey-dew.

From Dr. Richardſon's account the aphiſes on the roſe-tree appeared in February, when the weather happened to be warm, from ſmall black oval eggs; which were depoſited on the laſt year's ſhoots in autumn; and that, when the weather became colder, great numbers of them periſhed, by which circumſtance the roſe-trees are in ſome years almoſt freed from them.

They came to their full growth before April, and after having twice caſt off their exuviæ, every one of them produced about fifty young ones; all of which came into the world backwards, and adhered ſometime to the vent of the parent by their mouths or forepart; as ſhewn in a magnified ſtate at fig. 2. plate IX; and were at length ſet down on ſome tender ſhoots of the plant, and came to maturity in about ten days, caſting off their coats two, three, or four times.

The ninth generation in October conſiſted of males as well as females, which were ſeen to cohabit; and the eggs produced by their intercourſe, he aſſerts, were depoſited generally near the new buds, or on other parts of the twigs of the trees, which they poſſeſſed.

Theſe were at firſt green, but in a few days became brown, and by degrees quite black. They were of regular oval figures about one tenth of an inch in length, and about half as broad, and adhered firmly by means of ſomething glutinous, and reſiſted the ſeverity of the winter.

Other inſects, which are produced from eggs, and become winged butterflies or moths, live for ſome time in the intermediate ſtate of caterpillars or larvæ. During this ſtate of their exiſtence they feed on the leaves, on which they are hatched; or on fruits or kernels; but after they have acquired wings and organs of reproduction, ſome of them take no food, as the ſilkworm; and others live only upon honey, as bees, and moths, and butterflies. Now the aphis, I ſuppoſe, has no intermediate ſtate between the egg and the fly, and therefore makes no holes in the leaves by eating them; or if any of them previouſly exiſt in a caterpillar, or larva ſtate, it can be only thoſe which are produced from eggs in the early ſpring, which is worthy of future attention.

Whence I ſuppoſe, that this fly lives not by conſuming the foliage of the plants, which it inhabits; but by piercing the pulmonary veſſels in their natural ſtate, or the lymphatic veſſels of the leaf in their retrograde ſtate, by a fine tube or proboſcis, which it poſſeſſes, and which it may be ſeen by a common lens perpetually to employ, as ſhewn under its chin in the magnified inſect at figure firſt of plate IX. For the ſap-juice or vegetable chyle is brought from the radicles of each leaf-bud, and propelled up the long caudex to the pulmonary artery of the leaf, where it becomes oxygenated, and converted into vegetable blood. And may thus be extracted by the tubes of theſe inſects before its ſanguification.

Perhaps thoſe aphiſes, which were from eggs, might eat ſome part of the peach leaves during their larva ſtate, if ſuch exiſts, and occaſion them to curl up. While thoſe, which were a viviparous progeny, might only pierce the ſap-veſſels, or blood veſſels, and thus not ap-

parently injure the leaves; as on the nut-trees, where perhaps they were not hatched from eggs, but might have come thither in their winged ſtate, and have then produced their innumerable viviparous offſpring; as on the nut-trees above mentioned I could not diſcern the eggs, from which they were hatched, and a few larger aphiſes with wings appeared early in the ſeaſon amongſt the ſmaller ones without wings.

We may finally conjecture on this intereſting ſubject, firſt, that the aphiſes produced from eggs early in the ſpring may have a larva or caterpillar ſtate, and that during that ſtate they may feed on the young leaves of peaches, nectarines, plums, and cherries, and thus occaſion them to curl and die. 2. That thoſe, which are not from eggs, have no larva ſtate, and only puncture the larger chyle veſſels of the young twigs, or the pulmonary arteries of the leaves, which receive the vegetable ſap-juice from the roots, and thus that they ſuck it up, and live on it, before it is converted into blood, as moths, butterflies, and bees, live on honey in their winged ſtate, though on other parts of vegetables, as on their leaves, or anther-duſt, in their larva ſtate; and that theſe punctures are attended with no viſible injury to the leaf. 3. That for a week or two about Midſummer, when the umbilical veſſels of the new buds convey the ſap-juice to them, or to the reſervoirs of nutriment preparing for them, that the aphiſes by piercing theſe veſſels, or the pulmonary arteries of the leaves, acquire ſo large a quantity of this ſaccharine material, that it paſſes through them almoſt unchanged, falling on the leaves and ground beneath them, and produces what is called the honey-dew; but that this happens only for a ſhort ſeaſon, as a week or two about Midſummer, during the production of the new buds. And laſtly, that the black powdery material on the upper ſurface of the leaves of the nut-trees and plum-trees, and of the ſhrubs which grow beneath them, is an excrement from the aphiſes, which hang on the under ſurfaces of the leaves above them, like the black bitter powder in the nut-

nut-ſhell; which is the excrement of the curculio, which has eaten the ſweet kernel.

Secondly, having laſt year written the above, I have had another opportunity of attending to the aphis during the ſummer of 1799, and ſhall add the further remarks, which I have been able to make on this moſt curious and important animal, which may in proceſs of time deſtroy the vegetable world.

As the month of June was again in this ſummer very dry, though not very warm, the aphis was propagated in immenſe numbers on a great variety of trees, ſhrubs, and herbaceous plants. The row of nut-trees mentioned in No. 1. 7. of this Section was infeſted with a greater number of them this year than in the preceding one; yet during the ſeaſon about Midſummer there was ſo little honey-dew this year, that it might have eſcaped obſervation, if it had not been particularly attended to; yet what did appear was only on the upper ſurfaces of thoſe leaves, which had other leaves impending over them crowded with aphiſes; whence I had no doubt, but that it was voided by the millions of aphiſes, which adhered on the under ſurfaces of thoſe ſuperior leaves with their backs downwards.

On examining them with a ſtrong magnifier I could frequently perceive them inſert their proboſcis or trunk into the veſſels of the inferior ſurface of the leaf; and particularly obſerved, that when they were not moving from place to place, that they generally ſtood with their heads towards the foot-ſtalk of the leaf of nut-trees, or towards the baſe of the twigs of plum-trees, which circumſtance I ſhewed to many of my friends.

Both before and after the exiſtence of the honey-dew a black material, which was ſometimes moiſt and ſometimes dry, appeared on the upper ſurfaces of thoſe leaves only, which had other leaves crowded with aphiſes over them, and even on the upper ſurface of the leaves of ſome herbaceous plants, which grew under theſe nut-trees,

and alſo on others, which grew under plum-trees, which were much infeſted with an aphis of a greener colour.

To prove beyond poſſibility of error that this black matter was dejected on the leaves below by the aphiſes, which were walking with their heads downwards on thoſe above, I ſewed ſlightly with a needle and thread under ſeveral leaves a piece of writing paper about the ſize of the leaf; and obſerved on the next day that many black marks were diſtinguiſhable on the paper.

On plum-trees and on many herbaceous plants innumerable aphiſes were ſeen on the upper tender part of the upright ſhoots, adhering with their heads downwards; and on the hanging ſhoots with their heads upwards; and inſerting their proboſcis into the veſſels, I ſuppoſe, which contained the aſcending ſap-juice. But on the nut-trees the moſt tender or uppermoſt parts of the young ſhoots were covered with very numerous briſtles, which appeared to be an armour purpoſely produced to defend them from theſe deſtructive inſects, and hence they were principally found on the under ſurfaces of the leaves.

As the chyle of animals is mixed with the venous blood, and is immediately projected by the force of the heart into the pulmonary artery, at the extremities of which it is principally converted into blood by its expoſure to the air; ſo in the vegetable ſyſtem the ſap-juice muſt be mixed with the returning venous blood, and carried forwards to the extremities of the pulmonary artery of the leaf, before it is converted into vegetable blood. Theſe pulmonary arteries paſs along the under ſurfaces of leaves, as the upper ſurfaces of them are covered by the fine terminations of them on an air-membrane for the purpoſe of reſpiration; hence on theſe under ſurfaces of leaves the aphiſes adhere, and pierce the branches of the pulmonary arteries with their proboſcis ſtanding with their heads towards the ſtalk of the leaf, that they may thus meet the ſtreams of chyle or ſap-juice yet unchanged into

into blood; which accounts both for their exiſting in all kinds of weather on the inferior ſide of the leaves, and for their ſtanding with their heads towards the foot-ſtalks of them. Thus on an upright twig of a plum-tree I this day obſerved a number of aphiſes adhere with their heads downwards with their proboſciſes inſerted into the tender ſtem, and ſo near to each other, that the tail part of the lower ones extended one third of their length over the head part of thoſe above them, and gave ſomewhat the appearance of ſcales; while on the hanging twigs they adhered with their heads upwards, ſtill intent to meet the ſtreams of ſap-juice in the aſcending chyle veſſels, or in the pulmonary arteries.

Dr. Bradley and others obſerve, that about Midſummer there appears to be a pauſe in vegetation, and that at this time the new buds are generated; and Duhamel and others found, that the bark of ſeveral trees became at this time as eaſily to be ſeparated from the alburnum as in the ſpring; as is related in Sect. III. 2. 8. of this work. At this time therefore there exiſts a new flow of ſap-juice to ſupply preſent nutriment, or to furniſh a reſervoir of future nutriment to the newly generated or expected embryon, either before or after its vivification, or its impregnation, if ſuch a proceſs may be ſuppoſed to occur in the production of buds.

At this time then, when there exiſts a ſummer-flow of ſap-juice, this pernicious inſect in uncounted millions pierces the ſap-veſſels round the new ſhoots, or the pulmonary arteries beneath the leaves; and thus drinks the vegetable chyle, or ſap-juice, with ſuch avidity, as to part with much of it again almoſt unchanged. This I now believe with Sauvage to be the origin of one kind of honey-dew certainly; and if another kind of honey-dew exiſts, as he mentions, where there are no aphiſes, I ſuſpect, as obſerved in No. 1. 7. of this Section, that it muſt ariſe from the inverted action of the lymphatic veſſels of the leaf, at the time of the increaſed quantity of ſap-juice

about Midſummer; but have not had an opportunity to aſcertain theſe facts.

Thirdly. There appears to be a power impreſſed on organized bodies by the great author of all things, by which they not only increaſe in ſize and ſtrength from their embryon ſtate to their maturity, and occaſionally cure their accidental diſeaſes, and repair their accidental injuries, but alſo a power of producing armour to prevent thoſe more violent injuries, which would otherwiſe deſtroy them. Of this laſt kind are the poiſonous juices of ſome plants, as of atropa belladonna, deadly nightſhade, hyoſcyamus, hen-bane, cynogloſſum, hounds-tongue. Other plants are armed with thorns and prickles to prevent the depredation of animals, as ilex, holly, cratægus, hawthorn, ribes groſſularia, gooſeberry; the leaves of which would be perpetually devoured but for this kind of protection. Other plants ſecrete a viſcid juice to agglutinate the inſects, which crawl up towards their fructification, as ſilene, catchfly, droſera, ſun-dew; and others by the contraction of their leaves or petals arreſt or deſtroy the inſects, which attack them, as dionœa muſcipula, and apocynum androſemifolium.

But how can vegetables protect the whole inferior ſurfaces of their leaves, and of their young riſing ſtems from the innumerable progeny of the deſtructive aphis, which penetrates their chyle veſſels and their arteries; and which from their immenſe numbers may in proceſs of time deſtroy the vegetable world. Many vegetables have not yet acquired any means of defence, and have therefore the firſt growth of their foliage much injured, or totally deſtroyed by this deſtructive inſect, as the nectarine, and peach, and plum, and cherry-trees, in many parts of this country, as is every year ſeen and lamented.

Some vegetables have nevertheleſs already acquired an armour, which leſſens, though it does not totally prevent, the injuries of this animal. This is moſt conſpicuous on the ſtems and floral-leaves of moſs-

moſs-roſes, and on the young ſhoots and leaf-ſtalks of nut-trees. Both theſe are covered with thickſet briſtles, which terminate in globular heads, and not only prevent the aphis from ſurrounding them in ſuch great numbers, and from piercing their veſſels ſo eaſily, but alſo ſecrete from the gland, with which I ſuſpect them to be terminated, a juice; which is inconvenient, or deleterious to the inſect, which touches it.

Hence moſs-roſes appear to be leſs injured by the aphis, than other roſes, which have leſs of this armour; and while on plum-trees, and on many herbaceous plants, they hang round the upright young ſhoots with their heads downwards, and inſert their trunks, ſo as totally to conceal the riſing ſhoot; yet on nut-trees, though they are ſeen in millions beneath the leaves on the unarmed parts, they never appear round the young ſhoots, nor on the large trunks of the veſſels beneath the leaves, all which have acquired a panoply of briſtles with glandular heads to them, like thoſe round the moſs-roſe, but without the branching ſtructure of the latter. While thoſe plants, which are not infeſted with the legions of this ſelf-productive animal, have probably acquired ſome material mixed with their ſap-juice, or blood, which is poiſonous to them; as thoſe plants, which poſſeſs a milky or a yellow blood, as the ſpurges euphorbia, or the celandines chelidonium, or the fig-tree, ficus.

Nor is this more aſtoniſhing, than that the holly-trees ſhould annually ſupply prickles only to their lower leaves, about ſix or eight feet from the ground, as high as the animals can reach them, which would prey upon them; but refuſe the expence of putting forth prickles in their higher branches, which are ſaved by their ſituation, as I have repeatedly obſerved on the numerous holly-trees, which are the ornament of Needwood foreſt.

From hence I ſuſpect, that another reaſon, why the leaves of nut-trees and of roſe-trees are not curled up or bliſtered like thoſe of nectarines, peaches, plums, and cherries, is becauſe their foot-ſtalks,

and the larger branches of the pulmonary arteries, are defended by theſe briſtles, which are perhaps only beginning to appear on the leaf-ſtalks of the plum, but which may increaſe in the progreſſion of time; as all the works of nature may be approaching to greater perfection, as mentioned more at large in No. 2. of the laſt Section of this work.

Fourthly. The means of deſtroying an inſect ſo extenſively injurious not only to gardens and hot-houſes, but to half the vegetable world, would be indeed a valuable diſcovery. If the eggs exiſt on the young buds, as Dr. Richardſon affirms, ſome application to theſe, before they are hatched, which might diſſolve their ſhells, as by very dilute marine acid injected on them; or by ſome adheſive material, which might inviſcate them as ſoon as they are hatched, whether they appear firſt in their larva ſtate, like minute caterpillars, or in the form of the parent aphis, as ſoap-ſuds injected on the twigs before the leaves begin to unfold; or perhaps by rubbing them with oil or glue by means of a ſponge, or a painter's bruſh; but experiments alone can determine the effect of theſe applications, both on the inſect and on the tree.

Lime water alone will not readily deſtroy the aphis, as I obſerved by immerſing leaves with aphiſes on them; which crept up the leaves, and thus eſcaped. But if pot-aſh, or fixed alkali, be mixed with lime, the ſolution becomes ſo cauſtic as to deſtroy many inſects without injuring the foliage of trees, or the ſtems of wheat, if we may credit M. Socoloff, who in the tranſactions of an Academy at Peterſbnrgh, Vol.V. aſſerts, that he added three parts of quick-lime newly made to two parts of a ſaturated ſolution of fixed alkali in water; which poured on the ground deſtroyed the earth-worms, and ſprinkled on the leaves of trees deſtroyed the caterpillars, but did not injure, or much injure the foliage of trees, or the leaves of wheat plants.

Tar water has lately been ſaid to deſtroy ſlugs, white ſnails without

out ſhells, and might be worthy a trial by injecting it on trees at firſt with caution, leſt it ſhould injure them; as it is probably the vegetable acid chiefly, with a ſmall portion of eſſential oil, which is diſſolved, or mixed with the water, by agitation. See No. 3. 5. of this Section.

Previous to the pullulation of the buds, it is alſo believed to be of great ſervice to water wall-trees with lime-water, or with ſoap-ſuds, or perhaps with the addition of ſome pot-aſh to either of them to make a more cauſtic ley, ſuch as is recommended for ſteeping ſeed-wheat; but this with caution, as I have known a ſolution of hepar ſulphuris kill the branches of a tree, which were moiſtened with it, as well as the inſects, which were upon it. Nor am I certain that this will anſwer the purpoſe from the obſervations I have heard from thoſe, who have tried it.

The eſſential oils are all deleterious to certain inſects, and hence their uſe in the vegetable economy, being produced in flowers or leaves to protect them from the depredations of their voracious enemies. One of the eſſential oils, that of turpentine, is recommended by M. de Thoſſe for the purpoſe of deſtroying inſects, which infect both vegetables and animals. Having obſerved that the trees were attacked by multitudes of ſmall inſects of different colours (pucins ou pucerons), which injured their young branches, he deſtroyed them all entirely in the following manner. He put into a bowl a few handfuls of earth, on which he poured a ſmall quantity of oil of turpentine; he then beat the whole together with a ſpatula, pouring on it water, till it became of the conſiſtence of ſoup; with this mixture he moiſtened the ends of the branches, and both the inſects and their eggs were deſtroyed, and other inſects kept aloof by the ſcent of the turpentine. He adds, that he deſtroyed the fleas of his puppies by once bathing them in warm water impregnated with oil of turpentine. Mem. d'Agriculture, An. 1787, Printemp. p. 109.

I ſprinkled ſome oil of turpentine by means of a bruſh on ſome

branches of a nectarine-tree, which was covered with the aphis; but it killed both the inſect and the branches. A ſolution of arſenic much diluted did the ſame. Might not the ſcent of turpentine, or of tar, ſmeared on a fruit-wall deter the flies from approaching the trees to depoſit their eggs? or might not arſenic mixed with honey be ſmeared on the wall, to which the trees are nailed, be likely to attract the aphis as well as other kinds of flying inſects. But none of theſe ſhould be ſmeared on the branches, leſt it injure or deſtroy the tree. Perhaps if a few twigs ſmeared with turpentine, mixed with a little oil of turpentine to make it more fluid, and to increaſe its odour, were fixed in quince-trees, or in apple-trees, the flowers of which are liable to be deſtroyed by the eggs depoſited in them by a ſmall fly; they might be deterred from approaching the tree, as the great uſe of eſſential oils, which cauſe the fragrance of flowers, ſeems to be to deter inſects from infeſting their leaves, or preying upon their honey.

It is probable, that if infuſions were made in hot water, or perhaps for a longer time in cold water, of thoſe leaves which no inſects devour; as of the walnut, juglans; lauro-ceraſus, laurel; foxglove, digitalis; hen-bane, hyoſcyamus; hounds-tongue, cynogloſſum; rag-wort, ſenecio jacobæa; or of tobacco, nicotiana; and many others; and were ſprinkled on the curled leaves of wall-trees, or on the buds before they open, by a pump, or by a bruſh, or ſponge; they might deſtroy the inſects without injuring the trees, which might be determined by a few experiments.

The duſt of tobacco is frequently ſpread on affected leaves, but not I believe with very encouraging ſucceſs, owing perhaps to the powder not being very fine, or not ſoon enough applied. Some kinds of lime ſtrewed on in powder might probably be too cauſtic, and deſtroy the leaf along with the inſects; which alſo might be ſubjected to experiment. The powder of ſulphur, or of tobacco, or of any of the poiſonous leaves above mentioned, might be injected upon affected trees by

by a powder-puff, ſuch as hair-dreſſers uſe, or the ſmoke of tobacco, or of any other of the poiſonous leaves above mentioned, might be forcibly blown on them by an adapted pair of bellows, as the ſmoke of many of them may poſſeſs as poiſonous a quality as that of tobacco; and even the ſteam of a decoction of others, as of lauro-cerasus, and walnut; the poiſon of the former of which is known to riſe in diſtillation, might probably be uſed with effect; but this muſt depend on the greater or leſs fixity of their eſſential oils. The ſmoke or ſteam might be applied to wall-trees by previouſly ſuſpending over them a large ſheet of matting, or of linen, or of paper, or an old carpet; but may however be uſed with greater advantage in hot-houſes, than in the open air.

Since the above was written I directed in the early ſpring of this year one nectarine-tree to be moiſtened with tar-water, and parts of the wall to be ſmeared with tar; another to be moiſtened with lime and pot-aſh diſſolved in water; a third with ſoap-ſuds and lime added to them; and many both nectarine and peach-trees with ſoap-ſuds alone. This was done by means of a bruſh before any flowers appeared, and was repeated thrice on different days; but to my great diſappointment, when the leaves appeared, they became affected with the aphis as on former years. I alſo afterwards dipped many nut-leaves crowded with the aphis in ſtrong infuſion of tobacco, for a few minutes, as the leaves hung on the trees without, as I believed, deſtroying the inſects; though ſome of them appeared for a time to be rendered torpid.

Nevertheleſs on covering a low nut-tree with ſome ſheets of brown paper ſewed together, and throwing the ſmoke of tobacco under it from a proper pair of bellows, great numbers of aphiſes were killed, many of which dropped from the upper leaves on thoſe below them, and many adhered motionleſs to the under ſurfaces of the leaves. The fine powder of tobacco called Scotch ſnuff ſprinkled on the aphiſes by turning up ſome of the leaves quickly deſtroyed them.

As walnut-leaves may be had in great quantity in the autumn, and the whole plant of ſenecio jacobæa, rag-wort, at any time, both which are probably deleterious to inſects, as they ſeem never to be injured by them, theſe might be procured at ſmall expence, and might probably, when dried and burnt, produce a ſmoke equally deſtructive to them.

Fifthly. The moſt ingenious manner of deſtroying the aphis would be effected by the propagation of its greateſt enemy, the larva of the aphidivorous fly; of which I have given a print, and which is ſaid by Reaumeur, Tom. III. Mem. 9. to depoſit its eggs, where the aphis abounds; and that, as ſoon as the larvæ are produced, they devour hundreds around them with the neceſſity of no other movements but by turning to the right or left, arreſting the aphis and ſucking its juices. If theſe eggs could be collected and carefully preſerved dnring the winter, and properly diſpoſed on nectarine and peach-trees in the early ſpring, or protected from injury in hot-houſes; it is probable, that this plague of the aphis might be counteracted by the natural means of devouring one inſect by another; as the ſerpent of Moſes devoured thoſe of the magicians.

Mr. Horrocks of Derby ſhewed me this larva of the aphidivorous fly, which I ſaw devour two or three aphiſes, and Mr. Swanwick of this town at my requeſt made an accurate drawing both of the larva and fly, which he kindly favoured me with, accompanied with the following note.

"On Auguſt the 4th Mr. Horrocks obligingly ſent me an aphidivorous larva in a box on a leaf of a plum-tree, on which were a number of aphiſes; and I had almoſt immediately the pleaſure of ſeeing it eat one.

"The method of taking his prey is thus: he is like the ſloth in his diſpoſition, for he does not ramble about, while he has food around him. He only lifts up his head, and ſtrikes it down again, extending it in various directions, as if he was blind, and repeating the above ac-

tion. If by ſo doing he happens to feel an aphis, he immediately ſeizes it by the back, lifts it up and poiſes it in the air, as if to prevent it from liberating itſelf by its ſtruggles againſt the ſurface of the leaf, or that it may fall more eaſily into the cavity of his mouth. In this poſition he holds it, while he pierces it, and ſucks the juice out of the body; which having done, he drops the ſkin, licks his lips round with his little black tongue, contracts his head, and drops it down; thus reſting in perfect repoſe for ſome time, after which he repeats the ſame actions. But if he is in the midſt of plenty, he ſeldom gives himſelf this trouble, but waits till an aphis touches him, when he immediately turns his head round, and with fatal certainty ſeizes him, poizing him as before.

"For the purpoſe of ſeeing what fly was produced from this caterpillar, I procured him food for about ten days. During this time he eat a great number of aphiſes, and grew to about an inch in length; when he left off eating, contracted himſelf to about half his former length, fixed himſelf to the box by a little gluten, which he diſcharged from his mouth, and without caſting a ſkin changed to a chryſalis.

"In this ſtate he lay about ten or eleven days, at the end of which time he burſt his cell, and came out a beautiful fly, of which the figure is a good repreſentation."

No. 1. The caterpillar with an aphis in his mouth.

No. 2. The chryſalis open at one end.

No. 3. The fly.

Another enemy to the aphis is ſaid to be a beautiful ſmall ſpotted beetle, called a lady-bird by the people. Several of theſe were ſeen on the nut-leaves, and are believed firſt to appear there in their larva ſtate, and to feed on the aphis; they then change to a chryſalis, and laſtly to a ſmall wing-ſheathed beetle; and finally, I ſuppoſe, they bore holes into the earth, as would appear from their poſſeſſing ſheaths to their wings, and that they there depoſit their eggs to be hatched,

hatched, and to climb the trees infeſted with the aphis in the enſuing ſpring.

Thus from the exertions of a few aphidivorous larvæ or caterpillars, from the poiſonous juices of ſome plants, and from the briſtly armour on the young twigs and leaves of others, the vegetable world is ſo far protected from the deſtruction, with which it has been, and is threatened, by the fine proboſcis of this multitudinous inſect, which in its manner of attack reſembles that of the large bat of Aſia, veſpertilio-vampyris; which is aſſerted by Linneus to drink the blood by night of ſervants, who ſleep in the open air, Syſt. Natur. p. 46; and is ſaid by others to be ſo ſkilful an operator as not to wake the patient by the puncture, which it inflicts, as it agreeably fans them with its wings.

3. Many of the orchards of apple-trees in this country are liable to loſe all their leaves by the depredations of caterpillars; the ſame occurs to gooſeberry-trees in ſome gardens, and to cabbages in the latter part of the ſummer.

A few years ago I obſerved, that the bloſſoms of the quince-tree, before they were quite expended, were perforated by a fly; as the wound could be eaſily diſcerned like that on young nuts, when wounded by the curculio; and all the bloſſoms of a large tree were thus deſtroyed by a ſmall caterpillar. And in this late ſummer of 1799 the apple-bloſſoms in this country are much injured by a caterpillar, which eats the ſeed in the pericarp of each bloſſom either before or at the time of its impregnation, the petals of the flower cloſing again over it and dying.

The leaves of many trees are renewed after having been totally deſtroyed in the early part of the ſeaſon; as thoſe of the apple-tree above mentioned, which had loſt its leaves entirely by lightning; as the mulberry-trees in Italy, which are thus robbed of their firſt leaves to feed ſilk-worms, as the tea-tree in China, which is thus robbed for a faſhionable potation. And laſtly, as the euonymus, or ſpindle-tree, which

which in this country has its firſt crop of leaves almoſt perpetually deſtroyed by caterpillars. But though the leaves are reſtored after the depredation of this inſect, yet there follows an irremediable injury to the fruit. See Sect. IX. 2. 6.

As the eggs of butterflies are in the autumn wiſely depoſited in ſituations, where the young can find proper food, when they are hatched by the warmth of the ſpring; thoſe on apple-trees, and on gooſeberry-trees, are frequently depoſited on the leaves, as well as on other parts of the tree; and as theſe leaves fall on the ground, the eggs are thus covered and protected from the froſts, and the young caterpillars are believed to climb the trees in ſearch of their food. If this be true, it would be an advantageous practice to rake together the leaves in orchards, and to burn them; which ſome have done from an idea, that the ſmoke thus produced was noxious to the eggs of inſects depoſited on the branches.

Some gardeners for this purpoſe rear their gooſeberry trees on one ſtem only; and believe, that by tying a fringe round this ſtem the inſects, which are hatched in the ſoil, if ſuch there be, can not climb up the tree thus ſurrounded with a fringe; and as thoſe caterpillars, which are already on the tree, let themſelves down by a thread, when the tree is ſhaken, from the fear of being hurt by the vibrating twigs; if this thread be then broken, by moving a ſtick round under the tree, theſe inſects cannot reaſcend. A paper recently tarred on the outſide might be wrapped round the ſtem of the tree inſtead of the fringe with perhaps more certain ſucceſs; but the tar ſhould not be ſmeared on the bark of the tree, leſt it ſhould injure or deſtroy it.

It may be obſerved in the choice of apple-trees, that thoſe kinds, which flower early, are leſs liable to the depredation of inſects; and thoſe, which flower late, are leſs liable to the injuries of froſt. In apple-trees perhaps the former is in ſome ſituation the greater evil, but in pears I ſhould ſuſpect the latter, the bloſſoms of which are ſo often totally deſtroyed by one night's froſt.

The

The white butterflies, which depoſit their eggs on cabbage plants, are ſeen flying about awkwardly in ſummer, and ſhould be caught, and deſtroyed by the gardener. Or they perhaps might be invited and poiſoned by a mixture of honey, and water, and arſenic; as a wealthy man in Italy was ſaid to have poiſoned his neighbour's bees. See Sect. VI. 6. 3. Theſe cabbage-caterpillars would increaſe in deſtructive numbers, but are half of them annually deſtroyed by a ſmall ichneumon fly; which depoſits its own eggs in their backs, which are there hatched by the warmth of the animal, and live on the ſilk there ſecreted for its future neſt; and eroding their way out ſpin ſmall cacoons of their own; ten or twelve of which hang on each caterpillar; which thus periſhes inſtead of changing into a butterfly. This I ſaw happen to a great many of them, which were put into a box on bran with a few cabbage leaves, and covered with gauze, a few days before they were ready to change into chryſoliſts. This ichneuman fly ſhould therefore be encouraged, if his winter habitation could be diſcovered.

4. The variety of inſects, which infeſt hot-houſes, as the acarus, thrips, aphis, and cocci, and the means commonly uſed to deſtroy them by the ſmoke of tobacco, or by the powder of ſulphur and tobacco, or by ſolutions of lime and ſulphur, are deſcribed in Speechly's books on the Vine and Pine; but require ſome caution in their application. A friend of mine, by ſubjecting a wall-tree to the ſmoke of ſulphur by hanging a matt before it during the fumigation, killed both the inſects and the tree.

5. Other kinds of inſects are produced beneath the ſoil, or occaſionally retire into terreſtrial habitations. Of theſe are the various families of ſnails, with and without ſhells, and other inſects with ſheaths over their wings, with which they are furniſhed to prevent any injury from the friction of the ſides of the holes they make or deſcend into.

It has been lately ſuppoſed, that the great deſtruction of the crops of

of turnips, which occaſionally occurs, is owing to the depredation of a white ſlug, or ſnail, which comes out of the ſoil before ſun-riſe in dewy mornings; and that by rolling the young turnips with a heavy roller before ſun-riſe for a few mornings, theſe pernicious inſects may be deſtroyed, and add manure to the riſing plants they have injured.

The white ſlugs in gardens are very deſtructive to many flower-ſtems, as they riſe out of the ground, as to dictamnus fraxinella, apocynum androſemifolium, to phaſeolus, kidney-bean, to cinara, artichoke, and many other plants. I well remember in one ſeaſon favourable to their production in a garden by the ſide of the Derwent obſerving, that many artichoke ſtems above a foot high were eaten by them near the moiſt earth till they fell down, like trees felled by the ax. It has lately been aſſerted, that watering the ground with tar-water will deſtroy them; which may be made by adding a few pounds of tar to a hogſhead of water, and well ſtirring it, without perceptible injury to the tar. A circle of lime round the flower-ſtems, or of ſalt, or even of bran in dry weather, are means of preventing the approach of ſlugs; and ſome gardeners lay a board lightly on the ground between the alleys, under which the ſlugs hide themſelves when the ſun riſes, and are hence eaſily caught and deſtroyed.

The leaves of the young turnip are alſo believed to be deſtroyed by a fly; which, if it be of the ſcarabæus, or beetle kind, which ariſes out of the earth, may likewiſe be deſtroyed by rolling. The Chineſe are ſaid by ſir G. Staunton to ſteep all their ſeeds in liquid manure until they ſwell, and their germination begins to appear; which they believe not only haſtens the growth of the plants, but alſo defends them againſt inſects beneath the ſoil; and that to this ſir George obſerves it may be owing, that the Chineſe turnips eſcape the fly ſo injurious to them in this country. Embaſſy to China, 8vo edit. Vol. III. p. 310. An obſervation of Mr. Guillet in the Bath Agriculture, Vol. II. Art. 44, ſeems to confirm this idea. He aſſerts, that when turnip ſeed is ſown during rain, or has rain immediately afterwards,

wards, that the firſt leaves are ſo vigorous that the fly never attacks them; or that the rain itſelf is ſo inconvenient to the fly, as to prevent its appearance. It is alſo aſſerted by Mr. Exeter in the Tranſactions of the London Society for Arts, Vol. XVI. p. 191, that the ſowing turnips in drills deeper than by broad caſt, accelerates the growth of the plant by giving it more moiſture; whence it ſooner puts forth its rough leaves, and eſcapes the depredations of the fly. He ſpeaks highly of the uſe of the drill, adviſes the rows to be one foot diſtant, uſes three quarters of a pound of ſeed to an acre, and ſows them from one inch and a half to two inches deep.

6. The great numbers and varieties of animated beings, which live under the ſoil, and ſleep in winter, deſcending beneath the reach of froſt, is truly aſtoniſhing. I once obſerved ſuch immenſe numbers of ſmall wing-ſheathed inſects, which I believed to be the ſcarabæus ſolſtitialis, or fern-chaffer, as they were not one ſixth part of the ſize of a May-chaffer, ſcarabæus melolontha, though much of the ſame form and colour; which aroſe out of the ground near the cold bath at Lichfield, that I gueſſed, that one or two emerged from every ſquare inch of many acres of land.

The grubs or maggots, from which theſe wing-ſheathed flies aroſe, I ſuſpect in ſome ſeaſons and ſituations favourable to their production to be very deſtructive to the wheat in ſpring, or the early part of ſummer, devouring the ſtem near the ſurface of the ground at the joint, which is ſweet, till it falls down or withers, by which many crops were nearly deſtroyed this year, 1797, and that, I was informed, on ſome lands, which had been previouſly well limed.

Mr. Tull in his huſbandry, ſpeaking of wheat, adviſes not to ſow it deeper than an inch, ſince the thread or caudex, which connects the lower or ſeminal root with the upper or coronal root, he believes to be then not ſo readily found by worms in the winter, as one three inches long might be, both on account of the greater length of the

latter, and becauſe inſects do not riſe ſo near the ſurface in the winter months.

Where this peſtilential grub occurs, perhaps rolling the land early in the mornings in the ſpring might cruſh them. And when the fly is ſeen to come out in ſuch abundance in the ſummer evenings on graſs land or fallows, it is probable, that rolling the ground in the evening might prevent the return into the earth both of theſe and of the May-chaffers to depoſit their eggs, and thus prevent their future progeny; or during their grub ſtate, when they exiſt at the roots of wheat above or juſt beneath the ſurface of the ſoil, perhaps ſlaked lime might be ſprinkled over the crop in powder, or ſea-ſalt in powder, which might be waſhed down the ſtems of the corn in a wet day, and deſtroy the inſect without injuring the vegetable; or laſtly, by tar-water; all which might be firſt tried on a ſmall part of a field; for as lime is not all of equal purity, it is not all of the ſame ſtrength or cauſticity.

Another inſect is ſaid to injure wheat when in flower, and is ſuppoſed to be the thrips phyſapus of Linneus, as mentioned in the tranſactions of the Linnean Society, Vol. III. But as it only attacks the late flowering ſtems, it may poſſibly be prevented by ſowing the wheat early, if it ſhould ever become a ſerious evil.

Some time ago an inſect called a corn-butterfly committed great ravages in France while in its vermicular ſtate, ſo as to ruin two hundred pariſhes. A cure for it was at length diſcovered, which conſiſted in drying the wheat in an oven before ſowing it, and thus expoſing it to ſuch a degree of heat as would deſtroy the eggs of the inſect without injuring the ſeed; or perhaps which hatched them without ſufficient moiſture to ſoften the grain for their ſupport. See Encycl. Britan. Agricult.

Between Cheſterfield and Plaiſly in Derbyſhire I well remember above forty years ago to have ſeen for two or three miles together every leaf of the hedges devoured by the May-chaffers, ſcarabæus

melolontha, which hung on each other, where the foliage was deſtroyed, like bees in a ſwarm. And to have found in the ſame year, as it lay dead in a field near Cheſterfield, a true locuſt, like a very large graſs-hopper with very long and broad wings; which I preſerved in ſpirits, and was informed, that many of them were found in other parts of England about the ſame time.

All theſe noxious animals might be deſtroyed or diminiſhed by encouraging the breed of ſmall hedge-birds, and perhaps of larks, and of rooks, by not taking their neſts. I have obſerved, that houſe ſparrows deſtroy the May-chaffer, eating out the central part of it; and am told that turkeys and rooks do the ſame; which I thence conclude might be as grateful food, if properly cooked, as the locuſts or termites of the eaſt. And probably the large grub, or larva of it, which the rooks pick up in following the plow, is as delicious as the grub called groogroo, and a large caterpillar, which feeds on the palm; both of which are roaſted and eaten in the Weſt Indies. The various ſpecies of linnets carry ſmall caterpillars to their gaping young; and hedgehogs are ſaid to devour ſnails, and on that account to be profitably kept in gardens.

When a ſevere froſt occurs, before the ground is covered with ſnow, thoſe inſects, which do not penetrate deeply into the earth during their hybernation, as the ſhell-leſs ſnails or ſlugs, are liable to be deſtroyed, and probably many of the larvæ of the fern-chaffer and May-chaffer, as is ſeen by their diminiſhed numbers in the enſuing ſeaſon.

In China the aurelia of the ſilk-worm, after the ſilk is wound off, and the white earth-grub, and the larva of the ſphinx moth, furniſh articles at the table, and are ſaid to be delicious. Embaſſy to China. Nevertheleſs all the caterpillar tribes may not be equally innocuous; as in this climate the hairy caterpillars, if laid between the fingers, where the ſkin is tender, I have obſerved to produce an itching, and leave ſome of their pointed briſtles in the ſkin. And M. Vaillant,

in

in his travels in Africa from the Cape, aſſerts, that both a black and a white hairy caterpillar becomes ſo poiſonous, when it feeds on a large euphorbia, that the natives put them in bags, bruiſe them, and after a few days poiſon their arrows with them. But that they are leſs poiſonous if they feed on leſs acrid vegetables.

There muſt be great difficulty in deſtroying the larvæ, or grubs, or caterpillars, of many inſects, which are injurious to the fruits and kernels, as well as to the foliage of plants, by any chemical mixtures; as in this ſtate, I ſuppoſe, ſome of them are uncommonly hardy or tenacious of life. Mr. Gouch affirms, that he kept the curculio nucum, or worm found in nuts, in brandy for ſeventeen hours, which recovered; and I remember putting a worm, which came from a perſon, who called it an aſcaris, though it was above an inch long, and nearly as thick as a thin crow-quill, into a ſaturated ſolution of ſugar of lead in water; which lived many hours without apparent injury. See Nicholſon's Journal, No. 21, for November 1798.

7. A great number of bees, as well as of moths, and butterflies, muſt be very injurious to flowers, and conſequently to the production of fruits, as all of them plunder the nectaries of their honey, and thence deprive the anthers and ſtigmas of their adapted nouriſhment, as mentioned in Sect. VI. 6. 3. This would be more deſtructive to the ſeminal products of plants, but that many of them poſſeſs means of defending their reſervoirs of honey, and yet of expoſing it to the influence of the air, ſome of them by long winding canals, as in the bottom of the tubes of the honey-ſuckles, trefoils, and lark-ſpurs, lonicera, trifolium, delphinium; others by covering it with a hood, as in monkſhood, aconitum; others by a gluten, as in catchfly, ſilene, and in ſun-dew, droſera; others by contracting ſome part of their leaves or flowers, and deſtroying the hoſtile inſect, as in dionœa muſcipula, and in apocynum androſemifolium; and finally, many other flowers have probably acquired the habit of ſecreting more honey

ney than is neceſſary for their own conſumption, as cacalia ſuaveolens, alpine colts-foot, and polygonum fagopyrum, buck-wheat. From all theſe contrivances the flowers of plants probably receive leſs injury from the depredations of bees, moths, and butterflies, in this country, and from the humming bird in tropical climates, than they otherwiſe would be ſubject to.

But beſides the loſs of much of their honey an abundance of bees muſt likewiſe injure the ſeminal products of vegetables by plundering the ſtamina of flowers of their anther-duſt for bee-bread, as Mr. Hunter believes; and alſo of the wax, which covers the anthers for their defence againſt rain. Nevertheleſs, as mankind convert to their own purpoſes the honey thus collected by bees, and the wax, with which they fabricate their combs; and as the ſeeds of plants and their fruits are nevertheleſs in ſufficient abundance; the depredations of bees are not counteracted like thoſe of other inſects, but on the contrary encouraged.

The following obſervations, which I made this ſummer, may be of ſervice to thoſe who keep bees, and which I ſhall therefore here relate. The bees of one ſociety frequently attack thoſe of another ſociety, plunder them of their honey, and deſtroy moſt of them, perhaps all of them, in battle; in this reſpect reſembling the ſocieties of mankind! This war for plunder occurs more frequently than is commonly ſuſpected. Laſt year I had one hive of bees totally deſtroyed, and the year before another, which I did not take means to prevent, though I ſaw the conteſt, and the number deſtroyed in the latter; but not early enough in the commencement of hoſtilities.

Laſt week, June 16, I happened to ſee a great number of bees on the wing near the mouth of my only hive, and ſuppoſed that they were about to ſwarm. In an hour or two, on again attending to them I diſtinctly ſaw it was a violent battle; and at night obſerved about a hundred dead bees on the ground, and on the bench before the hive. I then directed a board about an inch thick to be laid on the

the bee-bench, and ſet the hive on this board with its mouth exactly on the edge of this board, the mouth of the hive was alſo contracted to about an inch in length, and a ſemicircular hollow was made in the board immediately under the mouth of the hive. By this means the aſſailing bees were obliged to alight on the bee-bench, and then to climb perpendicularly up the edge of the board, on which the hive was now placed; and thus appeared to act with great diſadvantage; and a much leſs number of bees appeared to be ſlain in this day's battle; whence it would be advantageous always to place bee-hives in this manner.

Nevertheleſs, as the war did not ceaſe, I directed early on the next morning to remove the bee-hive to a diſtant part of the garden, and to a more eaſterly aſpect, and found to my great ſatisfaction, that the hoſts of the enemy did not follow; and that in a few hours the unaſſailed bees reſumed their work, as appeared by their going into the hive with loaded thighs; and though a few of them were ſeen on the following two nights reſting on their old habitation, theſe were carried early on the enſuing morning in their torpid ſtate to their new ſituation, and the war ended without extermination of either ſociety.

IV. DESTRUCTION BY VERMIN.

1. The deſtruction of grain, after it is ſown, by the field-mice, which mine their way very quickly under newly ploughed lands near the ſurface, is ſaid by Mr. Wagſtaff, in the papers of the Bath Society, Vol. VI. to be effected in ſome ſeaſons to a very great extent. He adds, that the tuſſocks of wheat, ſeen to ariſe in many fields, are owing to the granaries of theſe diminutive animals; which he has often found to contain nearly a hatful of corn, which grows into a tuft, if the owner becomes accidentally deſtroyed.

Mr. Wagſtaff alſo aſſerts, that they feed much on the young plants,

as

as they ariſe from the ſeed, and multiply at that time very faſt. He detects their habitations by ſmall mounds of earth being thrown up on or near the apertures of their dwellings, or of the paſſages, which lead to their neſts or granaries; and by following the courſe of theſe paſſages he found and deſtroyed the parents and the progeny.

Mr. Wagſtaff recommends the taking up and dividing the tuſſocks of wheat, thus ſown in the autumn by the field-mice, and tranſplanting them in the ſpring; and alſo to thin other parts of a young crop, as they appear too thickly ſown, which he eſteems an advantageous practice.

Acorns when ſown, and garden beans, and peas, are liable to be dug up or devoured by theſe voracious little animals, which may be deſtroyed by traps baited with cheeſe; or beſt of all by the encouragement of the breed of owls, ſo active in the purſuit of nocturnal vermin, and thence ſo uſeful to the gardener and farmer, who ſtill permit their ſervants and children to deſtroy both their eggs and callow young.

2. This country was infeſted with two kinds of rats, the houſe-rat and the water-rat; but it is believed, that within the laſt half century the water-rat has deſtroyed the houſe-rat. The water rats poſſeſs ſome kinds of ingenuity ſimilar to the beaver in the conſtruction of their houſes near the brinks of rivers and pools; which have two apertures, one above ground amongſt the graſs, and the other beneath the ſurface of the water; and unleſs they can hide their upper opening amid weeds or graſs, they forſake the ſituation. Thus if a rim, three or four feet in breadth, round a fiſh-pond be kept ſo low as to riſe only two, or three, or four inches above the level of the water; and if this be kept clean from high graſs, or weeds, the rats will deſert the pond.

I have ſeen a young water-rat devour a large leaf of water-plantain, aliſma plantago, and therefore ſuppoſe that they occaſionally prey on the foliage, as well as on the ſeeds and fruits of vegetables, and on young animals, as ducklings and rabbits. As theſe animals, like the dog,

dog, are of a laſcivious nature, and as ſome materials have a ſtrong ſcent, reſembling perhaps that of their venereal orgaſm, they are liable to be attracted by ſuch ſmells, as dogs are, on the ſame account, I ſuppoſe, inclined to roll themſelves on putrid carrion; and male cats to eat marum, valerian, and cat-mint. On this account it is uſual for rat-catchers to avail themſelves of this propenſity, and to mix eſſential oil of rhodium, or muſk, with the poiſonous powders of ſtrychnos nux vomica, or of delphinium ſtaviſagria, or perhaps of arſenic.

The great injury to vegetation effected by theſe rats conſiſts in their making innumerable burrows beneath the ſoil, and feeding on the roots of a great variety of vegetables. Some new planted apple-trees I remember to have ſeen taken out of the ground with nearly the whole of their ſmaller roots eaten, and the larger ones peeled by theſe reptiles. They will alſo deſtroy young ducks, young rabbits, and young chickens; and devour with great avidity every kind of food, with which poultry and ſwine are uſually fed; and are hence in many ways injurious in ſituations near water.

The ſubſequent receipts for poiſoning this miſchievous vermin are printed in the papers of the Bath Agricultural Society, and ſaid to have been attended with great ſucceſs. Firſt, to a quart of oatmeal add ſix drops of oil of rhodium, one grain of muſk, and two or three of the nuts of nux vomica finely powdered; make it into pellets, and put them into the rat-holes. This was at firſt greedily eaten, and did great execution, but the wiſe animals after a time ceaſed to eat it. The ſecond conſiſted of three parts of oatmeal, and one of ſtaviſagria, ſtave's-acre, mixed well into a paſte with honey. Pieces of this paſte were laid in their holes, and again did great execution. A third method of deſtroying them there recommended is by laying a large box down on its front ſide with the lid ſupported open by a ſtring over a pully; and by trailing toaſted cheeſe, and a red herring, from their holes to this box; and placing oatmeal and other food in this

box, which they are for a few nights permitted to eat unmoleſted; and finally to watch them by moonlight, the inſide of the box being painted white; and, when many of them are ſeen, to let down the lid; by which contrivance ſixty of them were taken at once.

3. Moles, as well as rats, have occaſionally increaſed ſo greatly in numbers as to much injure the agricultor; they perforate the earth near its ſurface, and are ſaid never to drink, but to feed on the roots of vegetable, as well as on ſubterraneous inſects; and though they are believed never to drink, yet they have been ſeen occaſionally to ſwim over lakes of water to the iſlands which they ſurround, of which an ocular proof is related in the tranſactions of the Linnean Society, Vol. III. 1797. Some have recommended to inject the ſmoke of burning ſulphur, or of tobacco, into their ſubterraneous manſions; but as the earth frequently falls in behind them, as they paſs, or is accumulated behind them by their hindermoſt feet, as they perforate the ſoil with their foremoſt feet or hands, this method of attack can ſeldom ſucceed, unleſs the neſt of the animal be near the fumigated aperture. Others have adviſed to pour water into their holes, which is equally inefficacious in general, though it may have effect in particular ſituations. Some alſo have baited traps with worms, and others have adviſed to put poiſon into their holes; but they are not to be attracted together like rats from their not appearing above ground.

The following method was related to me by Francis Paget of Elſton near Newark, a very popular and ſucceſsful mole-catcher, whom I once attended in his occupation to witneſs his operations. The moles have cities under ground, which conſiſt of houſes, or neſts, where they breed and nurſe their young; communicating with theſe are wider and more frequented ſtreets, made by the perpetual journeys of the male and female parents; as well as many other leſs frequented allies or bye roads, with many diverging branches, which they daily extend to collect food for themſelves or their progeny.

This

This animal is more active in the vernal months, during the time of the courtſhip of the males; and many more burrows are at this time made in the earth for their meeting with each other. And though theſe animals are commonly eſteemed to be blind, yet they appear to have ſome perception of light even in their ſubterraneous habitations; becauſe they begin their work as ſoon as it is light, and conſequently before the warmth of the ſun can be ſuppoſed to affect them. Hence his method of deſtroying them conſiſted firſt in attending their ſituation early before ſun-riſe; and at that time he frequently could ſee the earth move over them, or the graſs upon it; and by a ſmall light ſpade he frequently cut off their retreat, by ſtriking it into the ground behind them, and then dug them up. He added, that by laying the ear on a newly raiſed mole-hill, the ſound of the ſcratching mole might ſometimes be heard at a diſtance, and direct where to find it; as the ſolid earth conveys ſmall vibrations better, or to a greater diſtance, than the light air. And that a terrier dog, after having been accuſtomed to the buſineſs, was frequently of ſervice in detecting by his noſe the place of the mole beneath the ſoil, and by endeavouring to ſcratch the earth over it.

The mole he ſaid generally ſuckles four or five, and ſometimes ſix, young ones; which are placed conſiderably deeper in the ground than their common runs; and as theſe neſts are ſunk much deeper into the ground than their ſtreets or bye-roads, and the mole-hills conſequently larger, the earth on the ſummit of thoſe mole-hills is generally of a different colour, and is raiſed higher than that of the other ones. Theſe neſts are to be dug up, having firſt intercepted the canal between them and the mole-hills in their vicinity, to cut off the retreat of the inhabitants.

The next important circumſtance is to diſcover, which are the frequented ſtreets, and which the bye-roads, for the purpoſe of ſetting ſubterraneous traps. This is effected by making a mark on every new mole-hill by a light preſſure of your foot; and on the next morning

by obſerving whether a mole has again paſſed that way, and obliterated the foot mark; and this is to be done two or three ſucceſſive mornings. Theſe foot-marks ſhould not be deeply impreſſed, leſt it ſhould alarm the animal on his return, and he ſhould form a new branch of road, rather than open the obſtructed one.

The traps are then to be ſet in the frequented ſtreets, ſo as nicely to fit the divided canal. They conſiſt of a hollow ſemicylinder of wood with grooved rings at each end of it, in which are placed two nooſes of horſehair, one at each end, faſtened looſely by a peg in the center, and ſtretched above ground by a bent ſtick. When the mole has paſſed half way through one of the nooſes, and removes the central peg in his progreſſion, the bent ſtick riſes by its elaſticity, and ſtrangulates the animal. He added, that where the ſoil was too moiſt or tenacious, that the moles in paſſing the old runs ſometimes puſhed a little of it before them, and thus looſened the central peg before they were in the nooſe; in which caſe he fixed the peg a little faſter in the trap.

By theſe means Francis Paget cleared many of the neighbouring pariſhes of this kind of vermin in a few days, or a week or two, and laid them under an annual tax for the defence of their territories from theſe invaders. And added, that ſome other mole-catchers had carried moles into thoſe farms, whoſe occupiers refuſed to pay them an annual ſtipend, a practice which he ſcorned to uſe. I have detailed this method to prevent this impoſition, and to enable every farmer to be his own mole-catcher, or to teach the art to his ſervants.

PLATE IX.

PLATE IX.

Exhibits the aphis, puceron, or vine-fretter, and the inſects which deſtroy it.

Fig. 1. repreſents the aphis of the roſe-tree without wings very much magnified, copied from M. Bonnet, with its antennæ before, and its two horns behind, which are not half the length of the antennæ, are immoveable, and ſaid by Bonnet to be hollow canals from which the ſweet juice called honey-dew is evacuated; laſtly, with the trunk under its head in the poſition in which it penetrates the leaves. In ſome the horns behind are wanting, and little knobs ſupply their place, which Reaumur thinks ſupply the ſame ſweet juice. That ſome poſſeſſing wings, and others not, does not diſtinguiſh the ſexes is agreed by all obſervers.

Fig. 2. repreſents a magnified aphis of a pear-tree, from which a young one is ſuſpended for ſome time after it is otherwiſe born.


Fig. 3. repreſents the aphidivorous larva, with an aphis in its mouth, and the chryſalis of the ſame inſect, before it is transformed into the fly at fig. 4. All theſe were drawn from nature, and exactly reſemble ſimilar repreſentations in the work of Bonnet.

Fig. 5. repreſents an inſect from Bonnet, which he terms an aphis lion, as it ſo greedily devours the aphiſes. This inſect is transformed into the fly at fig. 6.

Fig. 7. repreſents a ſpotted hemiſpheric ſcarabeus, called by ſome a lady-bird, into which the inſect at fig. 8. is transformed, which is alſo ſaid to be a great aphis-eater. Oeuvres de C. Bonnet, T. 1.

Fig. 1.






2



3





4



5



6



7



8

London, Published Jan.ʸ 1.st 1800, by J. Johnson, St. Paul's Church Yard.

PHYTOLOGIA.

PART THE THIRD.

AGRICULTURE AND HORTICULTURE.

SECT. XV.

THE PRODUCTION OF FRUITS.

Buds immediately from ſeeds never produce ſeeds. Neither in annuals nor trees. As in wheat, tulip, apple-tree. Buds from the broad caudex of a tulip, and the long caudex of trees, are of different maturity. Leaf-buds changed into flower-buds at Midſummer, or flower-buds into leaf-buds by art. I. To produce fruit-bearing trees. 1. *Seedling-trees. Their puberty. Ingraft walnut and mulberry trees. If unpruned young trees or eſpalliers bear fruit ſooner than other ſtandards? Buds on bended branches earlier and larger. An apple ſour on one ſide. How to produce fine ſeedling-trees or flowers. Leaves of ſeedling-trees.* 2. *Root-ſuckers from apples, vines, briers, figs, are like ingrafted ſcions.* 3. *Scions from branches planted in the earth. A quick-hedge thus raiſed. Chineſe method. Vines how raiſed by Mr. Michel.* 4. *An ingrafted ſcion ſometimes affects the ſtock. Acquires vigour from a vigorous ſtock. On trees of the ſame genus. On trees of different genus. Subject to hereditary diſeaſes, not to old age, like the parent tree. Summits die firſt. Talicotius's ingrafted noſes. Sour apple on one ſide. Apply rind to rind in grafting. Flower-bud not proper for inoculation. Sweeter apples have whiter bloſſoms. Colour of black cherry and purple grape known by their red leaves in autumn. Lines from Virgil's Georgics.* II. To increaſe the number of fruit-buds. *Leaf-buds are furniſhed with new caudexes down the trunk. Flower-buds not ſo. Retard the production of new caudexes. Viviparous and oviparous progeny. Production of new caudexes, or bark filaments, are compound in ingrafted trees, and ſuddenly generated.* 1. *Bend down the viviparous branches, and*

and they become oviparous, and receive more nutriment. Apple-trees trained in horizontal circles. Nectarines and peaches trained on the ground. 2. *Twiſt a wire or tie a cord round viviparous branches. Apple-trees become dwarfs by frequent ingrafting on them.* 3. *Wound or break a viviparous branch, or cut off a cylinder of the bark. The veſſels of the alburnum ſometimes act as capillary tubes. Decorticated oaks. Tapped birch and maple. Decorticate alternate branches about Midſummer. Decorticated roots produce root-ſcions. Grafted roots. Layers. Take bark off and replace it. Cut three or four circular inciſions, or a ſpiral line. To make dwarfs.* 4. *Tranſplant a tree, or cut the roots, or confine them. Pluck up and tranſplant beans, brocoli, ſtrawberries. Alſo crowd the roots of ſtrawberries. Put a brick floor under fruit-trees. Confine lily of valley in pots. Orchis. Cucumbers and melons.* 5. *Cut away central viviparous branches. Why ſpurs are oviparous. Why terminal buds are viviparous. Effect of it. Management of melons. Management of vines. Pinch off viviparous ſecondary buds, and they become oviparous next year at the ſame eye. A longer heat to ripen the wood explained. If this could be practiſed on other fruit-trees.* 6. *Lines from Botanic Garden.* III. To perfect and enlarge the fruit. 1. *Shorten the oviparous branches. Cut away root-ſuckers.* 2. *Pinch off uſeleſs viviparous buds. Pick out ſecondary buds. And of melons.* 3. *Thin wall-fruits, and grapes. Mucor grows without light.* 4. *Tie waxed thread round twigs of fig-trees and pear-trees when in flower, to prevent new leaf-buds.* 5. *Give additional moiſture, manure, and warmth. Moiſture enlarges fruit by relaxing their cuticle, and preventing abſorption from them. Of ſuckling gooſeberries. Watering rice when in flower. Manure adds nutriment. Much warmth with much moiſture both enlarges fruit and adds to its flavour. Hot-houſes heated by ſteam. Pines cultivated in water.* 6. *Protect flowers and fruits from froſt. A low ſituation is not proper for a garden. Walls covered with projecting coping ſtones are uſeful in ſpring, not in ſummer. Moveable coping ſheds. Fire-flues in garden-walls. A ſecret in the management of them. Shade flowers from the ſun.* 7. *Fruits ripen ſooner if wounded, or gathered before they are ripe, or baked in the hot-houſe, or in an oven.* IV. 1. To preſerve fruit. *Keep it from heat and cold, and from moiſture. How heat and cold deſtroy the life of fruit. Congelation ſeparates ſalts, vinous ſpirit, and vinegar, from water. Condenſes clay. Repels mucilage. Thaw frozen fruit ſlowly. Preſerve fruits in ice-houſes, or by ſteam.* 2. *Gather fruit during*

its acid ſtate. Evaporate part of its water. Keep it cool. 3. *Impregnate fruit with ſugar. Brandy poiſons mucor or mould.* 4. *Fruits preſerved in brine, in vinegar, in ſpirit of wine, ratifie.* V. Verſes *on pruning trees and melons.*

THE objects of the culture of the farm or garden may be divided into the production of fruits, ſeeds, roots, barks, woods, leaves, and flowers.

We have repeatedly endeavoured to ſhew, that the buds immediately ariſing from ſeeds are not themſelves capable of producing ſeeds neither in herbaceous nor in arboreſcent vegetables; but that the firſt bud from every ſeed is ſucceeded by a ſecond bud more perfect than itſelf; and that by a third, fourth, or many more; each generation being more perfect than the preceding one, till they acquire a puberty, if it may be ſo called, or a power of producing ſexual organs, and a conſequent ſeminal progeny.

In thoſe plants, which are called annuals, becauſe their ſeeds are ſown, and produce other ſeeds, in the ſame year, and then periſh, ſome ſucceſſive buds grow on each other, before a flower can be produced; as is ſeen in the ſtems of wheat, and ſowthiſtle, triticum, ſonchus; which conſiſt of joints, which appear to be ſucceſſive buds growing on each other.

From the tulip ſeed a ſingle bud ariſes the firſt year with a circular flat caudex exiſting beneath it, on which one principal new bulb is formed annually more perfect than its parent, as is ſeen by the larger leaf; and alſo ſome leſs bulbs are produced around the more perfect one in the boſom of each rudiment of a leaf, which compoſes or encloſes the principal bulb, as deſcribed in Sect. VII. 1. 3. and Sect. IX. 3. 1. and 3. 6. Theſe leſs perfect bulbs round the principal one, after the principal one has acquired its puberty, or power of producing ſexual organs, are of greater or leſs degree of maturity, as appears by their ſize; and thence I ſuppoſe muſt require more or fewer years, before they flower.

Similar

Similar to this circumſtance of the tulip-root, the buds of trees, which firſt ariſe from the ſeed, produce annually other buds more perfect than themſelves, till they acquire the power of ſeminal generation; and afterwards not only a flower-bud is formed, which is in ſome trees the central bud on the extremity of the twig, as in pear-trees, and on the ſpurs of apple-trees; but alſo many leaf-buds of greater or leſs maturity are formed around the principal, or flower-bud; which require more or fewer years, before they obtain the maturity neceſſary to produce a flower.

It was ſhewn in Sect. VII. 1. 7. that every part of the long caudex, extending from a bud on the ſummit of a tree to the root, can produce a bud, like every part of the broad caudex of a tulip-root; but thoſe produced in the boſom of the leaf I believe generally to be the moſt mature; and thoſe which ariſe from a lower part of the caudex to be leſs mature, and will in conſequence require more ſucceſſive buds to proceed from them, before they can form a flower. Thus when the whole branches of a fruit-tree are lopped from the trunk, the new buds are produced from the lower parts of the caudexes of the branch-buds, which have been lopped off, and are therefore an immature progeny, and require ſome years before they can flower.

It hence appears, that a number of buds or bulbs in all vegetables muſt ſucceed each other from the ſeed, before a flower and conſequent fruit can be generated; but that theſe ſucceſſive generations are more numerous or fewer in ſome plants than in others; that they in ſome plants may only ſucceed each other annually; in others perhaps many of them in the ſame ſummer, as in the herbaceous plants, as wheat; and in thoſe trees, whoſe annual joints have their pith divided from each other, as in vines. And laſtly, that the number of theſe ſucceſſive generations, or the times of their production, whether only annually, or many of them in one ſummer, may be diminiſhed

niſhed or accelerated by art; and that in attending to all theſe circumſtances conſiſts the ſucceſsful management of fruit-trees.

The new buds on deciduous trees in this climate are produced about Midſummer, as obſerved in Sect. IX. 2. 9; and it is believed by the Linnean ſchool, that many of them at this time may be ſo affected by art, as to become either leaf-buds or flower-buds. At this ſeaſon therefore the production of buds on wall-trees, or eſpaliers, or on ſtandards, ſhould employ the attention of the horticultor; as thoſe ſeedling-trees produce leaf-buds only, which are too young to produce flower-buds; and as the particular ſhoots or buds of other trees are not ſo mature as to produce flower-buds; and laſtly, as ſome trees flouriſh too vigorouſly, as it is termed, to produce flower-buds. The things to be attended to are the age of the tree, from which the graft was taken, which now forms a branch; the maturity of the particular buds, which you wiſh to encourage; and the vigour of the whole tree, or its tendency to produce leaf-buds in preference to flower-buds.

I. TO PRODUCE FRUIT-BEARING TREES.

1. There are four methods of procuring fruit-trees for the purpoſes of horticulture, by ſeeds, by root-ſuckers, by planted ſcions, or by ingrafted ſcions.

1. *Of Seedling Trees.*

It was obſerved above in Section IX. 3. 1. and 3. 6. that in tulips and hyacinths, and even in potatoes and onions, the bulbs ſucceed each other for two or three years or longer, before they produce flowers; and that the ſame happens to the buds of ſeedling-trees, which are many years a ſucceſſion of leaf-buds only, before the propagation of a ſingle flower-bud; for the power, which produces the

lateral germination of buds, ſeems to require a leſs mature organization than that, which is employed in the ſexual generation of ſeeds; whence a kind of puberty of the plant ſeems to be acquired for the production of the ſeminal or amatorial progeny, analogous to the transformation of caterpillars into butterflies; which appears to be effected ſolely for the purpoſe of propagation.

M. Speechly, in his treatiſe on the Culture of the Vine, p. 49, ſeems to ſay, that ſeedling vines muſt be three or four years old, before they produce fruit; whereas a planted ſcion, or an ingrafted one, from an aged tree, will produce fruit the firſt or ſecond year; and according to the obſervations of Mr. Knight, ſeedling apple-trees will not bear fruit till they are twelve or fourteen years old; and other fruit-trees in ſimilar manner require ſome years after their birth from the ſeed, before they arrive at ſufficient maturity to bear flowers. See Sect. VII. 1. 3. Hence he adviſes the horticultor to procure ſcions for grafting from ſuch trees as already bear fruit; but pays no regard to the ſtock, into which they are to be inſerted; and adds, that he believes, if ſcions from a bearing walnut or mulberry tree were ingrafted on a ſeedling one, that it would produce fruit in two or three years; which otherwiſe would not occur in leſs than twenty. Treatiſe on Apple and Pear. Longman, London. And hence we ſee the advantage of ingrafting on ſeedling orange or lemon-trees in our green-houſes the ſcions taken from thoſe, which bear fruit; as otherwiſe they would continue ſo many years before the buds would acquire ſufficient maturity to generate flowers.

Some have believed that young trees will bear fruit ſooner, if they are not pruned, but permitted to grow quite wild in large buſhes. It is poſſible, that this may occur either from the unſkilful horticultor pruning off all the terminal twigs, whoſe buds were forwarder in reſpect to age, than the lateral ones much beneath them. Or becauſe the great number of new leaf-buds, proceeding from an exuberant branching head, may ſo crowd the bark of the trunk with their

their caudexes, that ſome of them may ſooner find a difficulty in forming their embryon caudexes, and may in conſequence become flower-buds. But I much doubt, that this can frequently occur from either cauſe, as I think, I have ſeen eſpaliers bear ſome years ſooner than ſtandards, which were ingrafted at the ſame time, and from the ſame trees. And I have been informed of other ſeedling apple-trees, which have born fruit in not much more than half the time above mentioned by Mr. Knight.

It is much to be wiſhed, that proper experiments were made on ſeedling trees by planting them as eſpaliers, or againſt walls, and bending down their branches below the horizon, ſince the difficulty of their generating leaf-buds might be thus increaſed; as they could not ſo eaſily form their embryon caudexes on the compreſſed bark of the bended branch; and the ſap-juice for the nouriſhment of fruit-buds would be thus rather increaſed than diminiſhed, according to an experiment of Dr. Walker, who found the buds at the extremities of bended branches to ſwell ſooner in the ſeaſon, and to become larger, than thoſe of an equal height on the more upright branches. Edinburgh Tranſactions, Vol. I.

Mr. Bradley has mentioned an apple, which was ſweet and boiled ſoft on one ſide, and ſour and boiled hard on the other; and aſcribed it probably to the real cauſe with much ingenuity in the year 1721, long before the publication of the ſyſtem of Linneus. He aſcribes it to the male farina of ſome neighbouring harſh apple-tree affecting at the time of the impregnation the ſtigma of the flower of a ſweet one; and thus a production of different ſeeds might be generated in the ſame pericarp, and a conſequent different kind of nutriment prepared for each; and thus the different parts of the apple become ſour or ſweet, which is analogous to a bitch producing different kinds of puppies at the ſame birth, reſembling the different dogs with which ſhe had cohabited. The ſame circumſtance is ſaid to have occurred in oranges and in grapes of different kinds.

By this method of applying the farina of one good variety of fruit, as of apple or pear, to the ſtigma of another good variety, it is very probable, that ſome very excellent new varieties of fruit might be produced from the ſeeds, which might ſupply for a century the orchards of the curious, inſtead of our golden pippins, and nonpareils; which are ſaid to be ſuperannuated, and ſo liable to canker as not to be worth cultivation. It is probable alſo, that new varieties of tulips and hyacinths, and of melons and cucumbers, as well as of all other vegetables, might be thus produced.

The following obſervations are from Mr. Knight's treatiſe on Apple and Pear, p. 47. "Every ſeed, though taken from the ſame apple, furniſhes a new and diſtinct variety; and ſome of theſe will grow with more luxuriance than others; and the fruits produced by the different plants will poſſeſs different degrees of merit; but an eſtimate may be made of their good and bad qualities at the concluſion of the firſt ſummer by the reſemblance the leaves bear to the highly cultivated, or to the wild kinds; as has been remarked by the writers on this ſubject of the laſt century. The plants, whoſe buds in the annual wood are full and prominent, are uſually more productive than thoſe whoſe buds are ſmall and ſhrunk into the bark; but their future produce will depend much on the power the bloſſoms poſſeſs of bearing cold; and this power varies in the different varieties, and can only be known from experience. Thoſe, which produce their leaves and bloſſoms rather early in the ſpring, are generally to be preferred; for though they are more expoſed to injury from froſt, they leſs frequently ſuffer from the attacks of inſects, the more common cauſe of failure.

"The leaves of young ſeedling plants annually change, become more thick and fleſhy, and aſſume more the character of the cultivated kinds. Theſe external changes indicate ſome internal ones in the conſtitution of the plant, which may poſſibly be ſimilar in their nature to thoſe, which take place in animals between their infancy

fancy and the time, when they become capable of propagating their ſpecies.

2. *Of Root-ſcions.*

Root-ſuckers from bearing bur-apples, or from bearing codlings, are believed to become fruitful as ſoon as grafts from thoſe trees; becauſe they are a viviparous offspring, as well as the ſcions or twigs from the branches; and are therefore not ſimilar to the oviparous progeny, or the young trees produced from ſeeds. This muſt nevertheleſs in great meaſure depend upon the age of the ſucker; as thoſe root-buds, which riſe into ſuckers, are not formed or generated in the boſom of a leaf, but from a part of one of the long caudexes of a branch-bud; and will therefore, I ſuppoſe, require a ſucceſſion of buds for ſome years, before they will acquire ſufficient maturity to produce a flower; as the central buds from the boſom of a leaf I ſuppoſe to be much forwarder than the lateral buds from the ſame caudex; as is ſeen in the central or flower-bulb of a tulip, and its immature lateral bulbs from the ſame caudex.

Root-ſuckers from thoſe trees, which have been ingrafted on the roots of other trees, as the robinia on the acacia, may ariſe above the grafted part, which is beneath the ſoil; but thoſe root-ſuckers, which ariſe from trees, which were grafted above ground, are ſimilar to the ſtock, not to the fruit-bearing head; which might have been a wild pear or wild apple; and will in that caſe produce crab-pears, or crab-apples, with thorny ſtems.

When a branch of a vine, or briar, or of many other trees, is bent down, and a part of it inſerted into the ground with its ſummit in the air, it will emit roots at the joints, and become a new tree. So the rough knobs on the bark of a bur-apple-tree, I am informed, will ſhoot out roots, if ſurrounded with moiſt earth; and the branch may be then cut off, and ſucceſsfully planted. And from almoſt every joint of a fig-tree roots will protrude, if ſurrounded even with a woollen

woollen ſhred, which happens to be frequently moiſtened by the dews or rain; and the branch may be ſucceſsfully bent down and planted in a garden-pot. All theſe, like ſuckers from the roots of ſeedling-trees, or like grafted ſcions, will become fertile, as ſoon as the tree, from which they are the offspring; whether it be a ſeedling-tree or not.

This circumſtance does not occur exactly ſimilar in the inſertion of buds from one tree into the bark of another; as thoſe buds, which do not ariſe from the boſom of a leaf, but from lower parts of the caudexes of a branch-bud, as from the bark of a branch, whoſe ſummit has been cut off, are leſs mature, I believe, than the ſummit-buds, or thoſe which ariſe from the boſom of a leaf; and will therefore require ſome years before they can produce flowers; as is ſeen in thoſe apple or pear trees, whoſe ſummits have been entirely lopped off. This is a new obſervation, I believe, and worth the attention of thoſe, who inoculate the buds of one fruit-tree into another.

Root-ſuckers may probably be liable to degenerate in reſpect to their vigorous growth by hereditary diſeaſes, owing to the too great age of the original plant of that variety, like the ingrafted ſcions from the branches. Whence it may be neceſſary to procure root-ſuckers of raſpberry-plants, and of gooſeberries, and even of artichokes, and ſtrawberries, from ſuch as have been raiſed from ſeed not too long ago, when any of theſe begin to degenerate.

3. *Of Planted Scions.*

The ſcions taken from the branches of many trees, if planted in the earth, will emit roots, and flouriſh in the ſame manner, as when they are grafted on other trees. This ſucceeds with great certainty, if an inverted glaſs be put over them for a few days to prevent their perſpiring more at firſt, than their abſorbent veſſels can ſupply. See Sect. I. 1. I have been informed, that a quickſet, or hawthorn

hedge, cratægus, was thus planted and became a good fence conſiderably ſooner than from ſowing the ſeed.

The Chineſe are ſaid by ſir G. Staunton to be unacquainted with the art of ingrafting, and to produce dwarf fruit-trees, which are brought to table loaded with fruit at their feſtivals, by ſurrounding a branch of a bearing fruit-tree at its bifurcation with a bag of earth, which is kept moiſt for ſome months; till the branch puts out roots, probably from the lips of a wound in the bark, and is at length ſeparated, and tranſplanted into a pot. Embaſſy to China, Vol. II. p. 54, 8vo. edition; and it is then rendered a dwarf by repeatedly cutting out the central buds, as in the management of melons, as mentioned in No. 2. 5. and 3. 2. of this Section.

Vines poſſeſs ſo vigorous a power of vegetation, that the preſent moſt approved method of propagating them in grape-houſes conſiſts in planting their ſcions. The late Rev. John Michel of Thornhill, in Yorkſhire, the philoſopher, who diſcovered to the world the art of making artificial magnets, which had been concealed by Mr. Knight; whoſe friendſhip I long poſſeſſed, and whoſe loſs I have long lamented; amuſed himſelf and family at vacant hours in his hot-houſe. The obſervations of a man of ſuch accurate and univerſal knowledge are always worth recording; and though his ideas on this ſubject have already appeared in Mr. Speechly's Culture of the Vine, I ſhall here tranſcribe a part of one of his letters to me dated in May 1785.

"The way in which we raiſe our vines we account our own; for I don't know, that it was practiſed by any body before we ſet the example. It is now pretty generally adopted however by the gardeners and nurſerymen in this part of the world. Inſtead of leaving three or four eyes on the cuttings, as uſed formerly to be done, which made them awkward ſtraggling things, we never plant more than a ſingle eye to each, cutting them with as long a part below the eye as they can admit, without encroaching too much upon the next eye below; that is to ſay, we leave perhaps about half an inch, or

or a little more, as it may happen, above it. Theſe cuttings we plant by half a dozen or a dozen together, at the diſtance of three, four, or five inches, in the bark-bed, where it is pretty warm, but not ſo hot as to endanger the burning of the roots, when they ſhall come out; and where it is alſo pretty moiſt, or elſe we water them. We plant them ſloping ſo as to make an angle of about thirty degrees perhaps, a little more or leſs, with the horizon, the eye being higheſt; but taking care that it alſo ſhall be covered about an inch with the bark, which is a very neceſſary precaution; for though it ought juſt to *ſmell* the freſh air, it muſt be kept moiſt, to prevent the bud and ſhoot, when it comes, from drying; otherwiſe it will very frequently die away preſently after it has ſhot a little, or at beſt it will grow unkindly, not having yet made roots ſufficient to ſupply it with the ſap neceſſary for its ſupport; which will not be the caſe, if the bud is ſufficiently covered at firſt, and till it has acquired more roots.

We generally plant our vines in this way, about the beginning or middle of January; and if the bark is pretty warm, and as moiſt as it ſhould be, the cuttings will begin to puſh both at top and bottom in about a fortnight or three weeks at the moſt. When the vines have ſhot a little, perhaps three or four inches, but before the roots are got too long, (in which caſe it would be impoſſible to avoid breaking them by removing, on account of their extreme tenderneſs and brittleneſs) we diſplace a good deal of the bark very near them, till we can throw them down all together, which ſhakes the bark very gently from their roots; ſo that one may diſengage them ſufficiently eaſy, and without much hurting them. We then plant three or four of the moſt promiſing and thriving ones out of the whole number ſingly in ſmall pots in earth, which has previouſly ſtood in the hot-houſe a day or two to get warm, letting the roots drop down on a little earth at the bottom, at firſt, as they conveniently can, and then covering them with more earth carefully, till the pot is properly filled, and the ſtem about three or four inches long, as I ſaid before,

before, ſtanding in the middle; and then plentifully watering the earth to ſettle it to the roots. We now plunge them again in the bark, where in five or ſix weeks, more or leſs, they will have filled their pots pretty well with roots; when they will begin to ſhew by their little progreſs, and the ſmallneſs of the ſhoots, that they want more room. We then take them carefully out of theſe ſmall pots, diſturbing the ball of earth as little as poſſible, and put it all together into larger pots, putting a little freſh earth at bottom and round about, and watering well as before; and we then again plunge them into the bark.

" By about the latter end of May, or beginning of June, the beſt of them will be four or five, or perhaps ſix feet high, and ought now to be removed, diſturbing the roots as little as poſſible, into the natural ground, where they are to remain. If this is done carefully, and the earth well watered about them to ſettle it to their roots, they will frequently begin growing again almoſt immediately, but at leaſt in three or four days; and will then often ſhoot in the hot-houſe two inches in a day, and by the end of the year will have ſhot from eighteen or nineteen, to three, four, or five and twenty feet. Though we approve of this as rather the beſt, yet if theſe cuttings are planted in the ſame way either ſingly in ſmall pots, or two or three together in each, with earth, inſtead of planting them in the bark, deſtroying all but the beſt one, when they have ſhot a little, and plunging them either in the bark, or in default of a bark-bed, in a common hot-bed, they will do equally, or nearly equally well; only taking care, that the hot-bed is not too hot, ſo as to injure the roots, of which there is ſometimes danger."

4. *Of Ingrafted Scions.*

The art of ingrafting trees is of great antiquity, and is attended with numerous well known advantages, but is not yet arrived to its

utmoſt perfection; for it is not yet certainly known, whether the ingrafted ſcion gives or takes any property to or from the tree, which receives it, except that it acquires nouriſhment from it.

There is one inſtance recorded by Bradley, where the ſcion of a variegated jaſſamine gave variegation to the leaves beneath it of the unvariegated jaſſamine, on which it was ingrafted, though the graft itſelf periſhed. See Sect. V. 1. This ſeems to ſhew, that a communication of juices exiſts between the graft and the ſtock; and that thus ſome change in the colour of the leaves of the ſtock might be occaſioned by the inoſculation of the veſſels of the new bud with thoſe of other buds in its vicinity. Thus if a ſcion of a purple grape was ingrafted on a white one, the leaves of the latter might probably become ſomewhat red in the autumn, like thoſe of the purple-vine; but there are no inſtances recorded, where this communication of juices from the graft to the ſtock, or from the ſtock to the graft, has varied the flavour or the form of the flowers, or fruit of either of them.

For though the ſame vegetable blood paſſes along both the upper and lower part of the caudex of the new ſcion, which extends from its ſummit on the branch to its baſe in the earth; yet the molecules ſecreted from this blood are ſelected or formed by the different glands of the part of the caudex, which was brought with the ingrafted ſcion, and of the part of it which remained on the ſtock, in the ſame manner as different kinds of ſecretions are produced from the ſame blood in animal bodies.

Some have nevertheleſs believed, that ſcions, ingrafted on more vigorous trees of the ſame genus, have acquired greater vigour in the growth both of their leaf-buds and fruit-buds. Mr. Speechly aſſerts, that he has improved many kinds of vines by ingrafting thoſe, which bear ſmall grapes, and which have generally weak wood, on ſtronger ones, which he has often experienced; and recommends the Syrian vine to graft upon, and prefers thoſe, which were raiſed from ſeed

for this purpoſe; and the contrary ſeems to appear, where more vigorous ſcions have been ingrafted on leſs vigorous ſtocks; as apple-ſcions on crab-ſtocks; where in a few years the part above the grafted joint becomes much larger in diameter than that below it.

Grafted ſcions ſucceed well in general on trees of the ſame genus, as in the common ingraftment of fruit-trees; ſo the laurel, prunus lauro-ceraſus, will grow on the common cherry, prunus ceraſus, and produce a tall evergreen tree. But there are ſaid to be inſtances alſo of ſucceſs in the ingraftment of trees not only of different genera, but even of different orders, and claſſes; as I have been informed, that apple-ſcions, pyrus malus, have grown, when ingrafted on hazels, corylus. And one of the fathers of the Carthuſian order is ſaid to have ſucceeded in grafting a vine, vitis, on a fig-tree, ficus; and a jaſſamine on an orange. Travels in France and Italy, by E. Wright. It is hence probable, that many new diſcoveries might be made by more frequent experiments on this ſubject.

It nevertheleſs appears, that in grafted trees, though the ſtock annually becomes covered with a new bark, as well as the graft, yet it does not change its nature; ſince any new buds, which come out from the ſtock afterwards, are ſimilar to the ſtock, not to the graft; and in many trees the graft grows ſo much faſter as to become nearly of double the diameter of the ſtock, as is frequently ſeen in old cherry-trees, and is ſpoken of in Sect. VII. 1. 7.

Thus the buds of fruit-trees, like the bulbs of tulips, when raiſed from ſeed, annually improve in their colour, length, thickneſs, and often in the ſhape of their leaves, for a certain number of years; and then acquire a male, or a female, organ of reproduction, as in the claſſes of monœcia, and dicœcia; or both, as in hermaphrodite flowers. After this period the central buds and bulbs annually produced are in every reſpect ſimilar to their parents, as mentioned in Sect. VII. 1. 3. except in the nearer progreſs to old age of the tree, or of the bulb-progeny; and the conſequent tendency to hereditary diſeaſes. But the

lateral buds from the lower parts of the caudex of the central ones, which are not generated in the boſoms of leaves, are of a more immature kind, and in that reſpect do not reſemble the central bud, or bulb; but require ſome years before they flower.

Mr. Knight has obſerved, that the grafts from thoſe fruit-trees, which have been in public eſtimation for a century or two, are now ſo liable to canker, that they bear very little fruit, and are not worth cultivation; which he aſcribes to the age of the tree; as a graft he ſays is ſimply an elongation of the parent tree. And as it demands ſome years to acquire the puberty neceſſary for ſexual generation, ſo it may become weak and inirritable by age, and periſh about the ſame time with the original tree; which is ſomewhat countenanced by another remark of Mr. Knight, that the ſummits, or long extremities of old trees, frequently die many years before ſome ſmaller branches from the trunk, which continue to flouriſh, as is frequently ſeen in old oaks as well as in fruit-trees; and which he might ſuppoſe to be occaſioned by the greater age of the terminal buds than of the lateral ones, as well as from the greater length of their abſorbent veſſels, and the conſequent greater reſiſtance to the aſcent of the ſap-juice, which may alſo be ſooner impeded, or totally ſtopped by the inirritability of old age.

Nevertheleſs as the buds of trees are ſucceſſive progenies, and cannot therefore be liable to old age, as they die annually; the degeneracy of the buds of very old trees, or of thoſe which have long ſucceeded each other by their lateral, and not by ſexual generation, muſt ariſe from their being liable to hereditary diſeaſes only, and not to hereditary improvements, as obſerved above in Sect. XIV. 1. 6.

That the degeneracy of ſome plants is owing to hereditary diſeaſes, and not to old age, appears from their continuing for long uncounted periods of time after the production of theſe diſeaſes, as berberries without ſeeds, and vines without ſeeds, and ſtrawberries without fruit, though probably with ſeeds, as the barren hautbois ſtrawberries,

ſtrawberries, which bear no fruit, ſo called, have perfect ſtamina and piſtilla, as I this day obſerved with a good lens; to which may be added thoſe female figs which have no aperture to admit impregnation, and the monſtrous double flowers, which have loſt the power of ſeminal propagation, and ſome mule-plants, which never poſſeſſed it.

We have nothing in the animal ſyſtem, except in the polypus, and a few obſcure inſects, ſimilar to lateral generation; and cannot therefore decidedly argue on this ſubject. Nor have we any thing ſimilar to ingraftment in animals, except that of inflamed parts growing together, the tranſplantation of teeth, and conſtruction of artificial noſes from the ſkin of the patient's arm, ſeriouſly delivered by Talicotius, with many engraved plates in a work on that ſubject. But this ingraftment of noſes was unfortunately burleſqued by the author of Hudibras; and perhaps this ingenious idea of Mr. Knight, that the ingrafted ſcion becomes diſeaſed by age, and periſhes about the ſame time with the parent tree, may be liable to a ſimilar ridicule by ſome future writer on gardening.

> So learned Talicotius from
> The brawny part of Porter's bum
> Cut ſupplemental noſes, which
> Would laſt as long as parent breech;
> But when the date of Knock was out,
> Off drop'd the ſympathetic ſnout.
>
> CANTO I. l. 281.

There is an apple ſaid to exiſt at New York in America, which is aſſerted to be ſour on one ſide of it, and ſweet on the other ſide; and to have been produced by ſlitting a ſcion of a ſour apple, and another ſimilar one of a ſweet apple, taking care to cut the buds of each ſcion with a very ſharp knife exactly in half, and by applying them and binding them nicely together, and then ingrafting this double

ſcion on a tree. I mention this, as it is related by Mr. Jay in the communications to the Board of Agriculture, Vol. I. part 3 and 4, p. 362; and is referred to in the Memoirs of the American Academy, Vol. I. p. 386. But there muſt undoubtedly have been ſome miſtake in reſpect to the production of ſuch an apple by any method of grafting, and which is ſo well explained as above by Mr. Bradley.

It only remains here to add in reſpect to grafting, that it is neceſſary to apply the bark, which contains or conſiſts of the caudex of the young ſcion, exactly to the bark of the branch, into which it is inſerted, or applied; and then all ſpecies of ingrafting ſucceeds, whether it is performed on a branch or on a root; and whether by exciſion, or inoculation, or inarching. But I ſuſpect, that where a ſingle bud is inoculated, it has often failed from the unſkilful operator having ſelected a flower-bud inſtead of a leaf-bud; which probably unites its caudex to thoſe of the ſtock with leſs vigour, and certainly dies after it has ripened its ſeed; or by his imprudently holding the bud in his mouth, as he aſcends the ladder, or while he makes the inciſion, and thus deſtroying it by heat, as I once obſerved. A leaf-bud may in general be diſtinguiſhed from a flower-bud by its being ſharper pointed and leſs ſpherical.

Where the ſummits of very young ſcions of only a few weeks old are to be uſed to ingraft with and upon, it may be neceſſary alſo to apply the pith exactly to the pith; as this ſummit bud is yet a primary being, and not like a lateral one, whoſe whole caudex exiſts in the bark, which adheres to it, when it is taken off for inoculation.

The choice of buds for the purpoſe of inoculation is probably of more conſequence than has hitherto been imagined. As we have endeavoured to ſhew, that buds from parts of the bark diſtant from the central bud, and which are not generated in the boſom of a leaf, are in different ſtates of maturity; they muſt require more years before they can produce a ſexual progeny of flowers, and a conſequent

ſeminal

ſeminal offspring, with the reſervoir of nutriment, or fruit, which attends it. A ſubject which is new, and merits to be further inquired into.

It is curious to obſerve, that when harſher fruits become ſweeter, that the bloſſom becomes whiter, as is univerſally ſeen in thoſe of our native crabs, and of our cultivated apples; and that the buds become larger, and the green leaves alſo become of larger area, and of paler complexion.

Thus Mr. Knight obſerves, "that the width and thickneſs of the leaves generally indicate the ſize of the future apple; and the colour of the black cherry and purple grape may be known by their autumnal tints; and that even in plants, which have ſprung from ſeed in the preceding ſpring; as the tinging matter in the leaves of theſe plants is probably of the ſame kind as that, to which the fruits will in future owe their colour." The leaves of the purple grape become quite red in autumn, as well as thoſe of the geranium robertianum, and many other kinds of foliage, which I ſuppoſe may be owing to their abundancy of acid, which uniting with the blue part of what conſtitutes along with the yellow part the green colour of vegetable leaves, converts it to red; as it changes the colour of blue flowers into red ones.

5. A tranſlation of the beautiful lines in Virgil's Georgics on ingrafting may amuſe the reader.

Where cruder juices ſwell the leafy vein,
Stint the young germ, the tender bloſſom ſtain;
On each lop'd ſhoot a foſter ſcion bind,
Pith preſs'd to pith, and rind applied to rind.
So ſhall the trunk with loftier creſt aſcend,
And wide in air robuſter arms extend,
Nurſe the new buds, admire the leaves unknown,
And bluſhing bend with fruitage not its own.

II. TO INCREASE THE NUMBER OF FRUIT-BUDS.

The terms ſtrength and weakneſs, in their uſual acceptation, when applied to the vegetation of trees, are metaphorical expreſſions, or denote the effect or conſequence, rather than the cauſe, of their bearing leaf-buds or flower-buds, as ſpoken of in Sect. IX. 2. 7. For the production of leaf-buds, or flower-buds, though it may be ſaid to accompany the greater or leſs vigour of a tree, depends on the facility or difficulty, with which the long caudexes of the new buds, which conſtitute the filaments of the bark, can be generated.

Thus the new vegetable production formed in the axilla of a leaf about Midſummer, which is called a leaf-bud, conſiſts of many embryon buds, perhaps twenty or thirty, which are to form the next year's ſhoot; and each of theſe muſt be furniſhed at the ſame time with a long caudex in miniature, extending from the leaf or ſummit to its radicle or baſe; which conſiſts of umbilical veſſels for its vernal nutriment, and of a continuation of other abſorbent veſſels, and of arteries and veins, as deſcribed in Sect. VII. 1. 7. which paſſes along the branches and trunk from the apex or leaf of the bud in the air to its baſe or radicle in the ground; and which thus forms the new bark, and contributes to thicken and ſtrengthen the trunk and branches of the tree; becauſe each new leaf-bud with its ſummit, caudex, and radicle, continues afterwards to adhere to the parent tree.

But the production in the axilla of a leaf, which is called a flower-bud, or fruit-bud, conſiſts only of an individual vegetable with the rudiments of a number of flowers, with one caudex for its growth and nutriment; for as the ſeed falls from the tree, when ripe, no new apparatus of caudexes in miniature for each individual ſeed, as for each individual embryon-bud, is required to paſs down the trunk into the ground to form a new bark; and thus to thicken and to ſtrengthen the trunk and branches.

Add

Add to this, that not only the ſeeds require no new caudexes to paſs down the trunk, but that probably the ſtamina and coral of each flower ſtrike their roots only into the blood-veſſels, which communicate with the bractes, like moſſes or funguſes, which grow on trees, or like cuſcuta, dodder, viſcum, miſletoe, and tillandſia, and epidendrum; and therefore require no caudexes and radicles to paſs down into the ground.

Whence it appears, that by rendering it more difficult for new buds to acquire new caudexes along the branches or trunk from the ſummit into the ground, the tree will be neceſſitated to produce flower-buds in preference to leaf-buds; a theory, which was firſt delivered in the Botanic Garden, Vol. I. canto 4. l. 470, note, and explains the whole art of the management of fruit-trees.

Vegetables therefore in reſpect to their mode of propagation are either viviparous or oviparous. The live progeny of vegetables conſiſts of the buds, which riſe on their branches in the boſom of each leaf, or on its long caudex extending down the bark of trees; or which ariſe on the bulbs, knobs, wires, or ſcions, from the broad caudex on the roots of herbaceous plants. The egg-progeny of vegetables conſiſts in their ſeeds, with the previous apparatus of the flower, and concomitant nutriment in the fruit and cotyledons. And as plants, or parts of plants, are ſaid to be in greater vigour, when the viviparous progeny is prevalent; as the caudexes of this adherent offspring form a new bark, and thence thicken and ſtrengthen the trunk and branches; and to be in leſs vigour when the oviparous progeny is prevalent; as the ſeeds fall from the tree, and conſequently require no caudexes to form a new bark, and thence to thicken and ſtrengthen the tree. We ſhall generally uſe the word viviparous inſtead of vigorous, when applied to vegetables, which generate leaf-buds principally; and oviparous inſtead of weak, when applied to vegetables, which generate flower-buds principally; for the

words vigorous or weak may properly expreſs the greater or leſs health of vegetables in both theſe ſituations.

The reader will pleaſe to obſerve, that in the Botanic Garden we have called the bark of trees an intertexture of the roots of each individual bud; but that this is not accurate language, as the filaments, which conſtitute the bark, are each of them the caudex of a bud, or central part of it; which has a leaf at its upper extremity, and a radicle at its lower one. And that each new caudex, or bark filament, is generated along the whole trunk of the tree by the caudex or bark filament beneath it; as appears in thoſe fruit-trees where one, or two, or three ſcions have been ingrafted on each other, as mentioned in Sect. VII. 1. 7. for in theſe compound trees, when a bud ariſes from any part of the trunk, it is ſeen to reſemble that part of the ſtock, and not to reſemble the new grafted ſcion above it. We finally ſuppoſe, that this whole long caudex of a new bud is generally generated all at the ſame time by the ſympathetic action of the parts of the parent caudex along with the bud in the boſom of the leaf of that parent caudex; and that it is not gradually produced, as we firſt ſuppoſed, by the elongation of the roots of each budlet in the boſom of the leaves.

The following methods will contribute to prevent the young buds from ſo readily acquiring new caudexes on the trunk of the tree; and will therefore retard the generation of leaf-buds, and conſequently aſſiſt the generation of fruit-buds; and ſhould be executed about Midſummer, or ſoon after, as at that time the new buds are formed.

1. *The firſt method conſiſts in bending the viviparous branches to the horizon, which converts them into oviparous ones*, for by the curvature of ſuch branches the bark will be compreſſed on the under ſide, and extended on the upper ſide of the curve, and its veſſels on both ſides will be contracted in their diameters, and thus the difficulty of producing new caudexes for the generation of embryon leaf-buds will

be increaſed, in whatever ſtate of miniature they may be conceived to exiſt.

A curious fact ſeems to be eſtabliſhed by the experiments of Dr. Walker in the firſt volume of the Edinburgh Tranſactions, which ſhews, that the bending of a branch even below its inſertion into the trunk does not impede the aſcent or derivation of the vernal ſap-juice into it; but on the contrary, that it rather appears to aſſiſt it, reſembling in ſome meaſure a capillary ſyphon, as mentioned in Sect. III. 2. 4. which may be owing to the vernal ſap-juice aſcending principally, or entirely, in the ſap-wood, as appears by the new leaves expanding to a certain degree on decorticated oak-trees, as ſhewn in Sect. IX. 2. 8. And as the veſſels of this alburnum are more rigid, they may be leſs liable to contraction or coarctation by bending down the branch than the bark-veſſels, as well as from their being placed within the latter, and therefore leſs liable to compreſſion beneath the curvature, and to elongation above it.

Whence it appears, that the bending down a branch of a fruit-tree below the horizon does not diminiſh the nutriment of the fruit-buds, but rather increaſes it; as Dr. Walker obſerved theſe buds to grow ſooner and larger at the extremities of the bended branches than on other parts of equal height.

It was aſſerted by Mr. Lawrence, that the more the branches of any tree are carried horizontally, the more apt that tree is to bear fruit; and that the more upright or perpendicular the branches are led, the more diſpoſed is that tree to increaſe in wood; which he aſcribes to the bending down of the branches impeding the circulation of the ſap. Art of Gardening. Mr. Hitt in his Treatiſe on Fruit Trees, affirms, that if a vigorous branch of a wall-tree be bent down to the horizon or beneath it, it loſes its vigour, and becomes a bearing branch; and therefore recommends his method of nailing the branches of wall-trees, and of tying thoſe of eſpaliers, in an horizontal direction or ſtill lower; as in this conſtrained ſituation there

muſt occur greater difficulty, I ſuppoſe, in the production of the new caudexes, neceſſary for the embryon progeny of buds, upwards or horizontally along the bended branch contrary to their natural habits, as well as from the compreſſion of the bark beneath the curvature of the branch, and its extenſion above it; whence more flower-ſhoots are produced, which do not require new caudexes to paſs along the bended branch; but which permit their progeny, the ſeeds, to fall upon the earth, and penetrate it with their new roots.

In Lord Stafford's gardens at Trentham I remember to have ſeen many years ago ſome ſtandard dwarf apple-trees with all their branches bent down, and fixed on a ſlight frame-work about a foot from the ground; which ſeemed to be uncommonly prolific, as a circle of white and purple flowers twenty feet in diameter on branches radiated from a center, appeared to a diſtant eye like a lunar halo, or a carpet of rich embroidery.

The greater production of fruit-buds on branches bended to the horizon muſt contribute, I ſhould ſuppoſe, to the prolific effect of training nectarine and peach-trees on tiles laid on the ground, or on the gentle declivity of a bank of earth facing the ſouth, which has lately been recommended by ſome one, whoſe name I do not recollect, who gained a patent for his diſcovery. And it is indeed probable, that both theſe modes of training fruit-trees, one of which may be called an horizontal wall-tree, and the other an horizontal eſpalier, would repay the labour of the horticultor; as they would be expoſed to a more vertical ſun in ſummer, which might more certainly ripen their fruit; and would be kept ſomewhat backwarder in the early ſpring, by the greater obliquity of the ſun-beams, and might be therefore leſs liable to injury from the vernal froſt; and when in bloſſom might eaſily be covered in the night, when neceſſary, by mats thrown over them ſupported by ſtakes with horizontal poles on them.

2. Secondly. *The twiſting a wire, or tying a waxed ſtring, round the*

the viviparous branches of a tree, induces them to become oviparous, as obſerved by Mr. Whitmill, who bound not only the viviparous ſhoots of various wall-trees with ſtrong wire, but alſo ſome of their large roots, and thus increaſed the product of his fruit. Bradley on Gardening, Vol. II. p. 155. And M. Buffon produced the ſame effect by a tight cord round the branches, which previouſly produced leaf-buds inſtead of flower-buds. Act. Paris. ann. 1738.

M. Buffon concludes from the above experiments, that an ingrafted branch bears fruit more copiouſly, and more certainly, from its veſſels being compreſſed by the callus around the ingrafted junction, which may have this effect, and at the ſame time contribute by preventing the luxuriant growth of its leaf ſhoots to render the tree of more dwarfiſh ſtature. I am informed that many dwarf apple-trees, which are now planted in garden pots both in France and England, bear much fruit, and are elegantly placed in the centre of a deſert at luxurious tables; and that the principal art of producing them conſiſts in ingrafting them three or four times, ſcion on ſcion; ſo that the ſtem is compreſſed by the callus of three or four ingraftments before the branches are permitted to divaricate; and the trees are thus rendered beautiful dwarfs.

The effect of thus compreſſing the bark by a wire, or a cord, or by the callus round the junctures of the ingrafted ſcions, is undoubtedly accompliſhed by the increaſed difficulty oppoſed to the production of the caudexes for each new embryon leaf-bud, as above explained, and the conſequent generation of flower-buds inſtead of them.

3. Thirdly. *The wounding, or breaking a viviparous branch, or cutting away a ring of the bark, as of pear-trees, or a ſemi-cylinder of the bark of other fruit-trees, induces them to become oviparous.*

Where young trees diſcover too great vigour, Mr. Lawrence adviſes to cut the moſt vigorous ſhoots two parts in three through, leaving a large notch, that the wound may not heal too ſoon; which he adds will both render them fruitful, make them more readily conform

form to the wall or eſpalier, and preſerve ſuch as are dwarfs from too much aſpiring in very ſtrong branches, eſpecially of pears; he recommends two or more ſuch inciſions to be made in the ſame branch.

Another method he propoſes is to break the too vigorous branches half through with the hand, which he has practiſed with ſucceſs in apricots and peaches, when the branches were formed directly forward from the wall, and theſe branches have continued ſeveral years to bear fruit, though ſome have occaſionally died by effuſing gum; and though theſe inciſions and breaking the branches may be performed at any time of the year, he prefers the ſpring on account of the wet or froſt of winter. Art of Gardening.

A complete cylinder of the bark about an inch in height was cut off from the branch of a pear-tree againſt a wall in Mr. Howard's garden at Lichfield about five years ago; the circumciſed part is now not above half the diameter of the branch above and below it, yet this branch has been full of fruit every year ſince, when the other branches of the tree bore only ſparingly. I lately obſerved, that the leaves of this wounded branch were ſmaller and paler, and the fruit leſs in ſize, and ripened ſooner than on the other parts of the tree; and another branch has the bark taken off not quite all round with much the ſame effect.

The theory of this curious vegetable fact receives great light from the foregoing account of the individuality of buds. A flower-bud dies when it has perfected its ſeed, like an annual plant, and hence requires no place on the bark for new caudexes to paſs downwards; but on the contrary leaf-buds, as they advance into ſhoots, form new buds in the axilla of every leaf; which new buds require new caudexes to paſs down the bark, and thus thicken as well as elongate the branch. Now if a cylinder of the bark be deſtroyed, many of theſe new caudexes cannot be produced; and thence more of the buds will be converted into flower-buds.

In

In this curious circumſtance the caudexes of the buds of the tree above the decorticated part ſeem to have emitted ſhort radicles into the alburnum; the veſſels of which muſt thus have acted as capillary tubes between the upper and lower caudexes of thoſe buds; as capillary tubes will raiſe water by the attraction of their internal ſurfaces nearly to their ſummits, when they are not too high in proportion to their diameter; but water will in no caſe flow over their ſummits, but will always ſtand with a concave ſurface below the uppermoſt rim of the tube, in which ſituation it may readily be abſorbed by vegetable radicles; and may be ſupplied from beneath by the ſap-juice raiſed by the vegetable action of the abſorbent veſſels of the caudexes, whoſe radicles terminate in the earth.

It is cuſtomary to debark oak trees in the ſpring, which are intended to be felled in the enſuing autumn; becauſe the bark comes off eaſier at this ſeaſon; and the ſap-wood, or alburnum, is believed to become harder, and more durable, if the tree remains till the end of ſummer. The trees thus ſtripped of their bark put forth ſhoots as uſual with acorns on the ſixth, ſeventh, and eighth joints, like vines; but in the branches I examined the joints of the debarked trees were much ſhorter than thoſe of other oak-trees, the acorns were more numerous, and no new buds were produced above the joints which bore acorns. From hence it appears, that the branches of decorticated oak-trees produce fewer leaf-buds, and more flower-buds. And ſecondly, that the new buds of debarked oak trees continue to obtain moiſture from the alburnum after the ſeaſon of the aſcent of the ſap in other vegetables ceaſes; which in this unnatural ſtate of the debarked tree may act as capillary tubes, like the alburnum of the ſmall debarked cylinder of a pear-tree above mentioned; or as the veſſels of the alburnum may not yet have loſt their vegetable life, they may continue to abſorb ſap-juice or water from their radicles, and carry it to the buds at the ſummits by their ſpiral contractions as in the bleeding ſeaſon.

It is probable, that if oaks were debarked in the ſummer, that much fewer leaf-buds would appear amidſt the flower-buds; becauſe many of the latter muſt be advanced too far, when the trees are debarked in the ſpring, to be converted into flower-buds by preventing the production of their caudexes, or by impeding the aſcent of the nutritive ſap-juice; which in theſe trees is lodged principally I ſuppoſe in the alburnum, as ſpoken of in Sect. IX. 2. 8. On the ſame account, when much ſap-juice is taken in the vernal months from the birch or maple for the purpoſes of making wine in this country, or ſugar in America, I am informed, that no great difference occurs in the reſpective numbers of flower-buds or leaf-buds, which then ſucceed; but that the general luxuriance of the tree is diminiſhed; which evinces, that for the deſign of generating more flower-buds and fewer leaf-buds by partial decortication, it ſhould be performed about Midſummer.

The cylindrical or ſemicylindrical decortication of a large root of a tree, as well as of a branch, is ſaid to anſwer the purpoſe of increaſing the production of fruit-buds by leſſening the number of leaf-buds; but may be ſubject to two inconveniences; firſt, that the wounded root being near the ſurface of the ground may be liable to rot like the bottoms of hedge-ſtakes; or like timber, which is kept in moiſt cellars; or the poſts of wooden bridges, which are alternately expoſed to water and to air. A ſecond inconvenience may occur from terreſtrial inſects having acceſs to the alburnum of the root, which is often full of ſweet ſap-juice to invite them, and is otherwiſe generally defended by an acrid rind.

The parts of a tree immediately below a decorticated or a ſtrangulated branch or root will generally become viviparous, and will thence be ſaid to be increaſed in vigour; that is, it will produce new leaf-buds, and thoſe of a luxuriant appearance; becauſe the injury of the bark of the branch or root will prevent the parts above from receiving ſo much of the nutritive ſap-juice, as in their ſound ſtate;

ſtate; and conſequently the parts beneath will poſſeſs more of it; and alſo becauſe theſe new buds are generated from a lower part of the caudex, and will thence be a few years before they will acquire that maturity, or puberty, which is neceſſary for the generation of flower-buds, or the production of a ſexual or ſeminal progeny; whence by ſtrangulating or decorticating the alternate branches of a pear-tree they will bear for ſix or eight years; and the other alternate ones will become in the ſame time ſtrong and vigorous, ready to undergo a ſimilar operation, when the former ceaſe to be of further uſe; but the fruit will become ſmaller in ſize, though in greater number, and ripen earlier in the ſeaſon.

In the ſame manner new root-ſcions are ſaid to be produced by ſtrangulating a branch of a root near the ſurface with a tight ſtring, or by ſlitting a root near the trunk, Evelyn's Sylva; as in theſe caſes the aſcent of the ſap-juice is impeded, and the part below becomes viviparous, or produces new leaf-buds for the reaſons mentioned in the laſt paragraph; as is frequently ſeen where the end of a branch is lopped, or beneath the ſcar of the junction of an ingrafted ſcion. On the ſame account it is not uncommon to ingraft with ſucceſs on roots taken out of the ground, and afterwards replanted; as the robinia on the root of acacia, and any other apples on the roots of the ſuckers of bur-apple, or codling, mentioned in Sect. IX. 3. 5.

For the ſame reaſon the roots of ſome plants, which are otherwiſe not eaſily propagated, will ſhoot up buds; if a part of them next the ſtem of the plant be half cut through, or raiſed out of the ground, and expoſed to the air; as in pyramidal campanula, and geranium lobatum. And for the ſame reaſon the lateral branches of numerous ſhrubs, as well as of herbaceous plants, will put forth roots, when they are bent down into the ground, if they are previouſly wounded to prevent the free ſupply of the vegetable nutriment in its uſual courſe, as in laying carnations, dianthus.

A method of converting the viviparous branches of pear and apple

trees into oviparous branches is deſcribed by Mr. Fitzgerald in the Philoſph. Tranſact. Vol. LII. and ſeems to be ſuperior to the exſection of a cylinder of the bark above mentioned; as the alburnum is not left naked after the operation. In the month of Auguſt he made a circular inciſion round the principal branches of ſeveral pear-trees, apple-trees, plum-trees, and cherry-trees, near the ſtems of each, quite through the bark. About three or four inches higher he then made another inciſion round the bark, and then a perpendicular one, joining theſe two circular ones, and ſeparated the cylinder of bark nicely from the wood, covering it, and the bare part of the wood, from the air for about a quarter of an hour, when the wound began to bleed. He then replaced the bark with great exactneſs, and bound it round rather tightly with baſs, ſo as to cover the wound entirely, and half an inch above and below the circumciſions.

In about a month the bark began to ſwell above and below the bandages, he then unbound them, and found the parts quite healed. He rebound them ſlightly with baſs, and let them remain ſo till the beginning of the next ſummer, when he again took off the bandages, and found them all healthy; and every one of them bore plentifully that ſeaſon, though it was in general reckoned a ſcarce fruit year.

He treated two young pear-trees in this manner, which never had yet had any bloom; on one of them he operated on the main arms, and on ſeveral of the leſs branches from thoſe main arms; and on only one of the main arms of the other. The firſt, he ſays, bore a ſurprizing quantity of fruit in the next ſummer; and the circumciſed arm of the other bore a moderate quantity; though no other part of the tree had any appearance of bloom.

Mr. Fitzgerald afterwards took a cylinder of the bark from the branches of two young apple trees about the ſame ſize, as exactly as he could by meaſure; and changing them, bound them each on the other tree. The bark of one had a leaf-bud and two apples growing on it; the barks of both of them healed perfectly, the leaf-bud put forth

forth leaves, and the apples remained on and ripened; and both the branches bore ſo plentifully, that one broke with its load, and it was neceſſary to prop the other.

The theory of the ſucceſs of theſe curious experiments confirms that delivered above concerning the ſcars made by the junction of ingrafted ſcions with the ſtocks; and it is probable, that three or four circular inciſions through the bark on viviparous pear or apple trees, or a ſpiral inciſion, as deſcribed in Sect. IX. 2. 8. might anſwer the purpoſe without detracting and replacing the bark; as ſcars or callous circles would be thus produced, which might render it more difficult for the new caudexes of the embryon leaf-buds to be generated, or their parts united, and conſequently increaſe the number of flower-buds.

Mr. Fitzgerald further obſerves, that he changed cylinders of the bark with equal ſucceſs of nectarine and peach trees; and that the branches thus operated upon were retarded in their general growth; which coincides with the idea of repeatedly grafting one ſcion above another on the apple-trees deſigned for dwarfs to be ſet in garden pots, as deſcribed in No. 2. 2. of this Section.

4. *The tranſplanting a viviparous fruit-tree, or deſtroying ſome of its roots before Midſummer, or the confining its roots in a garden pot, or on a floor of bricks beneath the ſoil, will induce it to become oviparous.*

Mr. Knight, in his treatiſe on the Culture of the Apple and Pear, p. 83, has the following paſſage. "In the garden culture of the apple, where the trees are retained as dwarfs or eſpaliers, the more vigorouſly growing kinds are often rendered unproductive by the exceſſive, though neceſſary, uſe of the pruning knife. I have always ſucceeded in making trees of this kind fruitful by digging them up, and replacing them with ſome freſh mould in the ſame ſituation. The too great luxuriance of growth is checked, and a diſpoſition to bear is in conſequence brought on." The ſame obſervation was made by Mr. Lawrence, who took up trees which were too vigorous;

that is, which produced viviparous buds inſtead of oviparous ones, and replanted them to render them fruitful. Art of Gardening. Lond. 1723.

In tranſplanting trees for any purpoſe it may be obſerved, that they ſhould not be replanted deep in the ſoil, ſince the moſt nutritive or ſalubrious parts of the earth are thoſe within the reach of the ſun's warmth, of the deſcending moiſture, and of the oxygen of the atmoſphere. And as the root-fibres of trees, like thoſe of ſeeds, always grow towards the moiſteſt part of the ſoil, as the young ſhoots and leaves grow towards the pureſt air and brighteſt light; it follows, that the root-fibres ſeldom riſe higher in the ground than they were originally ſet, and ſeldom elongate themſelves even perfectly horizontally; ſo that when a fruit-tree is planted too deep in the earth, it ſeldom grows with healthy vigour, either in reſpect to its leaf-buds or its flower-buds.

This curious effect cannot be produced by generally debilitating the tree from its want of due nouriſhment; becauſe it is ſaid to ſucceed beſt in very good ſoil, or by the addition of new garden mould, as before directed; but by rendering more difficult the production of radicles from the caudexes of the embryon leaf-buds; which deſcend to the fineſt ramifications of the old roots, and elongate themſelves beyond the extremities of their ultimate fibrils; a great number of which roots being torn off by tranſplantation, or compreſſed in a garden pot, the production or progreſs of many of the new radicles muſt be impeded or prevented; and the numerous caudexes of new leaf-buds be in conſequence formed with greater difficulty, whence an increaſed tendency to generate flower-buds.

For the ſame reaſon if beans, vicia faba, which are but a few inches high, be tranſplanted; they do not become ſo tall, but they flower and ripen their ſeeds ſooner; becauſe they can not ſo eaſily generate new leaf-buds. The ſame occurs in frequently tranſplanting brocoli, braſſica; the plant does not grow ſo tall, but has earlier flowers,

flowers, and in greater number; and it is hence better to pluck them up, than to dig them up, for the purpoſe of replanting them; as by that means more of the root-fibres are torn off, and the plants become almoſt totally oviparous.

It is well known, that the veſſels of animal bodies are leſs liable to bleed, when they are torn aſunder, than when they are cut with a ſharp inſtrument; as their diameters are contracted, or their internal ſurfaces brought into contact with each other, in the act of extending them, till they break. Thus if the navel-ſtrings of new born animals are cut inſtead of torn, they are liable to bleed to death; and there is a remarkable caſe of a miller's ſervant, who had his arm and ſhoulder bone, or ſcapula, torn off in a windmill without much loſs of blood. This is mentioned to ſhew, that it may alſo be better to tear up roots, which are tranſplanted for this purpoſe, than to dig them up; as they may thence effuſe leſs vegetable blood, and in conſequence be leſs weakened by the operation.

In tranſplanting ſtrawberries many of the roots being torn off, fewer leaf-buds, and conſequent wires, are produced from the difficulty, which their embryon caudexes find in producing new radicles over the old ones to ſupply nutriment to the wires, till they bend down and protrude roots into the ground at their other extremities, whence a greater number of flower-buds are generated; on this account the roots of ſtrawberries ſhould generally be tranſplanted, or new ones from the wires ſhould be cultivated, every third or fourth year, to prevent the too luxuriant growth of their wires; or a ſimilar difficulty of producing wires or leaf-buds may be effected by crowding the roots of ſtrawberries together, as ſome gardeners recommend; but I ſuppoſe by theſe means the fruit may become ſmaller from ſcarcity of nutriment, though more numerous.

A floor of bricks, or of ſtone, extended about two feet deep beneath the roots of wall trees, has been practiſed in ſome gardens from an idea, that the roots ſhot themſelves too deep into ſome unwholeſome

ſome ſtratum of earth; and it has been obſerved, that the trees became better fruit-bearers. In ſome ſituations it is poſſible, this might be the cauſe of the new prolific property of the trees; but I ſuſpect it has occurred generally from the difficulty oppoſed to the number and elongation of the root-fibres, and conſequently to the generation of the new caudexes of the embryon leaf-buds; whence a greater production of flower-buds enſued.

In ſimilar manner it is aſſerted by one of the Linnean ſchool in the Amœnitates Academicæ, that ſome bulbous rooted plants, which ſeldom produce ſeeds in Sweden, will produce prolific ſeeds, if their roots be confined in a garden pot, till they crowd each other; as thoſe of the lily of the valley, convallaria. And that the orchis will bear prolific ſeeds, if the new root early in the ſeaſon be ſevered from the old one, which has put up the flower-ſtem. This muſt occur in the former caſe from the difficulty, which the plants find to generate new offsets at their roots, which are their viviparous progeny; and in the latter caſe from the new offset being deſtroyed; whence in both ſituations more nutriment is expended on the flower.

On the ſame account it is probable, that confining the roots of cucumbers and melons in ſmall garden pots would ſtop the too luxuriant growth of their leaf-buds, and render them ſooner oviparous, if care was taken to ſupply them with water more frequently, and with ſufficient nutriment by mixing with the water ſome of the carbonic black fluid, which has drained from a manure heap.

5. *If the central viviparous branches of a plant be cut away or ſhortened, the lateral ones will ſooner or more completely become oviparous.* 1. There are many very ſmall buds on the lower parts of large branches, which do not ſeem to grow to maturity, and in conſequence produce neither new leaf-buds nor new flower-buds. There are other lateral ſhoots on many trees, which only puſh out a few inches, and are called ſpurs, and which bear fruit the ſucceeding ſummer at their extremities. In many other plants the lateral branches are oviparous,

except at the extremity, which is terminated with a viviparous bud; while the central branches continue long to generate only a viviparous progeny, as in vines and melons.

The firſt of theſe, or the unprolific exiſtence of the buds at the bottom of large branches, may be owing in part to their feebler efforts of pullulation from the want of ſufficient ſunſhine and ventilation; and alſo in part, like the ſpurs, and other lateral branches, to the difficulty they encounter in producing the embryon caudexes of new leaf-buds along the trunk; which is already occupied by thoſe of the more vigorous vegetation of the central branches, which poſſeſs a greater ſhare of ſunſhine and ventilation.

But the principal cauſe, which renders the ſpurs and lateral branches oviparous, reſults from the reſiſtance the embryon caudexes of leaf-buds experience by the curvature of the lateral branch, where it joins the trunk, and the conſequent coarctation of its veſſels, added to the difficulty every lateral bud has to encounter from its own curvature at its exit from the parent twig; on which laſt account the central bud at the extremity of an oviparous branch is generally viviparous, becauſe it has not any curvature at its exit. All this correſponds with the fact above deſcribed, that when the viviparous arms of wall-trees are bent down to the horizon, they become oviparous. See No. 2. 1. of this Section.

2. What then happens in all theſe ſituations when the central parts are cut away or ſhortened? Firſt the dwarf buds at the bottom of theſe large viviparous branches, which are in part cut away, will find more room to puſh down the embryon caudexes of new leaf-buds; and will produce a viviparous progeny; and thoſe at the bottom of oviparous branches, which are ſhortened by cutting off their viviparous extremities, will alſo now pullulate, and produce flower-buds for the ſucceeding year, owing to the derivation of ſome of that nouriſhment to them, which would otherwiſe have been expended on the ſummit-bud. Secondly, the ſpurs will generate an oviparous progeny,

geny, but will acquire more nutriment, becauſe all the veſſels of plants inoſculate, as mentioned in Sect. IX. 2. 10. and will thence produce larger fruit, and more certainly ripen it. Thirdly, the other lateral branches will receive more nouriſhment, and become more vertical, and will thence find leſs oppoſition to the production of the caudexes, both of their flower-buds and leaf-buds; either of which may become ſtronger or more numerous according to the greater or leſs inclination of the branches to the horizon; and both of them may be more vigorous properly ſpeaking; that is, they may become larger leaf-buds, or larger flower-buds, than others of the ſame tree.

3. Thus in the management of MELONS, which would grow into branches much too extenſive for the artificial glaſs-frames of our climate, and would not have time to ripen their later fruit in our ſhort ſummers; it is neceſſary firſt to check the vigour, properly ſo ſpeaking, of the whole plant. This is done by waſhing the ſeed from the ripe fruit, which ſhould naturally contribute to nouriſh it; and by keeping the ſeed four or five years, that the mucilaginous nutriment depoſited in the cotyledons may alſo be in ſome degree impaired; it is alſo probable, that confining the roots of melons and cucumbers in garden-pots, if they were well ſupplied with nutriment, warmth, and water, might be advantageous for this purpoſe.

Secondly, as ſoon as the leaf appears an inch in diameter, experienced gardeners pick out the central bud, which cauſes an oviparous, though a more vigorous, lateral ſhoot; which therefore ſooner bears fruit, and that of a larger kind; as it acquires more nouriſhment from the deſtruction of the central one.

And as theſe lateral branches are liable to produce other viviparous ſhoots at their extremities, after they have generated lateral flower-buds, it again becomes neceſſary to pinch off the viviparous extremities of them, not only to accommodate them to the ſize of the glaſs-frame, but alſo to ſupply them with more nutriment, which would otherwiſe have been expended on the viviparous ſummit.

The

The central bud, or ſummit, of the lateral branches, is generally viviparous, as well as of the central branches; becauſe the embryon caudexes of its new offspring are oppoſed in the production along the bark by only one curvature at the inſertion of the branch into the trunk; whereas the lateral buds of the lateral branches have the progreſs of the embryon caudexes of their new buds oppoſed by two curvatures, one of the bud to the branch, and another from the branch to the trunk.

There is another reaſon, why the lateral buds of many plants produce flowers ſooner than the ſummit; which is, that the lateral buds of thoſe plants, where the pith of the upright central ſhoot is not divided, are propagated from the central ſhoot, and are therefore one generation older; and have thus acquired the maturity neceſſary for amatorial reproduction. In other plants, where the pith of the ſtem is divided at every joint, the ſummit bud has been preceded by more generations, and is therefore more mature for the purpoſe of producing flowers, than the lateral ones, as in a ſtem of wheat; and probably in the artichoke, and on the ſpurs of ſome fruit trees, as of pears.

4. It was obſerved in Sect. IX. 3. 1. that in the ſtems of wheat three or four joints are formed above each other previous to that, which bears the ear; and that in many other annual or biennial plants two or three viviparous lateral ſhoots occur, as in artichoke, cinara; and ſalſafi, tragopogon, before the central one flowers. The ſame happens to the vine-ſhoots; two or three joints with a leaf and a viviparous bud at each are always firſt produced; and as each of theſe have a diviſion of the pith between every joint, as remarked in Sect. I. 8. I ſuppoſe, that theſe joints are ſeparate plants growing on each other like the joints of the ſtem of wheat; and that hence in vine-ſhoots three or four ſucceſſive generations of leaf-ſhoots muſt exiſt, before the new ſhoot can attain ſufficient maturity to form a flower; as the amatorial generation of ſeeds was ſhewn to require

higher animation, if it may be ſo called, than the lateral generation of leaf-buds. The ſame mode of growth occurs in the young ſhoots of oaks, and which is thus curiouſly accounted for.

The lateral branches of many mature trees, though they bear flower-buds on their ſides, are generally terminated with a leaf-bud, as above explained; but it happens in ſome of them, and particularly to vines, that after two or three flower-buds are produced on a lateral branch, that it ſhall proceed to grow in length, and to produce leaf-buds at every joint above the flower-buds, as well as at the ſummit; which may be thus perhaps ſatisfactorily explained. After the third, and fourth, and fifth joints of a new lateral ſhoot have generated flowers, which require few or no more caudexes; room enough is left on the bark of the ſhoot for thoſe above them to acquire the numerous new miniature caudexes of embryon leaf-buds, and where the new caudexes of embryon buds can eaſily be produced along the bark, and ſufficient nutriment is ſupplied; all vegetables are more liable to propagate themſelves by buds than by ſeeds.

Hence in the management of VINES, as well as of MELONS, it is uſeful at two or three joints above the laſt bunch of fruit to pinch off the viviparous end of the new branch, not ſo much to accommodate the length of it to the houſe, as to ſupply the growing fruit with more nouriſhment from the inoſculations of the veſſels of the caudexes of theſe viviparous buds, which are now cut off, with thoſe of the oviparous ones, which remain.

A curious vegetable fact, which appears in the culture of VINES in hot-houſes here preſents itſelf to our notice. When a vigorous ſhoot advances without producing fruit-buds at the third or fourth joint, it is frequently permitted to grow in length to above twenty feet; but at every joint the new or ſecondary bud is pinched off, either ſoon after its appearance, or after it has ſhot out one or two joints. By this management of permitting the central ſummit of the ſhoot to grow till Auguſt or September, the eyes, whoſe buds have been

pinched off, do not put out a freſh during that ſummer; but new buds are formed at each eye, which germinate the next ſummer, and almoſt all of them produce fruit.

If however ſome of the ſhoots in the boſom of theſe leaves are pinched off too ſoon after their appearance, they are occaſionally liable to generate new leaf-buds, which ſhoot out afreſh from the ſame eye; and it is ſaid, that theſe eyes, which have thus produced two leaf-buds in ſucceſſion in one ſummer, will not generally produce buds of any kind in the ſucceeding ſummer; for as ſeveral of theſe joints in vigorous vines bear two or three buds from the ſame eye at the ſame time, ſo others bear them in ſucceſſion.

The theory of theſe important facts may not be eaſy to inveſtigate; it is commonly ſuppoſed, that pinching off the lateral ſhoots at every bud of a new vine-branch ſtrengthens the next year's expected bud, by not expending ſo much nutritive juice; and that giving the vines a fortnight's artificial heat, after the ſummer heat leſſens, ripens the wood for the production of the next year's fruit; but theſe are words, I imagine, without accurate ideas. I ſuppoſe, when each lateral ſhoot of this year's branch of a vine is pinched off, that its caudexes, which had already formed a part of the bark, coaleſce; and may thus render it more difficult for the caudexes of the ſucceeding embryon bud in the ſame eye, which is to be expanded next ſpring, to be produced along the bark, by having previouſly occupied the ſituation which thoſe new caudexes would require; and that thus the ſecondary buds of theſe eyes become flower-buds, which might otherwiſe have been leaf-buds.

The continued heat a week or two above the uſual time of ſummer, which is ſaid to ripen the wood, may contribute to dry and harden it, as well as to forward the growth of the buds; and thus both to render the protruſion of embryon roots more difficult, and conſequently to produce flower-buds, and thoſe of a larger kind.

Whether a ſimilar method to this practiſed on vines could be ap-

plied with advantage in the management of other fruit-trees is a circumſtance of great importance, and can only be determined by experiment. But as the firſt foliage of euonymus is generally deſtroyed by inſects in this country, and yet a ſecond growth of foliage is produced; and as I witneſſed laſt year, that the whole firſt leaves of an apple-tree were deſtroyed, as was believed, by lightning, and which yet put forth an entire new ſet of leaves in a few weeks; is there not reaſon to conclude, that if the leaf-buds were picked out early in the ſeaſon from a ſtrong ſhoot of peach or apricot, either new leaf-buds might be produced in that ſummer, or flower-buds in the ſucceeding one, as happens to the vine-ſhoots above deſcribed; and that our wall-trees might be thus rendered more certainly prolific. And laſtly, might not the clipping out with fine ſciſſars the extremities of young vine-ſhoots, which would otherwiſe be barren ones, convert ſome of their tendrils into bunches by thus ſupplying them with additional nutriment, by preventing its expenditure in the elongation of the viviparous branch? This experiment might be the more readily tried, as ſome aſſert, that the barren buds may be diſtinguiſhed from the prolific ones by their form before they expand.

6. *Arts of producing flower-buds.*

The following quotation, partly from the Botanic Garden, Vol. I. Canto 4. l. 465, may amuſe the reader, and conclude the ſecond part of this Section.

> If prouder branches with exuberance rude
> Point their green germs, their barren ſhoots protrude;
> Lop with ſharp ſteel the central growth, or bind
> A wiry ringlet round the ſwelling rind;
> Biſect with chiſel ſharp the root below,
> Or bend to earth the inhoſpitable bough.
> So, while oppoſed, no embryon leaf-bud ſhoots
> Down the reluctant bark its fibre-roots;

New germs ſhall ſwell with amatorial power,
And ſexual beauties deck the glowing flower;
While the clos'd *petals* from nocturnal cold
With ſilken veil the virgin *ſtigma* fold,
Shake into viewleſs air the morning dews,
And wave in light their irideſcent hues;
With graceful bend the *anther* by her ſide
Shall watch the bluſhes of his waking bride,
Give to her hand the honey'd cup, or ſip
Celeſtial nectar from her ſweeter lip,
Hang in wild raptures o'er the yielding fair,
Love out his hour, and leave his life in air.

III. TO PERFECT AND ENLARGE THE FRUIT.

It is believed by ſome of the Linnean ſchool, that flower-buds or leaf-buds may be converted into each other in the early ſtate of their exiſtence, as mentioned in Sect. IX. 2. 8. It is indeed probable, that either a flower-bud or leaf-bud may be generated inſtead of each other reciprocally, before either of them exiſts; but after either of them has obtained a certain degree of maturity, ſo as to be diſtinguiſhed by its form being more pointed or more ſpherical; I ſuſpect no addition or detraction of nutriment, or of the facility of the production of its embryon caudexes down the bark and radicles beneath can change its deſtination.

1. *Shorten the oviparous branches, when the leaves fall off, by pruning their viviparous ſummits, and cut away the root-ſuckers.* The ſummits of the lateral branches, as well as the erect ones, are furniſhed generally with viviparous buds; which in many wall-trees ſhould be cut off, after the leaves fall in autumn; that more nutriment may be derived to the fruit-buds, which may occaſionally become ſomewhat enlarged during the milder days of winter; as they are now certainly too far advanced to be changed into leaf-buds; and

if

if this pruning be deferred till late in the winter months, the flower-ubds will not be quite ſo forward, as if it be performed earlier. For the ſame reaſon the root-ſuckers alſo ſhould be cut away in the autumn, that all the nutriment, which they would otherwiſe expend, may be derived to the flower-buds, and induce them early to enlarge themſelves.

2. *Pinch or rub off all uſeleſs viviparous buds in the ſpring or ſummer, as they occur.* In thoſe trees where the fruit-buds ariſe on the new leaf-ſhoots along with the leaf-buds, and cannot therefore be ſooner diſtinguiſhed or approached, as in figs and vines, the ſummit leaf-buds ſhould be pinched off two joints above the fruit-buds, as ſoon as they appear, that more nutriment may be conveyed to the fruit-buds. See No. 3. 4. of this Section.

And in the hardier wall-trees the new leaf-buds, which appear during the ſpring and ſummer months in wrong places, where they cannot be trained properly againſt the wall, or where they are too numerous, ſhould be rubbed or pinched off, as they occur; whence more nouriſhment will be derived to the ripening fruit, and to thoſe new leaf-buds which are to remain to produce future flower-buds.

And if the new buds, which are ſeen in their young ſtate in the axilla of the leaves of the new ſhoots, were picked out by the point of a knife, or pinched off, where they grow long enough for that purpoſe, as the ſecondary ſhoots of vines in grape houſes are pinched; it might probably induce thoſe eyes to produce flowers in the ſucceeding year, as ſpoken of in No. 2. 5. of this Section, as well as contribute to enlarge the preſent fruit by the expenditure of leſs nutriment on the leaf-buds, an idea well deſerving the teſt of experiment.

In the ſame manner in the cultivation of melons and cucumbers after the central bud is pinched off, as mentioned above, No. 2. 5. the viviparous extremities of the lateral branches ſhould be alſo deſtroyed, as ſoon as a ſufficient number of female flowers are impregnated; that

that a greater ſhare of nutriment may be derived to them, inſtead of crowding the frame with new branches, whoſe fruit-buds would be too late to ripen in our ſhort ſummers.

3. *Thin all thoſe fruits, which are too numerous; pluck off apricots, peaches, gooſeberries; and cut out many grapes from each bunch with ſciſſars.* By the inoſculation of the veſſels of vegetables mentioned in Sect. I. 3, when any parts of a tree are deſtroyed, thoſe in their vicinity become more vigorous. On this account when part of the fruit is taken away as early as may be, the remaining part acquires more nutriment. Add to this, that, where fruit is crowded, ſome of it becomes precluded from the ſun and air, and in conſequence does not perfectly ripen, and is liable to become mouldy; for mucor is a vegetable production, which like other fungi does not require either much light or air, as appears from the growth of ſome funguſſes in dark cellars, and of common muſhrooms beneath beds of ſtraw, as mentioned in Sect. XIII. 1. 4.

4. *Prevent the production of new leaf-buds.*

In ſome pear trees the whole of the bloſſoms become ſterile, and fall off without any apparent injury from cold, and this for many ſucceſſive years. The ſame occurs ſometimes to cheſnut trees, æſculus pavia, after the flower the fructification entirely falls off; ſome of theſe might be male flowers, as Miller obſerves, but the whole could not be ſuch. The ſame happens very frequently to the fig-trees of this climate, ſometimes the whole crop falls off, when they are about the ſize of filberts; that is, while they are ſtill in flower, which though concealed within the fig, muſt precede the ſwelling of the ſeeds, whether theſe be impregnated or not.

A correſpondent fact occurred to me a few years ago. I had ſix young trees of the Iſchia fig with fruit on them in pots in a ſtove. On removing them into larger boxes the figs fell off, which I aſcribed to the increaſed vigour of the plants; as they protruded very vigorous ſhoots occaſioned by the accumulation of new ſoil round their roots.

roots. Perhaps theſe plants might rather be ſaid to have been in flower than in fruit, and perhaps theſe flowers were all male ones only, or accompanied only with imperfect female ones?

Whence I conclude, that about the ſeaſon when the corals of theſe flowers with their ſtamens and ſtigmas die, the trees generate and nouriſh too many new leaf-buds, owing to the facility with which they can produce the new caudexes of theſe young buds down the bark; and that by the whole of the vegetable ſap-juice being derived to the new buds for their preſent growth, or to form reſervoirs for their future growth, the pericarp and ſeeds, whether impregnated or not, are deprived of their due nutriment and fall off. See Sect. XVI. 1. 4.

Hence I propoſe to tie waxed thread or fine wire round the twigs of pear-trees, which have uſually miſcarried, as ſoon as they are in flower, ſo as to compreſs, but not ſo as to ſtrangulate them; or to wound the bark by a circular or ſemicircular inciſion, which might counteract their facility of procreating new leaf-buds; which I ſuſpect would be more effectual in preventing the flowers from falling off, than pinching off the new leaf-buds, as they appear; which is recommended by Dr. Bradley in the management of fig-trees, and is done to vines in hot-houſes; but which I found to be ineffectual on many fig-branches both in the natural ground and in pots, and aſcribed its failure to the continuance of the efforts of the fig-tree to produce new leaf-buds; whereas in vines, I ſuppoſe, the grapes would ripen, whether the new leaf-buds remain or are deſtroyed. See No. 3. 2. of this Section.

Pontedera obſerved, that in the iſlands of the Archipelago ſome fig-trees bear in the ſpring many male flowers, and few female ones, the former of which fall off; and that they bear a ſecond crop chiefly of female flowers in the autumn, which ripen in the enſuing ſpring. Anthologia. Can this occur in the fig-trees of this country?

Other figs are ſaid not to ripen but to fall off before their maturity, unleſs

unleſs they be wounded by inſects in their caprification, or punctured by a ſtraw. A further inveſtigation of this ſubject is much wanted to propagate figs with ſucceſs in this climate. See Botanic Garden, Vol. II. note on caprificus. See alſo Milne's Botan. Diction. Article caprification.

5. *Give additional moiſture, manure, and warmth, during the early part of the growth of fruit.* By additional moiſture the fruit becomes larger; in hot-houſes this may be effected two ways, one by watering the earth on which the vegetables grow, and another by producing ſteam by watering the warm flues or floors; which will afterwards in the colder hours be again condenſed, and ſettle in the form of dew on the fruit and leaves.

By ſupplying vegetables as well as animals with an abundancy of fluid, they are liable to increaſe in bulk, both becauſe the external cuticle, which confines the growth of both of them, becomes relaxed, as is ſeen in the hands of thoſe women, who have many hours been employed in waſhing; and alſo becauſe the cutaneous abſorbent veſſels will thus imbibe more fluid from the external ſurface; and the cellular abſorbents will therefore imbibe leſs from the internal cells, and conſequently more mucus or fat will remain in them.

Thus in Lancaſhire, where premiums are given for large gooſeberries, I am told, that ſome of thoſe, who are ſolicitous for the prizes, not only thin the fruit of a gooſeberry-tree, ſo as to leave but two or three gooſeberries on a branch, but then by ſupporting a tea-ſaucer under each of theſe gooſeberries, bathe it for ſome weeks in ſo much water as to cover about a fourth part of it, which they call ſuckling the gooſeberry.

In ſome parts of the Carnatic, where rice is cultivated, they are ſaid not to derive the water on it, till it is in flower; becauſe that would induce the ſtem to ſhoot too luxuriantly, like our wheat-crops in wet-ſeaſons; but, as ſoon as it is in flower, they find it expedient to flood it with water for the purpoſe of filling and enlarging the

ears, (Communications to Board of Agriculture, Vol. I. p. 355,) which it may effect both by relaxing the cuticle of the grain, and preventing the too great internal abſorption of the mucus or ſtarch depoſited in the cells of it; and laſtly by ſupplying it with more nutriment.

There are two circumſtances to be attended to in giving water to plants; which are, not to water them during the hot part of the day in ſummer, nor in the evenings of ſpring, when a froſt may be expected; in both theſe circumſtances we may be ſaid to copy nature, as rain is generally preceded by a cloudy ſky, and is never accompanied by froſt; though that ſometimes follows it, and is then very injurious to vegetation.

When plants have been long ſtimulated by a hot ſunſhine into violent action, if this ſtimulus of heat be too greatly and too ſuddenly diminiſhed by the affuſion of cold water, or by its ſudden evaporation, their veſſels ceaſe to act, and death enſues; exactly as has too frequently happened to thoſe, who have bathed in a cold ſpring of water after having been heated by violent and continued exerciſe on a hot day. When ſevere froſt follows the watering of plants, they are rendered torpid, and die by the too great and ſudden diminution of the ſtimulus of heat; which is equally neceſſary to the activity of vegetable as to animal fibres; and in ſome inſtances the circulation of their fluids may be ſtopped by the congelation of them; and in others their veſſels may be burſt by the expanſion attending the converſion of water into ice; or laſtly, by the ſeparation of their different fluids by congelation. See Sect. XV. 4. 1.

When an addition of manure can be procured, as where the black carbonic juice from a dunghill mixed with water, or ſoap-ſuds, which have been uſed in waſhing, can be employed inſtead of water alone; it muſt undoubtedly add to the nutriment, and conſequently

enlarge the ſize of the fruit by that means alſo, as well as by the additional water.

Where too much moiſture is given without at the ſame time an addition of warmth, ſome inconveniences are liable to occur, as a leſs aromatic and ſaccharine flavour of the fruit. When therefore fruits become nearly ripe, leſs water ſhould be given them, unleſs it is convenient at the ſame time to increaſe the heat, in which they are immerſed, as may be done in ſome hot-houſes; and then the flavour of the fruit may be heightened, as well as its ſize increaſed, as ſhewn by Mr. Baſtard in the Philoſophical Tranſact. who planted pine-apple plants in veſſels of water, and placed theſe veſſels near the top of the hot-houſe, or on the fire-flues, for the purpoſe of ſupplying them with a greater heat; and produced by theſe means both larger, as he aſſerts, and better flavoured pine apples.

On this important ſubject I ſhall tranſcribe his words, and ſhall only add, that ſteam from boiling water is now ſucceſsfully uſed in ſome hot-houſes for the growth both of vines and of pines, but muſt require ſome attention in the application of it; as it is occaſionally conveyed through ſmall apertures, which perforate a brick arch, which is conſtructed ſomewhat like the floor of a malt-kiln, where the water boils beneath the beds of bark or of ſoil; and is occaſionally admitted into the room above, and thus ſupplies moiſture and heat both to the ground and to the air of the hot-houſe.

"My hot-houſe is covered with the beſt crown glaſs, which I apprehend gives more heat than the common ſort of green glaſs generally uſed for hot houſes. In the front part of the houſe, and indeed any where in the loweſt parts of it, the pine-apple plants will not thrive well in water. The way in which I treat them is as follows. I place a ſhelf near the higheſt part of the back wall, ſo that the pine-plants may ſtand without abſolutely touching the glaſs, but as near it as can be. On this ſhelf I place pans full of water, about ſeven or eight inches deep; and in theſe pans I put the pine-apple

plants, growing in the ſame pots of earth, as they are generally planted in to be plunged into the bark-bed in the common way; that is, I put the pot of earth with the pine-plant in it in the pan full of water; and as the water decreaſes, I conſtantly fill up the pan. I place either plants in fruit, or young plants as ſoon as they are well rooted, in theſe pans of water, and find they thrive equally well; the fruit reared this way is always much larger, as well as better flavoured, than when ripened in the bark-bed. I have more than once put only the plants themſelves without any earth, I mean after they had roots, into theſe pans of water, with only water ſufficient to keep the roots always covered, and found them flouriſh beyond expectation. A neighbour of mine has placed a leaden ciſtern upon the top of the back flue, (in which, as it is in contact with the flue, the water is always warm, when there is fire in the houſe,) and finds his fruit excellent and large.

"The way I account for this ſucceſs is, that the warm air always aſcending to the part, where this ſhelf is placed, as being the higheſt part of the houſe, keeps it much hotter than in any other part. The temperature at that place is, I believe, ſeldom leſs than what is indicated by the 73d degree of Fahrenheit's thermometer; and when the ſun ſhines, it is often at above 100°; the water the plants grow in ſeems to enable them to bear the greateſt heat, if ſufficient air be allowed; and I often ſee the roots of the plants growing out of the holes in the bottom of the pot of earth, and ſhooting vigorouſly in the water.

"It is not foreign to this purpoſe to mention, that, as a perſon was moving a large pine-plant from the hot-bed in my houſe laſt ſummer, which plant was juſt ſhewing fruit, by ſome accident he broke off the plant juſt above the earth in which it grew, and there was no root whatever left to it; by way of experiment I took the plant, and fixed it upright in a pan of water (without any earth whatever) on the

the ſhelf; it there ſoon threw out roots, and bore a pine-apple that weighed upwards of two pounds." Philoſ. Tranſact. Vol. LXVII.

6. *Protect the early flowers and the late fruits from froſt.* The vernal froſts are very pernicious to the early bloſſoms of apples and pears, and of all the tender wall-trees; various contrivances have been uſed to ſhelter them, as mats ſuſpended before wall-trees; which in Denmark are ſaid to be uſed to ſhelter them from the mid-day ſun, as well as from the night-froſts; both to prevent them from flowering too early, and being thence expoſed to ſeverer froſts; and becauſe vegetables ſuffer more from great cold, as well as animals, after having been expoſed to great heat, as explained in Sect. XIV. 2. 2.

Thoſe parts of vegetables, which are moſt ſucculent, ſuffer moſt from froſt, as the young tops of tender trees, as of the aſh, fraxinus, and weeping willow, ſalix babylonica; and alſo all other vegetables after having been expoſed to much moiſture, as to rain or dews; which probably may occur in part from the greater ſenſibility of the tender juicy ſummits of the preſent year's growth, and partly from the expanſion of their frozen juices, which may burſt the containing veſſels.

An important queſtion here occurs, is a low ſituation to be choſen for a garden? The greater warmth of low ſituations, and their being generally better ſheltered from the cold north-eaſt winds, and the boiſterous ſouth-weſt winds, are agreeable circumſtances; as the N. E. winds in this climate are the freezing winds; and S.W. winds being more violent, are liable much to injure ſtandard fruit-trees in ſummer by daſhing their branches againſt each other, and thence bruiſing, or beating off the fruit; but in low ſituations the fogs in vernal evenings, by moiſtening the young ſhoots of trees, and their early flowers, render them much more liable to the injuries of the froſty nights, which ſucceed them, which they eſcape in higher ſituations. Theſe fogs, which are ſeen by the ſides of rivers, and on damp plains or valleys after ſun-ſet, are converted into rime during the night. And as

at

at the time of theſe fogs there is generally no wind, the dew falls perpendicularly, and the rime is formed moſt frequently on the upper ſurface of objects, which may then therefore be more readily ſheltered from it than at other times, when the freezing fog is blown forwards by the wind, and the rime is formed on one ſide of the branches of trees.

In ſome circumſtances the rime is believed to defend the vegetables on which it is formed, by the heat it gives out at the inſtant of its freezing, and by covering them from the cold like ſnow upon the ground; and thence the black froſts, which are not attended with rime, are ſaid to be more prejudicial. But where dew or miſt deſcends on vegetable leaves before the act of freezing commences, and is in part abſorbed by them; they become more ſucculent, and hence are deſtroyed by their fluids being converted into ice, and burſting the veſſels already diſtended with more water, than they would otherwiſe poſſeſs. See Sect. XIII. 2. 2.

Mr. Bradley gives a deciſive fact in regard to this ſubject. A friend of his had two gardens, one not many feet below the other, but ſo different, that the low garden often appeared flooded with the evening miſts, when none appeared in the upper one; and in a letter to Mr. Bradley he complains that his lower garden is much injured by the vernal froſt, and not his upper one. A ſimilar fact is mentioned by Mr. Lawrence, who obſerves, that he has often ſeen the leaves and tender ſhoots of tall aſh-trees in blaſting miſts to be frozen, and as it were ſinged, in all the lower parts and middle of the tree; while the upper part, which was above the miſt, has been uninjured. Art of Gardening. In confirmation of this idea I well remember many years ago to have travelled ſixty miles, partly in the valley of the Trent, and partly over adjacent hills, on the ſixth of May; and to have obſerved that the new ſhoots of all the aſh-trees in the vallies had their young extremities entirely turned black by the froſt of the preceding night; but that on the hills they had eſcaped, which

I at

I at firſt aſcribed to the trees being leſs forward on the hills, but believe it was more probably owing to the greater ſucculence of thoſe in the valleys, and to their having been previouſly expoſed to the moiſture of the evening miſt.

The precipitation or adheſion of moiſture to vegetables, when miſty air is blown againſt them, is well deſcribed by Mr. White in his hiſtory of Shelborne; who obſerved on a foggy day with ſome wind, that ſo much moiſture was depoſited on a tree, that it ran down upon the ground, and filled the ruts of a lane beneath it, which was dry elſewhere. On the ſame account in the early ſpring the graſs is ſeen to become green ſooner under the ſpreading branches of trees than in their vicinity. See Botanic Garden, Vol. I. note 26.

It is hence evident, that very low and damp ſituations are not to be preferred for gardens and orchards in this climate; and that it is in all gardens an object worthy attention to protect in the early ſpring the bloſſoms and the young ſhoots from being moiſtened by the deſcending night dews; for this purpoſe ſome have put coping ſtones at the top of the fruit-walls, ſo as to project ſix or eight inches over the trees. By the ſhelter of theſe coping ſtones the deſcending dews, which would moiſten the young leaves and flowers, are prevented from falling on them, and in conſequence no rime is ſeen in the morning on theſe trees. I had once an opportunity of obſerving ſome trees beneath a projecting coping to be much ſafer in reſpect both to their fruit and foliage, than thoſe in their vicinity, and in the ſame aſpect, where there were no coping ſtones over them.

But I am informed, that after the vernal froſts have ceaſed, this kind of ſhelter is certainly injurious to the growth and perfection of the fruit; which may ariſe from the ſame cauſe, namely, the want of the ſummer night-dews to moiſten the fruit, and alſo the perpendicular ſun-beams to ripen it. On theſe accounts I have propoſed to make temporary ſheds of boards to project eight inches from the walls, to be held on by iron hooks, which might eaſily be removed,

moved, as ſoon as the vernal froſts ſhould ceaſe; and in one experiment on a ſingle apricot tree it appeared to ſucceed well.

From ſome experiments in a late volume in the Philoſophical Tranſactions, it appears, that very much more rain was caught in glaſſes placed on the ground near a high church, than was caught in ſimilar glaſſes on the roof of it; which evinces, that a much greater quantity of moiſture exiſts in the lower parts of the atmoſphere, and is precipitated from it, than from the higher parts; whence to protect the bloſſoms more effectually from the deſcending dews coping boards might be placed at every two feet or leſs above each other, with their front edges pointing upwards to the meridian ſun in March, and ledges nailed on the back edges to convey the rain or dews towards the central part of the tree, where by another croſs ledge at the end of each board it might be carried from the wall.

A ſimilar inconvenience from autumnal froſts affects ſome of the late fruits, as figs and grapes, which might alſo receive advantage from replacing the coping boards in the autumn.

Another method of effectually guarding againſt the vernal froſts, and alſo the autumnal ones, is by building the garden-walls with fire-flues in them, which is now frequently practiſed. There is one ſecret neceſſary to be known, and well attended to, in the management of fire-flues; and that is in the firſt place to plant trees, which will open their flowers about the ſame time, againſt the ſame flue, and then diligently to obſerve not to put fire into this flue, till the trees, it is deſigned to aſſiſt, are in flower; ſince if the fire be applied ſooner, the flowers are forwarded, and in conſequence expoſed to more danger from the ſeverer froſts. One friend of mine, who diligently attends to this circumſtance, aſſures me, that he never fails of producing a plentiful crop of excellent fruit.

And it is poſſible that one uſe of covering apricot trees, before they flower, from the mid-day ſun, which is ſaid to be practiſed in Denmark, may be to protract their time of flowering, and thus expoſe them

them to leſs danger from froſt, as well as to prevent their irritability from being exhauſted by the heat, and thus cauſing the night air to be more injurious to them.

7. *Fruits may be ſooner ripened by wounding them, or by gathering them.* The wounds inflicted by inſects on many fruits promotes their more ſpeedy ripening, as well as thoſe inflicted by caprification, mentioned in Sect. XIV. 3. 3. and in No. 3. 4. of this Section. It is ſaid that cutting the ſtalk of a bunch of grapes half through, which has acquired its due ſize, will expedite the ripening of it; becauſe it will then be ſupplied with a leſs quantity of new juices, and the change of its acerb juices into ſaccharine ones, which is partly a chemical, and partly a vegetable proceſs, proceeds more rapidly. See Sect. X. 8. 1. On the ſame account the pears on a branch, which has had a circle of its bark cut away, will ripen its fruit ſooner; and thoſe annual plants, which are ſupplied with leſs water than uſual, both flower ſooner, and ripen their ſeed ſooner.

To which may be added, that gathering pears from the tree before they are ripe, and laying them on heaps covered with blankets, is known conſiderably to forward their ripening, by ſomething like a chemical fermentation added to the living action of the fruit, which advances the ſaccharine proceſs with greater rapidity.

I have ſeen apricots at table, which I was informed were plucked from the tree, and kept ſome days in a hot-houſe, and thus became deliciouſly ripe; in the ſame manner as harſh pears ripen almoſt into a ſyrup during twelve or twenty hours baking in a ſlow oven; which occaſioned the jeſt of a French traveller, who on being aſked on his return, what good fruit they had in England, anſwered, that the only ripe fruit he happened to taſte was the baked pear.

IV. THE ARTS OF PRESERVING FRUIT, as they depend on the prevention of the chemical proceſſes, which produce their diſſolution, ought to be here mentioned.

1. As life whether animal or vegetable prevents putrefaction, and as many fruits exiſt long, after they are gathered from the tree, before they become ripe and die ſpontaneouſly, and in conſequence putrefy, as crabs, ſloes, medlars, and auſtere pears. The art of preſerving theſe conſiſts in ſtoring them, where the heat is neither much above or below 48 degrees, which is the temperature of the interior parts of the earth; that is, in a dry cellar, or beneath the ſoil, or well covered with ſtraw or mats in a dry chamber. As greater heat might make them ripen ſooner, than they are wanted, by the increaſed activity of their vegetable life; and froſt by deſtroying that life would ſubject them to putrefy, when they become thawed; as perpetually happens to apples and potatoes, which are not well defended from froſt. And laſtly, the moiſture would injure them many ways; firſt by its contributing to deſtroy their vegetable life; ſecondly in promoting the chemical proceſs of putrefaction; and thirdly by its encouraging the growth of mucor, or mould, which will grow in moiſt ſituations without much light or air.

Too great warmth deſtroys both animal and vegetable life by ſtimulating their veſſels into too great activity for a time, whence a ſubſequent torpor from the too great previous expenditure of the living power, which terminates in death. After the death of the organization a boiling heat coagulates the mucilaginous fluids, and if continued would I believe prevent the chemical fermentation of them; and that thus both vegetable and animal ſubſtances might be preſerved. The experiment is difficult to try, and could not therefore be of much practical utility if it ſhould ſucceed.

Great cold on the contrary deſtroys both animals and vegetables by the torpor occaſioned by the defect of ſtimulus, and a conſequent temporary death. Afterwards if a great degree of cold be continued, in ſome caſes the expanſion of their freezing juices may burſt the vegetable veſſels, and thus render the life of them irrecoverable. But there is another curious thing happens to many aqueous ſolutions, or

diffuſions, which is, that at the time of congelation the diſſolved or diffuſed particles are puſhed from the ice, either to the centre, if the cold be applied equally on all ſides, or into various cells, as mentioned in Sect. XIII. 2. 2.

This excluſion of ſalt is ſeen in freezing any ſaline ſolution in water; as common ſalt or blue vitriol expoſed to ſevere froſt in a two-ounce phial are driven to the center of it. Wine, vinegar, and even milk, may be thus deprived of much of their water. Very moiſt clay, when expoſed to froſty air, ſhrinks and becomes much more ſolid according to the aſſertion of Mr. Kirwan. Mineralog. Vol. I. p. 9, the freezing water covering its ſurface with ice, and driving the molecules of clay nearer the centre. And laſtly, the mucilage produced by boiling wheat flour in water, like book-binders paſte, if not too thick, loſes its coheſion by being frozen, the water driving, as it freezes, the ſtarch from its cryſtallization; and from this circumſtance probably is occaſioned the change of flavour of apples, potatoes, and other vegetables, on being thawed after they have been frozen.

It is nevertheleſs affirmed, I think, by Monſ. Reaumeur, that if frozen apples be dipped in cold water repeatedly, and the ice thus formed on their ſurface be wiped off, or if they be left in a large pail full of very cold water, ſo that they may not thaw too haſtily, they will not loſe their flavour. If this be true, and the apples will keep ſound ſome time afterwards, it would ſeem that the vegetable life was not deſtroyed; but that, like ſleeping inſects, they were reanimated by the warmth; otherwiſe, if the flavour be not deſtroyed, and they could be immediately eaten or uſed in cookery, it is ſtill a valuable diſcovery if true, and might lead us to preſerve variety of fruits in ice-houſes, as ſtrawberries, currants, grapes, and pines, to the great advantage of ſociety. See Sect. XVII. 2. 4.

As the proceſs of fermentation will not commence or continue, I believe, in the heat of boiling water, or 212; and as this degree of heat can be eaſily preſerved by ſteam, or by the vicinity of veſſels

containing boiling water; it is probable, that fruits for the uſe of cookery might be thus preſerved throughout the year, as the pulp of boiled apples, gooſeberries, &c. put into bottles, and placed ſo as to be expoſed to the waſted ſteam of ſteam-engines, or immerſed in the hot water, which flows from the condenſing of it; or near the boilers fixed behind ſome kitchen fires; as I ſuſpect, that if ſuch a degree of heat could be applied once a day, it would counteract the tendency to fermentation.

2. Another method of preſerving ſome fruits is by gathering them during their acid ſtate, before that acid juice is converted into ſugar, as lemons, oranges, gooſeberries, pears, and ſome apples; and if a part of the water be evaporated by a boiling heat ſo as to leave the acidity more concentrated, it is leſs liable to ferment, and in conſequence will be longer preſerved. For this purpoſe the fruit ſhould be kept in a cellar, and corked in bottles, ſo as to be precluded from the changes of air, and variations of heat; gooſeberries, and rhubarb-ſtalks, are thus ſucceſsfully preſerved for winter uſe; and if a tea ſpoonful of brandy be put into each quart bottle, it will prevent the growth of mucor or mould upon them.

3. As ſugar will not paſs into fermentation unleſs diluted with much water, and leſs ſo in low degrees of heat, many fruits may be thus preſerved by impregnating them with ſugar, and the better if they are kept in a dry cellar. Dr. Hales found that by inverting the end of a branch of a tree into a bottle of brandy for a few hours, that the whole branch died; hence it is uſual and uſeful to cover preſerved fruits with a paper moiſtened with vinous ſpirit, which prevents the growth of mucor or mould upon their ſurfaces, which is a vegetable thus eaſily killed by the intoxicating ſtimulus.

If ſweet fruits be dried by heat, not only the ſuperfluous water becomes exhaled, but the ſaccharine proceſs is alſo promoted, and much of the mucilaginous or acid particles are converted into ſugar, as in baking pears, or in drying figs, dates, raiſins, apricots; ſo that

by

by gradually drying them many fruits may be well preſerved, and require afterwards ſimply to be kept dry.

4. Some fruits, as the olive, are preſerved in their unripe ſtate in ſalt and water; the unripe pods of kidney-beans, and the hats of muſhrooms, may be thus alſo kept for months in weak brine in a cool cellar encloſed in bottles without much change. But the oily kernels of nuts are well preſerved in cellars beneath the ſoil to preclude the variations of heat, and covered in jars to prevent their evaporation. Other fruits are converted into pickles and preſerved in vinegar, but loſe their flavour; and others by being immerſed in vinous ſpirit are preſerved, as cherries, and thus tranſmuted from food to poiſon. And when the kernels of apricots, cherries, or bitter almonds, are preſerved in brandy, which is called ratafia, we poſſeſs a mixture of two of the moſt poiſonous productions of the vegetable kingdom; except perhaps the leaves of lauro-ceraſus diſtilled in alcohol, which was ſold as ratafia in Dublin, and produced many ſudden deaths in the gin-ſhops.

v. The following lines are inſerted to amuſe the reader, and to imprint ſome of the foregoing doctrine on his memory.

ART OF PRUNING WALL-TREES.

BEHEAD new-grafted trees in ſpring,
Ere the firſt cuckoo tries to ſing;
But leave four ſwelling buds to grow
With wide-diverging arms below;
Or fix one central trunk erect,
And on each ſide its boughs deflect.
In ſummer hours from fertile ſtems
Rub off the ſupernumerous gems;
But where unfruitful branches riſe
In proud luxuriance to the ſkies,

Exſect

Exſect the exuberant growths, or bind
A wiry ringlet round the rind;
Or ſeize with ſhreds the leafy birth,
And bend it parallel to earth.
When from their winter-lodge eſcape
The ſwelling fig, or cluſtering grape;
Pinch off the ſummit-ſhoots, that riſe,
Two joints above the fertile eyes;
But when with branches wide and tall
The vine ſhall crowd your trellis'd wall;
Or when from ſtrong external roots
Each rafter owns three vigorous ſhoots;
Watch, and as grows the aſcending wood,
Lop at two joints each lateral bud.
So ſhall each eye a cluſter bear
To charm the next ſucceeding year;
And, as the ſpiral tendrils cling,
Deck with feſtoons the brow of ſpring.
But when the wintry cold prevails,
Attend with chiſel, knife, and nails;
Of pears, plums, cherries, apples, figs,
Stretch at full length the tender twigs;
Vine, nectarine, apricot, and peach,
Cut off one third or half of each;
And, as each widening branch extends,
Leave a full ſpan between the ends.
Where crowded growths leſs ſpace allow,
Cloſe lop them from the parent bough;
But when they riſe too weak or few,
Prune out old wood, and train in new.
So, as each tree your wall receives,
Fair fruits ſhall bluſh amid the leaves.

ART OF PRUNING MELONS AND CUCUMBERS.

When melon, cucumber, and gourd,
Their two firſt rougher leaves afford,
Ere yet theſe ſecond leaves advance
Wide as your nail their green expanſe;
Arm'd with fine knife, or ſciſſars good,
Biſect or clip the central bud;
Whence many a lateral branch inſtead
Shall riſe like hydra's fabled head.
When the fair belles in gaudy rows
Salute their vegetable beaux;
And, as they loſe their virgin bloom,
Shew, ere it ſwells, the pregnant womb;
Lop, as each crowded branch extends,
The barren flowers, and leafy ends.
So with ſharp ſtings the bee-ſwarm drives
Their uſeleſs drones from autumn hives.
But if in frames your flowers confin'd
Feel not one breezy breath of wind,
Seek the tall males, and bend in air
Their diſtant lovers to the fair;
Or pluck with fingers nice, and ſhed
The genial pollen o'er their bed.
So ſhall each happier plant unfold
Prolific germs, and fruits of gold.

SECT. XVI.

THE PRODUCTION OF SEEDS.

I. To produce ſeeds early. 1. *Sow before winter, or in warm ſituations.* 2. *Tranſplant the roots.* 3. *Cut off ſuperfluous ſhoots.* 4. *Give leſs water.* II. To produce ſeeds in great quantity. 1. *Sow early, or when the ſeed ripens.* 2. *Tranſplant the roots deeper, or earth them up. Horſe-hoe and hand-hoe. Improved drill huſbandry. Dibbling. Corn lands laid level. Egyptian wheat with branching ears.* 3. *Deſtroy the central ſhoot. Eat down wheat and roll it. This is ſometimes injurious.* 4. *Pinch off uſeleſs ſummits of beans. Eat down too vigourous wheat.* 5. *Roll it to leſſen the ſtraw.* 6. *Give leſs water.* III. To ripen ſeeds. 1. *Warmth and dryneſs.* 2. *Froſty nights.* 3. *Lime forwards the ripening of ſeeds.* 4. *Cut off bulbs and root-ſuckers of orchis. Helianthus tuberoſus. Rheum palmatum.* IV. To generate beſt kinds of ſeeds. *Chooſe early plants inſulated from others. Impregnate the ſtigmas of ſome with the anther-duſt of others. Whence peas may be produced of different colours.* V. To collect good ſeeds. *Change of ſeeds is uſeleſs, unleſs for better kinds. Chooſe the earlieſt ſeeds. Pick out the largeſt potatoes for planting, and the beſt radiſhes for ſeed, and the earlieſt ears of wheat.* VI. To determine the goodneſs of ſeeds. *Weigh a meaſure of them. Caſt them into ſalt water. Beans more economical than oats as provender. Seeds continue to improve during the water-months.* VII. To preſerve ſeeds. 1. *Collect before they ſhed naturally. Dry them before they are ſtacked. Gluten of wheat deſtroyed by fermentation. Make the corn-ſtack higheſt in the middle. The great durability of ſeeds. Keep them dry. Not in contact with walls. Convenient oat-boxes for ſtables. Wheat dried on a malt-kiln to preſerve it.* 2. *Ventilation prevents mould.* 3. *Seclude them from heat, beneath the ſoil. In ice-houſes.* 4. *Magazines of grain ſuffered to vegetate at top. Covetous farmers.* 5. *New and old ſeeds.* 6. *Preſerve ſeeds in ſugar, or in charcoal, for long voyages. And fleſh-meat in treacle.* VIII. To ſow ſeeds advantageouſly.

Native

Native ſeeds, foreign ones. Sow ſoon after the ground is turned over, and early in the ſpring, in the autumn. 2. *Economy of ſowing three kinds of graſs-ſeeds, and two kinds of wheat. Kinds of ſoil.* 3. *Mix ſand or ſoil with ſome ſeeds. Soak them in water, ſalt and water, lime. Steep barley in dunghill water. Wood-aſhes. Sow wet as well as dry.* 4. *Bury the fruit with the ſeed.* 5. *Waſh the ſeeds of too luxuriant plants. Sow them early.* IX. Queſtion concerning general encloſure. Cain and Abel.

MANY of the circumſtances above related concerning the production and enlargement of fruit are applicable to the production of the ſeeds, which are included in them; but thoſe ſeeds, which contribute moſt to the nouriſhment of mankind, many of which are the progeny of annual or biennial plants, require other modes of cultivation.

As an introduction to this ſection it may be obſerved, how much more ingenuity was required in the diſcovery of nouriſhing mankind by the ſmall ſeeds of the graſſes, which have probably been ſince much enlarged by perpetual cultivation, than by the large roots of potatoes. The Iſis or Oſiris of Egypt ſeems to have invented the proceſs of cultivating wheat, as well as flax, on the banks of the Nile; and afterwards Ceres and Triptolemus to have taught the former of theſe important diſcoveries all over the known world. While in later ages the Incas or Motezumas of Peru and Mexico ſeem to have deſtroyed the cannibals, or men-eaters, of that continent, and to have diſcovered and taught their people to ſupport themſelves by the cultivation of potatoes.

I. 1. *To produce ſeeds early in the ſeaſon.*

Thoſe plants, which are required to yield a forward crop, as the peas and beans of our gardens, and thoſe which our cold and ſhort ſummers will not otherwiſe perfectly ripen, as wheat, ſhould be ſowed before the commencement of winter, either in natural ground, as in the

cultivation of wheat, or in ſituations ſheltered from the north-eaſt, as in the garden cultivation of peas and beans; or they may be ſowed very thick in hot-houſes, or under hot-bed frames, or under warm walls, and be tranſplanted, when they are one or two inches high, into the natural ground at due diſtances, when the weather is milder, and the plants are become hardier or leſs liable to be deſtroyed from their having longer acquired the habits of life.

When young plants of any kind are tranſplanted, the ground ſhould be recently dug, as their expeditious growth depends ſo much on the atmoſpheric air being buried in the pores or interſtices of the earth by the production of carbonic and nitrous acids, and ammonia, and heat.

The ſame advantage occurs by ſoaking ſeeds in water, or in the drainage from manure heaps, till they are ready to ſprout, and then ſowing them in a ſoil lately turned over; as their roots will then immediately put out by the newly generated heat, and newly produced carbonic acid in its fluid not its gaſſeous ſtate.

2. The tranſplanting of young roots, if they be ſet no deeper than before, does not, I ſuppoſe, multiply the number of ſtems, as occurs when wheat is tranſplanted ſo deep as to cover the ſecond joint; but by tearing off ſeveral ſmall extremities of the roots, the new production of many viviparous buds is prevented, and that of oviparous buds increaſed in conſequence, for reaſons mentioned in No. 2. 4. of the preceding Section.

When the roots of wheat are tranſplanted and divided, not only a great increaſe of the crop is produced, but I believe the ſeed is likewiſe ripened earlier, as is aſſerted by Mr. Bogle. Bath Society, Vol. III. p. 494. And it is well known to gardeners, that tranſplanting garden-beans forwards them in reſpect to time, but ſhortens the height of the ſtem. Hence tranſplanted vegetables grow leſs in height, as tranſplanted beans, and leſs branchy, as tranſplanted melons, but produce and ripen their ſeeds earlier; which is a great advantage in the

the ſhort ſummers of this climate; and if the roots can be divided, as in wheat, or new ſcions can be produced by their being tranſplanted deeper, as alſo occurs in wheat, the quantity of the ſeed may alſo be wonderfully increaſed by tranſplanting. See Sect. XII. 6.

3. Another mode of forwarding the production of ſeeds, and of ſooner ripening them, conſiſts in pruning off the viviparous tops or lateral ſhoots, which will bear no ſeeds at all, or only ſmall or imperfect ones, in our northern ſummers. For this purpoſe the cutting away the tops of beans and of peas, and the lateral branches of artichokes, after the fruit-buds are formed, both forwards and enlarges the flowers and ſeeds, which remain, as more nouriſhment is derived to them.

4. As a ſuperfluous ſupply of water is more friendly to the production of leaf-buds than to the generation of flower-buds, to derive leſs water than uſual to the roots, forwards the production of ſeeds, a fact well known in the gardens of warmer climates, which are perpetually watered from reſervoirs or wheel-engines. But when the bloſſoms appear, an addition of water muſt forward their growth by ſupplying nouriſhment, which ſhould again be leſſened when the fruit has acquired its full ſize, both to expedite its ripening, and to increaſe its flavour; as the ſaccharine matter and eſſential oil will be leſs diluted with water.

In the dry ſummer of 1799 I had the opportunity of flooding ſome rows of beans in my garden, which by being done too frequently, or too copiouſly, occaſioned them to grow to a much greater height than uſual, and in conſequence to bring to perfection few ſeeds, and ſome of them none. As I ſuppoſe the new ſhoots of fig-trees in the beginning of ſummer occaſions the firſt production of young figs to fall off from the want of that nouriſhment, which is now expended in the growth of new leaf-buds. See Sect. XV. 3. 4. Whence the facility of producing leaf-buds ſeems evidently to prevent the genera-

tion of flower-buds, and the uſe of cutting off the ſummits of tall beans is thus explained, as directed above.

II. 1. *To produce ſeeds in great quantity* from annual or biennial plants they ſhould be brought forward in reſpect to the ſeaſon in our northern ſummers; that a greater quantity of viviparous buds may arrive early at their maturity for the purpoſe of generating oviparous buds ſoon enough in the ſummer to ripen their ſeeds; on this account thoſe ſhould be ſown in the autumn which will bear the ſeverity of the winter.

Nevertheleſs the ſeeds of thoſe plants, which are natives of this climate, ſhould probably be ſowed at the time they become perfectly ripe, as occurs to them in their natural ſtate; that is, either when the ſeed is ſhed upon the ground by the parent plant, or when the fruit or huſk, which encloſes it, becomes naturally ripe after it has fallen on the ground. Thus I have ſeen crabs covered with leaves in hedge-bottoms, which have not decayed till the early ſpring. Many pears do not become ripe in our ſtore-rooms till March or April; and ivy berries and holly berries hang on their reſpective trees till the vernal months, and are not till that time eaten by the thruſhes. Hence it is probable, that the ſeeds in theſe durable fruits or berries continue to ripen, or to become more mature, and prepared for their future growth during the winter months.

2. It was ſhewn in Sect. IX. 3. 7. that when wheat was tranſplanted ſo deep as to immerſe the firſt joint above the root into the ſoil, many new ſtems would ſhoot up and ſtrike their roots into the earth; and that thus four or ſix new plants, or more, would be generated by the caudex of the leaf-bud, which conſtitutes that joint. This mode of tranſplantation therefore will much increaſe the quantity of the crop of ſeed, if it can be done ſoon enough for theſe additional ſtems to ripen their corn, before the ſummer ends.

There is another mode of increaſing this product of additional

ſtems

ſtems without tranſplantation, which conſiſts in ſowing the wheat in rows by what is called a drill-plough according to Mr. Tull's method; and when the firſt ſtems riſe a few inches high, a horſe-hoe, made like a very ſmall plough, is to be brought ſo near each row, as to turn up ſome earth againſt the ſtems, ſo as to cover the firſt joint above the root with ſoil; whence new ſtems will be generated, and ſhoot up round the old one; and thus increaſe the crop in the ſame manner as by deep tranſplantation.

The theory of Mr. Tull's drill huſbandry is explained in Sect. IX. 3. 7. and in XII. 5. which is of late years ſuppoſed to have been improved by introducing the hand-hoe in place of the horſe-hoe, and thus giving an opportunity of ſowing the rows or drills nearer together, as will be ſeen by the following method, now introduced into almoſt general uſe in Norfolk by Mr. Coke; though Mr. Tull himſelf much prefers the horſe-hoe as turning over the earth much deeper than the hand-hoe, and thus rendering that part of it more expoſed to the air, which was before more deeply ſecluded from it; and alſo rendering it more pervious to vegetable roots; to which may be added, that both kinds of hoeing render the ſurface more permeable to the rains and dews, and prevent the cracks in dry weather, which are very injurious to the roots of plants; both which advantages depend on the poroſity of the ſoil, which muſt extend deeper by the uſe of the horſe-hoe than the hand-hoe.

Mr. Tull makes other ingenious remarks on the uſe of horſe-hoeing. In the beginning of winter, when the wheat has obtained one blade like graſs, or two or three leaves, the horſe-hoe is brought near the rows and deep, and the earth turned from them ſo as to form a ridge between them. By this ridge in level grounds he thinks the rows are ſhaded from the cold winds in ſome ſituations, and that the roots of the wheat are kept drier, and thence leſs injured by froſts. In the ſpring this ridge in the intervals between the rows is divided by the horſe-hoe, and turned back againſt the rows of corn after it has

has been fertilized by the air and rains, and dews of winter. See Tull's Huſbandry, Ch. IX. and Sect. XII. 5. of this work.

Mr. Coke of Holkham in Norfolk aſſured me, that in thirteen years experience on a farm of 3000 acres he had found the drill huſbandry in that country greatly ſuperior to ſowing ſeeds of all ſorts by the hand in what is termed the broad-caſt method, but differs in the number and arrangement of his rows from the method of Mr. Tull in the following circumſtances.

Mr. Tull drilled two rows of ſeed a few inches from each other, and then left a ſpace of two or three feet, and then drilled two more rows near each other, for the purpoſe of paſſing a hoe between each double row drawn by a horſe, which was therefore termed a horſe-hoe; but Mr. Coke drills all his rows of wheat and of peas nine inches from each other, and thoſe of barley ſix inches and three quarters from each other; this is performed by a drill plough made by the Rev. Mr. Cook, which drills ſix rows at a time, and thus ſows an acre of land in an hour, and is drawn by a ſingle horſe; and the quantity of ſeed conſumed is about ſix or ſeven pecks to an acre, which is about half what is uſed in the ſowing by the hand in the broad-caſt method.

Early in March Mr. Coke uſes the hand-hoe, which for hoeing the rows of wheat and of peas is about ſix inches wide, and for hoeing thoſe of barley about four inches wide. By this hoe the ſurface is not only turned over, and the weeds between the rows rooted up, but it is alſo accumulated about the roots of the growing corn, and covers and conſequently deſtroys the low growth of poppies amongſt them; which are a very frequent weed in that part of the country. A ſecond hoeing is performed about the middle of May, and the ſoil is again not only cleared from weeds but accumulated againſt the riſing corn, each of which hoeings coſt about twenty-pence an acre.

Nevertheleſs I am informed, that ſome attentive agricultors uſe the horſe-hoe belonging to Mr. Cook's drill-machine, though the rows

of corn are but nine inches from each other; and aſſert, that this occaſional trampling of the horſe on the young plants is of no very ill conſequence, a circumſtance well worth obſerving, as it removes the principal diſadvantage of the horſe-hoe, which conſiſts in the too great diſtance of the alternate rows of the corn-plants.

By the earth being thus accumulated againſt the roots of the corn it is ſaid to tiller or tellure much; that is, to throw out four or ſix ſtems, or more, around the original ſtem, and thus to increaſe the number of ears like tranſplanting the roots, inſomuch that Mr. Coke obtains by this method between four and five quarters of wheat on every acre, which in the broad-caſt method of ſowing did not yield more than three quarters on an acre, beſide ſaving a ſtrike and half of the ſeed corn, unneceſſarily conſumed in the broad-caſt method of ſowing. To this ſhould be added another advantage, that as the land is thus kept clear from weeds, and has its ſurface twice turned over, and thus expoſed to the air, it is found to ſave one ploughing for the purpoſe of a ſucceeding crop of turnips.

It is probable, that one hand-hoeing in the beginning of winter, ſo managed as to turn the ſoil from the roots of the corn, and to leave it rather elevated between the rows, as Mr. Tull recommends to be performed by his horſe-hoe, might give a ſimilar advantage to this mode of cultivation; and alſo if another hand-hoeing was applied, as ſoon as the wheat is out of bloſſom, to ſupply more nouriſhment to the young ſeed might increaſe its plumpneſs and weight, as mentioned in No. 2. 3. of this Section.

The lands thus managed by Mr. Coke are laid level, and not in ridges and furrows, and can thus be ploughed croſswiſe; and the crop is equally good throughout the whole; whereas in the furrows of ſome lands it is leſs forward or leſs prolific than on the ridges; whence much light corn is mixed with the good, which is obliged to be ſeparated from that, which is marketable, and uſed for hogs or poultry. Add to this, that in this mode of huſbandry the ſtraw is believed

lieved to be larger and in greater quantity as well as the grain, and the land to be leſs impoveriſhed, as no weeds are ſuffered to grow on it, and as its ſurface is ſo frequently turned over, and expoſed to the air.

In China the corn lands are laid on a level, not in ridges and furrows; which is ſuppoſed to be the moſt advantageous plan in almoſt every ſituation, which is proper for the cultivation of corn, as by being thus rendered capable of being divided by croſs-ploughing, almoſt any kind of ſoil may be rendered more proper for the uſe of the drill huſbandry, by which it is ſeen in the above account of the Norfolk management, that twelve ſtrikes more of wheat are raiſed on an acre, and one ſtrike and a half ſaved in the conſumption of ſeed-wheat, which at ſix ſhillings a ſtrike ariſes to a conſiderable ſum on a large farm.

Nevertheleſs there ſeem to be many advantages attending the forming the ſurface of land into ridges and furrows; in wet lands with a ſubſtratum of clay the furrows are convenient channels to carry off the water, where there is a ſufficient declivity, as treated of by Mr. Tull in his Horſe-hoeing Huſbandry, Ch. XVI. Add to this, that in ſome ſituations a deeper ſtratum of the ſoil, where it is valuable, may be occaſionally turned up, and expoſed to the air, and to the roots of vegetables, by gradually changing the locality of the ridges; and laſtly, in every ſituation a greater ſurface both of the ſoil, and of the ſummits of the ſtems, or ears, are expoſed to the influence of the air by means of ridges and furrows; for as the plants of wheat are but three or four feet high, the ſurface of a crop of wheat is increaſed as well as the ſurface of the ground it grows upon, and not as the baſe on which the declivities or hills reſt, as ſome have erroneouſly ſuppoſed. See Sect. X. 3. 8.

There is another method of ſowing wheat in rows uſed in ſome counties, which is termed dibbling in the language of agricultors, and conſiſts in making perpendicular holes one inch and half or two

inches

inches deep, as is commonly done in planting potato-roots; theſe holes are made by a man, who has a proper ſtaff ſhod with iron in each hand, and as he walks backwards is able by looking at the part of the row already made to keep nearly in a ſtraight line, and to make two holes at once at about nine inches diſtant from each other every way. Two or more children attend the man, and drop two, or three, or four ſeeds into each perpendicular hole, which are afterwards covered by drawing over them what is called a buſh-harrow.

This method by ſowing the wheat in rows adapts it for the uſe of the hand-hoe, as by ſowing it by a drill machine, but muſt be attended with greater expence, and I ſuſpect with leſs accuracy of the diſtribution of the ſeed, owing to the hurry or fatigue of the children employed; and I alſo ſuſpect that ſowing in drills is preferable, becauſe a greater quantity of earth is turned over, and much air in conſequence included in its interſtices; whereas in making perpendicular holes the ſides of the holes are compreſſed, and rendered more ſolid; whence potato-roots alſo might probably be more advantageouſly planted by making drills inſtead of perpendicular holes.

A correſpondent of the board of agriculture aſſerts, that on looking over a field of potatoes near Leiceſter, which had all been planted at the ſame time, and on land equally manured, he obſerved a great difference of the growth of one part of the field, which on inquiry he found to have been owing to the roots having been planted in drills, where the plants were ſo much ſtronger; and by a ſetting ſtick in holes, where they were ſo muchleſs vigorous; Engliſh Enclyclopedia, Art. Huſbandry, p. 483: which difference of growth I ſuppoſe to have been owing to the circumſtances above mentioned.

A few ears of wheat were lately given me, which were branched, having four or five leſs ears growing out of each ſide of the principal ear; it was procured at Liverpool, and was called Egyptian wheat, or Smyrna wheat. It is deſcribed in the Supplem. Plantarum of the

younger Linneus, as well as in the ſpecies Plantarum of the elder; and is ſaid to be a native of Egypt, and to be cultivated at Naples; it is called "triticum compoſitum, or wheat with a compound ear, crowded with leſs ears, awned; and is ſaid to be related to triticum æſtivum, ſummer wheat; but the ſpike is four times larger, a hand in length, compoſed of leſs ſpikes, two faced, alternate, approximated, from nine to twelve, the lower ones being ſhorter, and the top one ſolitary." Suppl. Plant. p. 115.

The plant, which was given me, had five tall and thick ſtems from one root, but ſeemed to have been plucked up before it was quite ripe, whence I cannot judge of the ſize of the grain, but ſhould imagine, that it is a ſpecies well worthy of attention. The few ears, which I poſſeſſed, were ſown in the ſpring of this year, 1799, not having obtained them ſoon enough to ſow in the autumn. When they were an inch or two high, they were tranſplanted into a moiſtiſh part of my garden; and though the year has been uncommonly cold and wet, and a great part of the autumn-ſown wheat of this country is blown down upon the ground, and is not yet ripe, yet almoſt every root of the Egyptian wheat has from ten to twelve ſtems, and ſtands upright on ſtrong ſtraw about three and a half, or four feet high. The beſt ſtems have one principal ear about five inches long, with five or ſix ſhorter ones branching out on each ſide of it. They begin to appear brown, and I hope will ripen. I have ſince found that this ſpecies of wheat is mentioned in Tull's Huſbandry under the name of Smyrna wheat. He adds that it is highly productive, but on that account requires a good ſoil.

3. Another method of promoting the growth of lateral ſtems conſiſts in deſtroying the central ſhoot; when this is done, other new ſtems ariſe from the joint immediately above the root, which in wheat is in contact with the earth. On this account, when wheat plants are ſufficiently forward in reſpect to the ſeaſon, it is thought to be advantageous to eat the firſt ſtem down by ſheep to increaſe the

quantity

quantity of the ſubſequent crop. See Sect. IX. 3. 7. It ſhould be nevertheleſs obſerved here, that the trampling of the ſheep on lands, which are not too adheſive, will preſs down the firſt or ſecond joint into the earth, and thus aſſiſt the production of many ſide ſhoots. But in very adheſive ſoils this trampling of the ſtems into the ground may be injurious. See a paper in Bath Agriculture, Vol. I. Art. XV. In ſoils which are not too adheſive, when the crop appears thin, it is probable, that a roller drawn over it by preſſing the firſt or ſecond joint into the ſoil, might promote the production of ſide ſhoots, or make them tiller, or tellure, in the language of agricultors. And when graſs or clover ſeeds are deſigned to be ſown on the wheat-land, it might firſt be harrowed, and then either rolled or trampled by the ſheep, which eat it; either or both of which might preſs down the root-ſtems of the corn, and cover the newly ſown clover-ſeeds with ſoil.

This mode of eating down forward wheat with ſheep is analogous to cutting off the central buds of melons and cucumbers to make them produce earlier fruit, and in this climate perhaps in greater quantity; as thoſe produced after the great extent and elongation of the central branches would be too late to ripen in this climate: and by their exuberant generation of a viviparous progeny would retard the ſucceſſion of lateral ſhoots, and a conſequent quicker production of flowers.

Nevertheleſs where the crop is not too luxuriant or too forward, the eating down the firſt ſtem by ſheep may be an injurious practice; as Mr. Tull thinks, that by thus deſtroying the firſt ſtem, the ears of the later ones have not time to ripen, and thence become light in reſpect to the ſize or plumpneſs of the grain; and that theſe ſecondary ſtems become weak, and are liable to fall down, both which he ſays commonly occur where the crops are eaten by ſheep.

Mr. Tull, whoſe work is throughout a great effort of human genius, adds a very wiſe axiom, " that it is moſt advantageous to haſten,

what we can, the time of bloſſoming; and to protract the time of ripening." Horſe-hoeing Huſbandry, Ch. XI. p. 147; for it is the farinaceous reſervoir of nutriment laid up in the cotyledon of the new ſeed for the future growth of the corculum or new embryon, for which we cultivate the plant; and this reſervoir is formed between the bloſſoming and ripening of the grain, either before or after the impregnation of the pericarp, or ſeed-veſſels, and thus renders the grain plump and heavy. Mr. Tull in another part of his work recommends an additional horſe-hoeing immediately after the bloſſom is over, to ſupply more nutriment to the ripening grain. Ch. IX. p. 120. Mr. Tull eſteems the eating down of wheat by ſheep to be generally a very injurious practice in this climate, by rendering the ears light and the ſtraw weak; by retarding the time of bloſſoming, as well as the growth of the ſtems.

4. In the moiſt ſprings of this climate many annual or biennial plants are liable to ſhoot out too many or too ſtrong viviparous branches, which can not generate flower-buds ſoon enough to ripen their ſeeds in our cold and ſhort ſummers. This always happens to cucumbers and melons, which were brought from warmer countries, and to the peas and beans of our gardens, and ſometimes to corn-plants, which are liable in wet ſeaſons to produce too ſtrong ſtems and foliage, which have not time to generate the flower-bud at their ſummit ſoon enough to perfect and to ripen the ſeed. Melons and cucumbers have been mentioned in Sect. XV. 2. 5. and in reſpect to garden beans their viviparous tops ſhould be pinched off, which if not too old may be eaten as an agreeable vegetable, when well boiled; and thus more nutriment is derived to the oviparous buds beneath, which renders them larger, and perhaps more numerous. To prevent field peas from running into ſtraw in moiſt ſoils leſs manure ſhould be uſed; and field beans may have their tops cut off by a ſcythe fixed into a ſtraight ſhaft.

Annual cotton plants are much cultivated in ſome colder parts of the

the Chineſe empire, and the cultivators lop off the tops to increaſe the number of pods, and to haſten their production; and in the Weſt Indies the flowers of the roſe tree are believed to be accelerated and increaſed by topping the branches. Embaſſy to China by ſir G. Staunton, Vol. III. p. 202. 8vo. edit.

When the ſtems and foliage of wheat are thus too vigorous, it may be advantageous to eat it down by ſheep as above mentioned; which may not only deſtroy the too vigorous viviparous central ſtems, but alſo produce a greater number of lateral ones; which may ſooner terminate in oviparous ones, ſo as to produce more grain with leſs ſtraw.

5. It is alſo probable, that rolling them as mentioned above, if it be done in a morning before the dew is off, might ſo far bruiſe the ſtems and roots, as to ſtop their too great propenſity to nouriſh the viviparous buds, and in conſequence to favour the growth of the oviparous buds on their ſummits; which might forward the harveſt ſeaſon, as well as increaſe the product of grain in proportion to the quantity of ſtraw. From rolling wheat in ſpring on fields where the ſurface remains uneven or cloddy, another advantage may be derived, by breaking the clods or eminences, and thus earthing up many of the ſtems above the ſecond joint, and thus inducing a new ſet of root-ſcions to put forth, or tiller. See Sect. XII. 3.

6. The garden plants, which are too vigorous, in ſituations where there is a command of water, as in the gardens of warm climates, ſhould have leſs water derived to them, till the bloſſoms appear; becauſe a greater quantity of moiſture facilitates the production of viviparous buds ſo much as to retard that of oviparous ones, and thus diminiſhes the quantity as well as retards the ripening of the crop. But in theſe ſituations, as ſoon as the bloſſoms appear, a greater ſupply of water ſhould be allowed, which will contribute to nouriſh and enlarge them, as mentioned above; as is practiſed in ſome countries of the eaſt, where they do not flood their rice-grounds, till they are in flower.

flower. See Sect. XV. 3. 4. But leſs water is again required, when the ſeed has arrived at its full ſize, as before ſpoken of.

III. 1. *To forward the ripening of ſeeds.* A due degree of warmth and of dryneſs ſeems to include the circumſtances principally required. The warmth not only accelerates the various ſecretions of vegetables by increaſing their irritability and conſequent activity, but, after the mucilaginous, ſtarchy, ſaccharine, and oily matters are ſecreted into proper reſervoirs, may contribute perhaps chemically to their change into each other, or to their greater perfection. And the dryneſs of the air, whether hot or cold, is neceſſary to give perfect ripeneſs to ſeeds; as otherwiſe the due exhalation of the aqueous parts of the ſecreted fluids, which form the nutritive parts of ſeeds, does not properly proceed; and the ſeed gathered in this condition is liable to mildew in the barn or granary, or to become ſhrivelled and wrinkled, as it dries.

2. It is believed in Scotland, that even the froſty nights of autumn contribute to ripen the late crops in that inclement climate, which ſome have aſcribed to the moonlight, but, which I have indeed ſuſpected, that the froſt may in ſome meaſure effect by converting the mucilage of the grain ſooner into ſtarch. This I was induced to imagine by having obſerved that bookbinder's paſte, made by boiling wheat-flour in water, loſt its adheſion after having been frozen; and alſo from a culinary obſervation, that when ice or ſnow is mingled with flour inſtead of water in making pancakes, that it much improves them; the truth of which I have heard boldly aſſerted, but never witneſſed the experiment. See Sect. VI. 3. 3.

There is nevertheleſs an experiment related by Dr. Roebuck in the Edinburgh Tranſactions, Vol. I. which ſeems to ſhew, that the grains of oats continue to fill and to become heavier even during the autumnal froſts; which may probably occur during the ſunſhine of the middle part of the day, as occurs in the vernal froſts of this part of the country. In 1780 near Borrowſtoneſs the oats were green

even

even in October, when the ice was three fourths of an inch thick. He ſelected ſeveral ſtalks of oats of nearly equal fulneſs, cut half of them, and marked the remainder, which continued fourteen days longer in the field; after being dry, the grains of each parcel were weighed; and eleven of thoſe grains, which had remained in the field, weighed thirty of thoſe which had been cut a fortnight ſooner.

This important experiment ſhould teach our farmers not to cut their peas and beans too early in inclement autumns; which are ſo frequently ſeen to become ſhrunk and ſhrivelled in the barn or granary, and inclined to rot from deficient ripeneſs, and conſequent ſoftneſs or moiſture; and thus contain much leſs flour in proportion to the huſk or bran.

3. The wheat produced after land has been much limed, is believed to be thinner ſkinned, and to yield more good meal, than other wheat, and to make better bread. See Sect. X. 6. 7. On this account I ſuppoſe one uſe of lime is to forward the ripening of ſeeds by converting their mucilage ſooner into ſtarch or oil; as according to the experiments of M. Parmentier the goodneſs of bread depends much on the quantity of ſtarch contained in it; who found, that if the ſtarch taken from eight pounds of raw potatoes, by grating them into cold water, was mixed with eight pounds of boiled potatoes, as good bread might be produced as from wheat flour. See Sect. VI. 3.

4. The ſeeds of ſome plants, which alſo propagate themſelves by bulbs at their roots, will not ripen in this climate naturally, as the orchis; but are ſaid to ripen, if the new bulb be cut off early in the ſeaſon; or if the propagation by their roots be retarded or prevented by confining them in garden-pots, as the lily of the valley; and it is probable, that the ſeeds of potatoes might be rendered more perfectly ripe, and in conſequence better for the cultivation of new varieties; if the young roots were taken away early in the ſeaſon from that, which is to bear ſeed; or if they were confined in garden pots.

If the orchis could by theſe means be cultivated from ſeed on moiſt meadows or moraſſes, it might become a profitable article of huſbandry; as when it is ſcalded in boiling water, and the peel rubbed off, it is ſold by the name of ſalep, and might become a nutritive article of diet, like ſago and vermicelli, if it could be propagated at leſs expence.

It is alſo probable, that Jeruſalem, or ground artichokes, helianthus tuberoſus, might be induced to ripen its ſeeds in this country, if the new roots from a few of the forwardeſt plants were taken away early in the ſeaſon, or if they were confined in garden pots. And if this plant could be propagated by ſeed, it might make an uſeful product in agriculture, as horſes are very fond of the leaves, and ſwine of the roots; both of which are produced in great quantity; and as the latter contain much ſugar, they muſt be very nutritive; and in reſpect to their culinary uſe are remarkably grateful to moiſt palates, as well as nutritive, when cut into ſlices, and baked in beef or mutton pies; but are ſaid to be flatulent in the bowels of thoſe whoſe digeſtion is not very powerful; a property which might be worthy attention, where the propenſity to fermentation is required, as in making bread with potatoes, or in the diſtillery.

It is alſo probable, that if the large new root-ſuckers of other perennial plants, which do not bear bulbous or tuberous roots, and which are late in ripening their ſeeds, or do not ripen them perfectly in this climate, were cut or torn off early in the ſeaſon, as of the rheum palmatum, palmated rhubarb, or rheum hybridum, mule rhubarb; or if their roots were confined in garden-pots, that they might be more liable completely to ripen their reſpective ſeeds. See Sect. XV. 2. 4.

IV. 1. *To generate the beſt kinds of ſeeds* the moſt healthy plants muſt be choſen, and thoſe which are moſt early in reſpect to the ſeaſon; theſe ſhould be ſo inſulated, as to have no weak plants of the ſame ſpecies, or even genus, in their vicinity, leſt the fecundating

duſt of weaker plants ſhould be blown by the winds upon the ſtigmata of the ſtronger, and thus produce a leſs vigorous progeny.

Where new varieties are required, the male duſt of one good variety, as of the nonpareil apple, ſhould be ſhed upon the ſtigmas of another good variety, as of the golden-pippin; and it is probable ſome new excellent variety might be thus generated.

Mr. Knight has given a curious experiment of his impregnating the ſtigmas of the pea-bloſſoms of one variety with the farina of another. He ſays, Treatiſe of Apple and Pear, p. 42, "Bloſſoms of a ſmall white garden-pea, in which the males had previouſly been deſtroyed, were impregnated with the farina of a large clay-coloured kind with purple bloſſoms. The produce of the ſeeds thus obtained were of a dark grey colour, but theſe having no fixed habits, were ſoon changed by cultivation into a numerous variety of very large and extremely luxuriant white ones; which were not only much larger and more productive than the original white ones, but the number of ſeeds in each pod was increaſed from ſeven or eight to eight or nine, and not unfrequently to ten. The newly made grey kinds I found were eaſily made white again by impregnating their bloſſoms with the farina of another white kind. In this experiment the ſeeds, which grew towards the point of the pod, and were by poſition firſt expoſed to the action of the male, would ſometimes produce ſeeds like it in colour, whilſt thoſe at the other end would follow the female.

"In other inſtances the whole produce of the pod would take the colour of one or other of the parents; and I had once an inſtance in which two peas at one end of a pod produced white ſeeds like the male, two at the other end grey ones like the female, and the central ſeeds took the intermediate ſhade, a clay colour. Something very ſimilar appears to take place in animals, which produce many young ones at a birth, when the male and female are of oppoſite colours. From ſome very imperfect experiments I have made, I am led to ſuſ-

pect that conſiderable advantages would be found to ariſe from the uſe of new or regenerated varieties of wheat, and theſe are eaſily obtained, as this plant readily ſports in varieties, whenever different kinds are ſown together." See Sect. VII. 2. 6. of this work.

2. The white and blue peas ſown in fields as well as in gardens ſometimes poſſeſs the property of becoming ſoft by boiling, at other times not. This circumſtance is ſaid to depend on the nature of the ſoil, but has not yet been ſufficiently inveſtigated; perhaps the greater or leſs maturity of the peas at the time of reaping them may have more or leſs contributed to fill their fibrous cells or diviſions with mucilage or ſtarch. The greater or leſs mealineſs produced by boiling potatoes ſeems to be an analogous circumſtance, and is thought by ſome to ariſe from the nature of the ſoil rather than from the ſpecies or variety of the planted root.

The mealineſs of ſome boiled potatoes, and the ſoftneſs of ſome boiled peas, may occaſionally be affected by the acidity of the ſpring water, in which they are boiled; but is generally I ſuppoſe owing to the mucilage of ſome of them being more or leſs coagulable by heat, than that of others. Something ſimilar to which obtains in animal mucus, as the cryſtalline humour of the eyes of fiſh become hard and opake by boiling; while the ſkins of animals, and the tendons of their feet, become a ſoft mucus or jelly by boiling; and ſome of the liquids, which are found in the cells or cavities of the body in dropſies, are obſerved to coagulate by heat, and others to become more fluid. The cauſes of this difference merits further inquiry.

V. 1. *To collect good ſeeds*, according to the obſervations of Mr. Cooper of Philadelphia, conſiſts not in procuring new ſeeds from diſtant places, as is generally ſuppoſed, but in ſelecting the beſt ſeeds and roots of his own; which though he has continually ſown or planted them in the ſame ſoil, every article of his produce is greatly ſuperior to thoſe of any other perſon, who ſupplies the market, and they ſeem ſtill in a ſtate of improvement. He believed that no kind of inceſt would

would degenerate the breeds of vegetables, and therefore adopted the plan of Mr. Bakewell in England in reſpect to quadrupeds, who continued to improve his flocks and herds by the marriages of thoſe, in which the properties he wiſhed to produce were moſt conſpicuous without regard to conſanguinity or inceſt.

Mr. Cooper was led to his preſent practice, which he began more than forty years ago, by obſerving that vegetables of all kinds were very ſubject to change with reſpect to their time of coming to maturity, and other properties, but that the beſt ſeeds never failed to produce the beſt plants. Among a great number of experiments he particularly mentions the following.

"About the year 1746 his father procured ſeeds of the long watery ſquaſh, and though they have been uſed on the farm ever ſince that time without any change, they are at this time better than they were at the firſt.

"His early peas were procured from London in the year 1756, and though they have been planted on the ſame place every ſeaſon, they have been ſo far from degenerating, that they are preferable to what they were then. The ſeeds of his aſparagus he had from New York in 1752, and though they have been planted in the ſame manner, the plants are greatly improved.

"It is more particularly complained of, that potatoes degenerate, when they are planted from the ſame roots in the ſame place. At this Mr. Cooper ſays, he does not wonder, when it is cuſtomary with farmers to ſell or conſume the beſt, and to plant from the refuſe; whereas having obſerved that ſome of his plants produced potatoes, that were larger, better ſhaped, and in greater abundance than others, he took his roots from them only; and the next ſeaſon he found, that the produce was of a quality ſuperior to any, that he had ever had before. This practice he ſtill continues, and finds that he is abundantly rewarded for his trouble.

"Mr. Cooper is alſo careful to ſow the plants, from which he raiſes

his ſeed, at a conſiderable diſtance from any others. Thus, when his radiſhes are fit for uſe, he takes ten or twelve, that he moſt approves, and plants them at leaſt one hundred yards from others, that bloſſom at the ſame time. In the ſame manner he treats all his other plants, varying the circumſtances according to their nature.

" About the year 1772 a friend of his ſent him a few grains of a ſmall kind of Indian corn, not larger than gooſe ſhot, which produced from eight to ten ears on a ſtalk. They were alſo ſmall, and he found, that few of them ripened before the froſt. Some of the largeſt and earlieſt he ſaved, and planted them between rows of a larger and earlier kind, and the produce was much improved. He then planted from thoſe that had produced the greateſt number of the largeſt ears, and that were the firſt ripe, and the next ſeaſon the produce with reſpect to quality and quantity was preferable to any, that he had ever planted before.

" The common method of ſaving ſeed-corn by taking the ears from the heap is attended, he ſays, with two diſadvantages; one is the taking the largeſt ears, of which in general only one grows on a ſtalk, which leſſens the produce; and the other is taking ears that ripen at different times.

" Many years ago Mr. Cooper renewed all the ſeed of his winter grain from a ſingle plant, which he had obſerved to be more productive, and of a better quality than the reſt; which he is ſatisfied has been of great uſe. And he is of opinion, that all kinds of garden vegetables may be improved by the methods deſcribed above, particular care being taken that different kinds of the ſame vegetables do not bloom at the ſame time near together; ſince by this means they injure one another." Communications to the Board of Agriculture, Vol. I. part 3. Letter from Dr. Prieſtley.

2. As the varieties of plants are believed to be produced by different ſoils and climates, which varieties will afterwards continue through many generations, even when the plants are removed to other ſoils and

and climates, it muſt be advantageous for the agricultor to inſpect other crops as well as his own; and thus wherever he can find a ſuperior vegetation to collect ſeeds from it; which is more certain to improve his crops than an indiſcriminate change of ſeed.

But where ſeed-corn is purchaſed without a previous obſervation of its ſuperior excellence, perhaps it would be more advantageous to take that from better kinds of ſoil, and from ſomewhat better climates; as the good habits acquired by ſuch ſeeds may be continued long after their removal to inferior ſituations. And on the contrary, care ſhould be taken not to collect a change of ſeeds from worſe climates or inferior ſoils, unleſs the agricultor is previouſly certain that they are of a ſuperior kind.

VI. 1. *To determine the goodneſs of ſeeds*, the weighing a given meaſure of them may generally be eſteemed a criterion; as it is known, that when ſeeds are put into cold water, thoſe which are leſs perfect are liable to ſwim, and the ſound ones to ſink; thus the imperfect ſeeds of rye-graſs and of clover may be detected by throwing a ſpoonful of them into water; but the ſeeds of rye-graſs are ſaid to be frequently adulterated by a mixture of the ſeeds of twitch or dog's graſs, which can only be diſcovered by an experienced eye. This even is ſaid to be a teſt of the goodneſs of malt; as thoſe grains, which are not perfectly germinated, will ſwim with one end upwards, I ſuppoſe the root end; and thoſe which are perfectly germinated ſwim on their ſide, whilſt the ſound ungerminated barley ſinks in water.

It is therefore a proper criterion of good ſeed-wheat to caſt it into ſalt and water, juſt ſo ſaline as to float an egg; as the more ſalt is diſſolved in the water, the heavier it becomes; and hence none but quite ſound grains of wheat will ſink in this brine; and that which ſwims is properly rejected. This rejection of the light grains by ſteeping wheat in brine is probably of greater conſequence to the enſuing crop, than the adheſion of any ſalt to the grain, which has

been believed to deſtroy the eggs of inſects ſuppoſed to adhere to it, or to fertilize the ſoil.

2. The weight of a given meaſure of corn will alſo with conſiderable certainty diſcover the quantity of huſk or bran contained in it, compared to the quantity of flour; as that grain, which is cut too early, or which is otherwiſe not quite ripe, as happens in wet ſeaſons, ſhrinks in the barn or granary, and becomes wrinkled, and has thus a greater proportion of ſkin or bran, than that which has been more perfectly ripened, and will hence weigh lighter in proportion.

A teſt of this kind may enable us to determine whether peas and beans, or oats, are preferable in reſpect to economy as provender for horſes. A ſtrike or buſhel of oats weighs perhaps forty pounds, and a ſtrike or buſhel of peas and beans perhaps ſixty pounds; and as the ſkin of peas and beans is much leſs in quantity than that of oats, I ſuppoſe there may be at leaſt fifteen pounds of flour more in a ſtrike of peas and beans than in a ſtrike of oats. There is alſo reaſon to believe, that the flour of beans is more nutritive than that of oats, as appears in the fattening of hogs; whence according to the reſpective prices of theſe two articles I ſuſpect, that peas and beans generally ſupply a cheaper provender for horſes than oats, as well as for other domeſtic animals.

But as the flour of peas and beans is more oily, I believe, than that of oats, it may in general be ſomewhat more difficult of digeſtion; hence when a horſe has taken a ſtomach full of peas and beans alone, he may be leſs active for an hour or two, as his ſtrength will be more employed in the digeſtion of them, than when he has taken a ſtomach full of oats. According to the experiment of a German phyſician, who gave to two dogs, which had been kept a day faſting, a large quantity of fleſh food; and then taking one of them into the fields hunted him with great activity for three or four hours, and left the other by the fire. An emetic was then given to each of them, and

the food of the ſleeping dog was found perfectly digeſted, whilſt that of the hunted one had undergone but little alteration.

Hence it may be found adviſable to mix bran of wheat with the peas and beans, a food of leſs nutriment, but of eaſier digeſtion; or to let the horſes eat before or after them the coarſe tuſſocks of ſour graſs, which remain in moiſt paſtures in the winter; or laſtly, to mix finely cut ſtraw with them.

3. Another way of diſtinguiſhing light corn from heavy is by winnowing; as the ſurface of the light grains being greater in proportion to their ſolid contents, they will be carried further by the current of air, which is produced by the van; though the heavy grains would roll further on the floor after rolling down a grate to ſeparate the duſt; becauſe their vis inertiæ would carry them further, after they are put in motion; and their ſurfaces would be reſiſted by the air no more than thoſe of the lighter grains.

4. Finally, there is reaſon to believe that a progreſſive improvement of many ſeeds exiſts during the warmer days of winter in our granaries, which probably conſiſts in the proceſs of the converſion of mucilage into ſtarch; in the ſame manner as the harſh juices of crab-apples, and of auſtere pears, are continually changing into ſugar during the winter; both which proceſſes are probably in part chemical, like the ſlow but perpetual change of ſugar into vinous ſpirit, when the juices of ſweeter apples and pears, or grapes, are put into bottles in the manufacture of cyder, perry, and wine.

This improvement of wheat, and of barley, and of oats, is well known to the baker, the maltſter, and the horſe-dealer; as better bread is made from old wheat, and barley is converted into better malt in the vernal months; and horſes are believed to thrive better, and to poſſeſs more vigour, when they are fed with old than with new oats.

VII. 1. *The preſervation of ſeeds* next demands our attention. Thoſe ſeeds which are liable to lie upon the ground, as peas and

corn,

corn, when thrown down by ſtormy or wet ſeaſons, ſhould be gathered rather earlier; leſt they ſhould begin to germinate, as they lie upon the ground, and would hence become a kind of malt after drying. Other ſeeds ſhould be gathered, before they would ſpontaneouſly fall from their pericarps, to prevent the loſs which muſt otherwiſe enſue in the reaping, or mowing, and carrying them to the barn, which often amounts to as much as is neceſſary to ſow the land, which produced it, as well as to ſupply the depredations of birds, inſects, and vermin.

Monſ. B. G. Sage accuſes the farmers of ſome parts of France of collecting their wheat with many green weeds immediately after reaping it, and preſſing it cloſe together in their barns; by which the ſtack undergoes a fermentation with great heat like ſome hay-ſtacks; and that the corn is by this fermentation killed, and will not grow when ſown like hay-ſeeds from a fermented hay-ſtack, mentioned in Sect. X. 11. 7; and alſo that the gluten, or vegeto-animal matter of the corn, is deſtroyed; and it on that account makes leſs agreeable and leſs wholeſome bread; and laſtly, that the ſtraw is much injured by becoming mouldy. Journal de Phyſique, Sep. 1794.

Monſ. B. G. Sage adds, that the following proceſs will diſcover, whether wheat has been thus injured, which may be intereſting both to the baker, and wheat-buyer, who wants it for ſeed-wheat. Make a paſte with flour and water, then waſh it with your hands under water, which muſt be frequently changed, till it no longer becomes diſcoloured. The ſubſtance remaining in the hands is the gluten; if the corn be good, this is elaſtic, and will contract when drawn out; if the corn has begun to heat, it is brittle; if the corn has fermented, none of the gluten will be obtained.

In this country, where corn is ſeldom cut too early, or preſſed together on the ſtack, the principal circumſtance required is to keep it dry; as the ſtraw is not liable to ferment like new hay made with young graſs, which contains ſugar at every joint of the ſtem. To

preſerve

preſerve a ſtack of wheat dry, a good cover of thatch may ſeem ſufficient; but as this is liable to injury by vermin, it would be an additional ſecurity, if at the time of making the ſtack the ſheaves were laid higheſt in the middle, and lower on every ſide, ſo that if any wet ſhould find its way into the ſtack, it might drain onwards along the ſtraw of the ſheaves, which would thus act like thatch throughout the whole ſtack.

There are inſtances of great durability of ſeeds, which have been preſerved dry, and ſecured from either ſo great heat or ſo great cold, as might deſtroy their life or organiſm. Thus there is an account of the ſeeds of Indian wheat, which grew well in a hot-houſe after having been kept thirty-four years, as was accurately aſcertained. Bath Society, Vol. V. p. 464. And it has been lately aſſerted, that many ſeeds of more than a hundred years old, which were found in ſome old herbarium at Vienna, have been made to germinate by the uſe of oxygenated muriatic acid and water. Philoſ. Magaz. But if the organic life of a ſeed be deſtroyed by froſt, or fire, or mechanic injury, putrefaction ſucceeds, and decompoſition; as when the organic life of an egg is deſtroyed by violently agitating it, it is known ſoon to putrefy.

To preſerve ſeeds in barns or granaries our principal attention ſhould be firſt to make them dry, and ſecondly to keep them dry; becauſe no ſeeds can vegetate without moiſture. The art of drying moſt ſeeds muſt conſiſt in duly ventilating them, eſpecially on dry days; which may be done by frequently turning over the heaps of them; and to preſerve them dry in this climate the door and windows of granaries ſhould open to the ſouth to receive the warmth of the ſun, with apertures round the building for ſufficient ventilation; which muſt be prevented from admitting rain or ſnow by ſheltering boards on the outſide.

The heaps of corn ſhould be ſurrounded with boards to keep them from contact with brick or ſtone walls; which, when warm moiſt

ſouth-weſt winds ſucceed cold north-eaſt winds, are liable to precipitate the moiſture from the atmoſphere by their coldneſs, and to communicate it to all bodies in contact with them. For a ſimilar purpoſe in ſtables ſome have put up a tall wooden trunk from the chamber to the room below, three or four feet ſquare, and ten or twelve feet high, with a ſliding valve to draw out the corn below, which is poured in at the top; in three or four places a tin or wooden pipe full of holes is made to paſs horizontally through the box to give air to the corn, the whole of which, when any of it is drawn out below, is moved in deſcending; and new ſurfaces of corn are applied to the air-holes of the horizontal tubes.

The moſt ſecure way of preſerving a great quantity of wheat, according to Mr. Tull, is by gently drying it on a hair-cloth in a malt-kiln, with no other fuel but clean ſtraw, and no greater heat than that of the ſunſhine. In this ſituation the wheat remained from four hours to twelve hours, according to the previous dampneſs of it. Mr. Tull knew a farmer in Oxfordſhire who purchaſed wheat, when it was cheap, and kept it by thus drying it for many years, and made a large fortune by ſelling it again in dearer ſeaſons. The life of the ſeed was not deſtroyed by this proceſs; as he aſſerts, that ſome of it grew, which had been kept in this manner ſeven years; whereas in drying potatoes on a malt-kiln ſo great heat was employed as to deſtroy their life, and violent putrefaction enſued, as mentioned in Sect. X. 9. 2.

2. A due ventilation alſo, where corn is kept in the common warmth of the atmoſphere in this climate, is neceſſary, except in ſeaſons of froſt, and alſo the admiſſion of light; as otherwiſe the vegetable mucor, called mould, is liable to grow upon the corn, and injure it; as this mucor like ſome other funguſes will grow, where there is little or no change of air, and without light, as in cellars, if there be ſufficient moiſture and warmth.

3. Another method of preſerving ſeeds may conſiſt in ſecluding them

them from heat, as in granaries beneath the ſoil; which are ſo deep or ſo well covered with earth, as not to be affected by the difference of ſeaſons. Thus there have been inſtances of muſtard-ſeed producing a crop on digging up earth, which had not been removed for many years, and, as was believed, even for ages. And in ice-houſes it is probable, that not only ſeeds might be long preſerved, but perhaps fruits alſo; if they were afterwards very gradually thawed by putting them into cold water, that they might not be deſtroyed by the too great ſtimulus of ſudden heat, as mentioned in Sect. XV. 4. 1.

4. Where it has been neceſſary ſuddenly to collect and to preſerve great heaps of corn without ſhelter for the proviſion of armies, ſome have moderately moiſtened the upper ſurface of the heap daily, which has occaſioned the upper grains to grow, and thus to produce a ſward or turf over thoſe below; which, it is ſaid, has thus preſerved the lower part of the magazine. But in reſpect to granaries for the purpoſe of laying up very large quantities of grain to prevent famines in ſcarce years, I ſuppoſe the ſtacks of covetous farmers, who keep their corn in cheap years, hoping to ſell it at a better price in ſcarce ones, is a more certain method, and a cheaper one to the public, to keep up a ſufficient ſtock of corn, than by any other experiment that can be deviſed.

5. Gardeners in general prefer new ſeeds to old for their principal crops, as they are believed to come up ſooner, and with greater certainty, and to grow more luxuriantly. "But peas and beans of a year old," Mr. Marſhall obſerves, "are by ſome preferred to new, as not ſo likely to run to ſtraw. And cucumbers and melons are beſt to be ſeveral years old, in order to their ſhooting leſs vigorouſly, and thence becoming more fruitful. But this principle is carried too far by ſome gardeners, who ſay theſe ſeeds cannot be too old, and will allow ten years to be within bounds; three for cucumbers, and four for melons, however is age enough.

"As to the age of ſeeds, at which they may be ſown, it is uncer-

tain, and depends much upon how they are kept; thoſe of cucumbers and melons are good a long time, becauſe very carefully preſerved.

"Peas and beans will germinate very well at ſeven years of age; but the ſeeds of lettuces and kidney-beans, and ſome others, are not to be depended upon after a year or two; and generally ſpeaking the ſmaller ſeeds are of the leaſt duration." Marſhall on Gardening.

6. Where ſeeds of a periſhable nature are to be carried to, or brought from, diſtant countries, I ſuſpect that covering them in ſugar would be the moſt certain and ſalutary method of preſerving them; and even, that fleſh meat cut into thin ſlices, and covered with ſugar, or ſyrup, or treacle, would be better preſerved than in brine, and afford a much more ſalutary nouriſhment to our ſailors.

Since I wrote the above I have ſeen a paper in the Tranſactions of the Society of Arts, Vol. XVI. from Mr. Sneyde of Belmont in Staffordſhire, who having obſerved ſome ſeeds, which came accidentally amongſt raiſins, to grow readily, directed many ſeeds to be ſent from the Weſt Indies covered with raiſins, and others in ſugar, and others in the uſual manner of ſending them, and found, that thoſe immerſed in ſugar or covered with raiſins both looked well, and grew readily; whereas many of the others would not vegetate.

Since the powder of freſh burnt charcoal is known ſo powerfully to abſorb all putrid vapours, it is probable the ſeeds mixed with and covered with charcoal duſt, which has been recently burnt, or not long expoſed to the air, might be ſucceſsfully employed for the preſervation of ſeeds either in long voyages, or in domeſtic granaries.

VIII. 1. *To ſow ſeeds advantageouſly* it is probable, that thoſe of our native plants might be ſuffered to drop on the ſurface of the earth in the autumn, as they fall from their parent plants, covered only by their deciduous leaves; in which ſituation their fruit might contribute to nouriſh them, as our crabs and ſloes; or defend them from inſects, as the acrid huſk of the walnut; or from birds, as the hard

ſtones

ſtones or ſhells of nuts and cherries, ſince this is the proceſs of nature.

But when the ſeeds brought originally from other climates are to be ſown, an attention is required to the circumſtance of ſeaſon and of ſoil. Thoſe, which will ripen their ſeeds in the ſame year, are to be ſowed in the early ſpring, and covered lightly with earth to preſerve them from birds and inſects; and ſhould be buried thus beneath the ſoil, ſoon after it has been ploughed or dug, as its interſtices are then replete with atmoſpheric air; which may be neceſſary to ſtimulate into elevation the plume of the embryon plant; as the moiſture of the earth is neceſſary to ſtimulate the root into its elongation downwards.

Thoſe ſeeds nevertheleſs, which will not perfect their vegetation in the ſame year, muſt be ſown in the early autumn; and though all ſeeds vegetate better, when placed but a little beneath the ſurface of the ſoil, as one inch, becauſe they have then a better ſupply of atmoſpheric air, which may be neceſſary for their firſt growth, before they have acquired leaves above ground; yet as many foreign ſeeds may not be ſufficiently hardy to bear our inclement winters, it may be neceſſary, as ſome believe, to bury them an inch and a half, or two inches, deep in the ſoil, to prevent the froſts from doing them injury, as well as to preſerve them from the depredation of birds. And the drill ſemination, or ſowing all kinds of ſeeds in rows, is the moſt convenient method for ſowing them at a determined depth, and alſo for the purpoſe of keeping the young plants clear from weeds by the more eaſy application of the hoe.

To ſow many ſeeds earlier than is uſually practiſed is much recommended. There is a paper by Lord Orford in Mr. Young's Annals of Agriculture, Vol. IX. p. 385, who ſeems to have found conſiderable advantage by ſowing barley ſo early as the ſeventh of February, three and a half buſhels on an acre. But as much moiſture with or without ſubſequent froſt is more liable to deſtroy the embryon

bryon in its very early ſtate in the ſeed, than after it has ſhot out roots and a ſummit, and thus acquired ſome habits of life; this early ſowing muſt ſometimes be practiſed with caution. Seeds may nevertheleſs be ſown ſtill earlier in hot-houſes, or in warm ſituations, as peas, beans, wheat, and may be afterwards tranſplanted in the vernal months with ſafety and advantage. See Sect. X. 3. 6.

The difficulty of determining the beſt ſeaſon for ſowing ſeeds in the ſpring, owing to the variation of the weather in the ſame latitude, as well as in laying down the exact ſeaſons for ſowing in different latitudes, occaſioned Linneus to conſtruct, what he terms a calendar of Flora; which was afterwards adapted to this climate by Stillingfleet; which conſiſted in obſerving the firſt appearance of the root-ſcions, or flowers of the uncultivated native vegetables; with directions to ſow the cerealia, or harveſt ſeeds, when ſuch plants or flowers became viſible. By attention to ſuch obſervations on the uncultivated native plants in many climates, it is probable, that ingenious tables might be produced, which might direct the beſt time of ſowing the uſeful ſeeds in all latitudes, and in all ſituations.

Another table of the climates, where plants grow naturally, and of their native ſituations in reſpect to moiſture or dryneſs, hill or valley, with the kind of ſoil where they were originally found, might alſo contribute to their ſucceſsful cultivation.

2. In the gardens near large towns, where the land is more valuable and better manured, gardeners ſometimes ſow two or three kinds of ſeeds on the ſame ground for the purpoſe of economy. Thus Mr. Marſhall obſerves, that "on the ſame ground they ſow radiſhes, lettuces, and carrots; the radiſhes are drawn young for the table, the lettuces to plant out, and a ſufficient crop of carrots is left; for carrots, if you wiſh them to be large, ſhould not grow very near to each other."

In defence of this mode of culture it is ſaid, if one crop fails, the others may do well, and there is no loſs of ground or time; and if all

all ſucceed, they do very well. Radiſhes and ſpinach are commonly ſown together by the common gardeners, and many manœuvres of inter-cropping are made by them, as the ſowing or planting between rows of vegetables that are wide aſunder, or preſently to come off, or in the alleys of things cultivated on beds.

"Thus if a piece of horſe-radiſh be new planted, it may be top-cropped with radiſhes or ſpinach, &c.; or if a piece of potatoes be planted wide, a bean may be put in between each ſet in every or every other row; a thin crop of onions upon new aſparagus beds, is a common practice, drawing them young from about the plants." Introduc. to Gardening. Rivington.

The farmer likewiſe, in the cultivation of graſſes for feeding ſheep, finds an advantage in ſowing a mixture of ſeeds on the ſame ground, as rye-graſs, trefoil, and clover, which are ſaid to ſucceed each other in reſpect to the production or maturity of their herbage, as in Sect. XVIII. 1. 1. And for the purpoſe of preventing ſmut it may be uſeful, as I have before obſerved, to ſow in the ſame ground in ſeparate rows two kinds of wheat, one of a forwarder nature than the other; whence if the farina of one kind ſhould be injured by wet weather, that of the other may impregnate the ears of both. The two kinds of wheat recommended are bearded wheat and ſmooth-headed wheat, which are called by farmers cone wheat and Lammas wheat; of both of which there are many varieties, and it is aſſerted that one third of cone wheat is frequently ſowed with two thirds of Lammas wheat, and that the crops are much ſuperior to either of them ſeparately. Hall's Encyclop. Art. Agriculture.

In reſpect to kinds of ſoil thoſe ſhould be choſen, which have been found by obſervation to ſuit particular ſeeds, both in regard to their nutritive properties, and the moiſture and warmth of their ſituations. And for thoſe ſeeds, which produce tuberous roots within the earth previous to their flowering, as potatoes, parſnips, radiſhes, a ſoil of leſs coheſion ſhould be found or prepared.

3. Add to this, that there are ſome ſeeds, as thoſe of carrots, that are ſo difficult to be diſſeminated in uniform quantities, that it has been cuſtomary to mix them previouſly with ſand or garden mould, for the purpoſe of giving them weight, or bulk, or to detach them from each other. And ſome even ſuffer them to begin to put forth their roots in ſuch a mixture of moiſt ſand or garden mould for the purpoſe of more regularly diſperſing them.

In dry ſeaſons the ſoaking ſeeds in water, a day or two before committing them to the ground, will forward their growth, as well as by artificially watering the ground before or after ſowing them; and the ſoaking them in a ſolution of ſalt and water may have another advantage of giving an opportunity of rejecting the light ſeeds, which float, and perhaps of deſtroying ſome inſects which may adhere to them; the ſprinkling ſome kinds of ſeed with lime may alſo be of advantage for the purpoſe of deſtroying inſects, if ſuch adhere to them, and of attracting moiſture from the air, or lower parts of the earth, or for its other uſeful properties; but where the ſeed, ſoil, and ſeaſon, are adapted to each other, none of theſe condiments are required.

It may nevertheleſs on other accounts be very advantageous to ſteep many kinds of grain in the black liquor, which oozes from manure heaps. Mr. Chappel, in the papers of the Bath Society, found great benefit by ſteeping barley in the fluid above mentioned for twenty-four hours, and ſkimming off the light grains. On taking it out of the water he mixed wood-aſhes ſifted with the grain to make it ſpread regularly, and obtained a much finer crop, than from the ſame corn ſown without preparation. To this we may add, that to ſteep the ſeed in a ſolution of dung in water, as in the draining from a dung-hill, is believed in China both to forward the growth of the plant, and to defend it from variety of inſects, according to the information given to ſir G. Staunton.

There is an old proverb, "ſow dry and ſet wet;" but where the

earth has been lately turned over by the plough or ſpade, there can be no bad conſequence from ſowing during rain in general; but in ſome clay grounds much ſoftened by rain, if ſeed be put into holes, and a dry ſeaſon ſucceeds, an impenetrable cruſt may ſupervene by the exhalation of the water, and the ſetting, as it is called, of the clay; but even this could not frequently occur, when ſeeds are ſown in the moiſt weather of the autumnal months; but generally in both caſes the growth of the ſeed would be forwarded by the moiſture.

4. Where the fruit, which ſurrounds any kind of ſeeds, can be ſowed along with them, it may anſwer ſome uſeful purpoſe. Thus the fruit of crabs, quinces, and ſome hard pears, will lie all the winter uninjured covered only with their autumnal leaves, and will contribute much to nouriſh their germinating ſeeds in the ſpring. So the holly-berry and the ivy-berry remain during the winter months uninjured by the rains or froſts, and undevoured by birds or inſects, and contribute to nouriſh their germinating ſeeds, when they fall on the ground in the ſpring. The acrid huſk of walnuts ſowed along with them preſerves the ſweet kernel from the attack of inſects; the ſame muſt be the uſe of the acrid oil of the caſhew-nut. The haw-thorn poſſeſſes both a nutritive covering and a hard ſhell for the above purpoſes; and the ſeeds of roſes are armed with ſtiff pointed briſtles, as well as furniſhed with a nutritious fruit, ſo long known as an agreeable conſerve in the ſhops of medicine, conſerva cynoſbati; the former conſtitutes a defence againſt inſects, and the latter ſupplies a reſervoir of nutriment for the germinating ſeeds.

5. To this ſhould be added, that in our ſhort and cold ſummers the viviparous buds of ſome vegetables are too luxuriant, and do not produce oviparous buds ſoon enough to ripen their ſeeds, as melons and cucumbers, and many other plants, in thoſe ſeaſons which are moiſter than common. It is believed, that by waſhing the ſeeds of melons and cucumbers from the ſaccharine and mucilaginous matter of their fruit, and by keeping the ſeed three or four years before it is uſed,

that the viviparous buds become leſs vigorous, and the oviparous ones more numerous, and forwarder in their flowering; and for the production of earlier as well as of larger crops all ſuch luxuriant vegetables ſhould be ſown early in the vernal ſeaſon, or in the autumnal months, if they are not too tender to bear the winter froſts.

IX. *Queſtion concerning general encloſure.*

The political advantage or diſadvantage of the general encloſure of a country belongs to this place, as it more particularly affects the production of the cerealia, or corn-agriculture.

There can certainly be no objection to the encloſure of commons, or at leaſt to the diviſion of them into private property, as they are believed to produce more than tenfold the quantity of ſuſtenance to mankind, if they are employed in agriculture, or even in paſturage, than by nouriſhing a few geeſe, ſheep, or deer, in their uncultivated ſtate covered with fern, heath, or gorſe.

2. The advantage of encloſing paſture-lands, or meadows, can not be doubted; as the management of fattening cattle, of milch-cows, ſheep, and horſes, becomes ſo much eaſier; as well as the more convenient uſe of the aftermath, when the hay is carried away.

3. The lands alſo appropriated to the production of garden vegetables and fruit, as well as to the production of other perennial plants, which are uſed in the arts, as hemp, flax, madder, woad, rhubarb; and of the eſculent roots or herbage raiſed for the conſumption of cattle, as turnips, potatoes, carrots, cabbages, certainly require to be encloſed.

4. The political queſtion therefore finally concerns only the arable lands, and aſks ſimply, whether a general encloſure of arable lands be favourable or unfavourable to the population, and conſequent proſperity of the country, which muſt depend on the comparative quantity of nutritive proviſion, which is likely to be produced from the different modes of its cultivation.

Now as paſturage requires fewer hands in the management of it, and leſs art and attention to conduct it, than agriculture; and as its products in fleſh, cheeſe, butter, take a higher comparative price at market, and are articles of greater luxury, than the products of arable land in corn, we may conclude, that paſturage will prevail in all encloſed provinces over agriculture. And as perhaps tenfold the numbers of mankind can be ſupported by the corn produced on an hundred acres of land, than on the animal food which can be raiſed from it, it follows, that an encloſed province will afford ſuſtenance to a much ſmaller population; and as the number of inhabitants of a country depends on the eaſe, with which parents can procure ſuſtenance for their families, marriages will become fewer, and the people decreaſe, when an arable country is converted into paſturage.

This laſt circumſtance appears already to operate in theſe realms, ſince about half a century ago much corn was exported annually, but for ſeveral years laſt paſt great quantities of it have been annually imported for our own ſuſtenance; and that even though potatoes are much cultivated, and muſt therefore leſſen the conſumption of grain, and the ungraceful faſhion of covering the head with wheat-flour is much diminiſhed. Is this to be ſolely aſcribed to the numerous encloſures of arable lands, or in part to the conſumption of corn in the diſtilleries?

One very important conſequence of any country producing a greater quantity of corn, than it conſumes, and of thence exporting it to foreign nations, even by means of a bounty, conſiſts in its certainty of preventing famine, the moſt dreadful of human calamities; as in years of ſcarcity the ſtream of exportation can be ſtopped, and produce an ample ſupply by its ſtagnation at home.

Hence when a great part of any tract of country becomes employed in paſturage inſtead of agriculture, the inhabitants will become conſumers of fleſh inſtead of conſumers of grain, and will conſequently decreaſe in number from the want of ſufficient ſuſtenance.

Beſides which the people of agriculture are more active and robuſt than the people of paſturage, and more ingenious in the invention and uſe of machines neceſſary for the more artful cultivation of the ſoil, as well as more numerous, and will conſequently become ſuperior to them in arms and arts, and may in proceſs of time conquer them; which reminds us of the Egyptian Dynaſty of Shepherd-kings, who were ſubdued by their agricultural rivals; and alſo of the allegorical hiſtory of Cain ſlaying Abel, which were probably the names of two political hieroglyphic figures repreſenting the ages of paſturage and of agriculture before the invention of letters.

It muſt hence certainly be an object of good policy to encourage agriculture in preference to paſturage, which in this country might be effected by preventing the encloſure of arable lands, and alſo of thoſe parts of commons, which are beſt adapted to the growth of corn; though the whole might be advantageouſly divided into private property. Unleſs ſome other means could be deviſed of preventing a nation from becoming too carnivorous, or of duly promoting the cultivation of grain, the former of which was heretofore produced by religious faſt-days twice a week, and the latter by bounties on the exportation of corn. To which might be added a total prohibition of the deſtructive manufactory of grain into ſpirits, or into ſtrong ale, and thus converting the natural nutriment of mankind into a chemical poiſon, and thus thinning the ranks of ſociety both by leſſening their quantity of food, and ſhortening their lives by diſeaſe.

In many villages, where much arable lands have been lately encloſed, the numbers of labouring people have quickly been much diminiſhed both by the ſcarcity of food, and want of employment.

> Worſe fares the land, to haſtening ills a prey,
> Where wealth accumulates, but men decay;
> Princes or lords may flouriſh, or may fade,
> A breath can make them, as a breath has made;

But

But a bold peaſantry, their country's ſword,
When once deſtroy'd, can never be reſtor'd.
GOLDSMITH'S DESERTED VILLAGE.

Mankind nevertheleſs ſeems by nature to be deſigned to ſubſiſt on both vegetable and animal nutriment, which appears from the length of his inteſtines, which like thoſe of ſwine are much longer than the inteſtines of carnivorous animals, and much ſhorter than thoſe of the vegetable eaters; and which alſo appears from the ſtructure of his teeth, which partakes of the ſtructure of thoſe of the carnivorous and phytivorous animals; and laſtly, becauſe thoſe people, who live ſolely on vegetables, as the Gentoo tribes, and thoſe who ſubſiſt ſolely on animals, as the fiſh-eaters of the northern latitudes, are undoubtedly a feebler generation than thoſe of this country, who exiſt on a mixture of both. A due proportion therefore of the two kinds of nouriſhment, ſuch as perhaps at preſent exiſts, or lately did exiſt, in this nation, muſt be decidedly the beſt; the preſervation of which, with the prohibition of ſpirits, or of ſtrong fermented liquors, except occaſionally as medicines, might probably render theſe kingdoms more populous, robuſt, proſperous, and happy, than any other nation in the world. But if the luxurious intemperance of conſuming fleſh-meat principally, and of drinking intoxicating liquors, ſhould increaſe amongſt us, ſo as to thin the inferior orders of ſociety by ſcarcity of food, and the higher ones by diſeaſe both of mind and body, it may hereafter be ſaid of Great Britain, amid her foreign conqueſts, as formerly of ancient Rome,

——————— Sævior armis
Luxuria incubuit, victumque ulciſcitur orbem.

SECT.

SECT. XVII.

PRODUCTION OF ROOTS AND BARKS.

Barks of trees are similar to their roots. All roots now known were originally from seeds. I. 1. Tuberous or bulbous roots *of turnip, carrot, parsnip, beet, are reservoirs of nutriment for the future stem. Not so in grasses. Sugar visible in beet roots. Small beer from parsnip roots. Alcohol from carrots. The knobby root and flower-stem are successive plants. Select forward seeds from vigorous plants, and a soil not cohesive. Radishes on hot-beds.* 2. *Tuberous roots from subterraneous wires, as potatoes. Pinch off the flowers. Make a cellular soil. Aerial potatoes. Curled leaf of potatoes. Sow the seed. Plant large roots and whole ones. Early potatoes.* 3. *Improve ground artichoke and pignut by seed.* 4. *Onions, method to improve them.* 5. *Orchis, ripen the seeds of it. Snow drops. Hyacinths. Crocus. Martagon lily.* II. 1. Palmated, or branching roots, *not immediately from seed. Perennial roots, like barks of trees, continue to increase in size. Should remain four or five years in the ground, not longer, as rhubarb.* 2. *Pinch off the flowers, as in rhubarb.* 3. *Roots of aquatic plants. Nymphæa, butomus, cultivated for nutriment, wine, or vinegar.* 4. *Art to preserve roots. Keep them alive, between* 32 *and* 48 *degrees of heat, covered with pounded charcoal, saw-dust, and thatch, or dry them by ventilation and heat.* 5. *Of mushrooms. Their gills are their lungs. Are animate beings without locomotion. Are of animal origin. Conduct galvanism. Mushroom stone, truffles, morels, mushrooms with acrid juice. Ear-fungus.* III. 1. Barks *contain sugar and mucilage, and other ingredients. They should be taken off before the buds expand.* 2. *Oaks, why barked in spring.* 3. *Barks of elm and maple might make small beer. Of holly esculent. Bird-lime like caoutchouc.* 4. *Bitter, aromatic. Acrid barks.* 5. *Restringent and colouring barks for tanning and dying.* 6. *Fibrous barks of flax, papyrus, mulberry, and birch.* 7. *To increase the bark pinch off the flowers.*

flowers. 8. *Rub off the moſs. Sprinkle with water.* 9. *Wounds of the bark. Paint the naked alburnum.* 10. *Canker. Bind on a new bark. Plant the branch in a divided garden-pot.*

As the barks of trees are compoſed of a congeries of the long caudexes of the individual buds, which conſiſt of the abſorbent veſſels, which imbibe nutriment from the earth, and of the arteries and veins, which ſupply nutriment to the growing vegetable; of the glands, which ſecrete from the vegetable blood the various acrid, aſtringent, or narcotic, juices to defend them from the depredation of inſects; and the various mucilaginous, oily, or ſaccharine, materials for the nouriſhment of their embryon buds; and laſtly, of the organs of reproduction. There exiſts the ſtrongeſt analogy between the barks of the trunks of trees, and of their roots, in every reſpect; except that the former poſſeſſes a cuticle adapted to the contact of the dry atmoſphere, and the latter a cuticle adapted to the contact of the moiſt earth, which differ from each other like the external ſkin, and the mucous membranes of animals. And finally, as theſe long caudexes of the buds of trees, which form the filaments of the bark, terminate in radicles beneath the ſoil, and in leaves in the air, like the broad caudexes with the radicles and aſcending ſtems, or foliage, of herbaceous plants, they exactly reſemble each other.

We ſhall therefore divide roots for the purpoſe of treating of their production into bulbous or tuberous roots, into palmated or branching roots, and into barks; obſerving that though roots and buds might poſſibly have exiſted before ſeeds, and though a great number of the roots uſed for nutriment, or for the purpoſes of medicine, or for the arts of dying and tanning, are immediately produced by buds, or bulbs; yet are they all, which we now poſſeſs, originally derived, I ſuppoſe, from ſeeds; becauſe thoſe varieties, which have been propagated from buds or bulbs for many centuries, are believed to acquire hereditary diſeaſes, and gradually to periſh.

1. *Of*

1. *Of tuberous and bulbous roots.*

1. Some tuberous roots, as the turnip, braſſica rapa, are immediately produced from ſeeds, but differ from the other plants, which are called annual or biennial, in this circumſtance; that, as they are generally ſowed ſo late in the ſeaſon as not to have time to produce flowers and ſeeds in the ſame year, they produce a knobby root, which conſiſts of a reſervoir of nutritious matter for the future flower-ſtem, which is to riſe and flouriſh in the ſucceeding ſpring and ſummer; whereas the common annual graſſes, as oats and barley, do not previouſly lay up a magazine of nutriment in their roots, but in their joints, which are ſweet; and therefore their roots are not uſed for culinary purpoſes, or for provender.

Other tuberous roots are raiſed in the ſame manner from ſeeds, but are generally ſown alſo ſo late in the ſeaſon as not to form their flower-ſtems in the ſame year; as the carrot, daucus carota; the parſnip, paſtinaca ſativa; and the beet, beta vulgaris; theſe alſo lay up a ſtore of mucilaginous and ſaccharine matter in their roots for the growth of the future flowers. In the beet-root the cryſtals of ſugar are ſometimes viſible by a microſcope; and I was well informed, that a labourer in Lincolnſhire made ſmall beer from a decoction of parſnip roots, which was ſpirituous enough, and not of diſagreeable flavour; and Mr. Hornby of York, by boiling carrots, and fermenting the juice expreſſed from them, produced two hundred gallons of proof ſpirits from twenty tons of carrots. Edinb. Tranſact. Vol. II. p. 28. Now as all vinous ſpirit has been ſugar, there is foundation to hope that a method may be diſcovered of producing and ſeparating ſugar from theſe plants of our own climate in ſufficient quantity for our demeſtic conſumption, or even for exportation.

Other tuberous roots are propagated from ſeeds in the ſame manner; and though they are ſowed early, and produce their flower-ſtem and ſeeds in the ſame year, yet they form a knobby root, which conſiſts

ſiſts of a magazine of nutritious matter, previous to the elevation of the flower-ſtem, as the radiſh, rhaphanus ſativus, and carrot, and beet, when ſown early. I nevertheleſs ſuſpect that theſe, as well as the preceding, conſiſt in reality of two ſucceſſive plants; that which forms the knobby root, and that which is formed from it, as ſpoken of in Sect. IX. 3. 6.

For the production of roots of theſe kinds, which are immediately or ſecondarily propagated from ſeeds, our attention muſt be applied to collect the forwardeſt ſeeds, and from the beſt plants of the kind; and to ſow them at the proper ſeaſon of the early ſpring, or early autumn; and in a ſoil which contains ſufficient vegetable nouriſhment, obſerving, nevertheleſs, that as carrots, parſnips, beets, and radiſhes conſiſt of knobs formed in the ground, a leſs adheſive ſoil is to be ſelected; as one abounding with ſiliceous or calcareous ſand, as well as with carbonic earth. But as the turnips are formed chiefly above ground, this attention to the coheſion of the ſoil becomes leſs neceſſary, ſo that it is ſufficiently penetrable by the fibres of their radicles.

There is another art of producing larger roots from ſeed, and at an earlier ſeaſon, as of radiſhes; which is by ſowing them in hot-beds in the early ſpring, and expoſing the tops to the cold air during the day, as this prevents the luxuriant growth of the ſummit, and increaſes that of the root.

2. Other tuberous roots are generally propagated by ſubterraneous wires, or root-buds, from the tuberous roots of their parents through a long generation, and not either primarily or ſecondarily from ſeeds; as the potato, ſolanum tuberoſum; and the ground artichoke, or tuberous ſun-flower, helianthus tuberoſus; and perhaps the pig-nut, bunium bulbocaſtanum.

As the tuberous roots of the potato planted in the ſpring not only produces many other ſimilar tuberous roots, but flowers alſo during the ſummer; I was led to ſuſpect, that pinching off the flowers, as

they appeared, would contribute to increaſe the number or enlarge the ſize of the new roots; which experiment has been made on a ſmall ſcale by one, who believed it to ſucceed in a degree deciſive of its utility. See Sect. XIX. 3. 1. and Sect. VII. 1. 3, where it is ſaid, that pinching off the flower-ſtems of bulbous-rooted flowers, when they firſt appear on young bulbs only a few years from the ſeed, is believed to render the flower duplicate.

As the roots of potatoes are formed beneath the earth, the ſoil, in which they are planted, ſhould be laid hollow and full of cells, or ſhould poſſeſs leſs coheſion than uſual, to facilitate the protruſion of their wires, and the enlargement of their roots. This ſhould be done by burying ſome long litter of ſtraw and ſtable dung under the ſoil; for as potatoes are believed to require more carbonaceous earth than carrots, a mixture of ſand is leſs advantageous to them.

I was this day ſhewn by my friend Major Trowel of Derby a new variety of the potato in his excellent new-made garden, the ſoil of which conſiſts of marl mixed with lime and ſtable-manure. From one root there appeared to iſſue ſix or eight ſtems three or four feet long, at every joint of which were produced new potatoes; at the lower joints there were three of theſe aerial potatoes, one large one the ſize of a pullet's egg, and a ſmaller one on each ſide of it. At the upper joints only one new aerial potato adhered, and theſe became ſmaller the further they were removed from the root; and finally, at the ſummit there had been a flower as there was now a ſeed-veſſel, called a potato-apple. All theſe new potatoes at the joints of the ſtems were green, becauſe they had not been etiolated by being ſecluded from the light, but the terreſtrial roots were white. The larger new tuberous roots had eyes on them like a common potato, but the ſmaller ones had begun to ſhoot out a new ſtem or leaves from their upper part. This variety, which may be termed an aerial potato, is analogous to the magical onion, and other ſpecies of allium, which bear cloves, or roots on their ſummits inſtead of ſeeds,

and like the viviparous polygonum; but differs in this circumſtance, that in all thoſe, I believe, the flowers are barren in reſpect to bearing ſeeds, as thoſe are on the ſummit of the ſpike of polygonum viviparum; but in the aerial potato there was alſo a ſeed-bearing flower at the ſummit of the ſtem, and the new roots only at the lateral joints. I ſhould hope this proliferous variety by cultivation may become permanent, and give riſe to a new ſpecies, which may produce both aerial potatoes and ſubterraneous ones, a twofold viviparous progeny.

The curling of the leaves of potatoes, which is attended with ſo great a diminution of the quantity and ſize of the new roots, is ſuppoſed to be owing to their continued propagation by ſubterraneous buds or root-wires, inſtead of by ſeed; that hence they acquire hereditary diſeaſes, like the canker or gangrene of apple trees, which have for one or two centuries been propagated by grafting the ſcions, as mentioned in Sect. IX. 3. 4. and XV. 1. 4. Hence by ſowing the ſeeds of potatoes, and cultivating the roots thus produced, new varieties may probably be ſoon acquired, exempt from the diſeaſe of the curled leaf, and which may be as good in other reſpects as thoſe which have been too long propagated by their roots. Some have nevertheleſs affirmed, that they have ſeen curled potato-plants in the ſecond year from the ſeed; and others, that they have ſeen numerous inſects on theſe curled leaves; and others, that the potato-root, the leaves of which are curled, remains hard, and leſs diſſoluble in the ſoil, which I have myſelf witneſſed. More obſervations are wanted to elucidate this ſubject.

Another cauſe of the degeneracy of potatoes has ariſen, I believe, from planting the leaſt inſtead of the largeſt roots, ſee Sect. XVI. 5. and which conſequently poſſeſs leſs vigorous vegetation, as buds and bulbs ſo exactly reſemble the parent plant. Thus the ſmall bulbs, which ariſe from tulip-roots, will produce a rather larger bulb annually for three or four years, as I am informed; but it is the large

new central bulb only, which will produce a flower the next ſummer, and another large central bulb like itſelf. See Sect. IX. 3. 1. Another cauſe of the degeneracy of potatoes may ariſe from dividing the larger roots into too many ſets, which muſt deprive the embryon plant of much of its appropriated nutriment; as the umbilical part of the root is generally thrown aſide by thoſe idly-ingenious diſſecters of it; for though the part, where the umbilical veſſels were inſerted, may not after the mature growth of the bulb appear to poſſeſs new veſſels from the embryon plants, ſuch as are ſeen on the lobes of a growing garden-bean; yet, as it becomes decompoſed, it muſt ſupply mucilaginous or ſaccharine nutriment to the roots of the new plants.

As the potatoes raiſed from ſeeds do not flower on the ſecond or third year, reſembling in this circumſtance the bulbs of tulips and hyacinths; theſe new roots, I am told, are ſold as early potatoes, and that they are forwarder in their growth from their being generally planted without being divided; and that they form their new roots ſooner, as they do not flower. To improve the ſeeds of potatoes ſee Sect. XVI. 3. 4.

The following method of planting whole potatoes is recommended in Mr. Adam's Eſſays on Agriculture, and has a promiſing appearance.

"The idea," ſays he, "which I mentioned before, reſpecting the culture of the Scotch and Anjou cabbages, might be ſucceſsfully applied to that of potatoes. Let us ſuppoſe the ground, in which they are to be ſet, is properly prepared by plowing: let then the furrows be drawn in it at four feet diſtance all over the field, and croſſed by other furrows at an equal diſtance. Where theſe interſect each other lay in ſome dung from a wheelbarrow, extending from the point of interſection fourteen or fifteen inches each way: let a man following ſpread a little of the mould from the furrow over the dung; let a third hand put one whole ſound potato at the point of interſec-

tion, and one in each furrow, at a foot diſtance from the centre, which will make five in all: a fourth hand ſhould now follow with a barrow full of leaves, and lay them over the plants; ſhould then ſprinkle ſome mould lightly over them, and leave them ſo till the plants ſhoot.

"Thus the plants will occupy a ſpace of two feet each way, out of the four feet between the furrows; and the remaining intervals between the plants on each ſide will alſo be two feet, which intervals I would horſe-hoe at the proper periods, firſt one way of the field, and then acroſs, laying the mould upon the plants at each hoeing, ſo that the ſpaces which the plants occupied would by theſe means become little ſquare hills filled with roots; and the intervals between being thus hoed and croſs hoed, would have the uſual good effects of pulverizing the ſoil, deſtroying the weeds, and preparing the land in the beſt manner poſſible for a crop of wheat."

3. The ground artichoke, helianthus tuberoſus, ſeldom ripens its ſeeds in this country, and might probably be much improved by uſing methods to ripen the ſeed, which are mentioned in Sect. XVI. 3. 4; and by thus producing new varieties; and the pignut, bunium bulbocaſtanum, might probably by cultivation from the ſeed ſupply an agreeable and ſalutary root to be eaten like cheſnuts either raw or roaſted.

4. The ſeeds of the common onion, allium cepa, generally produce no flower-ſtems the firſt year; but each ſeed produces concentric leaves, which gradually form a large bulb below them with one or two, and ſometimes three, leſs internal bulbs, included within three or four general concentric coats, beſides the three or four coats appropriated to the individual bulbs, as deſcribed in Sect. IX. 3. 2. On the next year ſome ſpecies of this genus produce bulbs after their flowers inſtead of ſeeds, as allium ſativum and magicum; others produce not only flowers but alſo bulbs, as allium moly, and ſpherocephalum. If the bulbs of theſe leaſt kinds of allium were planted

with

with deſign to produce other bulbs, and not to produce ſeeds; it is probable, that pinching off the flowers might enlarge the new bulbs, as the pinching off the flowers of potatoes; and that by ſuch means a larger kind of bulbs of ſome of this genus might be procured.

5. Another bulbous root, which might be well worthy cultivation in moiſt ground, is the orchis morio; which is ſold under the name of ſalep, after it has been prepared by firſt ſcalding it in hot water to detract the ſkin, and afterwards by drying it in an oven; and which then affords a nouriſhing mucilage, which will long keep uninjured. And, if it was cheaper, might probably be brought into more extenſive uſe as a culinary vegetable, as mentioned in Sect. XVI. 3. 4. The orchis morio produces one large new root annually, and probably ſome ſmaller offsets, as otherwiſe I do not perceive, how it could increaſe in our meadows, as it does not ripen its ſeeds in this country.

If the new root be taken away from the old one early in the year, it is affirmed, that the ſeeds will ripen in Sweden; which are otherwiſe in that country, as in this, always unprolifie; this experiment might therefore be very advantageous to the cultivator. Another method of inducing orchis to bear prolific ſeeds may be by confining the roots in garden pots, which might be immerſed in a moiſt ſoil, and would probably bear ripe ſeeds; as the lily of the valley, convallaria, is ſaid to do by crowding its roots ſo much as to prevent the production of more of them, Amenet. Academ. Vol. VI. p. 120. A third method of procuring ſeed from orchis might be by cultivating a few of them in a hot-houſe for that purpoſe.

The root of the ſnow-drop, galanthus, if dug up in winter, and prepared in the ſame manner, might poſſibly ſupply a nutritious mucilage ſimilar to that of the orchis; as I once boiled a few of them, and found on taſting them, that they had no diſagreeable flavour. If prolific ſeeds could be procured from this plant, it might be worth cultivation for the ſame purpoſes as the orchis; and the roots of the hyacinth,

hyacinth, I am informed, are equally inſipid, and might be uſed as an article of food; but the roots of crocus, which I boiled and taſted, had a diſagreeable flavour, and might probably therefore be inſalubrious.

Mr. Gmelin in his Hiſtory of Siberia aſſerts, that the roots of the lilium martagon are uſed as food in that country; and it is probable, that the root of the arum, though it be acrid in its raw ſtate, might ſupply palatable and ſalutary nutriment by cookery; as Mr. White aſſerts in his Hiſtory of Selborne, p. 43, that it is ſcratched up and eaten by thruſhes in ſevere ſnowy ſeaſons, and it is known ſoon to loſe its acrimony even by expoſing its dry powder to the air; we may add, that the root of the aſphodelus ramoſus is uſed to feed ſwine in France, and that good ſtarch is obtained from the roots of white bryony and of alſtromeria licta.

Other bulbous roots are propagated by floriſts with great attention for the beauty of their flowers, as tulips, hyacinths, lilies, and many others. For an account of ſome of theſe ſee Sect. IX. 3. on the growth of bulbs, and Sect. XIX. 3. 1. on the production of flowers.

II. *Palmated or branching roots.*

1. The bulbous and tuberous roots already mentioned were either ſuch, as were primarily derived from ſeeds, as the turnip, carrot, parſnip, radiſh, beet, ſalſafi; or ſuch as were ſecondarily derived from ſeeds, but immediately from bulbs or knobs ſimilar to themſelves, as potatoes, ground artichoke, orchis, pig-nut. But the branching or palmated roots, which are uſed as food, or in medicine, or in the arts of dying, are ſeldom produced immediately from ſeeds, but generally from preceding roots, and are hence the product not of annual but of perennial plants; as the root of liquorice, glycyrrhiza; of marſh mallow, alcea; of rhubarb, rheum; and of madder, rubia tinctoria.

The roots of theſe perennial plants ſhoot out not only annual

ſtems

ſtems with numerous flower-buds above ground, but alſo other new buds on their caudex, or upper part of the roots beneath the ſoil; all which buds protrude their new caudexes not only over thoſe ſtems, but alſo over the old root-branches; and thus form annually a new bark over the old root, which remains alive beneath the ground, though the ſtem periſhes by the winter froſts. This happens exactly in the ſame manner as the bark of trees, which annually is produced over the old bark of the root as well as of the trunk; but in trees the ſtem-bark as well as the root-bark ſurvives the winter.

Hence theſe palmated or branching roots of perennial herbaceous plants, as of rhubarb, madder, liquorice, continue to increaſe in ſize by the ſuper-addition of an annual new bark; but in four or five years the internal part begins to decay, and the roots therefore ſhould be taken out of the ground for uſe before that time. It is ſaid in the tranſactions of the Society for Encouragement of Arts, Vol. XVI. p. 226, that thoſe rhubarb roots, which were not taken up, till they were ſeven or more years old, were moſt of them good for nothing from the decay of the internal part of the root. The ſame is ſaid to happen to ſome bulbous roots, as the hyacinth; and occurs in all thoſe roots, which are ſaid to be end-bitten, as a ſpecies of ſcabius called devil's-bit. See Sect. IX. 3. 5.

They ſhould then be taken up in the winter months, before the new buds or flower-ſtems begin to acquire nouriſhment from the root, by which it would be deprived of a part of the nutritious, colouring, or medical matters; which principally reſide in the bark, or alburnum of it. On this laſt account alſo theſe roots ſhould not be permitted to continue in the ground a much longer time than that above mentioned, though the internal or woody part of the root may not decay; as the woody part is leſs adapted to the purpoſes expected than the bark and alburnum, which cover or conſtitute the numerous branches of the root.

2. One method to increaſe the ſize of theſe palmated or branching

ing roots may be by pinching off the flowers, as ſoon as they appear, when the ſeeds are not wanted; this I once ſaw practiſed on the rheum palmatum with apparent advantage, as well as on potatoes, as mentioned above; as more nutriment may thus be derived to the new buds forming on the roots.

The colouring matter ſold under the name of annotta, or arnotta, which is ſaid to be obtained from the ſkin of the kernel of the bixa of South America, or of the enonymus ſhrub cultivated in our gardens, is believed to be much adulterated with madder, rubia tinctoria; the root of which for the purpoſe of colouring cheeſe may be uſed inſtead of arnotta, and is to my knowledge a perfectly harmleſs root, though it tinges the bones of young animals red, who eat it mixed with their food, and may be grown by cheeſe-farmers in their own gardens, as it is a very hardy perennial plant, and requires no art of cultivation. It may be uſed either by pounding the freſh root and boiling it in water, or by drying the root for the purpoſe of preſerving it, and afterwards bruiſing and boiling it.

For the cultivation of rubia tinctoria ſee Miller's Gardener's Dictionary, who deſcribes with ſeveral plates the manner of growing and of afterwards preparing this root in prodigious quantities in Holland; and adds, "that if the cultivation of madder was carried on properly in England, that it would not only ſave to the nation the great annual ſum now expended in the purchaſe of it from the Dutch, but would employ a great number of hands, from the time harveſt is over, till the ſpring of the year, which is generally a dead time for labourers; and the pariſhes might thence be much eaſed of the poor's rates, which is a conſideration well worthy public attention."

The external part of the root of rubia tinctoria is coloured red, and its internal part yellow, which diſtinguiſhes it from moſt other roots, which are generally etiolated owing to their ſecluſion from the light; which liberates their ſuperfluous oxygen, which otherwiſe deprives them of colour as in bleaching, by uniting with their colouring mat-

ter, and converting it into a colourleſs acid, except where the colouring matter abounds in too great quantity. This etiolation of moſt roots is evidently owing to the want of light, becauſe many of them, as of white potatoes, become green if they grow above ground.

3. The roots of ſome aquatic plants are uſed in medicine both of the bulbous and palmated kinds, as ſcilla maritima, ſquill or ſea-onion, and the iris luteus, yellow water flag, and the acorus calamus, aromatic flag. Other aquatic roots are ſaid to have ſupplied food, as the ancient lotus in Egypt, which has been by ſome writers ſuppoſed to be the nymphæa nelumbo. Herodotus affirms in his Enterpe, that the Egyptian lotus grows in the Nile, and reſembles a lily; and that the natives dry it in the ſun, and take the pulp out of it, which grows like the head of a poppy, and bake it for bread. The white-flowered and the yellow-flowered nymphæa of our ponds and rivers has a palmated root ſometimes three inches in diameter. In Siberia the roots of the butomus, flowering ruſh, are eaten; both which well deſerve further attention, as they grow ſpontaneouſly in our ditches and rivers, which at preſent produce no eſculent vegetables, and might thence become an article of uſeful cultivation. See Sect. IX. 2. 5.

Some other aquatic roots, as well as terreſtrial ones, might probably become eſculent and nutritive by boiling or roaſting them to deſtroy their acrimony. Or it is probable, that a wholeſome ſtarch might be obtained from them, as from the roots of white bryonia, as is affirmed by M. Parmetier, by the ſimple proceſs of grating the root by a bread-grater of tinned iron into cold water, and depriving it of its acrid mucilage by frequent cold ablution. And laſtly, that they might be ſo managed as to undergo fermentation either by previous germination, or by adding yeſt to the juice expreſſed from them after boiling, and thus be converted into wine or beer, from which a ſpirit might be diſtilled, or vinegar produced. See Sect. XI. 2. 5.

4. The art of preſerving roots, when taken out of the ground, conſiſts

conſiſts either in keeping them alive during the winter without ſuffering them to germinate, as life prevents the fermentation or putrefaction of their juices; or ſecondly, by depriving them of their water. For the firſt purpoſe the roots, whether bulbous or palmated, ſhould be kept in a degree of heat above the freezing point of 32; ſince freezing them deſtroys their life; whence they not only undergo a ſudden change in their flavour and nutritive quality, but quickly tend to putrefaction in conſequence of their loſs of life like the eggs of animals. Nevertheleſs both vegetable and animal products, as fruits and fleſh, as well as roots, may probably long exiſt unchanged in a frozen ſtate in ice-houſes; and if they are at length gradually thawed by covering them with melting ice, or immerſing them in cold ſpring water, it is ſaid by Mr. Reaumure, who tried the experiment on apples, that they do not loſe much of their flavour, if they be afterwards ſoon made uſe of; otherwiſe, I ſuppoſe, as the froſt has deprived them of life, they ſoon begin to undergo chemical changes.

If theſe roots are kept in a degree of heat above 48, which is the heat of the internal parts of the earth, and conſequently of ſpring water, they are liable to germinate, as happens to onions and potatoes in our ſtore-houſes during the vernal months. And if they be expoſed to a much greater heat, ſo as to deſtroy the life of the root, they ſoon run into fermentation or putrefaction, or become covered with mould; unleſs the water which they contain be quickly diſſipated by evaporation. A friend of mine once ſent many ſtrikes of potatoes to be dried on a malt-kiln, hoping by that means to preſerve them during the ſummer; but as the life of theſe roots was deſtroyed by the degree of heat, and only about half of their water evaporated, they ſoon became ſo putrid after being returned into his ſtore-room, that the ſtench of them was intolerable, and even the ſwine refuſed to eat them. Nevertheleſs I believe, if the parts either of vegetables or animals could be kept in an heat at or above the boiling point of 212 in cloſe veſſels, ſo as not to ſuffer their fluid part to evaporate,

porate, that neither fermentation nor putrefactiou would enſue; but that they might be kept for years unchanged, as in the cold of 32.

The degree of heat required for preſerving roots ſecure from froſt, and from the proceſs of germination, which is that between the degrees of 32 and 48 of Farenheit's thermometer, may be well managed by ſtoring them beneath the ſoil in dry ſituations, as in dry cellars, or in pits dug for that purpoſe, or even in barns; but this requires more attention than is uſually employed in the common manner of ſtoring potatoes, which are liable to be injured both by froſt and by germination. Theſe pits in a dry ſoil ſhould be covered with materials, which conduct heat ill, and alſo with ſuch as might abſorb any putrid exhalations, which may occur, and thus check the progreſs of putrefaction, if it ſhould commence.

Air is a bad conductor of heat, if it be confined over the ſurface of any body, but not ſo if it be perpetually changed; as it then carries away heat very rapidly, as any one may experience by being fanned on a hot day. Hence all ſuch materials as poſſeſs large pores or interſtices full of air, are bad conductors of heat; as blankets, ſaw-duſt, wood-ſhavings, or ſtraw; and will thence preſerve the bodies, they cover, both from external cold and from external heat. But as charcoal in coarſe powder not only includes much common air in its pores, but alſo has the property, eſpecially if recently burnt, of abſorbing putrid exhalations; and is alſo itſelf of an unperiſhable nature; it ſeems peculiarly adapted to the purpoſes above mentioned. Hence the heaps of potatoes, or carrots, or parſnips, or ground artichokes, or even the roots of turnips or of beets, and the heads of cabbages, and perhaps pears, and apples, as well as nuts, almonds, and walnuts, might be well preſerved in pits or cellars, or even in barns, if they were firſt covered with powdered charcoal an inch or two in thickneſs, and over that a covering of ſaw-duſt, and finally over theſe a thick impenetrable thatch of ſtraw; whence a ſtore of provender for the winter months and the ſucceeding ſpring

may be preſerved from any degree of cold or of warmth much above or below that of the internal parts of the earth, in which ſeeds are known to continue for ages even without germination or decay.

It is nevertheleſs neceſſary to dry many palmated roots, when they are taken out of the ground, either becauſe they will not continue to live in our barns or ſtore-rooms, like the bulbous roots, or becauſe they require to be kept for ſome years in the ſhops of medicine. Some of theſe roots, as thoſe of rhubarb, are ſaid like the bulbous roots of ſcilla or ſquill to contain five ſixths of their weight of water, and therefore require conſiderable care in the method of drying them; for unleſs they are properly dried, they are liable to contract mould or mucor; which is a vegetable production, which will grow on putrefying materials without light or much air; but might be prevented from growing by the vapour of perhaps a teaſpoonful of ſpirit of wine, as mentioned in Sect. XV. 2. 3.

There is nevertheleſs ſome precaution neceſſary in exhaling the moiſture of theſe roots, as they ſhould be placed in a ſituation, where they are ventilated as well as heated; for warmth alone is liable to forward the tendency of the ſaccharine and mucilaginous parts of them to paſs into fermentation or putrefaction, and thence to deſtroy them; as the alburnum or ſap-wood of timber trees is liable to decay by what is termed the dry rot.

With this deſign drying houſes are conſtructed for the preparation of madder, rubia tinctoria, as deſcribed in Miller's Dictionary; and the rhubarb of the ſhops has frequently large holes bored through it; which, it is ſuppoſed, were deſigned to paſs cords through for the purpoſe of ſuſpending it to dry, as it is conveyed on camels in a warm climate.

5. The cultivation of muſhrooms, morels, and truffles, agaricus, phallus, lycoperdon, ſhould be here mentioned; as they are propagated by their roots. The fungi ſeem to conſtitute an iſthmus between the two great continents of nature, the vegetable and animal kingdoms.

kingdoms. The odour of a fungus, when burning, approaches to that of burning feathers; and all of them putrefy like animal fleſh; ſome of them as the phallus impudicus, ſtink-horn, emits ſuch a putrid ſcent, as it grows, as to attract innumerable fleſh-flies to depoſit their eggs or ſpawn in it. And thoſe muſhrooms, which are cooked at our tables, as well as the catchup, made by preſerving their juices in ſalt and water, poſſeſs an animal flavour. Of this laſt circumſtance I was told a remarkable inſtance, where a cook-maid in a family of invalids, who frequently wanted weak broth, perpetually deceived them by a mixture of a ſmall quantity of good catchup with thin gruel, and with only the addition of ſhred leaves of parſley, and a little ſalt.

Another thing in which the funguſes differ from vegetables, conſiſts in their growing perfectly well without light, which is ſo neceſſary to the health of vegetables. The ſcarlet folds beneath the head of the common eſculent muſhroom are ſo like the gills of fiſh, that they have in our language obtained the ſame name. Theſe folds beneath the hat of the agarics, the pores beneath the boletus, and the thorny appearance beneath the hydnum, and the net-like pores of phallus, are all different means of expoſing a larger ſurface to the air; and therefore undoubtedly conſtitute the lungs of the funguſes, as leaves conſtitute thoſe of vegetables, and not their organs of reproduction, as ſome have ſuppoſed.

The chemical analogy, which exiſts between ſome of the muſhroom tribe and animal matters, led Van Humboldt to inveſtigate their conducting power of what he terms the galvanic fluid, which I believe to be ſimply a minute ſhock of the electric fluid; and he found, that morels and thoſe fungi, which in a ſtate of putrefaction emit a cadaverous animal ſmell, are equally good conductors as real animal ſubſtances. Annals of Medicine for 1798, Edinb. Van Humboldt aſſerts further, that by chemical analyſis they approach likewiſe to animal ſubſtances, as they contain much azote and phoſphorus. He alſo aſſerts, that he converted morels into fat by means

of

of ſulphuric acid diluted with water, which experiment he thinks is analogous to that of Gibbes, and of the burying ground of the Innocents, where fat was formed from muſcular fleſh. Journal de Phyſique, Vol. IV. p. 67.

The fungi would hence appear to be animals without locomotion, whoſe lacteal veſſels are inſerted into the earth, like thoſe of vegetables; but whoſe gills or lungs are covered from the light, like thoſe of animals, but expoſed to the open air like the leaves or lungs of vegetables. Another curious occurrence, which ſeems to aſſociate them with animals, if the truth can be depended upon, is that ſome of them are of animal origin; as the common muſhroom is ſaid certainly to be procured from horſe-dung, as mentioned below; and may therefore have its embryon or early ſtate in the inteſtines of animals, and its maturer ſtate in the ſoil or atmoſphere like other inſects, as the bot-fly, and perhaps the tape-worm, and aſcarides? as this production of muſhrooms is otherwiſe contrary to all known analogy. Other fungi are found on the decayed parts of peculiar vegetables, from which they ſeem to take their origin, perhaps like worms in the inteſtines of animals, as the agaric of the oak, of the beech, of the elder; the boletus of the beech, and of the willow; and many others mentioned by Linneus.

The lycoperdon tuber, or truffle, grows under ground without light, never riſing into day; and is propagated, I ſuppoſe, by only a paternal or lateral progeny, like the polypus of our ditches, and not by ſexual connexion, or ſeminal progeny. The truffle is hunted by dogs probably from its poſſeſſing ſomewhat of an animal ſcent, like the perſpirable effluvia left upon the ground, by which they hunt their game or diſcover the foot of their maſter.

The phallus eſculentus, morel, and the agaricus, muſhroom of various kinds, will grow without light in cellars, or on beds covered with ſtraw; and are alſo, I ſuppoſe, propagated by a paternal or lateral progeny only, and not by a ſexual or ſeminal one.

The roots, or ſpawn, or embryons, of the common muſhroom are ſaid by Mr. Kenedy and others to be certainly procured from horſe-dung laid unbroken in ſmall heaps under cover. It is aſſerted, that in a few weeks during the ſummer months theſe roots will appear like white threads; which on breaking the lumps have the muſhroom ſmell. Theſe horſe-droppings are directed to be as little broken as poſſible, and to be laid about three inches thick on a hot bed of moderate warmth, conſtructed of alternate layers of tanner's bark and horſe-dung, and whoſe uppermoſt ſtratum conſiſts of tanner's bark about two inches thick. The bed is then to be covered with a little manure, and about three inches of good ſoil, and finally with a thick coat of ſtraw. The ſhed behind moſt hot-houſes is found to afford a convenient place for a muſhroom bed; as no light is required, but only warmth, and occaſional moiſture. See Kenedy on Gardening, Vol. II. for a particular account of this proceſs.

In the tanyards of Derby, I am well informed, that a production of muſhroom ſpawn always occurs in the path, where the horſe walks, which draws the rolling ſtone to grind the bark, which path conſiſts of powdered oak-bark and horſe-dung trampled together. Of this I was in one inſtance an eye-witneſs, but whether the embryons of muſhrooms were derived from the oak-bark or horſe-dung was not eaſy to determine.

Mr. Ferber, in his Travels through Italy, tranſlated by Raſpe, mentions the muſhroom-ſtone. He ſays "the pietra fungaia is a white calcareous ſtalactite, or tuph-ſtone, dug in the limeſtone hills bordering on Romagna, and endowed with the quality to produce in any ſeaſon of the year eſculent muſhrooms, if kept in a moiſt cellar, and now and then ſprinkled with water. This quality is owing to a great many roots, or vegetable fibres, together with the muſhroom ſeeds encloſed in its ſubſtance. They are uſed in ſome great houſes in Naples and Rome. I ſaw an indurated mould from the ſame place

that

that had the ſame quality, which was uſed by Mr. Fabriani in the mint of Florence."

From this account the muſhroom-ſtone appears to conſiſt of a porous tupha, like that with which the houſes are built at Matlock Bath; and which has been depoſited from the water. But a later writer has ſince analyſed one of theſe ſtones, but does not mention how long it had been uſed for the vegetation of muſhrooms, which might in great meaſure affect the reſults of his analyſis. Mr. Gadd, in the Stockholm Tranſactions, ſays, that this pietra fungaia deſcribed firſt by Ferber conſiſts of forty-five or forty-ſix hundredth parts of ſiliceous earth, and twenty of a calx of iron, with a little magneſia and vegetable alkali. Analytic. Review, Dec. 1798.

In this country the cellars would not be ſufficiently warm to produce muſhrooms at any ſeaſon of the year; but as this muſhroom-ſtone is of calcareous origin according to Ferber, it ſhews, that calcareous earth is friendly to the growth of muſhrooms; and a ſimilar porous ſtone from the vicinity of Matlock Bath might probably be permeated in a ſimilar manner with the roots of them, as a convenient repoſitory of them to be raiſed into life occaſionally by warmth and moiſture.

Some of the fungi are believed to poſſeſs an intoxicating quality, and are eaten for that purpoſe by the peaſants in Siberia. One fungus of the ſpecies agaricus muſcarum eaten raw, or a decoction of three of them, produces intoxication for twelve or ſixteen hours. Hiſt. of Ruſſia, Vol. I. Nichols, 1780. The Oſtiachs alſo bliſter the ſkin by a fungus found on birch-trees, and uſe the officinal agaric for ſoap. Other fungi poſſeſs a juice ſo acrid in their raw ſtate as immediately to bliſter the tongue, as I once experienced on taſting a minute drop of the juice of a large muſhroom, which on breaking the hat poured out a yellow juice, which became purple or blue in a few ſeconds of time on its being expoſed to the air; which I believed to be the fungus delicioſus of Linneus; the acrimony of which might never-

theleſs probably be deſtroyed by a boiling heat. And it is alſo probable, that the common eſculent muſhroom may ſometimes diſagree from their being not ſufficiently ſtewed, or by the incautious mixture of ſome intoxicating fungi along with them.

Otherwiſe thoſe in common uſe at our tables appear to ſupply a wholeſome and nutritive food, approaching towards an animal nature. Two or three kinds are ſaid to be eaten in France beſides the red-gilled ones which are eaten here; and it is probable many other kinds of fungi might be found agreeable to the palate, and wholeſome food, if well boiled, which might deſtroy their acrimony; and eſpecially thoſe which when broken have ſimply the agreeable ſmell of the red-gilled ones in common uſe; and ſome of theſe, I ſuppoſe, might be eaten raw without injury, as many people eat the red gilled ones.

Beſides ſome muſhrooms with white gills, which when broken had the grateful ſcent of the common red-gilled muſhroom, and which were ſaid to be more delicious, I have known the peziza auricula, or ear-fungus, which was formerly an article of the materia medica under the name of Jew's ear, to be ſtewed and eaten in conſiderable quantity with impunity; and was eſteemed an agreeable article at the ſupper-table. And as this was eſteemed a pernicious genus of fungi by Cluſius, it is probable, that many other funguſes might loſe their acrimony by the heat of ſtewing, and become wholeſome and agreeable food; which are at preſent in diſuſe from their diſagreeable acrimony in their raw ſtate, or from the bad character they have accidentally acquired.

It ſhould be added, that though thoſe plants, which are ſuppoſed to poſſeſs an alkaleſcent property, and to be liable to putrefaction ſooner than other vegetables, loſe a part of their acrimony by a boiling heat, as water-creſſes, cabbages, onions; yet that plants, whoſe acrimony is of a different kind, as ginger, capſicum, arum, do not become much milder by boiling. I this morning directed ſome leaves

of

of common ſpotted arum, and of arum ariſſarum to be boiled, and on taſting them found my tongue and lips almoſt excoriated. The nature of this kind of acrimony has not been ſufficiently inveſtigated by the chemiſts, but probably depends on a fixed eſſential oil.

III. *Barks.*

1. The barks of the trunks of trees are ſimilar to thoſe of their roots, and may be eſteemed a part of them, as they conſiſt of an intertexture of the veſſels, which deſcend from the plume of each individual bud to the radicle of it, and conſtitute its caudex. The bark nevertheleſs of the root is furniſhed with lymphatics to abſorb water and nutritious juices from the earth, and is covered with a moiſter cuticle; while the bark of the ſtem is furniſhed with lymphatics to abſorb moiſture from the air, and is covered with a drier cuticle; the latter reſembling the external ſkin of animals, and the lymphatics, which open upon it; and the former reſembling the mucous membrane of the ſtomach, and its lacteals.

As the ſap-juice riſes in all deciduous trees during the vernal months to expand their foliage, though probably in greater quantity in ſome trees than in others, it muſt conſiſt not only of ſugar and mucilage, as in the maple and birch, but of various other ingredients in different trees, which have not been attended to; as appears from the taſte of their young leaves, as of oak or aſh. And as ſome of theſe materials reſide in the roots and ſap-wood or alburnum, ſo others of them may perhaps reſide in the bark, where they have been depoſited during the preceding ſummer, and become lignified by the warmth of the ſpring, or diſſolved by the moiſture abſorbed from the earth and air, and conveyed upwards to the opening buds; whence it is evident, that the barks of trees ſhould be taken off for uſe in winter or in early ſpring, before their buds begin to expand; as then a part of theſe nutritious juices, or of the other materials, which are required for medicines, or in the arts of dying and tanning,

ning, are in part expended on the young leaves; which generally poſſeſs the taſte and qualities of the bark, though in a leſs degree.

It may nevertheleſs be obſerved, that all theſe aſtringent, or other materials, may reſide in the alburnum of the trunk or roots of all perennial vegetables, as well as in their barks; becauſe the young leaves, which pullulate on decorticated oaks, have the ſame bitter flavour as the leaves on thoſe, which have not been decorticated; which may in part be derived from the bark of the root, which is ſtill in the ground, and be carried up the veſſels of the ſap-wood to the new buds.

2. Hence the bark of oak-trees ſhould be taken off during the winter; but when the ſap-juice reſiding or aſcending in the veſſels of the alburnum becomes more liquefied by the warmth of the ſpring, or is mixed with more moiſture, and puſhed up with great force by the abſorbent veſſels of the roots, it oozes out in ſome degree between the alburnum and the bark; and thus the bark becomes ſo much more readily ſeparated from the ſap-wood; whence this buſineſs is generally done early in the ſpring, and ſhould be performed as ſoon as this facility of detracting the bark appears, as mentioned in Sect. III. 5; becauſe this proceſs of the germination of the buds continues to injure the bark, whether the tree be cut down or not; as the buds expand their foliage on new felled trees, as they lie on the ground.

3. The interior barks of ſome trees, like the alburnum or roots above deſcribed, contain much mucilaginous or nutritious matter; as the bark of elm, ulmus, and of holly, ilex; and probably of all thoſe trees or ſhrubs which are armed with thorns or prickles, which are deſigned to prevent the depredations of animals on them, as the hawthorn, gooſeberry, and gorſe, cretægus, ribes groſſularia, ulex. The internal barks of theſe vegetables may be conceived to be their alburnum leſs indurated, and might probably all be uſed as food for ourſelves or other animals in years of ſcarcity, or for the purpoſe of fermentation; as I doubt not but the inner bark of elm-trees, ul-

mus, detracted in the ſpring by being boiled in water might be converted by the addition of yeſt into ſmall beer, as well as the alburnum of the maple and birch, acer et betula; all which are now ſuffered to be eaten by inſects when thoſe trees are felled.

For the ſugar, which is extracted from the vernal ſap-juice of the maple and birch, as well as that found in the manna-aſh, fraxinus ornus, ſeems to reſide during the winter months in the root or alburnum, rather than in the bark properly ſo called; and to become liquefied, as above mentioned, by the warmth of the ſpring, or diſſolved by the moiſture abſorbed from the earth, and conveyed to the opening buds; but reſides ſolely in the roots of perennial herbaceous plants; and in the economy of graſſes, and I ſuppoſe of the ſugar-cane, it is depoſited at the bottom of each joint, which is properly the root of the ſtem above it, as ſhewn in Sect. IX. 3. 1.

Of theſe the bark of the holly not only yields a nutritious mucilage, and thus ſupplies much provender to the deer and cattle in Needwood-foreſt by the branches being cut off, and ſtrewed upon the ground, in ſevere ſeaſons of froſt and ſnow; but contains a reſinous material, which is obtained by boiling the bark, and waſhing away the other parts of it. This reſinous material poſſeſſes a great adheſiveneſs to feathers and other dry porous bodies, and has hence obtained the name of bird-lime, and much reſembles the caoutchouc or elaſtic reſin brought from South America, and alſo reſembles a foſſil elaſtic bitumen found near Matlock in Derbyſhire, both in its elaſticity and inflammability. Hollies may be worth cultivating for this material beſides the uſes of their wood, as I was informed, that thirty years ago a perſon, who purchaſed a wood in Yorkſhire, ſold to a Dutch merchant the bird-lime prepared from the bark of the numerous hollies for nearly the whole ſum given for the wood; which if it could be hardened might probably be ſold for the elaſtic reſin above mentioned. Whether this reſembles the nutritive reſinous material found

found in wheat flour, when the mucilage and ſtarch are waſhed from it, might be worth inquiry, as mentioned in Sect. VI. 8. 5.

4. Other barks contain bitter, reſinous, aromatic, or acrid materials, which ſupply the ſhops of medicine, as peruvian bark, caſcarilla, cinnamon, and were deſigned by nature to protect thoſe vegetables from the depredations of quadrupeds or inſects. Hence many trees, and even the wood of them, after it is dried, and made into domeſtic furniture, is never devoured by worms, as the mahogany, cedar, cypreſs; and hence many plants, as the foxglove, digitalis, hounds-tongue, cynogloſſum, henbane, hyoſciamus, and many trees, are not devoured by any animals; as their juices would be poiſonous to them, or much diſagree with their ſtomachs, if their diſguſtful flavours to the noſe or palate did not prevent their eating them. The ſame defence of the vegetable kingdom from human digeſtion, except thoſe which have in long proceſs of time been ſelected and cultivated, appears from the relation of ſome unfortunate ſhipwrecked travellers, who have paſſed ſome hundred of miles along uninhabited countries almoſt without finding an eſculent vegetable production.

5. Other barks contain reſtringent or colouring particles, employed in the arts of dying and tanning, as berberry, oak, and aſh, berberries, quercus, fraxinus. The art of tanning conſiſts in filling the pores of the animal mucous membrane with theſe reſtringent particles found in ſome vegetables, which are believed to poſſeſs a quality of ſhortening animal fibres. Thus when a long hair is immerſed ſome time in a ſolution of the bark of oak, or of the galls produced on its leaves by the punctures of inſects, the hair is ſaid to be ſhortened. Whether this proceſs be occaſioned by chemical coagulation of the mucus, of which theſe fibres totally or in part conſiſt, or by capillary attraction tending to diſtend theſe fibres in breadth, and thus to ſhorten them, as a twiſted ſtring is ſhortened by moiſture, has not yet been well inveſtigated. By thus impregnating the pores of animal ſkins with vegetable particles, they become leſs

liable to putrefaction, as conſiſting of a mixture of animal and vegetable matter, as well as much better adapted to many domeſtic or mechanical purpoſes.

The art of dying conſiſts likewiſe in impregnating the pores of dry ſubſtances with a ſolution of the colouring matter extracted from vegetables by the capillary attraction of thoſe pores to the coloured ſolution. And ſecondly, by a chemical change of thoſe colouring particles after they have been imbibed, and the water of the ſolution exhaled, by again ſteeping them in another ſolution, which may chemically affect the former. Thus as green conſiſts of a mixture of blue and yellow, it may be beſt produced by boiling the material deſigned to be dyed firſt in a decoction of one of theſe colours, as of indigo; and then in that of another, as of the bark of berberry. And as a ſolution of iron becomes black when mixed with a decoction of oak-galls, by being in part precipitated; it is probable, that the particles of this combination of a ſolution of iron with reſtringent matter may be larger than either of thoſe particles ſeparately; and therefore that, if a dry porous ſubſtance be immerſed firſt in a decoction of oak-galls, and after being ſuffered to dry, is then immerſed in a ſolution of iron, the black tinge will penetrate into minuter pores, and thus become more intenſe, than if the ſubſtance had been immerſed in the black dye already prepared.

6. Other barks are uſed for apparel, paper, cordage, and for many mechanical purpoſes, owing to the ſtrength and tenacity of their fibres, or to the fineneſs of them; as hemp, cannabis; flax, linum; for the purpoſes of ſpinning and weaving; an art invented by Iſis, queen of Egypt, who ſeems firſt to have cultivated flax; which was brought into Europe from the banks of the Nile. The bark or leaves of the papyrus, a flag of the Nile, was firſt uſed for paper; and the bark of the mulberry-tree is ſtill made into cloth at Otaheite and other ſouthern iſlands.

The art of ſeparating the fibres of the bark of plants, as they conſiſt

ſiſt of the caudexes of buds, or the connecting veſſels between the plumules and the radicles of them, is performed by ſoaking them ſome weeks in ſtagnant water; till the mucous membranes, which connect theſe fibres, are deſtroyed by putrefaction; and afterwards by drying them, and beating off with hammers, what may ſtill adhere.

Theſe fibrous parts of the barks of trees, as they contain no ſaccharine matter, like the alburnum, are much leſs liable to decay than the ſap-wood, or perhaps than any part of the timber. Maupertuis, who went to Lapland to meaſure a degree of the meridian, ſays, that among the numerous trees which lay upon the ground deſtroyed by age, or blown down by the winds, many birch trees appeared whole, owing to the undecayed ſtate of their bark; but crumbled into powder on being trod upon; and that the Swedes took the practice from this of covering their houſes with this unperiſhable bark, on which they ſometimes lay ſoil, and thus poſſeſs aerial gardens. Voyages by Mavor, Vol. XII.

7. To increaſe the quantity of bark it muſt be remembered, that the leaf-buds, or viviparous offspring of trees, as they form new buds, acquire new caudexes extending down into the ground, and thus increaſe the bark of the ſtem in thickneſs; but the flower buds acquire no new caudexes, but die, as ſoon as they have ripened their ſeed, and conſequently do not increaſe the thickneſs of the bark. Whence one method of increaſing the quantity of the bark is to increaſe the number or vigour of the leaf-buds in contradiſtinction to the flower-buds, which may be done by pinching off the flowers as ſoon as they appear; and as the bark becomes gradually changed into wood, this may be one method alſo of forwarding the growth of timber trees, as mentioned in the next Section.

8. The method of preſerving the bark of trees from moſs conſiſts in rubbing off that paraſite vegetable in wet weather by means of a hardiſh bruſh; which is ſaid to be uſed with advantage on the apple-trees in the cyder countries; and may at the ſame time give motion

to

to the vegetable circulation, or forward the aſcent of their juices abſorbed by the radical or cortical abſorbents. In dry weather the bruſh ſhould be frequently dipped in water. Waſhing the barks of wall-trees by a water-engine may alſo facilitate the protruſion of their buds in dry ſeaſons; and might poſſibly prevent the canker, if applied to dwarf or aſpallier apple trees. Other paraſite vegetables muſt be occaſionally deſtroyed, where they occur, as the lichens, fungi, miſletoes; with the ivies and other climbers, as ſome kinds of lonicera, clematis, and fumaria, woodbine, virgin's bower, and fumitory.

9. When a wound is made in the bark ſo as to expoſe the alburnum to the air, the upper lip of the wound is liable to grow faſter downwards, than the lower one is to grow upwards, owing to the former being ſupplied directly with nutritive juices ſecreted from the vegetable blood, after its ventilation, and conſequent oxygenation in the leaves; whereas the lower lip only receives thoſe juices laterally by inoſculation of veſſels. Over theſe wounds the cuticle is liable to project, and to ſupply a convenient hiding place for inſects, which either eat the new fibres of the growing bark, and perforate the alburnum; or by their moiſture, their warmth, and their excrements, contribute to the decay of the alburnum, and prevent the healing of the wound. Theſe dead edges of the projecting bark or cuticle ſhould be nicely cut off, but not ſo as to wound the living bark.

Plaſters of lime, or of tar with ſublimate of mercury, have been recommended to preſerve the wounded parts from the air, and from moiſture, and from inſects; but as all theſe materials are injurious to the fibres of the living bark, they ſhould be uſed with caution, ſo as not to touch the edges of the wound, but only to cover the alburnum; for this purpoſe white lead and boiled oil, mixed into a thick paint, or with the addition of ſublimate of mercury, or of arſenic, or of ſpirit of turpentine, may probably anſwer the purpoſe; and may be of real utility on the wounds of thoſe trees, whoſe wood

contains leſs acrimony, and is therefore more liable to be bored into and eaten by a large worm or maggot almoſt as thick as a gooſe-quill: which I have ſeen happen to a pear-tree, ſo as to conſume the whole internal wood, till the tree was blown down.

In reſpect to the caution neceſſary to be obſerved in not touching the living edges of the wounded bark with ſuch materials as may injure the tree by their abſorption, I remember ſeeing ſeveral young elm trees, which died by their boles having been covered, as I was informed, by quick-lime mixed with cow dung to prevent their being injured by horſes; and I have ſeen branches of peach and nectarine trees deſtroyed by ſprinkling them, when in leaf, with a ſlight ſolution of arſenic, and others with ſpirit of turpentine.

10. A more curious method of cure is ſaid to have ſucceeded, where the bark of a tree has recently been torn off even to great extent, and that is by binding the ſame piece of bark on again, or another piece from the ſame tree, or from one of a ſimilar nature, nicely adapting the edges of the bark to be applied to the edges of that, which ſurrounds the wound of the tree, which it is ſaid will coaleſce in the ſame manner, as the veſſels of the bark of an ingrafted ſcion unite with thoſe of the bark of the ſtock ingrafted on; which is ſtrictly analogous to the union of inflamed or wounded parts of animal bodies, as in the cure of the hare-lip, or the inſertion of the living tooth from one perſon into the jaw of another, or the factitious noſes of Talicotius.

If the bark over the cankered parts of apple-trees could be thus renewed by paring the edges of the mortified bark to the quick, and then nicely applying a piece of healthy bark from an apple-tree of inferior value, and ſecuring it with an elaſtic bandage, as a ſhred of flannel, it would be a very valuable diſcovery.

Another method, where a branch of a valuable tree is in the progreſs of being deſtroyed by canker, might be by incloſing the cankered part, and ſome inches above it, in a garden-pot of earth previouſly

viouſly divided, and ſupported by ſtakes, and tied together round the branch; which might then ſtrike roots in the earth of the garden-pot, and after ſome months might be cut off, and planted on the ground, and might thus be preſerved, and produce a new tree; which experiment I have this ſummer tried on two apple-trees, and believe it will ſucceed.

SECT. XVIII.

PRODUCTION OF LEAVES AND WOOD.

I. 1. Leaves *are the lungs of vegetables. Graſſes propagated by their roots. Some are viviparous. Joints of graſſes are ſucceſſive vegetables. And their roots. Extract roots of twitch-graſs by a ſcarifier with inclined teeth. Produce root-leaves for grazing, and ſtem-leaves for hay. Eat down the firſt ſtem. Cut graſs young for hay. Why young hay is liable to take fire. How to prevent it by ſtraw. Eat low meadows late. Sow rye-graſs, trefoil, white clover, for ſucceſſive herbage. Other graſs ſeeds. Roll them in ſpring. Effects of froſt. Uſe more water as in rice grounds. Sow thick. Heavy cattle ſhould be ſtall-fed. How to deſtroy tuſſocks. How to make hay.* 2. *Some root-leaves eaten raw. Others previouſly boiled. Upper part of ſome roots and of ſome ſtems eſculent. Aſparagus. Art of cultivation of root-leaves and ſtem-leaves. Of mulberry-leaves.* 3. *Etiolation of leaves leſſens their acrimony. Etiolated flowers. Etiolated ladies.* 4. *Aromatic and bitteriſh leaves uſed as tea, as of ſage. When to be gathered. Tea recommended.* 5. *Leaves uſed in medicine. Bog-bean inſtead of hops. Others for tanning, as oak, aſh, and alder leaves. Others for dying, as indigo and woad.* 6. *Leaves will ferment and may make a kind of beer.* II. 1. Wood *is produced from leaf-buds. To increaſe wood moiſten the trees. Scratch the bark. How to ſtraighten crooked trees. Pinch off the flowers.* 2. *To render timber trees tall without knots, or crooked for ſhip-timber. Willows. Oziers. Sugar-maple. Scotch firs.* 3. *Preſerve wood from lightning, and from wood-peckers.* 4. *Woods differ in colour. Uſed in dying. Differ in medical and chemical properties.* 5. *Oak corrodes lead. Sap-wood rots under lead. How prevented. Whence the myſteries of Free Maſonry.* 6. *Woods differ in their hardneſs and ſmoothneſs. Blocks for printing.* 7. *In their durability as cypreſs. Alder for piles.* 8. *In lateral coheſion. Hygrometer. Pendulum.* 9. *In ſpecific gravity. Rafts of hollow trunks.* 10. *In elaſticity. Bows.* 11. *How to tranſplant large trees. How*

to

to prop them. 12. *Time of felling timber after barking it. The concentric rings of timber.* 13. *Pith is brain. Does not communicate from bud to bud. Sagoe from artichoke. From elder.* 14. *Boundary to the growth of trees. Not to coralline rocks.*

1. *Of Leaves.*

1. The buds of plants have already been ſhewn to be individual vegetable beings, and the leaves to conſtitute the lungs of each individual bud. And laſtly, that the new bud in the boſom of each leaf is the offspring from the caudex of that old bud, of which the leaf conſtitutes the lungs.

The leaves of graſſes are of great conſequence, as they nouriſh many of our domeſtic quadrupeds; the cultivation of graſſes has therefore been much attended to. Many of theſe propagate themſelves more by their roots than by their ſeed; eſpecially where their ſtems are perpetually deſtroyed by the grazing of cattle, ſheep, or geeſe; and ſome of them are ſaid to be viviparous, as the feſtuca dumetorum, or feſcue graſs; that is, that they bear bulbs on their ſtems after flowering inſtead of ſeeds, which in time drop off, and ſtrike root into the ground, like the polygonum viviparum, and the allium magicum; which circumſtance is ſaid to obtain in many alpine graſſes, whoſe ſeeds are annually devoured by ſmall birds.

The ſtems of the graſſes conſiſt in general of joint above joint without lateral branches; each joint of which ſeems to be a ſucceſſive plant growing on the preceding one, and generated in the boſom of the leaf, which ſurrounds it; the ſtem may therefore be eſteemed a ſucceſſion of leaf-buds, till at length a flower-bud is produced on the ſummit, as ſhewn in Sect. IX. 3. 1. In ſome graſſes, as the agroſtis canina, or triticum repens, dog's-graſs, twitch-graſs, or couch-graſs, the root conſiſts of joints as well as the ſtem; which may be conſidered as ſeparate individual plants, like the bulbs of potatoes, as every joint of theſe roots will grow into a new plant to the great

great annoyance of the agricultor, which, when the ground is not hard, may be beſt, I believe, drawn out by a deep harrow, or by Mr. Cook's ſcarifier; as a plough turns them over under the ſoil, as it breaks them, and thus much increaſes their number by in a manner tranſplanting them. The teeth of the harrow, or ſcarifier, ſhould be inclined forwards towards the horſe for the purpoſe of lifting up the roots, and that it may not too eaſily riſe out of the ſoil; and it ſhould be fixed by wedges or ſcrew-nuts to the wooden frame for the purpoſe of occaſionally lengthening them to adapt them to different ſoils, as the roots pierce deeper into leſs tenacious ſoils than into clayey ones.

Hence it appears, that a plant of graſs conſiſts not only of a tuft of leaves ſurrounding the root, but that the three or four lower joints of the ſtem, as of a wheat-ſtraw, are ſo many ſucceſſive leaf-buds, which are generated by the caudex of the leaf, which ſurrounds each joint, and precede the flower-bud at the ſummit; and that hence with the deſign of producing much herbage for cattle, the propagation of new leaves from the root is principally to be attended to; but with the deſign of producing hay, or winter fodder, the leaf-buds of the ſtem are principally to be attended to.

For the former of theſe purpoſes the ſtem of graſs ſhould be eaten down as ſoon as it riſes; whence more graſs leaves will ariſe from the root; as is well known to thoſe who eat down the firſt ſtem of wheat, when it is too luxuriant. For the ſecond purpoſe the leaf-buds, which conſtitute the ſtems of graſs, ſhould be cut down, before the flower-ſtem at the ſummit has begun to ripen its ſeeds; as at that time the ſweet juice lodged in the joint below the flower-ſtem becomes expended on the ſeed; and the ſtem becomes converted into ſtraw rather than into hay.

From hence it is readily underſtood, why thoſe paſtures, which are perpetually grazed, are ſo much thicker or cloſer crowded with graſs roots than thoſe, which are annually mowed; and why graſs cut

young makes ſo much ſweeter and more nutritive hay than that, which has ripened and ſhed its ſeed. And laſtly, why the hay from graſs cut young is ſo much more liable to take fire, if ricked too moiſt; becauſe the greater quantity of ſugar in the joints of the ſtems produces ſo violent a fermentation, when it has ſufficient water to diſſolve it, that it generates ſo much heat as to burſt into flame. This might beſt be prevented, where chopped ſtraw is deſigned to be given to horſes along with their hay, by laying alternately in the hay-ſtack a ſtratum of new hay and a ſtratum of ſtraw, or of clover and ſtraw; whence the rapid fermentation, which occaſions combuſtion, may be prevented, and the ſtraw may be rendered eaſier of digeſtion by being impregnated with the fermentative infection, or yeſt, of the fermenting hay.

The art of increaſing the quantity of leaves round the roots of graſſes conſiſts in eating off the central ſtems by ſheep, or horſes, or cattle, early in the ſeaſon, as above mentioned; whence new ones are produced around the firſt joint of the ſtem thus bitten off, and from the diſtant horizontal root-wires of ſuch graſſes, as produce them. In low meadows it is hence doubly profitable to eat down the early graſs till about the middle of May, as in moiſt ſituations there is no danger but a crop of hay will ſucceed; which by this method will be finer and more copious; and at the ſame time ſome weeks provender of hay will have been ſaved by the uſe of the early graſs.

On land intended for paſture, as for ſheep, many people adviſe to ſow three kinds of vegetables, which may in ſome meaſure ſucceed each other in their growth. Mr. Parkinſon ſows four buſhels of the ſeed of rye-graſs, lolium perenne, ten pounds of trefoil ſeed, trifolium pratenſe, and ten of white clover, trifolium repens, on every acre; and adds, that the rye-graſs ſhould be eaten early, while the white clover is ſtill concealed in the ground, and the trefoil makes only ſome ſmall appearance. That when the rye-graſs is eaten down the

the trefoil ſprings up, and becomes food for the ſheep; after which the white clover ſucceeds; and after this is conſumed, the rye-graſs again ſprings up, and ſupplies food during the winter months, if the weather proves tolerably mild; and he further aſſerts, that a third more of ſheep at leaſt may be thus nouriſhed than by any other means. Experienced Farmer, Vol. I. p. 88.

For the production of a meadow much ſuperior to thoſe commonly ſeen Mr. Curtis recommends ſix kinds of graſs and two of clover to be ſowed; the ſeeds are to be mixed together in the following proportions. Meadow foxtail, alopecurus pratenſis, one pint; meadow feſcue, feſtuca pratenſis, one pint; ſmooth ſtalked meadow-graſs, poa pratenſis, half a pint; rough ſtalked meadow-graſs, poa trivialis, half a pint; creſted dog's-tail, cynoſurus criſtatus, a quarter of a pint; ſweet-ſcented vernal graſs, anthoxanthum odoratum, a quarter of a pint; Dutch clover, trifolium repens, half a pint; red clover, trifolium pratenſe, half a pint; theſe ſeeds are to be mixed together, and about three buſhels to be ſown on an acre in rows for the convenience of hoeing them. About the end of Auguſt or beginning of September they ſhould be occaſionally weeded and thinned, and rolled in the ſpring, to preſs down into the ground ſuch roots as may have been raiſed by the froſt.

Mr. Curtis thinks that meadow foxtail and rough ſtalked meadow-graſs ſuit moiſt ſoils the beſt; and that the ſmooth ſtalked meadow-graſs and creſted dog's-tail ſuit dry paſtures; and laſtly, that the meadow feſcue, and the ſweet-ſcented vernal graſs, ſuit land either moiſt or moderately dry; and gives the following order of their times of flowering. 1. Sweet-ſcented vernal. 2. Meadow foxtail. 3. Smooth ſtalked meadow-graſs. 4. Rough ſtalked meadow-graſs. 5. Meadow feſcue. 6. Creſted dog's-tail. See Hall's Encycloped. Art. Agriculture.

Not only new ſown graſſes deſigned for meadows, but the larger graſſes, which have the names of corn, as wheat, oats, barley, may be advantageouſly rolled, when dry, after froſt, which by expanding the

water

water in moiſt ſoils leſſens the cavities, which are occupied by roots; and as roots or their branches are in general conical, they become puſhed upwards; and ſuch as are looſe riſe quite out of the ground, as is often ſeen to happen to the roots of the ſtrawberries, when a froſty night has occurred ſoon after their being tranſplanted. After a ſlight froſt the larger pebbles of a gravel walk are ſeen below the ſurface, as if they had ſunk downwards during the night; whereas this is owing to a ſimilar cauſe, the expanſion of the moiſt ſoil or gravel an inch deep; but as the froſt had not penetrated ſo low as to ſwell the ground beneath the large pebbles, theſe had not been lifted up like the ſmaller ones, or the wet ſand.

Secondly, both to increaſe the quantity of leaves round the root, and to increaſe the ſize or vigour, as well perhaps as the number, of leaf-buds on the ſtem, a greater ſupply of water than uſual, where it can be done, would be advantageous; as is done to the rice-grounds in warm countries in the early part of its growth, and as in flooding our own meadows occaſionally in the vernal months. Thus very moiſt ſeaſons are well known to forward the luxuriant growth of the herbage, and ſtems, in the cultivation of wheat, and to render the ears later, and leſs prolific.

Where plants are ſown for the purpoſe of conſuming the firſt foliage, as graſſes or ſaint-foin, the ſeed ſhould be ſown thicker, than where the plant is grown for the purpoſe of producing ſeeds, as in wheat or peas; becauſe the quantity of the firſt foliage will be greater in reſpect to number; and the central parts of the tuſſocks, as is often ſeen in wheat and peas, when ſown too thick, will riſe two or three inches higher in their conteſt for light and air, like the trees of thick planted woods; and will hence produce a forwarder paſture as well as a more copious one.

To which ſhould be added, that the plants with ſucculent ſtems, as ſaint-foin, lucern, red clover, receive ſo much injury from the trampling of heavy cattle, that they ſhould be mowed, and given to

cows and horſes in their ſtalls; which ſhould nevertheleſs have a yard or fold occaſionally to run into with the convenience of water; and if ſtraw be chopped along with this green food, it might be a cheap and a ſalutary addition.

Where a piece of graſs land is overrun with tuſſocks of ſour graſs, which often happens near towns, I have been informed, that lime or coal-aſhes ſpread on them would render the graſs ſweeter, ſo that horſes or cattle would eat it. But I ſuppoſe the more certain and advantageous management would conſiſt in mowing it frequently, and giving it to the horſes or cattle in the ſtable or ſtall; as I believe they will eat it greedily after it has been a few hours withered, and thus the land will not only yield more provender at preſent, but after a few mowings a ſweeter graſs will riſe in the place of that which was of a bad kind, or of too luxuriant growth; for which purpoſe it ſhould be mowed as near the ground as may be; or if it be frequently mowed during the ſummer, and left on the ground, ſome cattle will eat it, when it is withered to a certain degree; by which the diſagreeable flavour of it is probably leſſened or deſtroyed.

The art of making hay conſiſts in evaporating about two thirds of the weight of it, as obſerved by Young and Ruckert. Dr. Hales found a ſun-flower plant, which weighed forty-eight ounces to loſe thirty-ſix ounces by drying in the air during thirty days; and conſequently to have loſt three fourths of its weight. Vegetables to appearance perfectly dry contain three fifths or three fourths of their weight of water; a part of which water Mr. Kirwan thinks is not in its liquid ſtate, but that it is by a loſs of much of its ſpecific heat in a great meaſure ſolidified. Kirwan on Manures, p. 37. Thus when water is thrown on freſh quick-lime, a part of it unites with the lime, and becomes ſolid, giving out much heat; which converts another part of it into ſteam, as mentioned in Sect. X. 4. 4.

There are two methods of making hay practiſed in different parts of

of the country. In the more ſouthern counties the ſwarths are not turned over or ſcattered for a day, or two, or three, but remain as they were left by the ſcythe. In the more northern counties the hay-makers follow the mowers, and ſcatter the graſs immediately, or on the ſucceeding day. Perhaps a method between theſe may in general better ſuit this climate.

Herbs collected for medicinal purpoſes, as well as flowers, ſhould be dried in the ſhade; otherwiſe they become bleached, and loſe both their colour and their odour, by too great inſolation, and exhalation. Now if the ſwarth of cut graſs be only turned over once a day for three or four days, the internal parts of it may be ſaid to be dried in the ſhade; and afterwards if it be ſpread over the ground for only a few hours on a fine day, I ſuppoſe it would become dry enough to ſtack, and have loſt conſiderably leſs of its nutritive quality. Some adviſe a chimney to be left in the center of a ſtack to prevent the hay taking fire, but there ſhould then alſo be culverts under the ſtack to ſupply that chimney with air; which may be made by cutting three or four trenches in the earth, and covering them with boards or ſticks with their apertures expoſed to the wind in all directions. Perhaps the beſt way would be to make the ſtack narrow and long, and bent into a ſemicircle or creſcent to enable them the better to reſiſt the winds, inſtead of round or ſquare, though a greater ſurface would indeed be afterwards expoſed to the weather, and in ſome degree injured, by this mode of conſtruction.

When the graſs is ſpread uniformly over the whole meadow, which is called *tedding*, it will ſooner dry, as ſo much larger a ſurface of it is expoſed to the wind and ſun; but it ſhould certainly be put into ſmall cocks or wind-rows at night, eſpecially if the weather be moiſt; becauſe it will otherwiſe receive much dirt and ſlime from the innumerable worms, which riſe out of the ground always in moiſt warm nights, and generally when the ſurface is covered with moiſt

graſs at all ſeaſons; and when they retreat into their ſubterranean manſions in the morning, they are liable to draw in the ends of the graſs to ſtop up the apertures of their holes, and by that means prevent the centipes from following them into their homes, and deſtroying them. See Zoonomia, Vol. I. Sect. XVI. 16. Whence much of the new hay becomes injured by the ſoil, they previouſly puſh before them out of their mines, and by that which adheres to the graſs, which was drawn in to ſtop the apertures of them, as well as by the ſlime, which they leave behind them on the new hay, which they paſs through or over.

On this account hay-cocks ſhould be made as high as may be in proportion to their baſe, that leſs ſurface may be in contact with the ground, as well as that a greater ſurface may be expoſed to the air for a quicker exhalation of its moiſture, and for the purpoſe of the better ſecuring it from accidental ſhowers.

In wet ſeaſons, I ſuſpect, the beſt method muſt conſiſt in turning over the rows of ſwarth every day or every alternate day, or making it into ſmall cocks, and turning them over in the ſame manner, that the rain may not injure the whole of it by paſſing perpetually through it, and waſhing away its ſaccharine and mucilaginous fluids; and alſo that the part next the ground, and the central parts of the cock or ſwarth, may not paſs into fermentation and putrefaction. And laſtly, when it can be put into tall cocks, as the weather becomes drier, it will not only ſooner exhale its moiſture by the contact of the atmoſphere, but a beginning fermentation will ſet at liberty ſome degree of heat, and thus contribute to dry it by increaſing the evaporation; as the great heat generated in hay-ſtacks which have been finiſhed but one day or two, aſſiſts much to dry the whole ſtack in moiſt ſeaſons, as is ſeen by the denſe ſteam, which ariſes from them.

2. Many root-leaves are conſumed at our tables either in their raw ſtate, as thoſe of water-creſs, ſiſymbrium naſturtium, lettuce, lactuca ſativa, muſtard, ſinapis, celery, apium; many others are previouſly boiled

boiled to diminiſh their acrimony, and to coagulate their mucilage, as the root-leaves of ſpinach, ſpinacia, of cabbage, braſſica oleracea, and even of turnips, braſſica rapa; along with theſe ſtem-leaves of many plants the flower-buds at their ſummits are eaten, as thoſe of mercury, mercurialis, and of ſome of the cabbage kind called brocoli, braſſica italica.

Many of theſe leaves not only conſiſt of a reſpiratory organ, but at the lower parts of them eſpecially, or in their ſtalks, there exiſts a reſervoir of nutriment for the riſing flower-ſtem or for the ripening ſeed, as in rhubarb leaves, and in cabbage leaves, which is ſimilar to that in the roots of other herbaceous plants, and which renders them both palatable and nutritive. Moſt of theſe concentric leaves are ſituated in contact with the earth, as thoſe of lettuces, lactuca, and ſalſafi, tragopogon. But others of them, as the cabbages, are placed on a ſtem at ſome diſtance from the ground; in the former the upper part of the root or caudex is palatable and nutritious, as well as the lower part of the leaves; and ſome of them are of ſuperior flavour when boiled. In the latter the reſervoir of nutriment for the future flower-ſtem and ſeed conſiſts in the lower part of the ribs of the concentric foliage, as in the concentric leaves or lamina, which cover the bulb of the onion, or even in the ſtalks, as in cabbages, and artichoke, which are therefore not only eſculent, but palatable and nutritive.

Other leaves are eaten in their early ſtate along with the ſtem, which they ſurround, as aſparagus, and the young ſhoots of ſpinach, and of ſome kinds of brocoli, and of mercury; which laſt are ſometimes ſuffered to ſhew their flowers before they come to our tables, and are then treated of in Sect. XIX.

The art of cultivating all theſe conſiſts in ſupplying them with abundant carbonic earth, and with abundant moiſture, as theſe are more friendly to the luxuriant growth of root-leaves or ſtem-leaves, than to the production of the flowers, or ripening of the ſeeds, as appears

pears by the too luxuriant growth both of herbaceous plants and of fruit trees in moiſt ſeaſons.

Another method of forwarding the growth of the new leaves and ſtem-ſhoots of perennial herbaceous plants, as of aſparagus, is annually to looſen or turn over the earth around and above the roots, for the purpoſe of admitting air into its cells or cavities to convert a part of the manure or carbonaceous ſoil, with which they have been ſupplied, into ammonia, or into carbonic acid, and thus both to afford them warmth and nutriment.

Add to this, that the leaves of trees may be increaſed in ſize by lopping off the branches, by which means the remaining buds acquire more nutriment; the black mulberry tree is thus kept low, and formed into extenſive ſhrubberies in China for the purpoſe of feeding ſilkworms, as obſerved by ſir G. Staunton, who thinks the leaves are thus rendered both larger and more ſucculent; and adds, that the aſh-tree is alſo ſometimes uſed for the ſame purpoſe.

3. Another method of deſtroying the too great acrimony of leaves, beſides that of boiling them, conſiſts in ſecluding them from light, and is termed etiolation. This is chiefly practiſed on cellery, apium, by earthing it up nearly to the top of the plant; and on ſea-kale, crambe maritima, by covering the plant entirely with horſe-litter or ſtraw, as deſcribed in Sect. XIV. 3. 3; and on lettuces, and endive, by tying together the root-leaves with a bandage.

In many plants the central bud during its early growth ſeems to be naturally in a ſtate of etiolation, as it is excluded from the light by the curvature of the ſurrounding foliage, as in cabbages, and particularly in ſome ſpecies of aloe, which are ſaid to conſume nearly a century in opening their numerous concentric foliage. Theſe etiolated leaves, like flowers before the calyx is opened, are white; and the leaves become green, or the flowers of many other colours, when expoſed to the light, as explained in Sect. XIII. 1. 3. It is probable that the foliage of many other plants might be rendered eſculent by

thus deſtroying their acrimony, and decreaſing the tenacity of their fibres by etiolation, as well as the leaves of celery, apium; and cardoon, cinara; and of endive, cichorium endivia.

A ſecluſion from the ſun's light and from air has an effect ſomewhat ſimilar on animal bodies, rendering them pale and weak, as may be ſeen in the etiolated young ladies of ſome boarding ſchools; and in thoſe who paſs their waking hours in unventilated parlours during more than half the night.

4. Other vegetable foliage has been brought into very extenſive uſe infuſed in hot water for its agreeable aromatic or bitteriſh flavour, as thoſe of foreign tea, thea; and of the aſh, fraxinus, of our own iſland, the leaves of which were collected, before they became expanded, and ſold after being dried for the inferior kind of Bohea tea in ſo great quantity as to occaſion an act of parliament to be paſſed about forty years ago to lay a fine on any one, who ſhould have accumulated more than fifty pounds of aſh leaves, which were not the produce of his own trees. The leaves of many other of our domeſtic vegetables, as of mint, balm, and ſage, mentha, meliſſa, ſalvia, have been infuſed in hot water as an agreeable diluent beverage both in health and ſickneſs; the laſt of which, the ſage, poſſeſſes a very pleaſant aromatic flavour; and if the infuſion be poured from the leaves, before it has acquired too much of the bitter flavour, it is very grateful to the palate or ſtomach, and has been eſteemed ſalubrious from high antiquity to the preſent times, whence the line of Horace:

Cur moriatur homo, cui ſalvia creſcit in horto?

All theſe infuſions become nutritive, when drank with cream and ſugar, and have certainly contributed to the health of the inhabitants of this iſland by decreaſing the potation of fermented or ſpirituous liquors; and to their morality by more frequently mixing the ladies and gentlemen in the ſame ſociety.

The

The leaves of theſe plants, as well as the aromatic or balſamic buds of ſome other plants, as of myrica, gale; of tacamahaca, populus balſamifera; of balm of Gilead, amyris giliadenſis, and many others, ſhould be gathered at the time of their greateſt fragrance, as the eſſential oils, which conſtitute their odorous exhalation, perpetually evaporate, as our ſenſe of ſmell informs us; and were apparently for the purpoſe of defending the plants from the depredation of inſects in their ſtate of infancy.

5. Other leaves have been uſed for medicinal purpoſes, and for the arts of dying and tanning, like the barks before mentioned; as the leaves of carduus benedictus, cnicus acarna, as an emetic; thoſe of foxglove, digitalis purpurea, as an abſorbent in anaſarca; thoſe of bog-bean, menyanthes trifoliata, as a corroborant; which laſt might probably ſupply the place of hops, humulus lupulus, in the breweries of malt-liquors; and as it might be plentifully cultivated on boggy grounds, which are not at preſent uſed for other purpoſes, might be a cheaper bitter to the conſumer, and ſave to the public much more fertile ſoil for the cultivation of corn or other valuable vegetables.

The leaves of teucrium ſcorodonia, wood-ſage, are as bitter as thoſe of menyanthes, bog-bean, and have been uſed with ſucceſs, as I have witneſſed, in the cure of agues; and, as it grows on dry barren ſoils, might poſſibly be cultivated to ſupply the place of peruvian bark in ſome diſeaſes, or to ſupply the uſe of hops in the breweries of malt-liquor.

The leaves of oak-trees, quercus robur, and of aſh-trees, fraxinus excelſior, and of alder, betula alnus, even after they drop ſpontaneouſly in the autumn, are ſaid to ſerve the purpoſe of tanning animal membranes, like the barks of the ſame trees ſpoken of in Sect. XVII. 3. 5; and for the purpoſes of dying, the leaves of indigo, indigofera tinctoria; and of wood, iſatis tinctoria; and of weld, reſeda luteola,

have been much cultivated, and extenſively uſed; and a ſpecies of polygonum is ſaid to be much cultivated in China for the ſame purpoſes as indigofera by ſir G. Staunton; to which may be added the foliage of lichen fructicoſus, or archil, a whitiſh lichen brought from the rocks of the Canary Iſlands, which gives a beautiful bloom to other colours, but is itſelf very fugitive. Linneus aſſerts in the Swediſh Tranſactions, that this archil moſs is to be found on the weſtern coaſts of England; and it is ſaid, that the archil is now prepared by Meſſrs. Gordens at Leith near Edinburgh from a ſpecies found in the Highlands of Scotland. Encyclopedia Britannica. Art. Archil. The manner of cultivation and of the extraction of the colouring matter from the leaves of theſe plants may be alſo ſeen in Bomare's Dictionaire Raiſonne, and in Chambers's Encyclopedia. It it probable, that many other plants, as hedyſarum, ſaintfoin, or the broad thick leaves of phytolacca, might yield a ſimilar material to that of indigo, woad, and weld, if properly cultivated and prepared, as well as other kinds of moſſes or lichens to that above mentioned.

The green colour of perhaps all vegetables, as well as of thoſe from which indigo and woad are produced, is owing to the blue fecula, which has been obtained for the dyers principally from thoſe plants; and to a yellow material, which is more fugitive or more eaſily decompoſed, which yellow may poſſibly be owing to iron. This blue fecula is ſimply obtained from indigo, as it ſubſides from the fluid, in which the plant is ſuffered to ferment; and is obtained from woad along with the cellular parts of the leaves during their fermentation in water, and beaten into a maſs. It is probable that the blueſt kinds of vegetables may contain the moſt of this fecula.

For domeſtic purpoſes the juice of the ſage-leaf, ſalvia officinalis, has been uſed both to give colour and flavour to cheeſe; and the juice of ſpinach is employed, I am informed, to colour the green uſquebaugh, a favourite dram with the Iriſh vulgar. And it is probable, that the leaf of the vine, which bears purple grapes, might give

a ſimilar colour and aſtringent taſte to our domeſtic wines, as the ſkin of the ſame grape gives to the foreign wines made from it; ſince the leaves of this vine always become quite red in autumn, before they fall, probably by the concentration of their acidity, as their water evaporates unſupplied; as all blue vegetable juices become green by an admixture of alkali, and red by that of an acid.

6. Another uſe for which leaves are collected by ſome gardeners, as they fall in autumn from any kinds of trees, is for the production of heat by fermentation in hot-houſes, or melon-frames, inſtead of oak-bark, after its bitter particles have been much extracted by the tanner; and it is probable, that many leaves might be ſelected, as they will thus undergo fermentation, which might afford a ſpirituous drink like ſmall beer without any diſagreeable flavour, or unwholeſome material; which now ſerve only for manure when gathered into heaps, or by their ſlow decay on arable lands; or encumber the graſs lands, they fall upon.

II. *Of Woods.*

1. The leaf-buds of trees producing a viviparous offspring acquire new caudexes, extending from the branches to the ground, and the intertexture of theſe caudexes forms the new bark over the old one. But the flower-buds acquire no new caudexes down the bark, as their oviparous progeny does not adhere to the ſide of the parent bud, but falls down when mature, and ſtrikes root into the ſoil.

Now as the bark of trees is thus produced along with the leaf-buds, and as it annually becomes alburnum or ſap-wood; and that ſap-wood gradually loſes all vegetable life, and becomes heart-wood, it follows, that the art of forwarding the growth of the wood of trees muſt conſiſt in producing and nouriſhing the leaf-buds.

For this purpoſe the roots of trees ſhould be ſupplied with rather more water, than they generally poſſeſs in their moſt natural ſtate, or the branches ſhould be ſprinkled by a water-engine; as moiſture facilitates

cilitates the production of the new caudexes of the leaf-buds probably by leſſening the coheſion of the cuticle, or mechanically relaxing it, like the cuticle of our hands when long ſoaked in water, as well as by ſupplying them with more nutriment.

It may ſometimes occur, that the cuticle of trees, or exterior bark, may adhere too ſtrongly, and by not opening in cracks confine the growth, or prevent the production of the caudexes of the new buds. There is annually a new cuticle produced beneath the old ones, as well as a new bark above the old ones; hence ſome trees have as many cuticles as they are years old, others caſt them more eaſily, as a ſnake caſts its cuticle. When a number of cuticles thus exiſt one over another, it is uſeful to ſcratch them longitudinally, which will admit the new bark beneath, conſiſting of the caudexes of the various buds to ſwell out, and form a line more prominent than the other parts of the trunk of the tree. If crooked young trees be thus ſcratched internally in reſpect to the curvature, and this repeatedly, I am informed, that they will gradually become ſtraight, by thus encouraging the growth within the curvature more than on its convex ſide.

Another method of increaſing the number and vigour of the leaf-buds, and in conſequence of enlarging the wood of a tree, conſiſts in pinching off the flowers, as ſoon as they appear; as the nouriſhment is thus ſupplied to the leaf-buds by the inoſculation of the veſſels of the bark, which otherwiſe would have been expended on the flowers, fruit, and ſeeds. The truth of this circumſtance is not only countenanced by gardeners, who pull off the flowers of fruit-trees lately planted to encourage their growth, but alſo from the appearance of ſickly trees; which are liable to periſh, when in flower. In this caſe it often happens, that, after the flowers fade, ſome of the leaf-buds continue to expand, or new ones put out, owing to the ſupply of nutriment not being now expended on the flowers.

2. As tall timber trees without branches, and conſequent knots in the timber, are moſt valuable except for ſhip-building, this may be

certainly effected by planting them near each other; as then the powerful conteſt with each other for light and air propels them upwards, inſtead of producing many lateral branches; as may be ſeen in many woods, which have not been too much thinned. For this purpoſe ſome have planted trees of leſs value though of quicker growth, as pines, amongſt oaks; which may be pruned or lopped, if they ſhade the oaks too much, and may be finally removed, when the oaks are crowded by them; whence ſingle trees ſeldom grow ſo tall as thoſe in woods, and appear ſtunted, as it is called; which is generally aſcribed to the cold ſeaſons, or to their being expoſed more to the winds; which may perhaps ſometimes happen in this northern climate; or where trees are expoſed to inſalubrious air, as near the ſea; or exiſt in colder ſituations, as on the ſummits of mountains.

Something ſimilar to this may be ſeen in tuſſocks of graſs, or where too many ſeeds of wheat have been ſown near together. The central part of the knot of wheat or graſs grows much taller than the external part, ſo as to give it a conical figure; which has been by ſome aſcribed to the central part having been ſheltered from the cold by the external ring, but is more generally owing to the ſtruggle of the internal ſtems for the acquiſition of light and air.

The Society of Agriculture at Copenhagen has propoſed prizes concerning the cultivation of timber for ſhip-building. One queſtion is, whether the neceſſary form and degree of flexion can by any means be given to growing timber without injuring it? This I imagine may be done by annually ſcratching the external bark or cuticle either longitudinally or horizontally on the ſouth ſide of the part of a tree, which is wiſhed to be curved, as the ſouth ſide of trees are known to grow faſter annually than the north ſide, as is ſeen by the greater thickneſs of the concentric rings of a tree, when felled and ſawed into blocks; and becauſe the cuticle bounds the lateral growth of the trunks of trees, as the ſkin of animals bounds the growth of

the

the cellular parts beneath it; and hence that ſide of the tree, where the cuticle or exterior bark is frequently ſcratched through, will become larger than the other ſide of the tree, and tend to bend it into a curve with the ſcratched ſide outwards. Trees alſo on the outſide rows of woods will ſpontaneouſly bend outwards for light and air, and may I ſuſpect be more eaſily formed into proper curves by the method above propoſed. And where trees in a wood are at a proper diſtance from each other, they may forcibly be bent by cordage towards each other, and then by wounding the exterior and interior bark longitudinally, or perhaps horizontally alſo on the exterior ſide of the curved part of the tree, they may be brought into almoſt any degree of flexure, which they will afterwards preſerve as the tree advances.

Some of the quicker growing trees may be more valuable to the planter than oaks, and ſome in different ſoils are more valuable than others; as willow-trees in the hedge-rows in moiſt grounds are ſaid, if headed once in ten years, on an average to produce each of them one ſhilling a year. Perhaps the ozier for baſket making may be ſtill more advantageous in low grounds; there is a valuable paper on the planting of them and the choice of the kinds of them in the Tranſactions of the Society of Arts, Vol. XVI. p. 129, by Mr. Phillips. Perhaps the ſugar-maple may alſo be cultivated in this climate to advantage on many barren commons, as on Cannock Heath. And certainly pines, as Scotch fir, might in theſe ſituations ſucceed aſtoniſhingly, as appears by the plantations of Mr. Anſon on the barren mountains near his ſeat in Staffordſhire; and alſo from the plantations of the marquis of Bath at the foot of Wiltſhire Downs near Warminſter, whoſe ſteward, Mr. Davis, has given a valuable account of the profit of planting Scotch fir in preference to other timber trees; and finally aſſerts, "that although fir-timber is worth individually more per tree than oak or beech of the ſame ſize, theſe trees will nevertheleſs grow faſter and thicker together than any other trees. Four firs

firs will grow, where but one oak or beech will grow; for firs are the better, and deciduous trees the worſe, for being crowded." I ſuppoſe becauſe the branches of the latter are valuable, but the former is injured by the knots left in the trunk, where large branches have exiſted. Tranſ. of Society of Arts, Vol. XVI. p. 126.

Mr. Davis adds further, I ſuppoſe from his own obſervation, that "the chalk-hills in Hampſhire are peculiarly proper for beech; the flinty loams and clays of the ſame county for oaks and aſh; the moſſy ſteep ſides of the Wiltſhire Downs for hazel; the rugged and almoſt naked rocks of Mendip in Somerſetſhire near Chedder produce the lime-tree and the walnut in the greateſt luxuriance; and on the higheſt parts of the ſame Mendip hills, where no other tree can ſtand the ſea-breeze, ſycamore flouriſhes as well as in the moſt fertile vallies. But taking into conſideration the general demand of countries, and the peculiarities of different ſoils, no kind of wood is ſo generally profitable for planting in coppices as aſh." *Ib.*

3. Another thing concerning timber-trees, which ought to be attended to, is the injury, they are liable to receive from lightning; which, I am informed, is much more frequent than is generally ſuppoſed; inſomuch that in felling moſt woods, eſpecially thoſe which grow in wet ſituations, very many of the trees are found to be cracked longitudinally to the great injury of the timber; to prevent this, pointed wires, as thick as a gooſe quill, ſhould be attached to a few of the talleſt trees of all flouriſhing woods reaching above their ſummits, as conductors of lightning. Add to this that the holes made by wood-peckers, I am told, are very numerous, and do much injury to the timber of our foreſts, which can only be prevented by deſtroying that beautiful and ingenious bird.

4. Woods differ from each other in many reſpects, and are therefore uſed for many other purpoſes beſides mechanical ones; as in colour; whence particular woods are choſen for their beauty in the conſtruction of the furniture of houſes, as roſe-wood, aſpalathus;

others are uſed in the art of dying, as the Campechy wood, hæmatoxylum, and ſaunders, ſantalum, and pterocarpus; and ſeveral others. Other woods differ in their medicinal properties, as guaicum, quaſſia, Campechy wood, and ſaſſafras. Others differ in their chemical properties, affording eſſential oils, as oleum rhodii, and turpentines or balſams, and tar; and in their reſtringency, as the oak.

5. The oak probably contains much gallic acid, ſuch as has been extracted from the galls occaſioned on their leaves by the punctures of inſects; whence oak boards are ſaid to corrode the ſheets of lead, which are laid on them, and are hence believed to be improper for the gutture-boards on the roofs of houſes. But the ſap-wood, or external part of all timber, I ſuſpect, muſt be improper for this purpoſe on another account; as, when confined from much air by the ſheet of lead over it, it muſt lie for many months in the year in that ſtate of moiſture, which will favour the fermentation of the ſaccharine matter, which all ſap-wood contains; and will thence be ſubject to the dry rot, as it is called by architects. This may be long prevented by leaving proper holes in the walls on all ſides the building immediately under the roof, as has been generally done by thoſe itinerant bodies of architects, who ſhewed ſuch prodigies of genius in the conſtruction of cathedrals in this iſland, and all over Europe; and whoſe ſecret identifying words, and confederate ſigns, which were neceſſary to them in foreign countries, whoſe language they had not time to acquire, ſeems to have given origin to the modern myſteries of Free-maſonry.

The rot of wood might probably be entirely prevented by ſoaking dry timber firſt in lime-water, till it has abſorbed as much of it as may be; and then after it is dry by ſoaking it in a weak ſolution of vitriolic acid in water; which will unite with the lime already depoſited in the pores of the timber, and convert it into gypſum; which I ſuppoſe will not only preſerve it from decay for many centuries, if

it be kept dry, but alſo render it leſs inflammable, a circumſtance worthy attending to in the conſtruction of wood-built houſes. I alſo conceive that beams ſo impregnated would be leſs liable to ſwag, and boards ſo prepared leſs liable to warp. In the immenſe ſalt-mines of Hungary many large wooden props, which ſupport the roof, and are perpetually moiſtened with ſalt-water trickling down them, are ſaid to have ſuffered no decay for many centuries.

6. Woods alſo differ from each other in their hardneſs, or the general coheſion of their particles, whence one kind of timber has obtained the name of iron-wood, ſideroxylum. Others differ in the fineneſs of their conſtituent fibres, which ſhew a beautifully ſmooth poliſh, when planed, as roſe-wood, aſpalathus.

Where theſe two properties of hardneſs and ſmoothneſs exiſt together, as in box, buxus ſempervirens, the wood muſt be peculiarly valuable for the purpoſe of making wooden printing blocks, ſo well managed at this time by Mr. Bewick of Newcaſtle in his books of Natural Hiſtory of Quadrupeds and Birds.

7. Other woods differ in their durability, as cypreſs, cedar, mahogany, are ſaid to be indiſtructible by time, or by the depredation of inſects. The wood of the cedar of Bermudas, Juniperus Bermudiana, in which black-lead pencils are incloſed, is ſaid not to be eaten by either aerial, terreſtrial, or marine inſects, and is thence uſed in the Weſt Indies for building veſſels, whoſe bottoms are not penetrated by ſea-worms. The unperiſhable cheſts, which contain the Egyptian mummies, were of cypreſs, as well as the coffins in which the Athenians are ſaid by Thucydides to have buried their heroes. The gates at St. Peter's at Rome, which had laſted from the time of Conſtantine to that of Pope Eugene the fourth, that is eleven hundred years, were of cypreſs, and had at that time ſuffered no decay.

Of theſe ſome are believed to endure longer in water than others, as alder, betula alnus, and is therefore eſteemed preferable for piles to guard the banks of rivers. But Mr. Brindly, the conductor of the

grand trunk canal, aſſured me, that he believed from obſervation, "that red Riga deal, or pine-wood, would endure as long as oak in all ſituations," owing perhaps to its being ſo full of reſin or turpentine.

8. Other woods differ in the degree of the lateral adheſion of their longitudinal fibres, as the fir-wood, or deal, pinus, whence the timber readily ſplits by wedges. As the moiſture of the atmoſphere is abſorbed into the pores of the dry cellular membrane, whch connects the longitudinal fibres of theſe woods, more than into thoſe of the longitudinal fibres themſelves, they become much more dilated laterally than extended longitudinally, by the change of a dry atmoſphere to a moiſt one; whence by joining pieces of deal cut croſs-wiſe into a rod of ſome feet in length, a very ſenſible creeping hygrometer was made by Mr. Edgeworth, deſcribed in the Botanic Garden, Vol. II. note on Impatiens. And as this wood is not liable to be much extended by low degrees of heat, when it is impregnated with boiling oil, or covered with varniſh, to prevent the acceſs of aerial moiſture, the pendulums of time-keepers have been conſtructed of it, which have not perceptibly lengthened in any variations of the heat or moiſture of the atmoſphere.

9. Another circumſtance of great conſequence, in which woods differ, is their ſpecific gravity, as many of them will ſink in water, as oak after it has been long moiſtened; and others will ſwim with much of their contents above water, as deal, and hence have been uſed for the conſtruction of rafts for the purpoſes of rude navigation; and which are now ſaid to be conſtructed in France as engines of war, probably for the deſign of ſuddenly landing troops, horſes, artillery, and proviſions, from the ſhips of invading armies on dangerous ſhores, and for the certainty of re-embarking them. Theſe nevertheleſs can not carry great burthens ſimply by their ſpecific levity; but if each piece of timber could be made hollow, and rendered water-tight, ſo as to contain air, which might probably be done by

boring them, and plugging up the ends; or by joining thick boards together by means of paint and flannel, or caoutchouc, ſo as to conſtruct long ſquare wooden troughs filled with air, perhaps eight or ten inches diameter within, and twenty or thirty feet long. If the junctions of theſe could be rendered water-tight, and a number of ſuch hollow trunks could be chained looſely together, and laid croſs-wiſe three or four times over each other, they might carry very large burthens, not eaſily to be deſtroyed by ſtorms, or ſunk by cannon ſhot.

10. Another difference of the longitudinal fibres of timber conſiſts in their degree of elaſticity, a circumſtance of much greater conſequence to our anceſtors in reſpect to the art of war than to the preſent generation; as their bows for dicharging arrows, and the catapulta, or engine for throwing ſtones, depended on the recoil of rods or beams of timber forcibly bent into a curve. For the conſtruction of bows the yew-tree, taxus, was uſed in this iſland, and was planted in church-yards, probably for the purpoſe of ſupplying the youth of the pariſh with bows, that they might become expert in the uſe of them; many of which have acquired extreme old age, and remain to this day.

11. When tall trees are deſigned to be tranſplanted for the purpoſe of ornamenting a pleaſure-ground, it is proper to dig a circular trench round them two or three feet deep in the early ſpring; whence many new roots will ſhoot from thoſe, which have their ends cut off, and thus the ball of earth will be better held together, when the tree is removed in the ſucceeding autumn, and the tree by having previouſly produced ſo many more fine abſorbent radicles will be more certain to grow in its new ſituation.

Hence when new grafted fruit-ſcions on young ſtocks are deſigned to remain a few years in the nurſery, before they are deſigned for ſale, ſome provident gardeners I am told tranſplant them every two years, that the root-fibres may be more numerous in a ſmall compaſs,

paſs, which occaſions them to grow, when finally tranſplanted, with more certainty, and with greater vigour.

As tranſplanted trees ſhould not be ſet too deep in the ground, as their growth is then always much checked, as explained in Sect. XV. 2. 4. they generally require ſome kind of props to prevent them from being overturned, or much ſhook by the winds, before they have ſufficiently extended their roots. As the bark is the only living part of the tree, it is liable to receive much injury from its contuſion by the preſſure of the props againſt it, or by the ſtrangulation of the bandage which holds it to them. Hence as the internal wood of a tree is not alive, I remember many years ago, that I faſtened one prop by a ſtrong nail to each fruit-tree of a ſmall orchard, which I then planted; and found the tree ſupported with much leſs apparent injury than in the uſual manner by three props and adapted cordage.

12. The time for felling timber has generally been in the winter ſeaſon, when labourers could beſt be ſpared from other rural employments, and from the architecture of towns; but it was long ago obſerved by Mr. S. Pepys in a paper publiſhed in the Philoſoph. Tranſact. Vol. XVII. p. 455, that the beſt time for felling oaks for ſhip-building was after having taken off the bark in the early ſpring, and having ſuffered the new foliage to put forth and die. For by the pullulation of the new buds the ſaccharine matter in the ſap-wood or alburnum is expended, and it then becomes nearly as hard and durable as the heart-wood, being both leſs liable to decay, or to be penetrated by inſects; which was a curious and ingenious diſcovery at that time, though the theory was not well underſtood; the truth of which has now been eſtabliſhed, I believe, by the experience of a century.

As the bark of trees annually changes into alburnum or ſap-wood, ſo the alburnum annually changes into lifeleſs wood; whence the concentric rings, which are ſeen in the trunks of trees, when they

are felled, are annually produced; and are ſaid generally to be thicker on that ſide of the trunk, which grows towards the ſouth, than on the northern ſide, and thicker in the ſummers moſt favourable to vegetation than the contrary. Theſe rings, as they loſe their vegetable life, and at the ſame time a part of their moiſture by evaporation, or abſorption, gradually become harder and of a darker colour; inſomuch, that by counting their number, it is ſaid, that not only the age of the tree, but that the mildneſs or moiſture of each ſummer during the time of its growth may be eſtimated by the reſpective thickneſs of the rings of timber.

13. In the ſame manner the central pith alſo loſes its vegetable life, probably after the firſt year; and then gradually becomes abſorbed, or ſo impregnated with ligneous particles, as not to be diſtinguiſhed from the ſurrounding wood. The pith of a young bud ſo reſembles the brain and ſpinal marrow of animals in reſpect to its central ſituation, that it probably gives out nerves to every living fibre of the bud; though theſe have yet eſcaped our eyes and glaſſes; and thus furniſhes the power of motion, as well as of ſenſation, to the various parts of the vegetable ſyſtem. One curious fact, which I have obſerved, ſeems to countenance this conjecture; which is, that the pith of a laſt year's twig communicates to the leaves on each ſide of it, but not to the new buds in the boſoms of thoſe leaves; becauſe thoſe new buds are each an individual being, generated by the caudex of the leaf, and muſt therefore poſſeſs a ſenſorium of its own. See Sect. I. 8. and IX. 2. 4.

The pith of trees contains much mucilage, as well as the ſtalks of annual and perennial plants, whether they are hollow or not; the pith of a palm-tree, cycas circinalis, is ſoftened with water, and paſſed through ſieves, and thus forms the ſagoe of our ſhops; it is poſſible the large pith of the ſtalks of artichokes, cinara ſcolymus, might be manufactured into a ſimilar kind of taſteleſs mucilage; and the pith of the young ſhoots of elder, ſambucus nigra, might alſo poſſibly

poſſibly be made into taſteleſs mucilage, if previouſly agitated in cold water to waſh away any acrid material, as in the preparation of ſtarch.

14. When we contemplate the manner of the production of the internal wood of trees from the induration of the ſap-wood, and the annual increaſe of the ſap-wood from the bark, which was previouſly generated by the caudexes of the numerous buds; there would appear to be no natural boundary to the growth of trees. But that their trunks, though a mile diſtant from each other, might be enlarged, till they meet together, and cover the whole earth with ligneous mountains, conſtructed by ſucceſſive generations of vegetable buds; as ſome parts of the ocean are crowded with calcareous rocks, fabricated by the ſucceſſive generations of coralline inſects!

A very large tree is deſcribed by Mr. Adanſon in Africa, which is called by Linneus Adanſonia, in honour of that philoſopher; of which he ſays the diameter of the trunk frequently exceeds twenty-five feet, and the horizontal branches are from forty-five to fifty-five feet long, and ſo large, that each branch is equal to the largeſt tree in Europe. The breadth of the top is from 120 to 150 feet; and one of the roots bared only in part by the waſhing away of the earth by the river, near which it grew, meaſured 110 feet long, and yet theſe ſtupendous trees do not exceed 70 feet in height. Voyage to Senegal.

And in this country, when the internal wood is gradually detached from the alburnum, as it decays, as in ſome old hollow oaks and willows, ſo that it does not deſtroy the tree by the putrid matter being abſorbed, there ſeems to be no termination of the growth of the external remains of the tree, till the wind blows it down from its want of ſolid wood to ſupport it. Of this kind of hollow tree a remarkable inſtance remains in Welbeck Park in Nottinghamſhire, through the middle of which a coach is ſaid to have been driven. There is another oak of uncommon dimenſions in the foreſt of Needwood,

called Swilcar oak, celebrated in an unpubliſhed poem by Mr. Mundy, on his leaving that foreſt, and is there ſaid to be 600 years old.

But the caudexes of buds, which compoſe the barks and afterwards the timber of trees, differ from the neſts or cells of the coralline inſects, which compoſe their calcareous rocks beneath the waves, in this circumſtance. The cells of the coralline inſects, like the ſhells of other ſea-animals, become harder by time, changing by ſlow degrees the phoſphoric acid, which they contain, for carbonic acid; and ſome of them afterwards for ſiliceous acid, and are thus converted into limeſtone and flint, and remain eternal monuments of departed animal life.

Whilſt the remaining vaſcular ſyſtem, after the death of vegetable buds, like the fleſh of animals, undergoes in proceſs of time a chemical decompoſition, and loſes by fermentation and putrefaction both their carbonic and phoſphoric acids, which probably gave them their ſolidity, and crumble into duſt; which is ſeen in the rotten trunks of trees, which loſe ſo much of their carbon as they decay; and alſo become luminous, when expoſed to the air by the eſcape or production of phoſphoric acid. And finally, their other component parts are ſeparated by elutriation, and form moraſſes; whence coals, iron, clay, and ſandſtone; all which are found on the lime-rocks, which were previouſly generated in the ocean, and remain eternal monuments of departed vegetable life. Whence it appears, that a boundary is ſet to the ſize of trees by their internal decay, but none to the growth of coral-rocks, which are ſo formidable in the navigation of the ſouthern ocean.

15. *Queſtion on the cultivation of Timber.*

The political advantage or diſadvantage of cultivating timber in this iſland ſhould be here conſidered. In the preſent inſane ſtate of human

human ſociety, when war and its preparations employ the ingenuity and labour of almoſt all nations; and mankind deſtroy or enſlave each other with as little mercy, as they deſtroy and enſlave the beſtial world; and may in time, for what appears to the contrary, return to their ſavage ſtate, and begin to eat each other again, as ſeems to have occurred at or before the commencement of almoſt all civil ſocieties; the firſt political attention ſhould certainly in this period of human infatuation be employed to ſtrengthen the country, to enable it to repel the invaſion of foreign enemies, and to defend its natural rights, when they are infringed by them; but not to attack or invade other nations for any predatory or ambitious purpoſe. The next important thing ſhould be for this nation to ſet a great example of juſtice and humanity to all contending nations, and thence again to introduce truth and virtue into the world with peace and happineſs in their train.

Now as the power to reſiſt invaſion, and to defend our natural rights, when infringed by foreign enemies, muſt depend more on the number of men than on the number of trees; there need be no heſitation in determining, that thoſe lands, which can be employed in the preſent production of vegetable or animal food, ſhould not be occupied in the tedious cultivation of future timber.

But that, as the ſummits of this country conſiſt principally of a ridge of mountains extending from ſouth to north between the eaſtern and weſtern ſeas, as thoſe of the Peak of Derbyſhire and the Moorlands of Staffordſhire, which are ſo bleak or ſo barren as to be totally unfit for the plough or for paſturage, and yet might be employed for raiſing variety of timbers; which from our great ſucceſſes in naval engagements may be termed with great propriety, when employed in building ſhips, the wooden walls of this iſland: All thoſe unfertile mountains from the extremity of Cornwall to the extremity of Scotland, ſhould be covered with extenſive foreſts of

ſuch

ſuch kinds of wood, as experience has ſhewn them to be capable to ſuſtain, and which may be beſt adapted to the conſtruction of ſhips.

16. The following addreſs to Swilcar oak in Needwood foreſt, a very tall tree, which meaſures thirteen yards round at its baſe, and eleven yards round at four feet from the ground, and is believed to be ſix hundred years old, was written at the end of Mr. Mundy's poem on leaving that foreſt, and may amuſe the weary reader, aud conclude this Section.

ADDRESS TO SWILCAR OAK.

Gigantic OAK! whoſe wrinkled form hath ſtood,
Age after age, the Patriarch of the wood!—
Thou, who haſt ſeen a thouſand ſprings unfold
Their ravel'd buds, and dip their flowers in gold;
Ten thouſand times yon moon relight her horn,
And that bright ſtar of evening gild the morn!—
Erſt, when the Druid-bards with ſilver hair
Pour'd round thy trunk the melody of prayer;
When chiefs and heroes join'd the kneeling throng,
And choral virgins trill'd the adoring ſong;
While harps reſponſive rung amid the glade,
And holy echoes thrill'd thy vaulted ſhade;
Say, did ſuch dulcet notes arreſt thy gales,
As MUNDY pours along the liſtening vales?
Gigantic OAK!—thy hoary head ſublime
Erewhile muſt periſh in the wrecks of time;
Should round thy brow innocuous lightnings ſhoot,
And to fierce whirlwinds ſhake thy ſteadfaſt root;
Yet ſhalt Thou fall!—thy leafy treſſes fade,
And thoſe bare ſhatter'd antlers ſtrew the glade;

Arm

Arm after arm ſhall leave the mouldering buſt,
And thy firm fibres crumble into duſt!—
But MUNDY's verſe ſhall conſecrate thy name,
And riſing foreſts envy SWILCAR's fame;
Green ſhall thy gems expand, thy branches play,
And bloom for ever in the immortal lay.

SECT. XIX.

PRODUCTION OF FLOWERS.

I. Flowers from ſeeds. 1. *Double flowers from ſeeds. Hereditary diſeaſes in plants. Full flowers have no ſtamina. Three kinds of double columbine. Vegetable monſters analogous to animal mules. The ſtamen, piſtil, and calyx, are the moſt unchangeable parts. Double flowers diſtinguiſhed by the calyx, are much more durable than ſingle ones. Double poppies yield more opium. Annual inſects.* 2. *The colours of ſingle flowers from ſeed how varied. Variegation of foliage. Vegetable juices are hyper-oxygenated. This fluid oxygen is converted into gas by the ſun's light; which therefore colours living vegetables, and bleaches dead ones.* II. 1. Flowers from buds. *Double ones how cauſed. Surround the bud with water. Oil, and conſerve of roſes. Their double flowers. Acquired habits.* 2. *How to vary the colour of ſingle ſhrub-flowers, by anther-duſt, by inoculation. Trees how variegated by ingraftment, or made into evergreens.* 3. *How to increaſe the number of flowers.* III. 1. Flowers from roots. *Bulb-rooted flowers. To cauſe their duplicature, break off the flower, raiſe them out of the ground.* 2. *Single bulb-rooted flowers. To increaſe them in ſize or number, take away offsets, crowd their roots. Propagation by offsets. By ſeeds. How broken into colours. Plant them in different ſoils. Tulips break into colours from age.* 3. *Perennial branching roots. Duplicature of their flowers, propagated by offsets, by ſeeds. Their ſingle flowers. How broken into colours. By ſeeds, by tranſplanting.* IV. Eſculent and medicinal flowers. *Vegetable mucilage coagulated by boiling in water, in ſteam. They loſe their green colour in ſteam, Why? Artichoke-ſtalks.* 2. *Cultivation of brocoli. Knobs on its roots.* 3. *Hop. Camomile. Their duplicature.* V. Flowers uſed in the arts. *For dying, ornotto. For ſpinning, cotton, cotton-ruſh, cat's-tail.* VI. Nutritious parts of vegetables. 1. *Muſhrooms. Gluten of Wheat. Oils.* 2. *Sugar. Mucilage. Oil.* 3. *Starch. Meal.* 4. *Alburnum. Barks. Roots of fern and*

and of bryony. 5. *Immature flowers. Honey. Leaf-ſtalks. Leaves. Reſervoirs of nutriment.* VII. Happineſs of organized nature. 1. *Seeds and eggs have not ſenſitive life. Milk gives two-fold pleaſure. Dull animals and diſeaſed vegetables periſh, and give life to more ſenſible ones. Old age unknown before ſociety. Miſery is not immortal.* 2. *Animal abſorption and ſecretion is attended with agreeable ſenſation. Renders matter more ſolid. The ſame in vegetables.* 3. *Strata of limeſtone formed from animal ſhells. Thoſe of coal, clay, ſand, from vegetable ſecretions, gave pleaſure at the time of their production; and are monuments of paſt felicity, and of the benevolence of the Deity.* VIII. Cultivation of brocoli, *a poem.*

THE beautiful colours of the petals of flowers with their poliſhed ſurfaces are ſcarcely rivalled by thoſe of ſhells, of feathers, or of precious ſtones. Many of theſe tranſient beauties, which give ſuch brilliancy to our gardens, delight at the ſame time the ſenſe of ſmell with their odours; yet have they not been extenſively uſed as articles either of diet, medicine, or the arts. For the purpoſe of cultivation they may be divided into thoſe immediately derived from ſeeds, thoſe from buds, and thoſe from roots; to which may be added the eſculent and medicinal ones, and thoſe uſed in the arts.

1. *Flowers from Seeds.*

1. The eye of the floriſt is frequently delighted with double flowers, which ſhew a greater blaze of colour in a ſmall ſpace, and continue ſome weeks longer in blow than ſingle ones; and, though they are properly called vegetable monſters by the botaniſts, may give information to the philoſopher in reſpect to the ſexual generation of vegetables. The method therefore of producing double flowers from ſeeds is a matter of importance, as well as the art of giving to both theſe and the ſingle flowers their moſt healthy expanſion, and the greateſt brilliancy and variety of their colours.

Though thoſe multiplied flowers, which are ſaid to be full, poſſeſs no ſtamens, or piſtils, and conſequently can produce no ſeeds; yet are they frequently raiſed immediately from ſeeds; for thoſe flowers, which are cultivated with more manure, moiſture, and warmth, than is natural, become more vigorous and larger, and at the ſame time are liable to ſhew a tendency to become double, by having one or two ſupernumerary petals in each flower, as the ſtock July-flower, cheiranthus, and anemone. And what is truly curious, this tendency to duplicature is communicated to the ſeeds of thoſe individual bloſſoms; inſomuch that floriſts are directed to tie a thread round ſuch flowers, which have a ſupernumerary petal, to mark them, and to collect their ſeeds ſeparately; which are ſaid uniformly to produce double or full flowers, if cultivated as above with rather more manure, moiſture, and warmth, than thoſe plants have naturally been accuſtomed to.

The analogy of this circumſtance with the hereditary diſeaſes of animals is truly wonderful; as the children of thoſe parents, who have acquired the gout or dropſy by intemperance in the uſe of fermented or ſpirituous potations, become afflicted with thoſe diſeaſes, as I have frequently obſerved, in a much greater degree by the ſame quantity of intemperance, which originally produced them in their parents; or they acquire the ſame quantity of thoſe diſeaſes by a leſs degree of intemperance, than occaſions them in others, whoſe parents have not uſed fermented or ſpirituous liquors to exceſs.

The luxuriance of flowers, which is believed to ariſe from their cultivation in more nutritive ſoils with greater moiſture and warmth, conſiſts in the increaſe of ſome parts of the flower, and the conſequent excluſion of others; and is diſtinguiſhed by Linnæus into the multiplication and plenitude of flowers, and into proliferous ones. Multiplied flowers conſiſt of double, triple, or quadruple corols; but full flowers are ſo multiplied as to exclude the ſtamina; while in proliferous ones other flowers ariſe from within the principal

principal flower, and frequently from its center. Philoſ. Botan. p. 80.

It is ſuppoſed that the ſtamina of ſome double flowers are converted into petals; but on examination, I ſuſpect that the number of petals is increaſed, and the ſtamina prevented from growing by being compreſſed by them in their naſcent ſtate; as in many of them, I believe, the rudiments of ſome ſtamina may be ſeen, as in ranunculus. So when a new flower riſes in the center of the old one, it is ſuppoſed, that the piſtillum is converted into the ſtem of a new flower, as in proliferous daiſy, bellis prolifera; but I ſuſpect, that the piſtillum is prevented from riſing by the immoderate growth of the new flower-ſtem; as in ſome of them, I am told, the rudiment of the piſtillum may be perceived.

Thus monopetalous flowers are doubled or multiplied by the increaſed diviſions of the limb, as obſerved by Linnæus, Philoſ. Botan. p. 83, who adds, that the metamorphoſis of Engliſh ſoapwort is very ſingular, as its five petals are transformed into one petal, and that in opulus flore globoſo the central florets become ſimilar to thoſe of the circumference, acquiring wheeled corols, and being barren: in theſe caſes the ſtamens cannot be changed into corols, as the number of corols is not increaſed. Afterwards, in p. 84, the ſame illuſtrious author obſerves, that in double lychnis the rudiment of the common piſtil is preſent.

The luxuriance of flowers therefore conſiſts in the multiplication of the corols or nectaries, which laſt are properly an appendage to the former; and the prevention of the growth of the male and female organs is the conſequence. Thus the flower of aquilegia, columbine, has three kinds of plenitude: 1. the petals become multiplied, and the nectaries excluded; 2. the nectaries are multiplied, and the petals excluded; 3. the nectaries are multiplied, the petals remaining. So that there are five petals, and between each of theſe three nectaries, which exiſt within each other.

A curious

A curious analogy here alſo exiſts between theſe vegetable monſters and thoſe of the animal world; as a duplicature of limbs frequently attends the latter, as chickens and turkeys with four legs and four wings, and calves with two heads. And in mules the parts ſubſervient to generation become deficient, whence they cannot propagate their ſpecies; exactly as in theſe full flowers, which can thence produce no ſeed. And in reſpect to botanic ſyſtems, it may be obſerved from theſe vegetables of luxuriant growths, that the ſtamens and piſtils are leſs liable to change than the corols and nectaries, and are therefore more proper parts for the claſſification of plants; on which idea Linnæus has conſtructed his unrivalled ſyſtem. And laſtly that the calyx, or perianth, is the next moſt unchangeable part of the flower, as this is ſeldom doubled or multiplied; and that hence by inſpecting the calyx the genera of many double flowers may be detected; thus the double ranunculus poſſeſſes a calyx, but the double anemone is without one, like the ſingle ones of thoſe genera.

The greater duration of double flowers than ſingle ones is ſo remarkable in ſome poppies, that their ſingle flowers loſe the corolla in a few hours, while in the double ones it continues ſeveral days: this circumſtance is well worthy the attention of thoſe, who cultivate poppies for the purpoſe of wounding the head, which incloſes the ſeeds, for the opium, which thus exſudes. As poppies with double flowers may probably be capable of yielding opium, before they ſhed their flowers, and as long as other poppies, after they ſhed them, Dr. Smith aſcribes this event to the organs of reproduction being obliterated, and the conſequent want of impregnation; by the great ſtimulus of which he thinks the vegetable irritability may be ſooner exhauſted in ſingle flowers: and adds, "that on the ſame account many plants reſiſt a greater degree of cold for ſeveral winters before flowering; but after that event they periſh at the firſt approach of cold, and can by no art be preſerved ſo as to ſurvive the winter."

And repeats an obſervation from Linnæus, that the piſtilla of the female hemp, cannabis, continued much longer to exiſt when not expoſed to the male pollen, than thoſe piſtilla on which the pollen had been effuſed. Tracts on Nat. Hiſt. p. 177.

It may be obſerved, that many inſects may be called annual ones as well as many vegetables, and die, as ſoon as they have provided the eggs or ſeeds for the reproduction of their ſpecies, as the ſilkworm, and, I ſuppoſe, all the kinds of moths and butterflies; many of which take no food at all, after they have acquired their organs of generation and their amatorial paſſion, and yet appear fat and active; and others live only upon honey, and ſeem to die as ſoon as that paſſion is gratified, probably from having no further pleaſureable ſtimulus to excite the animal power into activity, rather than from its total exhauſtion; becauſe other animals, whoſe exiſtence is not naturally ſo ſhort, are not injured or deſtroyed by the moderate uſe of the powers of reproduction; and that power leaves them long before their death. An experiment to ſhew, whether the moths of ſilkworms would live longer if deprived of their paramours, might be worth the attention of naturaliſts; and alſo, whether the butterflies of our climate might not be preſerved during the winter, if fed with honey like bees, and kept from exceſſive cold. I directed ſome honey to be offered to the ſilkworm-butterflies, which they would not attend to, though they may probably ſeek for it in their native climates.

2. Varieties in the colours of ſingle flowers raiſed from ſeeds may probably be generally acquired by ſowing near together thoſe of the ſame ſpecies, which already poſſeſs different colours; ſo that during the diſperſion of their anther-duſt by the wind, or otherwiſe, they may intermix and adulterate each other. Or this may be more certainly effected by bending the flowers of one colour, and ſhaking the anther-duſt over thoſe of another colour. In this manner, I

ſuppoſe,

ſuppoſe, it happens, that the beds of centaurea cyanus become of ſuch various and beautiful ſhades of blues, purples, and whites.

Another method of giving variety of colours to ſeedling flowers conſiſts in ſowing them on natural ſoils, or on factitious compoſts, which differ much from each other in reſpect to vegetable nutriment, and perhaps in reſpect to their colour, as ſome animals change their natural colours when in different ſituations of ſoil. As frogs much reſemble the colour of the ſoil on which they live, and our domeſticated horſes, dogs, cats, rabbits, pigeons, and poultry, change their colours into endleſs varieties, owing to the difference of their nutriment or ſituation. But obſervations and experiments are wanting on this ſubject in reſpect to the colours of ſeedling flowers, as well as in reſpect to the variegation of the leaves of ſhrubs and trees; which laſt originates probably from ſoil or ſituation, and may be propagated by ingrafting.

As the origin of double flowers is believed to reſult from the luxuriant growth of the plant, owing to too much nouriſhment, moiſture, and warmth, ſo the origin of new colours in flowers, and of variegated foliage, is thought to occur from the innutrition of the ſoil, on which they grow, compared to that which they have naturally been accuſtomed to, or from defect of moiſture and of heat; which is countenanced by the dwarfiſh ſize of ſuch plants in general, and eſpecially by the leſſened ſtature of tulips, when their petals break into variety of colours.

The proximate cauſe of the change of colours in flowers or foliage muſt be ſought from the modern acquiſitions of aerial chemiſtry. The preſence of oxygen gas deprives dead vegetable fibres, as cotton-wool and the threads of flax, of their colour; that is, it bleaches them; which is probably owing to its uniting with the colouring matter and forming a new acid, which is tranſparent. Thus the hyper-oxygenated muriatic acid almoſt inſtantaneouſly deprives cotton and linen of their colour; and the ſun's light on moiſtened

linen

linen ſpread upon the ground ſeems to decompoſe the water, and the oxygen thus detached whitens the linen. The etiolation or blanching of living vegetables on the contrary ſeems to originate from the want of the ſun's light to convert into gas the fluid oxygen; which, by diſſolving their colouring matter, and forming new and perhaps taſteleſs acids, deprives them of colour. Hence the water, which vegetables perſpire in the ſunſhine, becomes hyperoxygenated, which has much puzzled philoſophers to account for; and the oxygen riſes from it without decompoſing it; which laſt circumſtance is evinced by the total abſence of the ſmell of hydrogen, which ſo powerfully affects our noſtrils, when a ſpoonful of water is thrown on burning coals.

Now as plants, which grow leſs vigorouſly from defect of nutriment, moiſture, air, or warmth, may acquire or poſſeſs leſs oxygen to diſſolve their colouring matter, their ſtructure may approach towards that of dead vegetables; and hence they may become bleached inſtead of coloured by the influence of the ſun's light, eſpecially in thoſe parts where their vital functions are performed with leſs vigour; ſo an etiolated vegetable, as a blanched plant of celery, apium graveolens, becomes green in a few days, when expoſed to the light and air; and white again, if deprived of life, and expoſed to the ſunſhine and dews.

The immediate cauſe of the various colours of ſome flowers, as of poppies, might be a ſubject of curious inveſtigation. I once ſuppoſed, that the thinneſs of the pellicle of ſome flowers might occaſion them to reflect different colours, as is ſeen on dropping a drop of oil from a bridge on the water below on a bright day. But colours thus produced vary with the ſituation of the obſerver, in reſpect to the obliquity or angle of reflection, in which they are ſeen; and are thence variable with every motion of them, as thoſe colours ſeen on ſoap-bubbles, and on mother-pearl, and on the Labradore-ſtone, and on ſome ſilks. For thoſe colours depend on the thinneſs of the

reflecting ſurface, which when ſeen more obliquely become thicker; and then reflects thoſe colours, which paſſed through thinner plates; in the ſame manner as the red light of the ſetting ſun is reflected from glaſs windows, ſeen very obliquely by the obſerver.

The colours of flowers therefore, as they are not variable by the obliquity, with which they are ſeen, like thoſe of mother-pearl card-fiſh, do not depend on the thinneſs of their pellicle; but, I ſuppoſe, to the greater facility that ſome parts of them poſſeſs in parting with their oxygen, when expoſed to the ſun's light, than other parts of them; for all flowers are more or leſs etiolated, before they firſt open. In the ſilk manufactory a variable colour is produced by making the warp of one colour and the woof of another; perhaps the variable colour of a peacock's tail may be owing to a mixture of different coloured down placed in lines near each other.

II. *Flowers from Buds.*

1. The flowers ariſing from the buds of ſhrubs or trees are liable to become double or full by the multiplication of their petals, as thoſe of roſes, cherries, hawthorn, peach, roſa, prunus, ceraſus, crategus oxyacantha, amygdalus perſica. Which tendency to duplicature, as in the flowers of annual plants, is probably owing to the too vigorous growth of the bud from a too nutritious ſoil, or the combination of abundant moiſture and warmth, and would probably be forwarded by ſurrounding the bud itſelf frequently with water; as is ſo beautifully ſeen in thoſe plants, which have a cup round their joints to preſerve for a time the rain, which falls upon them, as round the joints of dypſacus, teaſel, ſilphium, tillandſia, and nepenthes.

It is remarkable, that though the duplicature of many flowers is believed to have been owing to the more nutritious ſoil, in which they

they have been cultivated, yet that, when tranſplanted into leſs fertile ſoils, or ingrafted on leſs luxuriant trees, they ſtill retain their tendency to duplicature; which can only be aſcribed to the continuance of an acquired habit, or to the ſucceſſion of hereditary diſeaſes, ſo frequently obſerved in the animal ſyſtem.

This duplicature of flowers from buds is generally propagated by ingrafting the ſcions of ſuch, as bear multiplied petals, on ſimilar plants, which bear ſingle flowers; and may be of ſervice not only for beauty, but for the purpoſe of increaſe in thoſe plants, the petals of whoſe flowers are conſumed for any purpoſe, as the leaves of roſes. A gentleman at Nottingham annually diſtils a profitable quantity of eſſential oil of roſes, by collecting all of them he can purchaſe in the neighbourhood during the ſeaſon; and this by the uſual proceſs, which is not difficult though tedious. And a ſurgeon at Stafford has introduced an agreeable and profitable kind of agriculture, by planting half an acre of ground with red roſes, and converting the flowers into conſerve with ſugar, or by ſimply drying them for the London market.

2. It is probable, that numerous varieties of colour in the ſingle flowers of ſhrubs, as well as thoſe of annual plants, might be obtained by ſhaking the anther-duſt of one variety over the ſtigma of another, where any difference of colour already exiſts in the ſame ſpecies. And perhaps ſome changes of colour of the flowers might be produced by inoculating the buds of a ſhrub, whoſe flowers are of one colour, into the branches of another variety of the ſame ſpecies or genus; as the variegation of the foliage of plants is ſaid to have been produced in this manner, according to the aſſertions of Mr. Bradley and Mr. Laurence, who budded a ſpotted paſſion-flower and a ſtriped jaſmine on thoſe, which were not variegated, and produced a ſimilar variegation of them, as related in Sect. V. 1. This has been aſcribed to the abſorption of ſome infectious matter from the inoculated bud, which propagated a ſimilar diſeaſe to the whole tree; and

has thence been uſed as an argument in favour of a vegetable circulation of juices.

A ſimilar fact is alſo aſſerted by Mr. Milne. He ſays, that "an evergreen tree ingrafted on a deciduous one determines the latter to retain its leaves; this obſervation is confirmed by repeated experiments, particularly by grafting the laurel, lauroceraſus, an evergreen, on the common cherry, ceraſus; or the ilex, an evergreen oak, on the common oak." Botanical Dict. Art. Defoliatio. All theſe ſeem to want further experiments to authenticate the facts ſo delivered on the authority of ingenious men.

3. To increaſe the number of the flowers of ſhrubs, all thoſe arts are applicable, which are deſcribed in Sect. XV. 2. for the production of fruit on wall trees; which, when the tree is of a proper age, conſiſt, 1. in bending down the viviparous branches to the horizon, which renders them oviparous; 2. by twiſting a wire, or tying a cord round the viviparous branches; 3. by wounding or cutting away a narrow cylinder of the bark; 4. by tranſplanting or cutting off ſome of the roots; 5. by cutting away the central or viviparous branches; 6. by ingrafting.

III. *Flowers from Roots.*

1. Many bulb-rooted flowers are deſervedly in great eſtimation by floriſts, as the tulip, hyacinth, lily, colchicum, crocus, fritillary, &c. and of thoſe many are liable to become double, which adds in general ſo much to their ſplendour and to their duration, as narciſſus, hyacinth, colchicum, tulip.

The immediate cauſe of duplicature or multiplication of the petals of theſe flowers is probably ſimilar to that of thoſe above mentioned, and originates from their luxuriant growth, owing to the fertility

fertility of the ſoil, and the abundance of moiſture and of warmth in combination.

Other circumſtances, which may add to their luxuriant growth, may alſo contribute to their duplicature; ſuch as by breaking off the flower as ſoon as it begins to fade; and thus, by preventing the nutritious vegetable juices from being expended in the growth of the ſeeds, more of it may be derived to the principal ſucceeding bulb.

Thus it is aſſerted, that the preventing ſome annual plants from flowering lengthens their lives, which it may effect by occaſioning them to produce new root-ſcions, and thus to become perennial vegetables. The very ingenious Mr. Bogle, in the papers of the Bath Society, believes that wheat, oats, and barley, may be made perennials, if they are eaten down by cattle or ſheep, or cut by the ſcythe or ſickle, ſo as to prevent them from producing ears.

As tulip-bulbs raiſed from ſeed produce a larger bulb the ſucceeding year, and again a larger with a different leaf on the third year, and ſo on till the fifth or ſixth, the bulbs thus annually improving till they flower; and even after they flower they are believed to continue to improve for ſome years, till the colour of the petals become ſtriped: I ſuſpect that the art of procuring a great duplicature of the petals of theſe flowers conſiſts in breaking off the flower-ſtem on the fifth, ſixth, and ſeventh years, from the ſowing of the ſeed; that is, for a year, or two, or three, after the flower-ſtem firſt appears, as noted in Sect. VIII. 1. 3. And that the tendency to duplicature will continue in the ſucceeding bulbs by the acquired habit, as in the hereditary diſeaſes of animals.

And ſecondly, theſe flower-roots become more luxuriant by raiſing them out of the ground, as ſoon as the leaves wither, which are the parents of the new bulbs; and then by taking away the ſmaller or collateral new bulbs from the principal one, which might otherwiſe incommode its growth by their vicinity, and conſequent compreſ-

ſion,

ſion, both theſe methods are of equal uſe to enlarge and render more vigorous the ſingle flowers of bulb-roots, as well as to increaſe their tendency to duplicature.

2. The ſingle flowers of ſome of theſe plants may be probably not only enlarged, but ſo ſtrengthened as to ripen their ſeeds in this climate, by nicely laying bare the root, and taking from it the new progeny; whether a ſingle new bulb, as in orchis maſcula, or the numerous ones of hyacinth, tulip, or lily of the valley; as by theſe means the vegetable nutriment is not expended on the new bulbs, and probably more of it may thence be derived to the flower. See Sect. XVII. 1. 3.

Another method of increaſing the bulb-rooted flowers in ſize or number conſiſts in crowding their roots in garden-pots, or by not annually tranſplanting them; and thus by preventing their offsets from being formed, or by decreaſing the number or vigour of them; thus lily of valley, and jonquil, ſeldom afford large or numerous flowers, till they have remained three or four years in the ſame ſituation; but muſt nevertheleſs be then occaſionally in part tranſplanted, leaſt the roots ſhould die from being ſo crowded as not to form each of them one annual new bulb, which is their mode of reproduction.

The uſual method of propagating bulbous roots has been by the ſmaller offsets, which are formed annually round the principal or central new bulb, as in tulips; which central new bulb has commonly been miſtaken for the old root; by this mode of propagation the ſimilarity of the new progeny to the parent is nicely preſerved; and on that account ſome of theſe new roots of tulips and hyacinths have been ſold at extravagant prices. For the circumſtance of this mode of reproduction ſee Sect. IX. 3. 2.

But in reſpect to producing variety of colour in the ſingle flowers of bulbous roots, the moſt effectual method, I ſuppoſe, muſt be by ſowing their ſeeds, and waiting a few years, till their ſucceſſive bulbs

at

at length produce flowers, as deſcribed in Sect. XVII. 1. 2. and particularly if the anther-duſt of one variety in reſpect to colour be ſhed on the ſtigma of another variety.

Another method of producing a change or variety of colours in bulb-rooted flowers may be by planting them every year, till they flower, on very nutritious ſoil, with an abundant combination of moiſture and of heat, as theſe two elements ſhould exiſt together to effect the moſt luxuriant growth of vegetables. And after they have flowered, or on the year in which they are expected to flower, they ſhould be tranſplanted on a leſs nutritive ſoil, with leſs heat and moiſture. Or probably this leſs quantity of nutriment, heat, and moiſture, might be uſed at the commencement of their growth, or even at ſowing their ſeed, with ſimilar effect of ſooner breaking into variety of colours.

The beauty of the double yellow tulip, and its greater longevity, much recommend it to common eyes; but the endleſs variety in the colours of ſingle tulips has long and deſervedly been the admiration of floriſts. The curious event of their breaking into various colours from an uniform purple, a year or two after their firſt flowering, and at the ſame time of their loſing nearly one third of the height of their ſtems, ſeems to indicate, that this effect reſults not from the debility of age, but from the acquiſition of hereditary diſeaſes, as theſe new colours, into which they break, afterwards remain for uncounted generations, and may in this reſpect be compared to the canker in apple-trees, mentioned in Sect. XIV. 1. 3.

This change of colour from darker to lighter in tulips may probably be accelerated or increaſed by keeping the roots long out of the ground in dry or warm apartments, ſo as to harden their fibres, and diminiſh the diameters of their ſecreting veſſels, and thereby hindering their abſorption of colouring molecules, ſimilar to grey hairs produced on animals by age or external injury of the part. This would ſeem to obtain in tulips, as when they break into colours,

they loſe one third of their ſize, and conſequently the diameters of their ſecretory and of their abſorbent veſſels muſt be much diminiſhed.

New kinds of varieties in the ſituations or production of white parts of the petals of flowers might be cauſed, I ſuſpect, by compreſſing ſome parts of them before the flower opens, by tying fine threads round the calyx, which incloſes them; as many darker coloured cats and dogs have all thoſe parts lighter or quite white, which have been compreſſed together, as they lay in their fetus ſtate in the uterus; an inſtance of which exiſts in a black male cat, which now lies upon the hearth, and an inſtance of a black terrier bitch is deſcribed in Zoonomia, Vol. II. Claſs I. 2. 2. 11. This may be worth the attention of floriſts and flowerſellers; and it is probable, that the white ſtreaks in dark flowers may have been thus produced by their greater compreſſion in the calyx, before the flower opens.

3. The cauſes of duplicature in perennial flowers with branching roots, as ranunculus, caltha, hepatica, anemone, cheiranthus, dianthus, ſilene, wallflower, carnation, catchfly, are probably ſuch as afford a general luxuriancy of growth to thoſe vegetables, and may be certainly propagated by offsets from thoſe roots, or by laying their branches in the ground, ſo as to exactly reſemble their parents. Many of theſe double flowers may alſo be procured by collecting the ſeeds from ſuch ſingle flowers of the ſame ſpecies, as poſſeſs a ſupernumerary petal; which, if ſowed on fertile ground, will preſent us with double or multiplied flowers, as the anemone and july-flower mentioned in No. I. 1. of this Section.

The effect of breaking the ſingle ones into varieties of colour, which, in anemones and poppies as well as in tulips, are uncommonly beautiful, is probably owing to the leſs fertility of the ſoil, or leſs ſupply of heat and moiſture, where they have happened to reſide, and that more effectually if they were removed from more favourable ſituations.

The

The varieties of the ſingle flowers alſo of thoſe roots may be propagated unchanged, as well as the double ones, by dividing the roots or tranſplanting the offsets, or by laying their branches in the ground, as of pinks and carnations. Other varieties may be procured by collecting ſeeds and ſowing them in diſſimilar ſoils and ſituations; and ſuch flowers as are of approved beauty, may probably be occaſionally ſtrengthened and enlarged by depriving them in part of their offsets early in the ſeaſon; or may be broken into colours by keeping the roots ſome weeks or months out of the ground in the autumn in dry or warm apartments.

The colours of flowers of this kind, I believe, are frequently changed by ſituation; in my garden ſome roots of comfrey, ſymphytum, with purple flowers had long exiſted on a moiſtiſh border; and laſt year other roots, I ſuppoſe from the ſeeds of the former, grew in a dryer ſituation, and bore white flowers. And Mr. Bradley aſſerts, in his Philoſ. Account of Nature, p. 71, that ſome roots of purple hepatica, which were removed from Tothill-fields to Henley on the Thames, became white; and became purple again, when they were returned to their native ſituation.

IV. *Eſculent and Medicinal Flowers.*

1. The eſculent flowers moſt in uſe at our tables have their mucilage in ſome degree coagulated by boiling them in water or in ſteam, and are conſumed before their maturity, as thoſe of artichoke, cinara ſcolymus; of mercury, mercurialis; of ſea-cale, crambe maritima; and of brocoli and cauliflower, braſſica oleracea, italica and botrytis. The flowers of the naſturtion, tropeolum majus, poſſeſs an agreeable acrimony, and are eaten raw, ſhred with the freſh leaves of lettuce, young muſtard plants, or red cabbage. Other flowers are uſed for domeſtic or medicinal purpoſes, as thoſe

of hops, humulus lupulus, camomile, anthemis nobilis, roſes, cardamine, violets.

The three foremoſt of theſe, the artichoke, and mercury, and ſea-cale, are perennial plants; and, as they put forth numerous root-ſcions or offsets, may have their principal ſtem much invigorated, and will conſequently produce larger flowers, by taking away many of theſe offsets, ſo as to leave but two or three on a root. And as the ripening of the ſeed is no object, a greater abundance of moiſture, than theſe plants have been naturally accuſtomed to, with proportional increaſe of warmth in reſpect to ſituation, will forward their growth, and increaſe their ſize.

A great part of the nutritious mucilage in the artichoke is placed in the upper part of the ſtem, as well as in the pericarpium of the flower, which ſhould therefore be boiled along with it for the purpoſe of coagulation; and might then probably be managed ſo as to reſemble ſagoe, if granulated by paſſing it through ſieves.

The art of boiling vegetables of all kinds in ſteam inſtead of in water, might probably be managed to advantage, as a greater degree of heat might be thus given them, by contriving to increaſe the heat of the ſteam after it has left the water; and thus the vegetable mucilage in roots and ſeeds, as in potatoes and flour-puddings, as well as in their leaves, ſtems, and flower-cups, might be rendered probably more nutritive, and perhaps more palatable.

But many of the leaves of vegetables, as the ſummits of cabbage-ſprouts, loſe their green colour by being boiled in ſteam, and look like blanched vegetables. This etiolation of ſome vegetables by ſteam is probably owing to its diſſolving their colouring matter, which may then become decompoſed; and may render them leſs agreeable to thoſe who chooſe by the eye rather than by the palate; which green colour is however heightened by boiling them in ſome hard waters which contain diſſolved lime or ſea-ſalt, or by a ſlight admixture of common ſalt with ſoft water. An effect which

is

is owing to the evaporation of a part of the marine acid, and to the remaining alkali, which was the basis of it, when applied to bluish vegetables converting them into green, as in the common experiment of adding salt of tartar to syrup of violets; or, according to the custom of some cooks, who add a little potash, or fixed vegetable alkali, to the water, in which young peas are boiled to make them green, and afterwards a very little sugar to sweeten them.

The same effect of making vegetables green, when boiled in other kinds of hard waters, is probably produced by the lime, which abounds in them; and which like the vegetable alkali when the aerial acid, which was united with it evaporates, is said to convert bluish vegetable colours into green ones.

The nutritious mucilage resides likewise in the young stems of mercury, which should therefore be eaten before the flower begins to open. The stalks and immature flowers of sea-cale are similar to good brocoli, if eaten young; though many gardeners prefer the blanching them, which supplies an early and agreeable repast, described in Sect. XIV. 3. 3. Asparagus does not perhaps properly belong to this section, as the stem is eaten, before the flower becomes visible.

2. The cultivation of brocoli and cauliflower must be very similar, except as to the seasons of the year, as they are varieties of the same species of plant of the cabbage family. The following directions for the cultivation of brocoli were sent me by Edward Tighe, Esq. an ingenious gentleman of Ireland, along with an elegant Latin poem on the same subject, a free translation of which is placed at the end of this section.

"Brocoli may be so managed as to supply the table with a delicious and salutary vegetable during the months of November, December, January, February, March, April, and May.

1. Procure prime ſeed from Rome or Naples both for early and late ſowing.
2. Sow at the ceſſation of the vernal ſnows, and repeat it once a month till the end of May, or longer.
3. When three leaves appear, tranſplant them; and when ſix leaves appear, tranſplant them again. Afterwards in June, July, and Auguſt, tranſplant them two or three feet aſunder, to remain.
4. During September and October the ground muſt be looſened, and repeatedly cleared from weeds and ſtones; and the plants earthed up to preſerve their roots from the froſt, and to prevent their being injured by the equinoctial winds.
5. Water them occaſionally with water impregnated with dung.
6. Sow and plant them far from hedges, trees, and walls.

The head is generally completed in five or ſix days from its firſt appearance, and ſhould not remain much longer; the ſtalk ſhould be boiled with the flower, and peeled in the kitchen, before it is brought to the table."

Some kinds of Italian brocoli are ſaid to produce ſome knobs or bulbs at their roots, which are ſuppoſed to be for the purpoſe of raiſing other ſtems; if this laſt circumſtance be aſcertained, they ſhould be broken off, when the principal ſtem is tranſplanted; like the new root of orchis to enlarge the flower, mentioned in Section XV. 2. 4. But they may be ſimply a reſervoir of nutriment for the principal ſtem, as in carrots and turnips; in that caſe they ſhould certainly remain, and be tranſplanted along with the ſtem.

3. In reſpect to the flowers of hop, humulus lupulus; and chamomile, authemis nobilis; as well as thoſe of roſes, violets, cardamine, and the naſturtion above mentioned; as their petals only are required, it would add much to their quality, if they could be cultivated in their double or multiplied ſtate, as is generally indeed

practiſed

practiſed in reſpect to roſes and chamomile; many acres of the latter of which are cultivated near Cheſterfield in Derbyſhire, and are ſold, I am informed, to mix with hops, when thoſe crops are deficient, as well as for the purpoſes of medicine. What might be the effect of endeavouring to introduce a duplicature or multiplication of the flowers of artichoke, ſea-cale, cauliflower, and brocoli, has not, I believe, been experienced.

V. *Flowers uſed in the Arts.*

1. The beautiful membrane, which covers the ſeeds of euonymus, or ſpindle-tree, and of the bixa of South America, is ſaid to be manufactured into the anotta, or arnotta, uſed in colouring cheeſe; but I am told that madder, made from the root of rubia tinctoria, is ſold frequently in its ſtead, and may be readily grown by farmers in their own gardens. Few flowers are uſed in the art of dying, their colours are ſo fugitive, as they readily bleach when expoſed to the light, and cannot be kept long even in the herbariums of botaniſts without loſing their colours; which is believed to be owing to the oxygen of the atmoſphere being ſeparated from the aerial water by the ſun's light, and converted into a gas combined only with heat or light, and in that ſtate more readily uniting with the colouring matter of flowers, and producing a new acid, which is tranſparent, colourleſs, or white, or is diſſolved and waſhed away by the dews or rains.

The blue colour of the flowers of violets has been extracted by water, and preſerved by the addition of ſugar converting it into ſyrup for the purpoſes of medicine in part, but chiefly for thoſe of chemiſtry, to ſhew the change of vegetable blues into greens by an admixture of fixed alkali, as ſalt of tartar or potaſh; and into red

by the admixture of an acid, as thoſe of ſulphur, nitre, or marine ſalt.

2. Another very important flower, which is ſuffered to grow to maturity for the purpoſe of uſing the fine fibres which wing or invelope its ſeeds, is that of the cotton plant, goſſypium; which, as it requires ſo much leſs preparation than the fibres of the ſtems of flax and of hemp or nettles, is likely to become the principal clothing of mankind; and eſpecially ſince the art of ſpinning it was brought to ſuch wonderful perfection by the genius of Sir Richard Arkwright, who diſcovered that two ſets of rollers moving with different velocities would draw out the fibres of cotton into a fine thread more accurately than could be done by the human hand, as well as more expeditiouſly, along with much other very ingenious machinery.

There are two bog or water plants in our moraſſes, which produce much vegetable fibres attached to their ſeeds, one of theſe is the typha, or cat's-tail; and the other eriophorum, or cotton-ruſh. The fibres of the former are ſhort and coarſe, but might ſerve perhaps to ſtuff cuſhions, or even coarſe beds; thoſe of the latter are longer, and perhaps fine enough to ſpin. And as both theſe only grow on bogs or in water, where we at preſent cultivate no uſeful vegetables, one, or both of them, might poſſibly be worthy the attention of thoſe, who poſſeſs aquatic or marſhy ſituations. The cultivation of the cotton plant belongs to warmer climates, and may probably require abundant water for its vigorous growth, as well as the typha and eriophorum of this country.

VI. *Nutritious parts of Vegetables.*

1. Having treated of the cultivation of fruits, ſeeds, roots, barks, leaves, woods, and flowers, an important queſtion preſents itſelf; which

which of them may ſupply the moſt nutrition to mankind, or to other animals?

It may be anſwered firſt, that thoſe vegetables, or parts of vegetables, which approach neareſt to the nature of animal bodies, are moſt likely to ſupply them with the moſt nutriment; as the eſculent muſhrooms, and the gluten of wheat, and the oils of ſeeds and kernels. The former claſs of plants ſeems to connect the animal and vegetable kingdoms of nature, as ſpoken of in Sect. XVII. 2. 5. and though many of them poſſeſs an acrid, and ſome of them an intoxicating quality, it is probable that the former might be deſtroyed, and the latter diminiſhed, by the heat employed in cookery. This ſhould nevertheleſs be attempted with due caution; ſince, though one kind of vegetable acrimony, as that of water-creſſes and of cabbages, is much diminiſhed or deſtroyed by a boiling heat, yet that of the leaves of arum maculatum, and of arum ariſarum, I found by experiment, was not decreaſed by boiling. And a few grains of the powder of lycoperdon, puff-ball, have lately been recommended in epileptic fits, and may thence poſſibly poſſeſs a powerful narcotic quality. The gluten of wheat is ſuppoſed to approach towards the coagulable lymph of animal bodies, as referred to in Sect. XVI. 7. 1. and was once, I believe, advertiſed as an alimentary powder, and recommended as a nouriſhment of the moſt portable kind for the ſuſtenance of marching armies. And laſtly the oils of vegetables approach much to a ſimilitude with thoſe of animal bodies.

2. Secondly, it may be anſwered, that ſince the chyle of all red-blooded animals is believed to be nearly ſimilar, and to conſiſt principally of ſugar, mucilage, and oil; the laſt of which ingredients renders it white by its inſolubility in water, and thence diſtinguiſhes it from the vegetable chyle or ſap-juice of trees, which is tranſparent, and is believed to conſiſt principally of ſugar and mucilage without oil; thoſe parts of vegetables which contain the greateſt quantity of

theſe ingredients which compoſe animal chyle, or are convertible into them by the power of digeſtion, may be ſuppoſed to contain the moſt nutriment for red-blooded animals.

To this may be added, that the nutritive quality of ſugar is inconteſtably evinced from the known fact, that the ſlaves in the ſugar iſlands become in better condition during the ſugar ſeaſon, though they are compelled to labour harder. The nutritive quality of ſimple mucilage was ſhewn in a remarkable inſtance on record; where a caravan by ſome misfortune had conſumed or loſt all their other proviſions, and lived many weeks on the gum arabic alone, which conſtituted their principal merchandiſe. The nutritive quality of oil is obſervable in the proceſs of feeding cattle with oil-cake, and in the habits of the natives of the northern latitudes, who uſe the oil of fiſh for both meat and drink, and derive from it their principal nouriſhment.

Sugar is known to be the ſame, from whatever vegetable it is extracted, whether from the fruit of the vine or apple-tree, from the joints of the ſugar-cane, from the ſap-veſſels of the maple, from the alburnum of the manna aſh, from the ſeeds of germinated barley and rice, from the roots of beets, carrots, and potatoes, or, laſtly, from the nectaries of flowers. The expreſſed oils of vegetables are alſo believed not much to differ from each other in reſpect to the nutriment they contain, though ſome of them may approach nearer to the nature of animal fat; as the painters diſtinguiſh them by their greater aptitude to dry, when mixed with their colours and expoſed to the air. But the word mucilage has been uſed for ſtarch, which will not diſſolve in cold water, as well as for gum arabic, and other mucilages properly ſo called, which will diſſolve in cold water, and even for the gluten of wheat, which will not diſſolve in either hot or cold water. We may therefore conclude, that thoſe parts of vegetables, which contain the moſt of theſe materials, are the moſt nutritive,

nutritive, if they do not contain along with them ſome noxious materials united with their ſalutary ones, and which cannot be readily ſeparated from them.

3. Though the parts of vegetables, which poſſeſs much oil, ſugar, or mucilage, may afford more expeditious nutrition, as they conſtitute the ingredients of the chyle of all red-blooded animals; yet there are other materials, which appear to be ſo readily convertible into ſugar or into mucilage, as perhaps nearly to ſupply an equal quantity of nutriment. Thus by the proceſs of germination, as when ſeeds of barley are converted into malt, and when roots pullulate in our ſtore-rooms, as of onions or potatoes; the farina, conſiſting of meal or ſtarch, is in part converted into ſugar, and in part into mucilage; ſimilar to this proceſs of germination appears to be that of ripening, by which the auſtere juices of fruits are tranſmuted into ſweet ones; and alſo the culinary proceſſes of baking or boiling, by which the auſtere juices of unripe pears are changed into ſweet ones by the application of heat, as mentioned in Sect. VI. 5. But another more expeditious converſion of vegetable materials into ſugar is by the digeſtion of animals, which may be truly termed a ſaccharine proceſs; as appears in thoſe, who labour under diabates, as by evaporating the urine of one of theſe patients, ſixteen ounces of impure ſugar were daily extracted for ſome time. Zoonomia, Vol. I. Sect. XXIX. 4.

Hence, though the oily kernels of nuts, walnuts, almonds, and the oily ſeeds of flax, hemp, rape, may contain moſt expeditious nutriment; and next to theſe the ſaccharine fruits of figs, dates, raiſins, and the ſweet roots of beet, mungel-worſal, ground artichoke, helianthus tuberoſus, parſnip, carrot, may contain expeditious nutriment. Yet the more farinaceous ſeeds, as of wheat, peas, rice, barley, oats, and buck-wheat, polygonum fagopyrum, and the roots of potatoes, which contain ſtarch, and flour, and mucilage, which are convertible into ſugar in the ſtomachs of animals, and are pro-

bably by that digeſtive proceſs, and their previous maſtication in the mouth, mingled with more animal coagulable lymph, as the ſaliva, gaſtric, and pancreatic juices, and may thus ſupply a more animalized nutriment than the former; and may on that account contribute more to ſtrengthen the ſyſtem. Of theſe ſeeds and roots it appears probable, that thoſe, which contain the moſt ſtarch or gluten, as wheat, afford the moſt nouriſhment, as they are believed to make the beſt bread.

4. The alburnum, or ſap-wood, of moſt trees in the winter months probably contains much nutritious matter; whence it is ſo ſoon deſtroyed by fermentation or putrefaction when deprived of life; and by inſects, when it is deprived of its protecting bark. This nutritious matter might be obtained by grating, or raſping, or pounding it, and boiling the powder or ſaw-duſt thus procured. The bark of all thoſe vegetables, which are armed with thorns or prickles, is believed to contain much nutritious matter, which their armour was deſigned to protect; as the inner barks of elm, holly, gooſeberry, whin or gorſe, contain much nutritive mucilage; thus the deer in Needwood Foreſt greedily peel the bark from the branches of holly, which are cut from the ſummits of thoſe trees, where they have no prickles, as mentioned in Botanic Garden, Vol. II. note on Ilex. And horſes are ſaid to be well nouriſhed by gorſe, if the prickles are previouſly deſtroyed by rolling a ſtone over it, as the tanners bruiſe their oak-bark; and ſome horſes are ſaid to be ſo fond of it, and ſo wiſe, as to bruiſe young gorſe-buſhes with their feet, and then to eat them.

Fern roots are ſaid to be eaten by the natives of New Holland, and in other countries in times of ſcarcity; but as their farinaceous or mucilaginous matter is included in ligneous fibres too hard for maſtication, the method of cooking it is ſaid to conſiſt in boiling the root, and then extracting the fibres by hammering it to pieces. The root of white bryony, which grows to a great ſize in our hedge-bottoms,

toms, is ſaid, by M. Permentier, to poſſeſs a quantity of ſtarch, which was capable of being waſhed from the acrid mucilage by grating it into cold water, and of being manufactured into an agreeable and ſalutary bread; like the bread made from the caſſava, which is ſaid to undergo a ſimilar proceſs, by expreſſing ſome of the acrimonious mucilage previous to the application of the heat of cookery. Which however not only deſtroys the acrimony of many vegetables, as of water-creſſes, cabbages, and the ſkins of potatoes, but is alſo believed to render ſome of them more nutritive by coagulating their mucilage, which was previouſly combined with too great a proportion of water.

5. It would appear therefore in general, that the ſeeds or kernels of vegetables afford the moſt nutriment; next to theſe their fruits and roots; and afterwards the alburnum or bark. Some of the flowers alſo in their early ſtate before impregnation, as thoſe of artichoke, cinara, and cauliflower, braſſica, are nutritious from the mucilage, which they poſſeſs; and ſome ſeeds already impregnated, but ſtill in their immature ſtate, along with their huſks or capſules, as thoſe of kidney-bean, phaſeolus, and of very young peas, afford a ſalutary nutriment. And laſtly all flowers after the expanſion of their corols ſecrete honey; which ſupplies food to innumerable inſects, who plunder it, as well as to mankind. In the baſes of many leaves another ſaccharine or mucilaginous juice is ſecreted, as at the joints of graſs, on the bulbs of onions, and at the lower parts of the leaves of cabbages, and around the ſtems of aſparagus, mercury, and hop-buds, during the early ſtate of their flowers; but the leaves themſelves, like the lungs of animals, ſeem to poſſeſs leſs nutritious aliment than many other parts of their ſyſtem.

VII. *The Happineſs of Organic Life.*

All organized nature may be divided into ſtationary organizations, and locomotive organizations; the former of which are called vegetables, and the latter animals. All thoſe parts of vegetables, which are moſt nutritious to animals, conſiſt, as obſerved above, of aliment ſecreted from the vegetable blood, and laid up in reſervoirs for the future ſuſtenance of their embryon or infant progeny; which reſervoirs are plundered by locomotive animals, and devoured along with the progeny, they were deſigned to ſupport! add to this, that the ſtronger locomotive animals devour the weaker ones without mercy. Such is the condition of organic nature! whoſe firſt law might be expreſſed in the words, "Eat or be eaten!" and which would ſeem to be one great ſlaughter-houſe, one univerſal ſcene of rapacity and injuſtice!

1. Where ſhall we find a benevolent idea to conſole us amid ſo much apparent miſery?—I hope the ſympathizing reader will not think the following account of the happineſs, which organized beings acquire from irritation only, impertinently inſerted in this place; their happineſs derived from imagination and volition may be treated of in ſome future work.

It may firſt be obſerved, that the ſeeds of plants and the eggs of animals, when they have left the pericarp or uterus, and have not yet commenced their new growth upon the ſoil, or beneath the wings of the mother, exiſt in a torpid ſtate, not poſſeſſed of ſenſitive life; and cannot therefore at this time be ſuppoſed to ſuffer pain, when they are deſtroyed by other animals; though thoſe animals obtain pleaſure from the activity, into which their vaſcular ſyſtems are excited by the ſtimulus of the aliment thus ſupplied.

Secondly, that the young of lacteſcent animals both acquire and communicate pleaſure to the enamoured mother, from whom they receive

receive their nutriment, as mentioned in Botanic Garden, Vol. I. Canto I. l. 278, note; which conſtitutes the moſt beautiful and moſt benevolent part of the great ſyſtem of nature.

Thirdly, all animals, and, I ſuppoſe, vegetables, receive pleaſure in the reproduction of their ſpecies; and where ſeeds are diſperſed on the ſoil, and the eggs of ſome animals and of many inſects are buried beneath it, to be revived and hatched by the warmth of the ſun; there can be no pain in theſe caſes inflicted on the mother, when they are deſtroyed by animals or by inſects, as ſhe is unconſcious of their deſtruction.

Fourthly, as all animal exiſtence muſt periſh in proceſs of time, by the inirritability and conſequent debility occaſioned by the repetition of ſtimulus, which is termed habit, and appears to be an univerſal law of nature: it is ſo ordered, that as ſoon as any organized being becomes leſs irritable and leſs ſenſible, and in conſequence feeble or ſickly, that it is deſtroyed and eaten by other more irritable and more ſenſible, and in conſequence more vigorous organized beings; as inſects attack the weaker vegetable productions in preference to the healthy ones; and beaſts of prey more eaſily catch and conquer the aged and infirm, and the young ones are defended by their parents. By this contrivance more pleaſureable ſenſation exiſts in the world, as the organized matter is taken from a ſtate of leſs irritability and leſs ſenſibility, and converted into a ſtate of greater; that is in other words, that the old organizations, whether ſtationary or locomotive ones, are tranſmigrated into young ones: whence it happened, that before mankind introduced rational ſociety, and conquered the ſavage world, old age was unknown on earth!

Finally, the aged and infirm, from their preſent ſtate of inirritability and inſenſibility, loſe their lives with leſs pain, and which ceaſes inſtantly with the ſtroke of death; inſomuch that death cannot ſo properly be called poſitive evil, as the termination of good.

To

To this ſhould be added, that a long continued or a great exceſs of pain cannot afflict an organized being; as ſyncope or ſudden death, and conſequent decompoſition, attends very violent pains; and a lingering death attends the continuation of leſs violent ones. Hence it becomes a conſoling circumſtance, that miſery is not immortal.

A philoſopher, whom I left in my library, has peruſed the above paragraphs, and added the ſubſequent one to my manuſcript. "It conſoles me to find, as I contemplate with you the whole of organized nature, that it is not in the power of any one perſonage, whether ſtateſman or hero, to produce by his ill-employed activity ſo much miſery, as might have been ſuppoſed. Thus, if a Ruſſian army, in theſe inſane times, after having endured a laborious march of many hundred miles, is deſtroyed by a French army in defence of their republic, what has happened? Forty thouſand human creatures dragged from their homes and their connexions ceaſe to exiſt, and have manured the earth; but the quantity of organized matter, of which they were compoſed, preſently revives in the forms of millions of microſcopic animals, vegetables, and inſects, and afterwards of quadrupeds and men; the ſum of whoſe happineſs is perhaps much greater than that of the haraſſed ſoldiers, by whoſe deſtruction they have gained their exiſtence!—Is not this a conſoling idea to a mind of univerſal ſympathy?

"I well remember to have heard an ingenious agricultor boaſt, that he had drained two hundred acres of moraſſy land, on which he now was able to feed a hundred oxen; and added, 'is not that a meritorious thing?' 'True,' replied one of the company, 'but you forget, that you have deſtroyed a thouſand free republics of ants, and ten thouſand rational frogs, beſides innumerable aquatic inſects, and aquatic vegetables.'

"Having written the above, I fear you may think me a miſanthrope, but I aſſure you a contrary ſenſation dwells in my boſom;

and though I commiſerate the evils of all organic being, Homo ſum, humani nihil a me alienum puto."

2. The vaſcular ſyſtems of animal bodies are excited into action by the ſtimulus of the fluids, which they abſorb, circulate, and ſecrete; and when this action is exerted in its natural or moſt uſual quantity, it is attended with agreeable ſenſation, which conſtitutes the pleaſure of organized exiſtence. Theſe vaſcular actions of animals, which perform digeſtion, ſanguification, and ſecretion, convert the aliment, after its ſolution in the ſtomach, into more compounded and more ſolid materials; as into muſcles, membranes, nerves, bones, and ſhells; at the ſame time that pleaſurable ſenſation attends this activity of the ſyſtem. The vaſcular actions of vegetables, which perform their digeſtion, ſanguification, and ſecretion, convert the elements of air and water, or other aliments, which they receive from organized matter decompoſing beneath the ſoil, into more compounded or more ſolid materials, as into vegetable veſſels, muſcles, membranes, nerves, and ligneous fibres; and a degree of pleaſureable ſenſation muſt be ſuppoſed from the ſtrongeſt analogy to attend this activity of their ſyſtems.

3. Many of the materials, which have been thus produced by the digeſtion and ſecretion of organized beings, and have given pleaſure in their production, have been ſlow in their decompoſition after the death of the creature; as the ſhells of fiſh were originally thus formed, and were left at the bottom of the ocean, till they became wonderfully accumulated, were afterwards elevated by ſubmarine fires, and conſtitute at this day the immenſe rocks and unmeaſured ſtrata of limeſtone, chalk, and marble. As mentioned in Sect. X. 10. 1.

The ſtrata, which are incumbent on the calcareous ones, which conſiſt of coals, ſand, iron, clay, and marl, are all of them believed to have been originally the products chiefly of vegetable organization; whatever changes they have ſince undergone in the long progreſs

progreſs of their decompoſition, and that all thoſe ſolid parts of the earth have been thus fabricated from their ſimpler elements by vegetable and by animal life, and have given pleaſure to thoſe organized beings, which formed them, at the time of their production.

We hence acquire this ſublime and intereſting idea; that all the calcareous mountains in the world, and all the ſtrata of clay, coal, marl, ſand, and iron, which are incumbent on them, are MONUMENTS OF THE PAST FELICITY OF ORGANIZED NATURE!—AND CONSEQUENTLY OF THE BENEVOLENCE OF THE DEITY!

VIII. *The Cultivation of Brocoli.*

Tranſlated in part from an elegant Latin poem of Edward Tighe, Eſq.

THERE are of learned taſte, who ſtill prefer
Cos-lettuce, tarragon, and cucumber;
There are, who ſtill with equal praiſes yoke
Young peas, aſparagus, and artichoke;
Beaux there are ſtill with lamb and ſpinach nurs'd,
And clowns eat beans and bacon, till they burſt.
This boon I aſk of Fate, where'er I dine,
O, be the Proteus-form of cabbage mine!—
Cale, colewort, cauliflower, or ſoft and clear
If BROCOLI delight thy nicer ear,
Give, rural Muſe! the culture and the name
In verſe immortal to the rolls of Fame.
When the bright Bull aſcending firſt adorns
The Spring's fair forehead with his golden horns;

When the bright Bull, 19th of April.

Italian

Italian ſeeds with parſimonious hand
The watchful Gardener ſcatters o'er his land;
Quick moves the rake, with iron teeth divides
The yielding glebe, the living treaſure hides;
O'er the ſmooth ſoil, with horrent thorns beſet,
Swells in the breeze the undulating net;
Bright ſhells and feathers dance on twiſting ſtrings,
And the ſcar'd Finch retreats on rapid wings.
Next when the Twins their lucid forms diſplay,
And hand in hand ſalute the lord of day;
When climbs the Crab the blue ethereal plain,
Or ſhakes the Lion his refulgent mane;
Each paſſing month renew the grateful toil,
Upturn with ſhining blade the fertile ſoil;
New ſeeds inſert, whoſe vegetable birth
May riſe ſucceſſive from the womb of earth.
So ſhall hibernal hours on frozen wing
View the green products of the breezy ſpring;
Admiring nymphs the genial banquet ſhare,
Smile on thy labours, and reward thy care.
But when three leaves the young Aſpirer ſhoots,
To other ſoils tranſplant the ſhorten'd roots;
Where no tall branches form a vaulted glade,
Nor ivy'd tower projects a length of ſhade;
There in wide ranks thy verdant realms divide,
Parting each opening file a martial ſtride.
There with charm'd words of ſome poetic ſpell
Call the blue Naiads from their ſecret cell;
From ſilver urns in lucid circles pour
Round each weak ſtem the ſalutary ſhower.
Pants thy young heart to graſp the laurel'd prize,
And ſwell thy Brocoli to gigantic ſize?—

The Twins, 20th of May. *The Crab*, 20th of June.
The Lion, 22d of July.

Soon as each head with youthful grace receives
The verdant curls of ſix unfolding leaves;
O, ſtill tranſplant them on each drizzly morn,
Oft as the moon relights her waining horn;
Till her bright veſt the ſtar-clad Virgin trails,
Or corn-crown'd Autumn lifts his golden ſcales.
Then ply the ſhining hoe with artful toil,
Ere the grey night-froſt binds the ſtiffen'd ſoil;
And, as o'er heaven the riſing Scorpion crawls,
Surround the ſhuddering ſtems with earthen walls.
So ſhall each plant erect its leafy form,
Unſhook by Autumn's equinoxial ſtorm;
And round and ſmooth, with ſilvery veins emboſs'd,
Repel the dew-drops, and evade the froſt.
Thus on the Stoic's round and poliſh'd brows
Her venom'd ſhafts in vain misfortune throws;
By virtue arm'd, he braves the tented field,
The innocuous arrows tinkling on his ſhield.
Hence when aſcendant rules the watery Star,
Or the celeſtial Fiſhes ſwim in air,
Thy guarded ſtalks ſhall lift their curled heads,
And fringed foliage ſhade thy ample beds,
Gem with bright emerald Winter's trackleſs ſnows,
Or bind with leafy wreaths his icy brows.
When leads the Spring amid her budding groves
The laughing graces, and the quiver'd loves;
Again the Bull ſhall ſhake his radiant hair
O'er the rich product of his early care;

The ſtar-clad Virgin, 22d of Auguſt. *Golden ſcales*, 22d of September.

Scorpion, 22d of October. *Evade the froſt.* One advantage, which vegetables receive by repelling the water by the upper ſurfaces of their leaves, is, that it may not incommode their reſpiration; but another is, that by not being thus moiſtened they are leſs injured by froſt.

Watery Star, 19th January. *Celeſtial Fiſhes*, 17th February. *The Bull*, 19th April.

With

With hanging lip and longing eye ſhall move,
And Envy dwell in yon blue fields above.—
Oft in each month, poetic Tighe! be thine
To diſh green Brocoli with ſavory chine;
Oft down thy tuneful throat be thine to cram
The ſnow-white cauliflower with fowl and ham!—
——Nor envy thou, with ſuch rich viands bleſt,
The pye of Perigord, or Swallow's neſt.

The pye of Perigord was made of the red-legged partridges before the French revolution; and was ſold in London at the price of a guinea for each bird it contained.

Swallow's neſt. There is a ſpecies of ſwallow, that builds a neſt on the banks of the Nile and Ganges, which conſiſts of iſinglaſs; which the bird collects from putrid fiſh left on the ſands; and which is eſteemed a great delicacy, and enters the moſt coſtly ſoups at the luxurious tables of the eaſt.

SECT. XX.

PLAN FOR DISPOSING PART OF THE VEGETABLE SYSTEM OF LINNEUS INTO MORE NATURAL CLASSES AND ORDERS.

I. *The claſſes of plants diſtinguiſhed by the proportion or ſituation of the ſtamina are more natural than thoſe diſtinguiſhed by their numbers. Many Linnean claſſes thus diſtinguiſhed. Many of the orders are natural claſſifications. Uſe of natural claſſes.* 2. *The ſituation and proportion of the ſexual organs are leſs liable to variation than their numbers. Great variation in reſpect to number of the ſtamina. From luxuriant growth. Some ſpecies have but half the number. Others have part of them without anthers. The number of piſtilla varies in different ſpecies of the ſame genus. Progreſs of nature to greater perfection. Of the claſs Syngeneſia.* 3. *Immutable parts diſcovered by reaſoning as well as by obſervation. Filaments of Meadia unchangeable, and of hemerocalis fulva, nigella, collinſonia, ſpartium.* 4. *Some natural orders might become claſſes. As the graſſes, and the umbellatæ, and ſtellatæ. Forms of the filaments, and of the anthers, as well as their ſituations, leſs variable than their numbers.* 5. *Claſſic characters. From ſhort and long filaments. From their unequal heights. From their different inſertions. From their reſpective ſituations. From their adheſions to each other. Or to the corol, or ſtyle. From their exiſtence in different flowers. From the connexion of the anthers, or from the forms of the filaments and anthers.* 6. *Uncertainty of the number of piſtilla. Their proportions and figures leſs variable. And would define more natural orders.* 7. *Characters of orders from the length of the ſtyle. The curvature of it. The attitudes of it. Diviſions of the ſtigma. Abſence of the ſtigma. Adheſions of the ſtyle.* 8. *Concluſion.*

I. OFTEN as I have admired the claſſification of vegetables by the great Linneus deduced from their ſexual organs of reproduction, ſome

ſome of the claſſes have appeared to me to be more excellent than others, as they ſeemed to approach nearer to natural ones. On further attention to this ſubject, I perceived that thoſe claſſes, which were deduced from the proportions or ſituations of the ſtamina, or which included the number of the ſtamina along with their proportions and ſituations, were more natural claſſes than thoſe, which were diſtinguiſhed ſimply by the number of them.

Thus the claſſes termed Dydynamia and Tetradynamia, which are derived from the proportions and ſituations of the ſtamina as well as their number, are wonderfully natural; to which may be added the claſſes Icoſandria, and Polyandria, as their diagnoſtic character conſiſts in the ſituation of the ſtamina on the calyx or petals in the former claſs, and on the receptacle in the latter, though the names of theſe claſſes are not ſo happy, as they ſimply refer to their numbers, which are unfortunately very variable.

Some other of the Linnean claſſes are diſtinguiſhed by the ſituation of the filaments, as the Monadelphia, Diadelphia, Polyadelphia, and Gynandria; all which approach towards natural claſſes; and the Syngeneſia, which is diſtinguiſhed by the adheſion of the anthers, is a claſs beautifully natural, except the laſt order.

Many of the orders alſo in the ſexual ſyſtem are natural claſſifications, as the graſſes in the claſs Triandria, the umbellated plants in the claſs Pentandria, and perhaps the cruciform plants in the claſs Tetandria; with many amongſt thoſe which are termed natural orders at the end of the Genera Plantarum; all which might probably be diſcriminated by ſome ſituation, or proportion, or form, of their reſpective ſtamina.

As the claſſes deduced from the proportions or ſituations of the ſtamina alone, or conjointly with their reſpective number, appear thus to produce more natural diſtributions of vegetables, than thoſe derived ſimply from their number; it might have been more fortunate for the ſcience of Botany, if the great author of the ſexual

ſyſtem

ſyſtem had turned his mind to have claſſed all of them from the proportions, ſituations, and forms of the ſtamina alone, or from theſe conjointly with their number, and to have diſtinguiſhed the orders according to the proportions, ſituations, or forms of the piſtilla alone, or conjointly with their numbers.

The great uſe of diſtributing plants into natural claſſes is not only for the purpoſe of more readily diſtinguiſhing them from each other, and diſcovering their names, but alſo for that of more readily detecting the virtues or uſes of them in diet, medicine, or the arts; as for the purpoſes of dying, tanning, architecture, ſhip-building; which has already been happily experienced in attending to the genera or families of plants, which are all natural diſtributions of them, whence the ſame virtues or qualities generally exiſt among all the ſpecies of the ſame genus, though perhaps in different degrees.

2. But another great advantage would probably occur from deducing the characters of the claſſes of vegetables from the ſituations, proportions, or forms of the ſexual organs rather than from their number; which is, that theſe criterions of the claſſes and orders would be much leſs ſubject to variation.

The variation of the number of ſtamina not only frequently occurs from the too luxuriant growth of many cultivated flowers, or by the duplicature or multiplication of their petals, or nectaries, which is liable much to inconvenience the young botaniſt; but ſeveral of the ſpecies of plants have but half the number of ſtamina, which other ſpecies of the ſame genus poſſeſs. This occurs ſo frequently, that the defect of number is expreſſed as an eſſential character of the ſpecies in many inſtances. Thus the ceraſtium pentandrum, and ſpergula pentranda, diſtinguiſh thoſe ſpecies from the other plants of the genus, which poſſeſs ten ſtamens; ſo tamarix floribus pentandris, tamarix floribus decandris, ſalix floribus diandris, ſalix triandra, ſalix pentandra, valeriana floribus monandris, valeriana floribus diandris, verbena diandra.

So the vernal flowers of the corchorus ſiliquoſus have but four ſtamina, but the autumnal ones have numerous ſtamina. The linum flax of this country has but five perfect ſtamina, and five without anthers on their ſummits; whereas the linum luſitanicum, Portugal flax, poſſeſſes ten complete ones. The verbena, vervain, of our country has four ſtamina, that of Sweden but two; the genus albuca, bignonia catalpa, gratiola, and hemlock-leaved geranium, have only half their filaments crowned with anthers; all which and many others evince the uncertainty of depending on numbers alone for diſtinguiſhing the claſſes of plants.

Nor are the number of piſtilla more certain as a criterion of the orders. Thus there is nigella pentagyna, and nigella decagyna; hypericum floribus pentagynis, trigynis, and digynis, with innumerable other ſimilar inſtances, as mentioned in No. 6 of this Section. Which evince, that great confuſion muſt be occaſioned by a reliance ſimply on the number of the piſtilla for defining the orders of plants.

I contend, that the number of the ſexual organs in flowers is more liable to change by the influence of ſoil or climate, or by the progreſs of time, than their ſituations or proportions, or forms, and might therefore probably be more advantageouſly employed in diſtinguiſhing their claſſes and orders from each other, as well as in rendering them more natural combinations.

This mutability or uncertainty of the number of the organs of reproduction belonging to individual flowers, would ſeem to ariſe from an attempt of all organized beings towards greater perfection. Whence as the ſucceſs of the proceſs of reproduction becomes more certain from the greater perfection of the vegetable being, the organs for the purpoſe of reproduction ſeem to become fewer. Whence ſome flowers have loſt half the ſtamina, and in others the anthers of thoſe ſtamina are yet only deficient, and in others the piſtilla are deficient; all which in proceſs of time may gradually become leſs numerous,

numerous, or ſeparate themſelves from hermaphrodite flowers into ſexual ones, as in the claſſes of monœcia and dicœcia; and all of them finally, after a long proceſs of ages, become of the orders monandria and monogynia of thoſe claſſes; whilſt new kinds of vegetables may begin a ſimilar progreſs from leſs to greater perfection. So in animals, the leſs perfect ſeem to poſſeſs organs for a more numerous reproduction, as fiſh and inſects. Such would ſeem to be the perpetual progreſs of all organized being from leſs to greater perfection exiſting from the beginning of time to the end of it! a power impreſſed on nature by the great Father of all.

Thus in the claſs ſyngeneſia, the tendency of theſe vegetables from more numerous to a more ſimple organization for the purpoſe of reproduction is wonderfully conſpicuous. In the order polygamia æqualis, all the florets are furniſhed with male and female organs. In the order polygamia ſuperflua, the florets in the centre have both male and female organs, thoſe in the circumference have only female ones; and of thoſe ſome have loſt the corol of the floret. In the order polygamia fruſtranea the florets in the centre poſſeſs both male and female organs, but thoſe in the circumference have neither; though at the ſame time the corols of thoſe florets remain. And laſtly, in the order polygamia neceſſaria the central florets are ſimply male florets, and thoſe in the circumference ſimply female ones; and thus approach to the claſs of monœcia, having the male and female organs in ſeparate florets; and may in proceſs of time exiſt in ſeparate flowers, and afterwards in ſeparate plants, like the two ſexes of the more perfect animals. Something ſimilar to this ſeems already to have occurred in the plant phytolacca, of the claſs decandria decagynia; which poſſeſſes one ſpecies with twenty males, another with ten, another with only eight males and eight females, and laſtly one of the claſs dicœcia, or two houſes.

3. In many flowers ſome circumſtances of the ſituations or proportions or forms of the filaments or anthers may be ſhewn, by *reaſoning*

ſoning as well as by obſervation, to be leſs mutable than others; as the ſhortneſs of the filaments of dodecatheon meadia, cyclamen, ſolanum, borago, fuſchia, and others. As mentioned in Botanic Garden, Vol. II. note on Meadia. Thus in the flower of meadia the filaments are exceedingly ſhort compared to the ſtyle, and ſeem to have been in that circumſtance immutable. Whence it became neceſſary, firſt to furniſh them with long anthers, which ſtand pointed towards the diſtant ſtigma apparently endeavouring to reach it. Secondly, it was neceſſary to bend the flower-ſtalks, when the corols open into thoſe graceful curves, which conſtitute the uncommon beauty both of this flower and of the fuſchia; that the ſtigma by hanging down immediately beneath the anthers might thus receive, as it falls, the prolific farina. And that this was the evident deſign of the curvature of the flower-ſtalk appears from its riſing again, and becoming quite erect, as ſoon as the impregnation of the pericarp is accompliſhed. Thirdly, as the flower thus becomes perpendicularly pendent, it was neceſſary to reflect the petals for the purpoſe of admitting light and air to the ſexual organs.

We may reaſon from this ſtructure of the meadia, that all this apparatus of long erect anthers to approach the ſtigma; of bending the flower-ſtalk, that the ſexual organs might become pendulous; and then of reflecting the petals to give light and air; might have all been ſpared, if the filaments alone could have grown as long as the ſtyle; as occurs in moſt other flowers. And that therefore in theſe flowers the filaments are the moſt unchangeable parts of them; and that hence the comparative length of the filaments in reſpect to the ſtyle would afford the moſt immutable mark of their eſſential character, or for the purpoſe of claſſification.

Another apparent inſtance of the great unchangeableneſs of the length of the filaments exiſts in the hemerocallis fulva, tawny daylily, in which I obſerve the ſtyle is crooked, or bent into a zigzag, about the middle of it, evidently for the purpoſe of ſhortening it,

that the anthers might approach the ſtigma; the ſtalk of the flower not being ſo flexible as to allow it to become pendent, as in the hemerocallis flava, or yellow day-lily.

In nigella, devil in the buſh, the ſtyles are very long compared with the filaments, and bending down their ſtigmas over the anthers in curves, give the flower a reſemblance to a regal crown; which need not to have occurred, if the filaments could more eaſily have been lengthened.

In collinſonia the two anthers ſtand widely diverging on ſhort filaments, and the tall capillary ſtyle bends its ſtigma into contact firſt with one of them, and afterwards with the other. In the ſpartium ſcoparium, common broom, the long ſtyle bends round into a circle to accommodate the ſtigma to the ſhort ſet of anthers, which great curvature need not have exiſted, if the filaments could more eaſily have grown longer. Other inſtances of ſimilar ſtructure are related in Sect. VII. 2. 2. of this work.

It is probable, that ſimilar obſervations, and a conſequent reaſoning on them, might be applied to many other kinds of flowers ſo as to detect the moſt unchangeable parts of them: but great time, labour, opportunity, and ingenuity, would be required to eſtabliſh from them the moſt invariable and moſt natural claſſes of vegetation.

4. Many different proportions and ſituations and forms of the filaments are enumerated in the Philoſophia Botanica of Linnæus; ſome of which might poſſibly have become claſſical characters, if he had turned his attention to them, and given them adapted names; as he has done to thoſe claſſes, which he has derived from the ſituations of the ſexual organs, as didynamia, tetradynamia, ſyngeneſia, and others, which approach nearer to natural claſſes, and are ſubject to leſs variation than the numerical ones.

Some of thoſe collections of plants, which Linnæus has termed natural orders, and ſome of thoſe of Ray, and Tournefort, might

perhaps have had names affixed to them, denoting the ſituations or proportions or forms of their ſtamina, and have thus conſtituted natural claſſes in the Linnæan ſyſtem. Thus for example the natural order of graſſes might perhaps have had a name denoting their long capillary filaments. The natural order of graſſes is ſo conſpicuous, as to have ſtruck all beholders; they conſtitute, it is ſaid, nearly a ſixth part of the vegetable kingdom, eſpecially in open countries; the leaves are not eaſily broken by being trampled on, but die in winter, becoming yellow and dry; but what is wonderful, they are ſaid to revive in the ſpring, and become green again. This natural order of plants has been divided into cerealia and gramina, corn and graſſes; which however only differ in reſpect to the ſize of the ſeeds. It is much diſunited by the numerical diſtinctions of the ſexual ſyſtem, as ſome graſſes belong to the claſs monandria, diandria, triandria, and hexandria; and thoſe of the triandria, and hexandria, are either hermaphrodite, or monœcious, or polygamous plants. Of theſe a very curious and extenſive table is given in the Prælectiones in Ordin. Natur. a Giſeke Hamburg. 1792, p. 138.

A great part of the natural order of caryophyllei, in which the number of the ſtamina is very variable, are obſerved by Mr. Milne to have their filaments alternately attached to the claws of the petals and to the receptacle, and might poſſibly have a claſſical denomination from that circumſtance. Botan. Dic. Art. Caryophyllei.

The five ſtamina of the umbellated plants in the claſs of pentandria digynia, with five petals, two ſeeds, above; which are termed umbellatæ in the natural orders of Linnæus; as they diverge from each other, might perhaps be called five ſtarred, or cinque-pointed ſtamina from this ſituation. And in part the natural order of plants termed ſtellatæ by Linnæus, as galium, and aſperula; which belong to the claſs tetandria monogynia with one petal, two berries, above; the four diverging ſtamina might perhaps be termed cruciform, as they oppoſe each other. And thus theſe natural collections of vege-

tables might acquire a claſſical denomination from the ſituations of their ſtamina, or perhaps from the form of their filaments or anthers.

To theſe ſituations and proportions of the ſtamina, with many others, might be added the form of the filaments, as capillary, flat, wedgeform, ſpiral, awled; and alſo the forms and ſituations of the anthers, as globular, oblong, arrowy, angular, horned. Which may be ſeen in the Philoſophia Botanica of Linnæus, p. 65; or a tranſlation of them in Miln's Botanical Dictionary, under the titles of filament and anther. All which, I ſuppoſe, are much leſs variable by ſoil or climate, than the numbers of their reſpective ſexual organs, and would in the hands of an ingenious botaniſt form more natural claſſifications.

5. Claſſical characters might perhaps be taken from the length of the filaments compared to that of the ſtyle, with ſome other concomitant circumſtances; as firſt where they are ſomewhat ſhorter than the ſtyle, as in the pendent bell-flowers of lily, fritillaria, campanula. Secondly where the filaments are more than twice as ſhort as the ſtyle, as in meadia, cyclamen, ſolanum, borago, fuſchia. Or thirdly where the filaments are more than twice as long as the ſtyle, and in the natural order of graſſes.

Secondly, the unequal heights of the filaments at the firſt opening of the corol. In many flowers the inferior ſet of ſtamina riſe up to the ſtigma, when the higher ſet have diſcharged their pollen. To theſe ſituations of the ſtamina may alſo be added their number, as in the two very natural claſſes of Linnæus, the didynamia and the tetradynamia. One of theſe might be termed two higher than two; the other four higher than two. To which might perhaps be added a third claſs, of many higher than many; as ſix above ſix in lithrum ſalicaria, five above five in lychnis.

Thirdly, the different inſertions of the filaments, as firſt on the calyx, which principally diſtinguiſhes the claſs icoſandria of Linnæus,

næus, and which thus approaches towards a natural claſs. Secondly on the receptacle, which diſtinguiſhes the claſs polyandria of Linnæus, which alſo approaches toward a natural claſs. And thirdly, the inſertion of the filaments alternately to the claws of the petals, and to the receptacle; which diſtinguiſhes a part of the natural order of the caryophyllei, in which the number of the ſtamina is very various.

Fourthly, the ſituation of the filaments in reſpect to each other; as firſt in the natural order of Linnæus termed ſtellatæ, or a part of the tetrandria monogynia; the diverging filaments oppoſe each other, and might be termed cruciform, as in galium, aſperula. Or ſecondly, where five diverging filaments aſſume the appearance of a ſtar, as in the natural order of umbellatæ, or a part of pentandria digynia, and might have a name borrowed alſo from their number, like five-ſtarred, or cinque-pointed, applied to the filaments, as mentioned above.

Fifthly, the adheſions of the filaments to each other at their baſe. This has given names to three claſſes of the Linnæan ſyſtem, which approach to natural ones, under the term of brotherhoods; as firſt, where the filaments all adhere at their baſe, as in the claſs monadelphia; ſecondly, where they adhere in two ſets, as in the claſs diadelphia; and thirdly, where they adhere in many ſets, as in the claſs polyadelphia.

Sixthly, the adheſions of the filaments to the corol, as where they adhere more than half their length to the internal part of it, as in many monopetalous flowers, as primula, auricula; or where the filament ariſes from the petal, or where the anthers adhere to the margin of the petal, as in many of the natural order of ſcitamineæ, as obſerved in the Prælect. in Ord. Natur. a Giſeke, p. 189.

Seventhly, where the filaments adhere to the ſtyle, as in the claſs gynandria, which approaches to a natural one.

Eighthly, the ſituations of the ſtamina not in the ſame flowers with

with the piſtillum. This has alſo given names to three claſſes of the Linnæan ſyſtem, monœcia, dioecia, polygamia.

Ninthly, the connexion of the anthers, which has given the name to the claſs ſyngeneſia, which excepting the laſt order, is a wonderfully extenſive and natural claſs.

To theſe varieties of ſituation, proportion, and adheſion, of the filaments, may be added thoſe of the anthers on their ſummits; which to an attentive obſerver may perhaps be as numerous as thoſe of the filaments, and to theſe may again be added the various forms of the filaments, as capillary, flat, wedgeform, ſpiral, feathered, &c. and alſo the various forms of the anthers, as oblong, globular, arrowy, angular, horned. All which are deſcribed in the Philoſophia Botanica. And by an adoption of ſome of theſe ſeparately or in conjunction for claſſical characters, I ſhould hope that new claſſifications might be diſcovered inſtead of thoſe, which are ſimply numerical. Which might be more natural ones, leſs ſubject to variation, eaſier to be diſtinguiſhed from each other, and more ſimilar in their good or bad qualities; and might thus add to the great beauty and utility of the preſent wonderful arrangement of ſo many thouſand vegetables in the Linnæan ſyſtem.

6. The ſame obſervations and mode of reaſoning are applicable to the various orders of the ſexual ſyſtem. Which if the great Linnæus had fortunately deduced them from the proportions, ſituations, or forms of the ſtyles and ſtigmas, the characteriſtic ſigns might have been leſs liable to change by ſoil or climate, and many of the orders have been more natural collections of vegetables, than thoſe are, which he has derived ſimply from their number.

The uncertainty of the number of piſtilla, and the confuſion, which might be occaſioned by a reliance on it, was mentioned in No. 2 of this ſection; there is a nigella pentagyna, and a nigella decagyna; there is an hypericum floribus pentagynis, trigynis, and digynis; and in the whole order of fruſtraneous polygamy in the

the claſs ſyngeneſia the florets of the ray are furniſhed with a ſtyle and no ſtigma, as in the ſunflower.

The flowers of the polygonum, whoſe claſſical character is octandria, and its order trigynia, affords many inſtances of the uncertainty of the number of the ſexual organs, both in reſpect to the ſtamina and piſtilla. Thus the ſpecies 4, 5, 6, 7, poſſeſs but five ſtamina in each; the ſpecies 8, 9, 10, have each of them ſix ſtamina, and the eleventh ſpecies has ſeven ſtamina. And laſtly the ſpecies 4, 5, 6, 8, 9, 11, 12, have each of them but two piſtilla, and all the reſt three piſtilla.

From theſe and other innumerable inſtances there is reaſon to conclude, that the proportions, ſituations, and forms of the ſtyle and ſtigma, to which might be added their number conjointly, would have made eſſential characters for the orders, which would have been leſs variable than thoſe derived only from the number of them, and would have rendered them more natural collections.

7. The characters of the orders might be deduced firſt from the length of the ſtyle compared with that of the filaments; as where the ſtyle is more than twice as long as the filaments, as in meadia, cyclamen, ſolanum, fuſchia. Secondly, where the ſtyle is about one third longer than the filaments, as in lilium, fritillaria, campanula, and many other bell-flowers. Thirdly, where the ſtyle is very ſhort compared to the filaments, as in poppies.

2. The characters of the orders might be deduced from the curvatures of the ſtyle. As firſt, where the ſtyle bends into a curve over the anthers to bring the ſtigma into contact with them, as in nigella, devil in the buſh. Secondly, where the ſtyle bends into a circle like a french-horn to accommodate the ſtigma to two ſets of ſtamina in ſucceſſion, firſt the lower, and then the higher, as in ſpartium ſcoparium, common broom. Thirdly, where the ſtyle is crooked in the middle of it, making a kind of zigzag, to lower the

ſtigma

ſtigma to the anthers beneath it, as in hemerocallis fulva, tawny day-lily.

3. Characters might be deduced from the attitude of the ſtyle; as where it is pendent, that the ſtigma may be accommodated to the anthers above it, as in many bell-flowers. Secondly, where it is inclined at a conſiderable angle to accommodate the ſtigma to the inclined anthers, as in epilobium, willow-herb, and glorioſa ſuperba. Thirdly, where the ſtyle is erect, to adapt the ſtigma to the upright anthers, as in many flowers.

4. Where the diviſions of the ſtigma expand, and bend down toward the anthers beneath them, as in ſome kinds of dianthus, pink, and in epilobium.

5. The total abſence of the ſtyle might mark an order.

6. The total abſence of the ſtigma, which is a characteriſtic mark of the florets of the ray in the order fruſtraneous polygamy of the claſs ſyngeneſia.

7. Where the ſtyle adheres to the ſtamina, as in the natural order of Linnæus termed calamariæ, as obſerved in Philoſ. Botanica, No. 102, on the Piſtilla, p. 68.

8. Where the ſtyle ſupports the ſtamina as in the claſs gynandria.

9. Where the ſtyle appears to exiſt both above and below the germ, as in capparis, euphorbia.

10. The lateral adheſion of the ſtyle to the germ, as in one of the natural orders of Linnæus, which he has termed ſenticoſæ, or briers, which includes the roſe, raſpberry, ſtrawberry, agrimony, alchemilla, and many others, which might be named from the lateral adheſion of the ſtyle to the germ, which Linnæus aſſerts to exiſt both in the natural order above mentioned, and in the order Icoſandria polygyna. Philoſ. Botan. p. 67.

If to theſe proportions or ſituations of the ſtyle were added the varieties

rieties of its figure, as cylindrical, angular, awled, capillary; and to theſe were again added the diviſions of the ſtigma, as convolute, revolute, ſix-parted, many-parted. And to theſe were again added the various forms of the ſtigma, as globular, egged, end-nicked, cruciform, feathery, &c. which are enumerated in the Philoſophia Botanica; there is great reaſon to believe, that characteriſtic marks of all the orders of plants might be deduced and named from ſome of thoſe circumſtances ſeparately or conjointly; which might diſtinguiſh them from each other with greater eaſe and certainty, and by marks leſs variable by ſoil or climate, than by the number alone; and by rendering them more natural add to the beauty and utility of the Linnæan ſyſtem.

Concluſion.

Nevertheleſs I am well aware of the great general inconvenience of altering ſo extenſive a ſyſtem once eſtabliſhed, and am ſorry to ſee ſome idle efforts to add the claſſes already deduced from ſituation or proportion to thoſe, which are ſimply numerical; and thus rather to deteriorate than to improve the preſent ſyſtem of the great maſter.

I profeſs myſelf incapable to execute the plan, which I have here ſuggeſted, as it would require a moſt exact knowledge of the detail of botany, as well as of the outline; would require many years of unremitted application, with every opportunity of viſiting botanic gardens, or examining dry collections, and inſpecting prints and drawings of vegetables; and would demand a genius, which few poſſeſs, capable of reducing the complex and intricate to the ſimple and explicit.

But if the ſyſtem of the great Linnæus can ever be intrinſically improved, I am perſuaded, that the plan here propoſed of uſing the ſituations, proportions, or forms, with or without the numbers of

the ſexual organs, as criterions of the orders and claſſes, muſt lay the foundation; but that it muſt require a great architect to erect the ſuperſtructure. And my principal deſign in adjoining this imperfect ſketch at the end of this work was to warn thoſe botaniſts, who have began to interweave ſome of the Linnæan claſſes deduced from ſituation or proportion of the ſexual organs into thoſe diſtinguiſhed ſimply by number, that they ſo far contribute to deteriority the great ſyſtem, which they mean to amend.—At the ſame time I much applaud, and beg leave to recommend to the attention of the public, the ſuperb pictoreſque botanical coloured plates now publiſhing by Dr. Thornton, which I ſuppoſe have no equal.

ADDITIOTAL

ADDITIONAL NOTES.

1. *To be inſerted before the laſt paragraph of Sect.* IV. 2. 1. *at p.* 45, *line* 22.

In the preſent year 1799, Auguſt 18, there was an uncommon ſummer-flood on the Derwent, which covered my garden above three feet deep with muddy water. Many plants of the rheum hybridum, mule rhubarb, which were tranſplanted in the ſpring, and had not flowered, had their large pointed leaves covered with mud, ſo as to render the green colour totally inviſible after the water ſubſided. They appeared ſtrong as before for a day or two, and then every one withered and dropped down. The ſame happened to the leaves of many other vegetables, and to eſpallier apple-trees, as high as they were immerſed; which was doubtleſs owing to their reſpiration being precluded by the veil over them of a fine tenacious mud. See Sect. VII. 2. 6.

2. *To be inſerted in Sect.* VII. 2. 6. *at p.* 115, *after line* 23.

The rheum hybridum, mule rhubarb, deſcribed in Murray's Syſtema Vegetabilium, edition the fourteenth, I believe to be produced between the palmated rhubarb, and the common rhubarb of our gardens, or rheum rhaponticum; as it appeared both in my garden

and my neighbours amongſt a mixture of thoſe two kinds of rhubarb, without being previouſly placed or ſown there. The leaf is very large and pointed, without being palmated, and is a week or two forwarder in the ſpring than either of the other rhubarbs, and the peeled ſtalks are aſſerted by connoiſſeurs in eating to make the beſt poſſible of all tarts, much ſuperior to thoſe of the palmated or raphontic rhubarb; and are ſo much more valuable as a luxury, as they precede by a month the gooſeberry and early apple; and may be well propagated by dividing the roots, as they do not produce ſeed in all ſummers. See Sect. IV. 2. 1.

3. *To be inſerted at the end of Sect.* X. 4. 9. *p.* 207.

Mr. Ruckert planted two beans in pots of equal ſize filled with garden-mould; the one was watered almoſt daily with diſtilled water, and the other with water impregnated with carbonic acid gas, in the proportion of half a cubic inch to an ounce of water; and both of them were expoſed to all the influence of the atmoſphere except to the rain. The bean treated with the carbonic acid water appeared above ground nine days ſooner than that moiſtened with diſtilled water, and produced twenty-five beans; whereas the other pot produced only fifteen. The ſame experiment was made on ſtock-july flowers, and other plants with equal ſucceſs. An. Chym. 1788.

4. *To be inſerted at the end of Sect.* X. 7. 7. *p.* 228.

Beſides which the vitriolic acid abounding in many clays, when brought into contact with mild calcareous earth, by the various operations of agriculture, muſt unite with it, and ſet at liberty the carbonic acid either in a fluid form, or a gaſſeous form beneath the ſoil;

which is known to be ſo friendly to vegetation, when applied to the roots of plants; and at the ſame time a gypſum will be produced, which is now alſo believed to be uſeful in agriculture.

Mr. Kirwan aſſerts, "That the gypſum uſed with ſucceſs in agriculture is of a fibrous texture; and that clay lands, he believes, to be more improved by it than calcareous ones. The time of ſpreading it is in February or March, and it is then to be thinly ſtrewed on graſs-land at the rate of about eight buſhels to an acre; as more he ſays would be hurtful. He further adds that the theory of its effects is to be deduced from its extraordinary ſceptic power; as it is found to accelerate putrefaction in a higher degree than any other ſubſtance, (Hiſtoire de Putrefaction, p. 36), whence it is not to be ploughed in, but barely to be ſtrewed on the ſurface of the land in the month of February, to convert the old graſs quickly into coal to nouriſh the young growths."

I have tranſcribed the above from Mr. Kirwan's Treatiſe on Manures, but am liable to doubt the experiments concerning bodies promoting putrefaction; as the progreſs of that proceſs has generally been only judged of by the odour; which may poſſibly be altered or deſtroyed by many bodies, by their uniting with it without otherwiſe affecting the tendency to diſſolution. Add to this another circumſtance, ſhewing the uncertainty of theſe deductions, that ſome of theſe antiſeptic materials, as ſea-ſalt, and lime, are ſaid to promote putrefaction, when uſed in ſmall quantities; and to ſuppreſs it, when uſed in large ones.

5. *To be inſerted in Sect.* XIII. 2. 2. *at the end of the paragraph which mentions Mr. Lawrence's letter to Mr. Bradley.*

Another thing, which renders low ſituations leſs proper for gardens, is, that I believe them to be much more liable to be infeſted by

by the aphis; as leaves of the nut-trees in my garden on the banks of the Derwent are every year crowded with innumerable aphiſes on their inferior ſurfaces, and yet I have ſeen few, if any of them, on nut-trees in ſome higher ſituations, which I happened to inſpect. Add to this, that the great honey-dew, mentioned in Sect. XIV. 1. 7. was produced on a row of willows by the ſide of water. This may nevertheleſs be in part aſcribed to ſome other local circumſtance; as I this year obſerved numerous large black aphides round the ſtalks of garden-beans on a clayey ſoil, which did not exiſt in my garden, which may be called a carbonic ſoil. Though on the peach and nectarine trees, againſt the walls in my low garden, and on ſome plum-trees, the aphides exiſt almoſt every year in ſuch deſtructive multitudes as to prevent the fruit from ſucceeding, and thence to render them not worth cultivation; and to render the leaves of the nut-trees leſs in ſize, and leſs prolific than other nut-trees on a more elevated and clayey ſoil, with which I this year compared them.

Why the aphis ſhould be ſo much more numerous in moiſt ſituations is a curious ſubject of inquiry, but is ſo ſimilar to another animal fact, that they may illuſtrate each other. The cough and conſequent conſumption of ſheep, which occurs annually in moiſt ſituations, is owing to an inſect called a fleuk-worm, about the ſize and ſhape of a child's finger-nail, which creeps up the gall-ducts from the inteſtines, and preys upon the livers of ſheep; as may be ſeen in moiſt ſeaſons in our ſhambles. This ſeems to occur from the bile becoming too dilute from ſo much watery nouriſhment in thoſe animals, and that thence it does not poſſeſs ſufficient bitterneſs or acrimony to prevent the depredation of theſe inſects, as in drier ſeaſons. On the ſame account I ſuſpect the juices of nut-trees and of willows planted in very moiſt ſituations may be rendered too dilute; but that in higher ſituations they may poſſeſs ſufficient acrimony or bitterneſs mixed with the ſap-juice to prevent the depredations of the aphis. See Sect. XIV. 2. 8.

6. *To*

6. *To be inſerted at the end of Sect.* X. 5. 3.

Phoſphorated lime is ſaid to be found in the greateſt quantity in wheat, where it contributes to the formation of the gluten, which is thence not improperly denominated by ſome writers animal gluten; which in rainy years has been obſerved by Witwer to be in ſmaller quantity. Diſſert. II. p. 103. Hence the uſe of bone-aſhes as a manure for wheat, as obſerved by Mr. Kirwan. Eſſay on Manures, p. 53.

7. *To be inſerted at the end of Sect.* VI. 10.

Beſides the various ſecretions above deſcribed Brugmanns is ſaid by Humbolt to have ſhewn, that plants void an excrement like animals, which might be noxious to them, if retained; that he put the plant, lolium, ray-graſs, into a glaſs of water, and obſerved daily at the extremities of the roots a ſmall drop of a viſcous material; which he detached and found to be renewed on the next day. But this I ſuſpect to have been produced by the death and conſequent decompoſition of the extremities of the roots in their unnatural ſituation. Journ. de Phyſique Delametherie, T. IV. p. 388.

8. *To be inſerted at the end of Sect.* XIV. 4. 2.

In the Tranſactions of the American Philoſophical Society there is a paper ſhewing, that the water-rats of that part of the country are ſo liable to be affected with tape-worm, as is ſuppoſed much to diminiſh their numbers. In this country many animals, as I believe dogs, cats, and geeſe, as well as the human ſpecies, are afflicted with this inteſtine enemy. Could ſome of theſe diſeaſed American rats be

imported into this country, and propagate their malady amongſt the native rats of this climate?

9. *To be inſerted at the end of Sect.* X. 7. 8. *p.* 228.

Having now ſpoken of carbon, of lime, and of clay, which with ſiliceous ſand conſtitute the principal ingredients of fertile ſoils, ſome rules may be required for diſtinguiſhing the goodneſs of ſoils by the purchaſer, as well as by the poſſeſſor. For this purpoſe the chemical analyſis would firſt preſent itſelf, as attempted by Fordyce, many years ago, and lately by Giobert, Bergmen, Kirwan, and others.

M. Giobert found, that one pound of a fertile ſoil in the vicinity of Turin contained of carbonic matter, which would burn and flame, about twenty-five grains, of flinty ſand about 4400 grains, of clay about 600 grains, of lime about 400 grains, and laſtly, of water about 70 grains. The ſame author found that one pound of ſome barren ſoils was compoſed of ſiliceous earth about 3000 grains, of argillaceous earth about 600 grains, and of calcareous earth about 400 grains, and I ſuppoſe without any carbonic matter.

Mr. Kirwan ingeniouſly obſerves, that the quantity of moiſture, which ſome countries are more liable to than others, ſhould be nicely attended to, at the ſame time that you eſtimate the fertility of land by its analyſis, as moiſt climates or ſituations may require more ſand than drier ones; and therefore the ſame component parts of ſoil would not be the moſt fertile, on both the weſtern and eaſtern coaſts of this iſland; as the former experiences more rain than the latter; nor on the ſummit, declivity, and baſe of moſt mountains, which differ in their degree of moiſture.

It appears from hence, that the chemical analyſis of ſoils is not yet arrived at ſufficient accuracy to be depended upon with certainty to diſcover their degrees of fertility. But as the carbonic part of ſoil probably

probably contributes moſt to the growth of vegetables, and next to that the calcareous part; there is reaſon to conclude, that if a few pounds of different ſoils are dried by the ſame degree of heat, and then weighed, and afterwards expoſed to a red heat in an open fire; that the ſoil, which loſes moſt weight, is probably the moſt fertile; becauſe the carbonic matter will almoſt all eſcape in flame, and almoſt half the weight of the calcareous earth in carbonic acid.

Another method of giving ſome conjecture concerning the fertility of a ſoil may be by examining its ſpecific gravity; as the ſpecific gravity of garden-mould is ſaid by Muſchenbroek to be 1,630, compared to 1,000 of water. And Fabroni found the ſpecific gravity of barren ſandy land to be 2,210 to 1,000 of water. This experiment would not be difficult to try with ſufficient accuracy by drying two different ſoils at an equal diſtance from a fire, or in the ſame oven, and then weighing a pound of each in a thin bladder with apertures near its top or neck; and then letting the bladder ſink ſo low into water, as to admit the water through the apertures amongſt the ſoil; and laſtly, obſerving the difference between their reſpective weights in air, and in water.

Nevertheleſs the method moſt in uſe by the purchaſers of land to judge of its value is by attending to the growth and colour of the vegetables, which cover it; which requires an experienced eye, and cannot be eaſily deſcribed in words. Add to this that vegetables, which grow wild on ſoils, will in ſome meaſure indicate the nature of them. As the digitalis, and arenarea, are found generally on ſandy ſoils, the veronica becabunga, and creſſes of ſome kinds, belong to moiſt ſituations, and others to mountainous ones. A particular catalogue of ſuch plants, as ſpontaneouſly grow in different ſituations, might aſſiſt in diſcovering the degree of fertility, and the nature of the ſoil; as other flowers by the time of their opening in each climate, which is termed the Calendar of Flora, may teach the temperature of the ſeaſon.

In ſome parts of the country the ſpontaneous production of many

docks, rumex, has been reckoned the mark of an inferior ſoil, and the production of thiſtles, ſerratula arvenſis, to be a ſign of a good one; which explains a ſtory in a black letter book on huſbandry, which ſays, "A blind man went to purchaſe a farm, which was offered to ſale, and riding over the paſture land, and hearing the goodneſs of the ſoil much applauded by the poſſeſſor, at length diſmounted, and ſaid to his ſervant, 'Tie my horſe to a thiſtle!' 'Here are no thiſtles,' replies the ſervant, 'but I can tie him to a dock.' 'Then I will not purchaſe the land,' ſays he, and mounting his horſe with a good morning to you, Sir, left the owner of the eſtate in great ſurpriſe."

10. *To be inſerted at the end of Sect.* XV. 3. 7.

To diſcover when the ſeeds of herbaceous plants are ripe, as of wheat, the dryneſs or ſtraw-colour of the ſtem is in general a good criterion; as when the ſtem dies, and becomes bleached by the oxygen of the atmoſphere, no more nutriment can be conveyed to the mature ſeed. And to determine at what time to collect thoſe fruits, which never ripen on the trees in this climate, as crab-apples, and baking-pears, change of colour or fall of the leaf ſhews, that they can acquire no more nouriſhment, and may receive injury from the approaching froſt.

But to determine when our beſt or earlieſt apples and pears are ripe enough to gather, that is, when they will acquire no more nutriment from the tree, depends on a very curious circumſtance of the colour of the ſkin of the ſeeds. During the infant ſtate of the ſeed there is no cavity round them, but the ſeed is in contact with the ſeed-veſſel, as may be ſeen on cutting an unripe pear or apple; and the ſeed therefore is perfectly etiolated, as it cannot part with any of its oxygen. Afterwards when there is no more depoſition of nutri-

tious

tious matter to enlarge the fruit, the cells, in which the ſeeds are contained, become hollow, producing an air-veſſel for the living embryon; of what purity the air may be, which is produced in theſe cells, has not I believe been tried, and may differ as the embryon-ſeed grows older; but the oxygen, which it contains, ſeems to have been diſengaged from the membranes, which cover the ſeeds, which thence become coloured; whence the dark colour of the ſeeds of apples and pears is a proper criterion of the time, when they ſhould be gathered; as it indicates, that the fruit will no longer increaſe in ſize, as it now waſtes and becomes hollow by abſorbing ſome of the mucilage from the central parts of it.

11. *To be inſerted at the end of Sect.* VI. 5. 5.

Sugar is not only afforded by the ſap-flow of trees, as the maple, birch, and vine, but alſo I ſuppoſe from that of herbaceous vegetables, as heracleum ſpondilium, cow parſnip, and ſerratula arvenſis, field thiſtle; when the former of theſe plants has been cut off near the ground in the vernal months, the ſap-juice from the ſtump I have obſerved to flow in ſuch quantity for many days, that I have doubted whether by a proper apparatus for catching it the plant might not be advantageouſly cultivated for the purpoſe of making wine, or of extracting the ſugar as from the maple of America. This circumſtance has been ſaid to ſhew a proper time for deſtroying the weeds, as if they be mowed in the bleeding ſeaſon, they are believed to periſh by the loſs of ſap-juice.

As all ſpirit is the ſame, when nicely diſtilled, whether it be found in wine, ale, cyder, brandy, rum, gin, and is the product of ſugar by the chemical proceſs of fermentation; and as all ſugar is the ſame, when nicely cleaned, whether it be obtained from fruits, grains, roots, canes, or ſap-juice; there is reaſon to believe, that ſugar as well as

ſpirit may ſome time or other be economically procured from the vegetables of this climate, as Margraff extracted it from the beet-root, and from potatoes. For the ſtrength of common ale, which is produced from the ſugar contained in malt, is ſaid to be about the ſame as that of ſome domeſtic wines, which owe their ſpirit to prepared ſugar. And as in the former a buſhel or ſtrike of malt is uſed to about ſix gallons of water, and in the latter about twenty pounds of ſugar to ſix gallons of water, it follows, that one ſtrike of malt contains about twenty pounds of ſugar; which if an eaſy method of cleaning it from the mucilage and from the eſſential oil of the ſeed could be diſcovered, it may ſome time be manufactured at home cheaper, than it can be procured from abroad.

We may add, as all ſugar is the ſame, and all ſpirit is the ſame, from whatever plant they are procured; that the flavours of wines differ from each other ſolely in the eſſential oil, which they contain, or the quantity of acidity, or of ſugar not yet fermented; and that in reſpect to wholeſomeneſs wines only differ from each other in their ſtrength or quantity of ſpirit, unleſs where ſome noxious material has been uſed to fine them, or to counteract their tendency to the acetous fermentation, as lead has been employed in ſome of the cyders of our country, and in ſome of the white wines of France, to correct their acidity; and it is ſaid that arſenic is occaſionally employed for the purpoſe of fining white wines.

The injurious methods of fining wines, and of ſtopping their tendency to acidity having been mentioned, the innocuous ones ought to be ſubjoined; for the former it has been propoſed to filter muddy wine through fine ſand laid on a ſieve; but this I am told does not ſucceed, as the mucilage of the foul wine ſoon fills up the interſtices of the grain of ſands; but that an efficacious method is to ſhower the fine ſand on the wine through a ſieve; which as it paſſes down by its own weight will carry the mucilaginous mud of the wine along with it. And laſtly, if ſome colouring particles cannot thus be made

made to ſubſide, a little more ſimple mucilage muſt be added, as gum arabic or whites of eggs, and a ſand-ſhower be again paſſed through it.

In reſpect to the tendency of wines to become vinegar, this I am informed may be prevented by not expoſing the fermenting material to the air more than can be eaſily prevented, as it is the union of the oxygen of the atmoſphere with the ſpirit that converts it into vinegar; and though the vinous fermentation proceeds ſlower, when ſecluded from the air, yet it finally becomes more perfect; as the ſugar in ſweet wines continues to become ſpirit, after it is corked up in bottles, though the proceſs is ſlower, and the wine conſequently becomes ſtronger as it grows older, and the ſweetneſs vaniſhes.

Hence I obſerve the manufacturers of raiſin-wines ſet them to ferment in large caſks with only the bung-hole open, that they may not be too much expoſed to the atmoſphere; and ſoon ſtop them up or bottle them, before the ſweetneſs vaniſhes, which they judge of by the taſte.

I was once told by a gentleman, who made a conſiderable quantity of cyder on his own eſtate, that he had procured veſſels of ſtronger conſtruction than uſual, and that he directed the apple-juice, as ſoon as it had ſettled, to be bunged up cloſe; and that though he had had one veſſel or two occaſionally burſt by the expanſion of the fermenting liquor, yet that this rarely occurred, and that his cyder never failed to be of the moſt excellent quality, and took a conſiderably greater price at market.

Nor ſhould this account of fermentation be concluded without obſerving, that it converts ſugar, which is a wholeſome nutriment both to young and old, into ſpirit, which is a poiſonous material to all; as it ſtimulates the whole ſyſtem into too violent exertion for a few hours, and leaves it afterwards in conſequence torpid and inactive; and hence that the ſtrongeſt wines are the moſt pernicious, and that all of them ſhould be diluted with water. As thoſe in general, who

drink

drink ale to exceſs, acquire the gravel; thoſe, who drink wine to exceſs, acquire the gout; and the drinkers of ſpirits die of the dropſy!—but it is the cuſtom of moſt of the inebriates of this country to begin their unfortunate career with the firſt, and terminate it with the laſt.

12. *To be inſerted at the end of Sect.* X. 6. 8.

An important paper concerning lime is this year publiſhed in the Philoſophical Tranſactions by Mr. Tennant, who having been informed, that two kinds of lime were uſed in agriculture, which differed greatly in their effects, one of which it was neceſſary to uſe ſparingly, and to ſpread very evenly over the land; for it was ſaid, that a large proportion of it diminiſhed the fertility of the ſoil; and that wherever a heap of it had been left on one ſpot, all vegetation was prevented for many years. And that of this kind of lime fifty or ſixty buſhels on an acre were as much as could be uſed with advantage; while of the other ſort of lime a large quantity was never found to be injurious; and that the ſpots, which were entirely covered with it, became remarkably fertile, inſtead of being rendered barren.

Mr. Tennant having analyſed thoſe two kinds of lime found, that the latter conſiſted ſolely of calcareous earth; but that the former contained two parts of magneſia with three parts of calcareous earth. He afterwards obſerved, that though vegetable ſeeds would grow equally well in both theſe kinds of limeſtone, when ſimply reduced to powder; yet that, when they were calcined ſo as to become lime, and both of them ſtrewed about the tenth of an inch thick on garden mould, that the magneſian lime prevented nearly all the ſeeds, which had been ſowed, from coming up; while no injury was occaſioned by the calcareous lime uſed in the ſame manner.

This important diſcovery ſeems to explain the cauſe of ſuch variety of opinion about the uſe of lime, which ſome have believed to be of

no

no advantage, and even injurious to land; which has probably been owing to their having uſed the magneſian lime, and having laid on too much of it.

Mr. Tennant firſt found magneſian lime near the town of Doncaſter, and afterwards at York, at Matlock in Derbyſhire, and at Breeden in Leiceſterſhire, and at Workſop in Nottinghamſhire. He obſerves, that the cathedral and walls of York are built with this magneſian limeſtone; and that at Matlock the magneſian and calcareous limeſtones are contiguous to each other; the rocks on the ſide of the river Derwent, where the houſes are built, being magneſian, and on the other ſide calcareous. He obſerved alſo here, that the magneſian limeſtone was incumbent on the calcareous; for in deſcending into a cave formed in that rock, he found a ſeparate vein of calcareous limeſtone, which was full of ſhells, but contained no magneſia; and obſerves in general, that magneſian limeſtone may be readily diſtinguiſhed from the calcareous by its ſo much ſlower ſolution in acids, and that it contains generally very few ſhells, but that thoſe alſo are impregnated with magneſia.

As all limeſtone may be divided into three kinds; the rocks, which remain, where they were formed from ſhells beneath the ocean, except that they were afterwards elevated by ſubmarine fires; and ſecondly into alluvial limeſtone, as thoſe which have been diſſolved in water, and ſimply precipitated, as the beds of chalk, which contain only the moſt inſoluble remains of ſea-animals, as the teeth of ſharks; and thirdly thoſe which after having been diſſolved and precipitated, have been long agitated beneath the ſea, till the particles have been rolled ſo againſt each other, as to acquire a globular form, which is ſaid to reſemble the roe, or ſpawn, of fiſh, and which contain very few ſhells or none, as the Ketton ſtone, and that which I have ſeen on Lincoln Heath extending almoſt from Sleaford to Lincoln.

Now as the ſalts of the ſea conſiſt of only two kinds, common

ſalt,

ſalt, or muriate of ſoda, and vitriolated magneſia, commonly called Epſom ſalt, which in the ſea-waters ſurrounding this iſland were found at a medium to exiſt in the proportion of one thirtieth part of common ſalt, and one eightieth part of vitriolated magneſia compared to the quantity of water. And ſecondly as theſe ſalts are believed by many philoſophers to have been formed by vegetable and animal matters, which principally grew upon the ſurface of the dry land, after it was raiſed out of the primeval ocean; and that in conſequence the ſaltneſs of the ſea was poſterior to the formation of the primeval rocks of limeſtone; and from hence we underſtand, why thoſe limeſtone ſtrata, which have not been diſſolved or waſhed in ſea-water ſince the ſea became ſalt, are not mixed with magneſia.

The chalk muſt have been diſſolved and precipitated from water, as it exactly reſembles the internal part of ſome calcareous ſtalactites, which I have in my poſſeſſion; yet there is no appearance of its component particles having been rubbed together into ſmall globules, and may not therefore have been removed from the ſituation, where it was produced, except by its elevation above the ſurface of the ocean.

But that alluvial limeſtone, which conſiſts of ſmall globules adhering together, called Ketton limeſtone, and of which there appears to be a bed ten miles broad from Beckingham to Sleaford in Lincolnſhire, and twenty miles long from Sleaford to Lincoln, I ſuſpect may probably conſiſt of magneſian limeſtone; which is alſo ſaid in that country to do no ſervice to vegetation; for this alluvial limeſtone by having evidently been long rolled together beneath the ſea, by which the ſmall cryſtalliſed parts of it have had their angles rubbed off, is moſt likely to have thus been mixed with the magneſia of the ſea-water, which is ſaid to contain one eightieth part of its weight of vitriolated magneſia, as above mentioned.

At the lime-works at Ticknal near Derby there appears a ſtratum of

of alluvial limeſtone, like Ketton limeſtone, which they do not burn for ſale, over the bed of the calcareous limeſtone, which they get from beneath the former, and calcine for ſale. It is probable, that the ſuperior bed may contain magneſia, which has rendered it not ſo uſeful in agriculture.

It is more probable, that alluvial limeſtone has acquired its mixture of magneſia from the ſea-water; as magneſia in its uncalcined ſtate will precipitate lime from water, as obſerved by Dr. Alſton; who thence propoſes to render water pure and potable, which has been long kept at ſea free from putridity by having lime mixed with it, by precipitating the lime by the addition of mild magneſia; which is a ſubject now perhaps worthy the attention of the court of admiralty, ſince magneſian limeſtone appears to be ſo plentifully diffuſed over the earth. See Dr. Black's Exper. on Magneſia in the Eſſay Philoſ. and Literary, Edinb.

The lime from Breedon is magneſian, that from Ticknal (which is ſold) is calcareous lime I believe; and ſome farmers in the vicinity of Derby aſſert, that two loads of Breedon lime will *go as far*, that is will apparently do as much ſervice to their land as three loads of Ticknal lime. Breedon lime, I am alſo informed, is preferred in architecture, and is ſaid to *go further* in making mortar; which I ſuppoſe means, that it requires more ſand to be mixed with it. Mr. Marſhall in his account of the agriculture of the Midland counties ſpeaks of lime made at Breedon near Derby as deſtructive to vegetables when uſed in large quantities. And in Nottinghamſhire it is aſſerted, that the lime from Critch in Derbyſhire is ſo mild, that thiſtles and graſs ſpring up through the edges of large heaps of it, when laid in the fields. Dr. Fenwick of Newcaſtle obſerves, that the farmers in that country divide lime into hot and mild; which Mr. Tennant believes to mean magneſian and calcareous lime.

By experiments which were made by Mr. Tennant by ſowing ſeeds of colewort on various mixtures of calcined magneſia with ſoil, and

of calcareous lime with ſoil, he found that thirty or forty grains of lime did not retard the growth of ſeeds more than three or four of calcined magneſia; from hence what can we conclude? but that, as they both injure vegetation in large quantities, they may both aſſiſt vegetation in ſmall ones? and that this is more probable, as the farmers believe, that they find both of them uſeful, though in different quantities; and as the magneſia would form Epſom ſalt, if it meets with vitriolic acid, which Dr. Home found from his experiments to be friendly to vegetation, when uſed in very ſmall quantities. More accurate obſervations and more numerous experiments on this ſubject are required, which this important diſcovery of Mr. Tennant's will I hope ſoon occaſion.

13. *To be inſerted at p.* 286, *l.* 16, *at the end of No.* 2 *of Sect.* XII.

Another method has been attempted by ſome for the purpoſe of ameliorating clayey lands, which were unfit to be turned up deeper than they had been accuſtomed to be ploughed, on account of their acidity or tenacity being very injurious to vegetation; as the white ſaggar clays over many coal countries; or ſome very tenacious red clays, which may contain a vitriol of iron; not an oxyde, or oxygenated calx of it.

The method I allude to conſiſts in firſt turning over a ridge of earth, as in common ploughing; and then with a plough, made on purpoſe, to penetrate ſome inches deeper into the clay ſo injurious to vegetation; this plough is to be ſo contrived, as to raiſe up the clayey ſoil about the breadth of the furrow recently made, and three or four inches deep, or more; but not to turn it over, ſo that it may ſtill lie under the fertile ſoil, which is to be turned over it with the common plough, in making the adjoining furrow. So that this

plough

plough is only to paſs under the ſoil, and thus looſen it, and mix it with atmoſpheric air without turning it over.

By this manœuvre the clay a few inches deep beneath the fertile ſoil becomes broken in its texture, and obtains ſome air intercepted in its pores; from the former circumſtance it may contribute to retain the vernal ſhowers, which would otherwiſe run off over the clayey ſurface beneath the more fertile one, and might thus in drier ſeaſons prevent the upper ſurface from being ſo much indurated, and might gradually become leſs injurious by the frequent admixture of atmoſpheric air, and at length even ſalubrious to the roots of vegetables.

APPENDIX.

IMPROVEMENT OF THE DRILL PLOUGH.

THE firſt experiment I tried to improve this valuable machine was that mentioned in Sect. XII. 5. of this work, by enlarging the axis of Mr. Tull's ſeed-box into a wheel of ſixteen inches diameter, with excavations in the rim to raiſe portions of the corn above the ſurface of that in the ſeed-box. But I found to my ſurpriſe the friction of the corn to be ſo much greater than expected, when ſix ſuch large wheels were immerſed in it, that an additional hopper became neceſſary to deliver the ſeed ſlowly into the ſeed-box, as in Mr. Cook's drill plough; which, as it would add much to the intricacy and expence of the machinery, and to the inaccuracy of the quantity of ſeed delivered, occaſioned me to relinquiſh that idea, and after many deſigns and many experiments to conſtruct the following machine, which I believe to be more ſimple, and conſequently leſs expenſive to conſtruct, and leſs liable to be out of order, and to deliver the ſeeds of all kinds with greater accuracy than any drill plough at preſent in uſe; and that it poſſeſſes every other advantage that they can boaſt. The ſcale of the three following plates is half an inch to ten inches.

Conſtruction of the Carriage Part.

Plate X. Fig. 1. *a a*, are the ſhafts for the horſe, which are fixed to the center of the axle-tree by a ſimple univerſal joint at *z*, whence,

if the horſe ſwerve from a ſtraight line, or is purpoſely made to paſs obliquely to avoid treading on the rows of corn in hoeing; the perſon, who guides the plough behind, may keep the coulters of the plough or hoe in any line he pleaſes; which is thus performed with much ſimpler mechaniſm, than that uſed in Mr. Cook's patent plough for the ſame purpoſe, which has many joints like a parallel rule.

b b are the horns or ſhafts behind, for the perſon who guides the drill coulters or hoes; they are fixed to the axle-tree before, and have a croſs piece about ſix inches from it at *g g* for the purpoſe of ſupporting the ſeed-box deſcribed below. Behind this about a foot diſtant from it is another croſs piece at *c c*, called the coulter-beam, which is fifty inches long, ſix inches wide, and two inches thick; it is perforated with two ſets of ſquare holes, ſix in each ſet, to receive the coulters in drill-ploughing, and the hoes in horſe-hoeing.

The ſix light ſquare holes are nine inches from each other, and are to receive the coulters or hoes in the cultivation of wheat, the rows of which are deſigned to be nine inches from each other, and the ſix dark ſquare holes are placed ſeven inches from each other to receive the coulters or hoes for the cultivation of barley, the rows of which are deſigned to be but ſeven inches diſtant from each other.

Beſides theſe there are ſix round holes through this coulter-beam at one part of it, and ſix iron circular ſtaples fixed into the edge of the other part of it; theſe are to receive the ends of the tin flues, which croſs each other, and convey the ſeed from the bottom of the ſeed-box into the drills or furrows, when the coulters are diſpoſed in the ſquare perforations before them.

Theſe coulters or hoes the perſon, who guides the machine, can raiſe out of the ground in turning at the ends of the lands, or in paſſing to or from the field, and can ſuſpend them ſo raiſed on the iron ſprings *d d*, which at the ſame time ſo fixes the ſhafts to the axle-

tree

tree that the wheels will then follow in the ſame line with the horſe.

e e are wheels of four feet in diameter, the nave of one of which has on it a caſt-iron wheel at *f f*, for the purpoſe of turning the axis of the ſeed-box, which has a ſimilar wheel of one fourth its diameter; whence the axis of the ſeed-box revolves four times to one revolution of the wheel.

Conſtruction of the ſeed-box. Plate XI. Fig. 2.

This conſiſts of boards about an inch in thickneſs, is forty-eight inches long within, twelve inches deep, twelve inches wide at top, and ſix inches wide at bottom; it is divided into ſix cells, in which the corn is to be put, as repreſented in Plate XI. Fig. 2. and ſhould alſo have a cover with hinges to keep out the rain, and is to be placed in part over, and in part before, the axle-tree of the carriage, at *g g*. Plate X. Fig. 1.

Beneath the bottom of the ſeed-box paſſes a wooden cylinder, at *h h*, Plate XI. Fig. 2. with excavations in its periphery to receive the grain from the ſix cells of the ſeed-box, *l m n o p q*, and to deliver it into the ſix oblique flues *i i*, which are made of tin, and croſs each other, as repreſented in the plate. The uſe of the ſeed-flues thus interſecting each other is to increaſe the length of the inclined ſurface, on which the ſeed deſcends, that if ſix or eight grains be delivered together, they might ſo ſeparate by their friction in deſcending, as not to be ſown together in one point, which might be liable to produce tuſſocks of corn.

As theſe ſeed-flues croſs each other, before they paſs through the coulter-beam at *c c*, Plate X. Fig. 1. it was neceſſary to make three of the round holes of the coulter-beam at one end backwarder than thoſe at the other end; and on that account to uſe iron ſtaples or

rings at one end inſtead of perforations, as at *w w*, Plate X. Fig. 1. Theſe tin flues deliver the ſeed at the time of ſowing into the ſmall furrows or drills, which are made by the coulters before them.

Theſe ſeed-flues have a joint at z z, where one part of the tin tubes ſlides into the other part, and they by theſe means can be occaſionally ſhortened or lengthened to accomodate them to the coulters, when placed at ſeven inches diſtance for ſowing barley, or at nine for ſowing wheat.

At the bottom of this ſeed-box are ſix holes, one in each cell, to deliver the corn into the excavations of the cylinder, which revolves beneath them. Theſe holes are furniſhed on the deſcending ſide, as the cylinder revolves, with a ſtrong bruſh of briſtles about three fourths of an inch long, which preſs hard on the tin cylinder. On the aſcending ſide of the revolving cylinder the holes at the bottom of the ſeed-box are furniſhed with a piece of ſtrong ſhoe-ſoal leather, which rubs upon the aſcending ſide of the cylinder. By theſe means the corn, whether beans or wheat, is nicely delivered, as the axis revolves, without any of them being cut or bruiſed.

Conſtruction of the iron axis and wooden cylinder beneath the ſeed-box. Plate XI. Fig. 3.

An iron bar is firſt made about four feet ſix inches in length, and an inch ſquare, which ought to weigh about fifteen pounds; this bar is covered with wood, ſo as to make a cylinder four feet long, and two inches in diameter, as at *k k*, Plate XI. Fig. 3. The uſe of the iron bar in the centre of the wood is to prevent it from warping, which is a matter of great conſequence.

This wooden cylinder paſſes beneath the bottom of the ſeed-box, and has a caſt-iron cog-wheel at one end of its axis, as at *r r*, which is one fourth of the diameter of the correſpondent caſt-iron wheel, which

which is fixed on the nave of the carriage-wheel, as in Plate X. Fig. 1. *ff*, ſo that the axis of the ſeed-box revolves four times during every revolution of the wheels of the carriage.

In the periphery of this wooden cylinder are excavated four lines of holes, ſix in each line, as at *n n n n n n*. A ſecond line of excavations is made oppoſite to theſe on the other ſide of the cylinder, and two other lines of excavations between theſe; ſo that there are in all twenty-four excavations in the wooden part of this axis beneath the ſeed-box, which excavations receive the corn from the ſeed-cells, as the axis revolves, and deliver it into the flues ſhewn in Plate XI. Fig. 2. *o o i i*, not unſimilar to the original deſign of the ingenious Mr. Tull.

The ſize of theſe excavations in the wooden cylinder to receive the ſeed are an inch long, half an inch wide, and three eighths of an inch deep; which are too large for any ſeeds at preſent employed in large quantities except beans, but have a method to contract them to any dimenſions required, by moving the tin cylinder over the wooden one, as explained below in Plate XI. Fig. 4.

Conſtruction of the Tin-cylinder. Plate XI.

A B at Fig. 4. repreſents a cylinder of tin an inch longer within than the wooden cylinder on the iron axis at Fig. 3. and is of two inches diameter within, ſo as exactly to receive the wooden cylinder, which may ſlide about an inch backwards or forwards within it. C D are two ſquare tin ſockets fixed on the ends of the tin cylinder to fit on the ſquare part of the iron axis, which paſſes through the wooden cylinder at *l l*, Fig. 3. on which they ſlide one inch backwards or forwards.

The following directions in making the holes in this tin cylinder,

and thoſe in the wooden cylinder, which are to correſpond with them, muſt be nicely attended to.

Firſt, when the tin-cylinder is ſoldered longitudinally, and one end of it ſoldered on, as at A, ſix holes through it muſt be made longitudinally on four oppoſite ſides of it, each hole muſt be exactly half an inch wide, and five eighths of an inch long, the length to be parallel to the length of the cylinder.

The centre of the firſt of theſe holes muſt be five inches diſtant from the cloſed end A, the centre of the ſecond hole muſt be eight inches diſtant from the centre of the firſt, and ſo on till ſix holes are made longitudinally along the cylinder. Then another ſuch line of ſix ſimilar holes is to be made on the oppoſite ſide of the cylinder, and then two other ſuch lines between the former, in all twenty-four; and the ſize of all theſe holes muſt be nicely obſerved, as well as their diſtances.

Secondly. The wooden cylinder fixed on the axis is now to be introduced into the tin cylinder, but not quite to the end of it, but ſo as to leave exactly one inch of void ſpace at the cloſed end A, and then the ſize of all theſe apertures through the tin cylinder, each of which is exactly half an inch wide, and five eighths of an inch long, are to be nicely marked with a fine point on the wooden cylinder, which muſt not previouſly have any excavations made in it.

Thirdly. The twenty-four holes thus marked on the wooden cylinder are now to be excavated exactly three eighths of an inch deep, but with an addition alſo of three eighths of an inch at that end of every one of them which is next to A; ſo that, when the wooden cylinder is again replaced in the tin cylinder as before, with one inch of void ſpace at the cloſed extremity of it, the excavations in the wooden cylinder will be three eights of an inch longer, than the perforations in the tin cylinder over them. Theſe excavations in the wooden cylinder muſt alſo be rather narrower at the bottom than at the

the top, to prevent with certainty any of the grain from ſticking in them, as they revolve.

Fourthly. A ſcrew of iron about three inches long, with a ſquare head to receive a ſcrew-driver, is to paſs through the end A of the tin cylinder on one ſide of the axis, as at *x*, Fig. 4. The ſcrew part of this is to lie in a hollow groove of the wooden cylinder, and to be received into a nut, or female ſcrew, which is fixed to the wooden cylinder. The head part of the ſcrew, which paſſes through the end A of the tin cylinder at *x*, muſt have a ſhoulder within the tin cylinder, that it may not come forwards through the end of it; and a braſs ring muſt be put over the ſquare end of the ſcrew on the outſide of the tin cylinder, with a pin through that ſquare end of the ſcrew to hold on the braſs ring.

Thus when the ſquare head of the ſcrew is turned by a ſcrew-driver, it gradually moves the tin cylinder backwards and forwards one inch on the wooden one, ſo as either to preſs the end A of the tin cylinder into contact with the end of the wooden cylinder within it, or to remove it to the diſtance of one inch from it, and leave a void ſpace at the end A.

Fifthly. The ends of all the holes of the tin cylinder, which are next to the end A of it, are now to be enlarged, by ſlitting the tin three eighths of an inch towards A, on each ſide of the hole; and then that part of the tin, included between theſe two ſlits, which will be half an inch wide, and three eighths of an inch lengthways in reſpect to the cylinder, is not to be cut out, but to be bent down into the excavations of the wooden cylinder beneath, ſo as to lie againſt that end of the excavation which is next to A.

But theſe projecting bits of tin, before they are bent down into the excavations of the wooden cylinder, muſt be filed a little leſs at the projecting end, which is to be bent down, than at the other end; as the excavations of the wooden cylinder are to be rather narrower

at the bottom than at the top, and theſe pieces of tin, when bent down, muſt exactly fit them.

Laſtly. When all theſe holes through the tin-cylinder are thus enlarged, and the bits of tin filed rather narrower at their projecting ends, and then bent down into the excavations of the wooden cylinder, the other end of the tin cylinder with its ſquare ſocket may be ſoldered on.

And now when the end of the tin cylinder at A is preſſed forwards upon the wooden cylinder towards B, by turning the ſcrew at *x* above deſcribed; every excavation of the wooden cylinder will be gradually leſſened, and finally quite cloſed; by which eaſy means they may be adapted to receive and deliver ſeeds of any ſize from horſe-beans and peas to wheat, barley, and to turnip-ſeed, with the greateſt accuracy, ſo as to ſow four, five, or ſix pecks on an acre, or more or leſs, as the agricultor pleaſes, by only turning the ſcrew a few revolutions one way or the other.

Obſervations.

1. In the conſtruction of the tin and wooden cylinders beneath the ſeed-box another ſmall improvement may be neceſſary in ſowing very ſmall ſeeds, which is this: As the ſcrew at the end A is turned, ſo as to contract all the excavations of the wooden cylinder, the ſurface of the wooden cylinder for one inch from the end of each excavation towards the end B, Plate XI. Fig. 4. will become bare without being covered by the tin cylinder; and on theſe bare parts of the wooden cylinder, which will be one inch long, and half an inch wide, ſome ſmall ſeeds may chance to ſtick, and evade the bruſhes, which ſhould prevent them from paſſing, as the cylinders revolve.

To prevent this, when the wooden cylinder is ſo placed within the tin cylinder, that all the holes are quite open, let a piece of the tin cylinder

cylinder about an inch and a half long, and half an inch wide, be cut out from the extremity of each hole next to the end B, and let this piece of the tin cylinder thus cut out be fixed by a few ſprigs on the wooden cylinder exactly in the ſame place, which it covered before it was cut out of the tin one, by which contrivance, when the tin cylinder is afterwards puſhed forwards by turning the ſcrew at its end, ſo as to contract the excavations of the wooden cylinder beneath, the bare parts of the wooden cylinder will exiſt an inch and a half from the extremities of the excavations next to the end B, and thus will not paſs under the bruſhes, and in conſequence no ſmall ſeeds can lodge in them.

2. Some kind of iron ſtaple ſhould be fixed at each end of the ſeed-box on the outſide, which when the hinder part of the carriage is raiſed up by the perſon who guides it, might catch hold of the two iron ſprings at *d d* in Plate X. Fig. 1. for the purpoſe of ſuſpending the coulters out of the ground, and connecting the hinder part of the machine with the ſhafts before; that in turning at the ends of the lands, or in paſſing from or to the field, the wheels may not ſwerve at the joint *z*, at the centre of the axle-tree, but may follow in the ſame line with the ſhafts.

3. The ſeed-box muſt alſo be ſupported on upright iron pins paſſing through iron ſtaples, with a lever under the end of it next to the wheel *r r*, Plate XI. Fig. 3. for the purpoſe of eaſily lifting that end of the ſeed-box about an inch high, to raiſe the teeth of the iron cog-wheel on its axis out of the teeth of the correſpondent iron wheel on the nave of the carriage-wheel.

4. The conſtruction of the coulters, which make the drills, and of the rakes, which again fill them, after the ſeed is depoſited, and alſo of the hoes, are not here delineated; as they are ſimilar to thoſe ſo often deſcribed or uſed by Mr. Tull and his followers.

5. When the lower ends of the ſeed-flues are placed through the holes in the coulter-beam, Plate I. Fig. 1. at nine inches diſtance from

from each other, the rows of wheat or beans will then be ſown nine inches from each other; and as the wheels of the carriage are four feet in diameter, and therefore travel about twelve feet at each revolution; and as there are four excavations round the axis of the ſeed-box, which revolve four times for one revolution of the carriage-wheels; it follows, that the ſeeds contained in the excavations of the cylinder beneath the ſeed-box will be ſown at nine inches diſtance in each drill or furrow, as the plough proceeds; and as theſe rows are nine inches aſunder, any deſired number of ſeeds may be depoſited in every ſquare of nine inches, which are contained in the ſurface of the field.

6. Mr. Coke of Norfolk acquainted me, that on his very extenſive farm the wheat ſown on an acre was ſix or ſeven pecks by the Rev. Mr. Cook's drill plough, which was about half the quantity generally uſed in broad-caſt ſowing. If the wheat was nicely depoſited in the drills, I ſuſpect one buſhel would be quite ſufficient for an acre, as the rows are at nine inches diſtant from each other; for there would in that caſe be about eight grains or nine grains depoſited in every nine inches of the drill-furrow; that is, in every ſquare of nine inches contained in the ſurface of the land ſo cultivated.

Which may be thus eſtimated. Mr. Charles Miller, in the Philoſophical Tranſactions, Vol. LVIII. p. 203, has eſtimated the number of grains in a buſhel of wheat to amount to 620,000; and Mr. Swanwick of Derby has lately eſtimated them to be 645,000. We may ſuppoſe therefore, that a buſhel may at an average contain 635,000 grains of wheat. Now as a ſtatute acre contains 4840 ſquare yards, and there are ſixteen ſquares of nine inches in every ſquare yard, 4840 multiplied by 16 gives 77,440, which is the number of ſquares of nine inches in ſuch an acre. If 635,000 grains in a buſhel be divided by 77,440, the number of ſquares of nine inches in an acre, the quotient will ſhew, that rather more than eight

eight grains of wheat will thus be depoſited in every nine inches of the drills.

7. Now if eight or nine grains were dropped altogether in one inch of ground, they would be too numerous, if they be all ſuppoſed to grow, and would form a tuſſock; but by making them ſlide down an inclined plane, as in the tin-flues, from the ſeed-box to the coulters, which are croſſed for the purpoſe of lengthening them, as ſeen in Plate XI. fig. 2. ſome of the ſeeds will be more delayed by their friction in deſcending than others, and the eight or nine ſeeds will thence be diſperſed over the whole nine inches of the drill; which renders drill-ſowing ſuperior to dibbling, as in the latter the ſeeds are dropped all together.

8. When the holes in the wooden cylinder are completely open, they are about a proper ſize for ſowing horſe-beans or peas: when they are completely cloſed, there will remain a ſmall niche at the end of the excavation in the wooden cylinder next to B, Plate XI. fig. 4. for turnip-ſeed, or other ſmall ſeeds.

For wheat and barley and oats, a wooden wedge ſhould be made of the exact ſhape of the area of the hole, which the director of the plough requires; who will occaſionally inſert it into the holes, when he turns the ſcrew at the end of the cylinder to enlarge or to leſſen them to theſe exact dimenſions.

Theſe wedges ſhould be written upon with white paint, wheat, barley, oats, &c. which will much facilitate the adapting the ſize of the excavations to each kind of grain, and may be altered, if required, to ſuit larger or leſs ſeeds of the ſame denomination.

9. In ſome drill-ploughs, as in Mr. Cook's, there is an additional machinery to mark a line, as the plough proceeds, in which the wheel neareſt the laſt ſown furrow may be directed to paſs at a proper diſtance from it, and parallel to it. But in ſowing wheat or peas and beans this may be done by making the wheels, as they run upon the ground, to be exactly fifty-four inches from each other; and

then at the time of ſowing to guide the wheel next to the part laſt ſown exactly in the rut, which was laſt made; by which guide the rows will all of them be accurately at nine inches diſtant from each other.

The Simplicity of this Drill-Plough.

1. The ſimplicity of this machine conſiſts firſt in its having only a ſeed-box, and not both a hopper and a ſeed-box, as in the Rev. Mr. Cook's patent drill-plough.

2. The flues, which conduct the ſeed from the bottom of the ſeed-box into the drill-furrows, are not disjoined about the middle of them to permit the lower part to move to the right or left, when the horſe ſwerves from the line, in which the coulters paſs, as in Mr. Cook's patent drill-plough; which is done in this machine by the ſimple univerſal joint at z, Plate I. fig. 1.

3. In this machine the horns or ſhafts behind, between which the perſon walks, who guides the coulters, are fixed both to the coulter-beam, and to the axle-tree; whereas in Mr. Cook's patent plough theſe are all of them moveable joints like a parallel rule, for the purpoſe of counteracting the ſwerving of the horſe; which in this machine is done by the ſimple univerſal joint at z, fig. 1, Plate I. before mentioned.

4. The altering the dimenſions of the holes in the axis of the ſeed-box by only turning a ſcrew, ſo as to adapt them to all kinds of ſeeds, which are uſually ſown on field-lands.

5. The ſtrong bruſh of briſtles, which ſweep over the excavations of the cylinders beneath the ſeed-box, ſtrickle them with ſuch exactneſs, that no ſupernumerary ſeeds eſcape, and yet none of them are

in the leaſt bruiſed or broken, as I believe is liable to occur in Mr. Tull's original machine.

Laſtly it ſhould be obſerved, that the leſs expence in the conſtruction, the leſs propenſity to be out of repair, and the greater eaſe of underſtanding the management of this machine, correſpond with its greater ſimplicity; and will, I hope, facilitate the uſe of the drill-huſbandry.

Mr. Swanwick's Seed-Box.

As the dibbling of wheat, deſcribed in Sect. XVI. 2. 2. is a very ſlow and laborious method of depoſiting the corn, and is yet coming, as I am informed, more and more into faſhion in ſome counties, I ſuſpect this muſt be owing to the expence of procuring, and the difficulty of managing the drill-ploughs now in uſe, or to the greater inaccuracy, with which they deliver the ſeed. I flatter myſelf therefore, that I am doing a benefit to ſociety in endeavouring to ſimplify this machine, and to increaſe its accuracy as much as poſſible: and ſhall therefore here deſcribe another method of delivering the ſeed from the ſeed-box, which was invented by Mr. Swanwick, an ingenious teacher of writing and arithmetic, with ſome branches of natural philoſophy, in Derby; and who will not be averſe to ſhew the working models of the ſeed-boxes, or to give aſſiſtance to any one, who wiſhes to conſtruct either this drill machine, or the preceding one.

Mr. Swanwick's ſeed-box is forty-eight inches long within, is divided into ſix cells for the purpoſe of ſowing ſix rows of ſeeds at the ſame time, like that above deſcribed. And at the bottom of each cell is a hole *a*, *a*, &c. Fig. 1. Plate XII. for the ſeed to paſs

through into the ſeed-flues, as in the machine before deſcribed: but in this there is no revolving axis, but a wooden or iron bar B B, fig. 3. Plate XII. about two inches broad, and about four feet eight inches long, and exactly three eighths of an inch thick. Through this bar there are ſix perforations, *e e e*, &c. which are each of them exactly one inch long, and half an inch wide; and three eighths of an inch deep, which is the thickneſs of the bar. The centres of theſe holes are exactly eight inches diſtant from each other, correſpondent to the holes at the bottom of the ſeed-box; over which it is made to ſlide backward and forwards in a groove. By this ſliding motion it paſſes under ſtiff bruſhes, which are placed over it on each end of the holes at the bottom of the ſeed-box, and ſtrickle off the grain, as the holes in the ſliding-bar paſs under them, which thus meaſure out the quantity with conſiderable accuracy.

In order to increaſe or diminiſh the quantity of grain delivered, the ſlider is covered with a caſe of tin C C, fig. 4, Plate XII. which has ſix perforations exactly correſponding with the holes in the ſlider; but inſtead of the bit of tin being cut out the whole length of the hole, part of it is left at the end *i*, fig. 6, equal to the thickneſs of the ſlider, and is bent down as at *b*, after the ſlider is put into the caſe, like the tin cylinder in the preceding machine. This caſe is moveable about one inch backward and forward by turning the finger ſcrew *s*, fig. 4 and 5; and thus the holes are made larger or leſs to ſuit various ſorts of grain, or different quantities of the ſame ſort, exactly as in the wooden and tin cylinders in Plate XI. The ſlider is moved forwards by a bent iron pin *h* attached to it, which paſſes into a ſerpentine groove Y, fig. 5, fixed to the nave of the wheel: and backwards by a ſteel ſpring at the other end of the ſeed-box, which is not repreſented in the plate.

Fig. 5 is a bird's eye view of the parts before deſcribed: E E the ſeed-box divided into cells by the partitions *d d*, &c.—*c c c* the ſlider,

with a part of the apertures ſeen juſt appearing from under the bruſhes. X the axis of the wheel.

Fig. 6 is a drawing of part of the tin caſe, nearly of the full dimenſions as to breadth and thickneſs, but only a ſmall portion of the length; and is intended to ſhew more diſtinctly the conſtruction of it.

Fig. 2 repreſents a ſide-view of one of the ſix bridges lying over the holes at the bottom of the ſeed-box, on each ſide of which the bruſhes are fixed, which ſtrickle the holes, when they are full of corn, as the bar ſlides backwards and forwards.

The ſimplicity of this ſlider at the bottom of the ſeed-box may be in ſome reſpects greater, than that of wooden and tin cylinders in the former machine; as this has but ſix holes to meaſure out the corn, and the other has twenty-four. But perhaps in other reſpects leſs ſo; as in this twelve bruſhes are uſed, one on each ſide of each of the ſix holes; whereas there are only ſix bruſhes rub upon the tin cylinder in the former machine. And the reciprocating motion of this ſlider muſt be quick, as it muſt act once every time the periphery of the wheel of the carriage has paſſed nine inches forward; which may not be ſo eaſy to execute as the cog-wheel, and uninterrupted movement of the axis and cylinder in the preceding machine.

I have only to add, that the facility of adapting the holes to the dimenſions required in both theſe machines, and their not bruiſing or breaking the grain in their operation of delivering it, as well as their not being encumbered with an additional hopper, which muſt deliver the quantity of ſeed with great inaccuracy from the unequal ſhaking of the machine, adds much to the excellency and ſimplicity of them both. And I hope will render more general the uſe of the drill huſbandry invented by the ingenious Mr. TULL; who was on

that account an honour to this country, and ought to have a ſtatue erected to his memory, as a benefactor of mankind, like Ceres and Triptolemus of old.

Ille Ego, qui quondam gracili modulatus avena
Carmen, et egreſſus ſylvis vicina coegi,
Ut quamvis avido parerent arva colono.



INDEX.

INDEX.

A.

ABSORBENT veſſels of vegetables, ii.
..... have rigid coats, ii. 3.
..... conſiſt of a ſpiral line, ii. 5. and 7.
..... act direct or retrograde, ii. 6.
..... abſorb poiſons, ii. 9.
..... their force ſtronger than the heart, v. 3. and 5.
Acid muriatic oxygenated, xv. 3. 1. x. 2. 8.
.... vegetable, vi. 10.
Acrimony vegetable, xvii. 2. 5.
..... of two kinds, xvii. 2. 5. xix. 6. 1.
Adanſonia the largeſt tree, xviii. 2. 14.
Adultery vegetable, viii. 8.
Agriculture ſuperior to paſturage, xvi. 9. 1.
Agroſtis canina, xviii. 1. 1.
Air atmoſpheric, x. 2.
... buried beneath the ſoil, xii. 1.
... heats hot-beds, x. 8. 2. x. 11. 5.
... its ſurface over ridges and furrows, x. 3. 7.
Air-veſſels of vegetables, ii. 4. iii. 2. 6.
Alburnum contains ſugar, iii. 2. 3.
..... acts ſometimes as capillary tubes, ix. 2. 10.
..... ſometimes as capillary ſyphons, iii. 2. 4.
Alum, uſe of it in bread, vi. 3. 1.
..... how detected in bread, vi. 3. 2.
..... ſalutary in the bread of London, vi. 3. 2.
..... uſe in making hair-powder, vi. 3.
..... unfriendly to vegetation, x. 7. 8. x. 11. 9.
Alum reſiſts putrefaction, x. 7. 8.
Ammonia, x. 2. 6. x. 7. 8.
Animals diſtinguiſhed from vegetables, x. 1. 4. x. 12. 4.
Animalcules microſcopic, xiv. 3. 2.
Annuals converted into perennials, xix. 3. 1.
Anthers and ſtigmas live on honey, iv. 5. 6.
..... bend to the ſtigmas, vii. 2. 2.
Aorta of plants, v. 1.
Appetencies and propenſities, vii. 3. 7.
..... formative and nutritive, vii. 3. 7.
Aphis, iii. 2. 8. vii. 1. 5. ix. 3. 1. xiv. 1. 7. and 3. 2. add. note v.
Apple ſour on one ſide, xv. 1. 1. xv. 1. 4.
..... tree ſpread horizontally, xv. 2. 2.
Archil, xviii. 1. 5.
Armour of vegetables acquired, xiv. 3. 2.
Arnotto, xvii. 2. 2.
Artichoke ground, xvi. 3. 4. xvii. 1. 3.
Arſenic to poiſon flies and waſps, vi. 6. 3. xiv. 3. 3.
Aſſociation vegetable, viii. 5.
Aſh-tree uſed to feed ſilkworms, xviii. 1. 2.
Aſh-leaves uſed for tea, xviii. 1. 4.
Aſhes of plants contain phoſphorus, x. 5. 6.
..... of bones, x. 5. 4.
Aſparagus, xviii. 1. 2.
Attractions and aptitudes, vii. 3. 6.
Azote forms ammonia, x. 2. 6.
Azotic gas, x. 2. 8.
..... in ſpring water, x. 3. 5.

B.

Barks, xvii. 3.
..... wounds of, xvii. 3. 10.

Barks veſſels of inoſculate, ix. 2. 10.
.... exterior annually renewed, ii. 4.
.... interior of elm, xvii. 3. 3.
.... ſcratched longitudinally, xviii. 2. 1.
.... unperiſhable, xvii 3. 6.
Barley ſteeped in dunghill water, xvi. 8 3.
..... three buſhels and an half on an acre, xvi 8. 1.
Beans uſed for provender, xvi. 6. 2.
..... injured by cold water, xi. 3. 4.
..... injured by too much water, xvi. 1. 4.
..... enrich clayey ſoils, x. 7. 7.
Bees injure vegetation, vi. 6. 3. xiv. 3. 7.
.... how to ſave them when attacked, xiv. 3. 7.
.... how to place their hives, xiv. 3. 7.
Beetles, xiv. 3. 5.
Bird-lime, xvii. 3. 3.
Bitter juices of plants, vi. 9. 1. xvii. 3. 1.
Bloſſoms whiter as fruits become ſweeter, xv. 1. 4.
Bogbean uſed for hops, xviii. 1. 5. xi. 2. 5.
Bone-aſhes, uſe of, x. 5. 4.
Bounties on exportation of corn, xvi. 9. 1.
Bows from yew, xviii. 2. 11.
Brain of vegetables, viii 1. and 9.
Branches, lower ones firſt in leaf, iii. 5.
Bread and beer made from hay, x. 9. 4.
Bredon-lime is half magneſia, x. 6. 8.
Briſtles on moſs-roſes, uſe of, xiv. 3. 2.
..... on young ſhoots of nut-trees, xiv. 3. 2.
Brocoli, cultivation of, xix. 4. 2.
..... poem on, xix. 8.
Broth from muſhrooms, xvii. 2. 5.
Buds, parts of, ix 2. 12.
.... of different maturity, xv. 1. 3.
.... lateral and ſummit ones, xv. 2. 5.
.... converted into each other, ix. 2. 11.
Budding on roots, ix. 3. 5.
Bulbs, ix. 3.
..... produce other bulbs, ix. 1. 5.
Bunium pignut, xvii. 1. 3.
Burying-grounds, x. ii. 3.
Butomus flowering ruſh, xvii. 2. 3. xi. 2. 5.

C.

Cain and Abel, xvi. 9. 1.
Calamine for manure, x. 7. 1. x. 9. 4.
Calcareous earth. See Lime, x. 6.
Calender of Flora, xvi. 8. 1. add. note ix.
Canker, xiv. 1. 6.
..... propoſed cures of, xvii. 3. 10.
Caoutchouc, vi. 8. 5. xvii. 3. 3.
Capillary attraction in alburnum, ix. 2. 10. xv. 2. 3.
Caprification, xiv. 2. 9.
Carbon, x. 4.
..... diſſolved by lime, x. 4. 7.
..... by ammonia, x. 4. 3.
Carbonic acid, x. 2. 5.
..... incompaſſes the earth, x. 4. 1.
..... compoſes mountains, x. 4. 1.
Caterpillars in apple-bloſſoms, xiv. 3. 3.
..... to deſtroy, xiv. 3. 3.
..... eſculent and poiſonous, xiv. 3. 6.
Caudex of a bud, i. 2.
..... of buds of trees, vii. 1. 7. xv. 2. 1.
..... multiplied by dividing, vii. 3. 4.
..... buds from every part of, vii. 1. 7.
..... triple, vii. 3. 1.
Charcoal injected with quickſilver, v. 4.
..... to preſerve ſeeds, xvi. 7. 6.
Chick in the egg, iii. 1. 4. vii. 1. 2.
Chorion of the chick, iii. 1. 4.
Chyle of animals, x. 1.
Circulation of vegetables, v. 1. xix. 2. 2.
..... without a heart, v. 2.
..... in fiſh, v. 2.
..... in the veins, v. 3.
..... by abſorption and by ſpiral veſſels, v. 5.
Clavus or ergot, xiv. 1. 4.
Clay, x. 7. Add. note xii.
..... effervеſces, x. 7. 2.
.... has a ſmell when breathed on, x. 7. 3.
.... burnt for manure in coal countries, x. 7. 4.
.... is condenſed by froſt, xv. 4. 1. xiii. 2. 2. x. 7. 1.
.... acidity of, injurious, xiv. 2. 5.
Coals, origin of, vi. 8. 2.
Coke, his drill huſbandry, xvi. 2. 2.
Colchicum autumnal, iv. 5. 4.
Cold after heat more injurious, xiii. 2. 4. xiv. 2. 2.
.... exceſs of, xiv. 2. 2.
Colouring, matters of, xviii. 1. 5. xvii. 2. 1. xvii. 3. 5.

INDEX.

Colouring for cheeſe, xvii. 2. 1.
Colours of flowers, xix. 1. 2.
..... how to change, xix. 3. 2.
..... white owing to compreſſion, xix. 3. 2.
Condiments, xiv. 2. 8.
Congelation condenſes clay, xv. 4. 1. x. 7. 1.
..... ſeparates fluids, xv. 4. 1. x. 7. 1.
..... repels mucilage, xv. 4. 1.
Coping of ſtone, x. 3. 8. xv. 3. 6. xiii. 2. 2.
..... temporary of boards, xv. 3. 6.
Coralline rocks, xviii. 2. 14.
Corn ripened in froſt, xvi. 3. 2.
.... ripened ſooner by lime, xv. 3. 3.
Corols are reſpiratory organs, iv. 5. 1. vii. 2 3.
Cotyledons of ſeeds, ix. 1. 3.
Couch-graſs, xviii. 1. 1.
Crambe ſea-cale, xiv. 2. 4. xviii. 1. 3. xix. 4. 1.
Crooked trees to ſtraighten, xviii. 2. 1.
Cuticle, or exterior bark, xviii. 2. 1.
..... may be ſcratched, xviii. 2. 1.
Cyder, xiv. 2. 9. additional note xi.

D.

Deity, benevolence of, xix. 7. 3.
Degeneracy of grafted trees, vii. 1. 3. xv. 1. 4. xiv. 1. 6.
Dew-drops, form of, xiii. 1. 5.
Dibbling wheat, xvi. 2. 2.
Digeſtion, experiment on, xvi. 6. 2.
Diſeaſes of plants, xiv.
..... hereditary, xv. 1. 4.
Dogs, experiment on their digeſtion, xvi. 6. 2.
Double flowers, duration of, xix. 1. 1.
..... to produce, vii. 1. 3. xix. 3. 1.
Draught, exceſs of, xiv. 2. 1.
Draining lands, xi. 1.
Drill-machine improved, xii. 5. and Appendix.
..... print of, Appendix at the end of the work.
Drill-huſbandry, ix. 3. 7. xvi. 2. 2.
Drill-huſbandry, advantage of, x. 12. 2. xii. 5.
..... for turnips, xiv. 3. 5.
Dry-rot of timber, to prevent, xviii. 2. 5.
Dunghill water, xvi. 8. 3.
Dwarf fruit-trees, xv. 1. 3. xv. 2. 2.
Dyeing matters, xvii. 3. 5. xvii 2. 1.

E.

Ear fungus, xvii. 2. 5.
Egypt, its fertility from want of rain, x. 11. 1.
..... wheat from, xvi. 2. 2.
Elaſtic reſin, vi. 8. 5.
Electricity, xiii. 3.
..... affects plants, viii. 1. xiv. 2. 3.
..... points to precipitate dew, xiii. 3. 4.
..... pendulum doubler of, xiii. 3. 5.
Elm-tree, bark of, xvii. 3. 3.
Ergot, clavus, xiv. 1. 4.
Eryſiphe, mildew, xiv. 1. 2.
Eſpallier, horizontal, xv. 2. 1.
Etiolation of leaves, xiii. 1. 3. xiv. 2. 4.
..... of flowers, xviii. 1. 3.
..... of ladies, xviii. 1. 3.
..... of roots, xvii. 1. 2. xvii. 2. 2.
Evaporation of water injurious, x. 3. 8.
Evergreens have no bleeding ſeaſon, ix. 2. 2.
..... made by ingraftment, xix. 2. 2.
Excrement of plants, add. note vii.
Exportation of grain, xvi. 9. 1.
Exſudatio miliaris, xiv. 1. 8.

F.

Fallowing, uſe of, xii. 3.
Faſt-days, uſe of, xvi. 9. 1.
Fatneſs, how to produce, xiv. 2. 8.
Fermentations, x. 8. 2. xvi. 3. 4.
Figs fall off in flower, xv. 3. 4.
.... pinch off their ſummits, xvi. 1. 4.
.... compreſs them with wire below, xv. 3 4.
.... wound them with a ſtraw, xv. 3. 4.
Fire-flues in garden walls, xv. 3. 6.
Fiſh propagated for manure, x. 10. 4.

Flax, linum, xvii. 3. 7.
Flewk-worm in ſheep, xiv. 2. 8. additional note v.
Flies, how to poiſon, vi. 6. 3. xiv. 3. 3.
Floods injurious, x. 3. 7.
Flooding meadows, art of, xi. 3.
Flower-buds terminal, ix. 2. 11.
..... converted into leaf-buds, ix. 2. 11.
Flowers require leſs water, x. 3. 9. xvi. 1. 4.
..... enlarged by deſtroying the leaves, iv. 5. 4.
..... cauſes of their colours, xix. 1. 2.
..... to render double, xix. 3. 1.
..... double ones from ſeeds, xix. 1. 1.
Fluor, cubic ſpar, x. 5. 3.
..... uſeful in agriculture, x. 5. 4.
Fluxus umbilicalis, ſap-flow, iii. 2. 2.
..... diſeaſe of, xiv. 1. 9.
Fogs injurious, xv. 3. 6.
.... daſhed againſt trees, xv. 3. 6.
Food of plants or manures, x.
.... of young vegetables, x. 1. 3.
.... of adult vegetables, x. 1. 4.
Fowls, how fattened, xiv. 2. 8.
Free-maſons, xviii. 2. 5.
Froſt ripens corn, x. 3. 9.
.... black or rimy, xiii. 2. 2.
.... deſtroys by expanding fluids, xiii. 2. 2.
.... by ſeparating fluids, xiii. 2. 2. xv. 4. 1.
.... by decreaſing irritability, xiii. 2. 2. and 2. 3. xiv. 2. 2.
.... ſtops the ſap juice, xiii. 2. 3.
.... deſtroys the old and infirm, xiii. 2. 2.
.... and the children of the poor, xiii. 2. 2.
.... how to be ſaved in ſnow, xiii. 2. 2.
.... its effect on ſolutions, xv. 4. 1. xiii. 2. 2. x. 7. 1.
.... how it deſtroys life, xv. 4. 1. xiii. 2. 3.
.... raiſes roots out of the ground, xviii. 1. 1.
.... raiſes the ſmall pebbles of gravel walks, xviii. 1. 1.
.... makes clay more ſolid, xv. 4. 1. x. 7. 1.
.... prevented from injuring meadows, xi. 3. 1.
Fruit wounded, ripens ſooner, x. 8. 1. xv. 3. 7. xiv. 2. 9.
.... to preſerve in ice-houſes, xvii. 2. 4. xvi 7. 3.
.... to raiſe good from ſeed, xv. 1. 1.
.... to preſerve by heat, xv. 4. 1.
.... when ripe, to diſcover, Add. note x.
.... deſtroyed by haſty thawing, why? xvi. 7. 3.
Fungi, xvii. 2. 5.
..... grow without light, xiii. 1. 4. xv. 3. 3. xix. 6. 1.
.... are of animal origin, xvii. 2. 5.
.... are animals without locomotion, xvii. 2. 5. xiii. 1. 4.
.... are nutritious, xix. 6. 1.
Furrows and ridges, xvi. 2. 2.

G.

Gangrena, canker, xiv. 1. 6.
Garden, beſt ſituation of, xiii. 2. 2. xv. 3. 6.
Garden-walls with flues, xv. 3. 6.
Garden-mould, x. 4. 3.
Generation, vegetable, vii. 3.
..... lateral, vii. 1. 1. vii. 3. 9.
..... ſexual, vii. 2. 1. vii. 3. 10.
Glands of vegetables, vi.
Glaſs, x. 7. 2.
..... fine ſand for, xi. 1. 3.
Gluten of wheat nutritious, xix. 6. 1.
..... deſtroyed by fermentation, xvi. 7. 1.
Gooſeberry-trees, to protect, xiv. 3. 3.
... . to ſuckle, xv. 3. 5.
Gout, xix. 1. 1.
Granaries, xvi. 7. 1.
Grain, preſervation of, xvi. 7.
Grafts and ſtocks ſecrete from the ſame blood, xv. 1. 4.
Graſſes forwarded by flooding, xi. 3.
..... preſerved from froſt by flooding, xi. 3.
..... when beſt for hay, xi. 3. 1.
..... ſtems and roots of, ix. 1. 6. ix. 3. 1.
..... have no nectary, ix. 1. 6.
..... ſix kinds for meadows, xviii. 1. 1.
..... three kinds for paſtures, xviii. 1. 1.
..... ſeeds of, xvi. 2. 3. xviii. 1. 1.

Growth of turnips does not impoveriſh land, xii. 3.
..... of trees, its boundary, xviii. 2. 14.
Gum, effuſion of, to prevent, xiv. 1. 10.
Gypſum, x. 5. 3. x. 5. 4.
..... with magneſia, x. 6. 8.
..... how to be uſed, Add. note iv.

H.

Habits of plants, xiv. 1. 1. xix. 2. 1.
Hair-powder, vi. 3.
Happineſs of organized nature, xix. 7. 1.
Harrogate water as a manure, x. 4. 7.
Harrow to extract roots, xviii. 1. 1.
Harrowing wheat in ſpring, xii. 7.
Hawthorn-hedge from ſcions, i. 1. xv. 1. 3.
Hay ſhould be cut young, xi. 3. 2. xviii. 1. 1.
... loſes two thirds of its weight, xviii. 1. 1.
... injured by worms, xviii. 1. 1.
... making, xviii. 1. 1.
Heart-wood is lifeleſs, ix. 2. 10.
..... ſmall force of, v. 3.
Heat, uſe of in vegetation, ix. 1. 3. xiii. 2. 3. xiv. 2. 2.
.... internal of vegetables, xiii. 2. 3.
.... from dunghills, x. 2. 1.
.... combined, xiii. 2. 1.
.... variations of, wholeſome, xiv. 1. 1.
.... above 212 preſerves fleſh, xvii. 2. 4.
Hedgehogs uſeful in gardens, xiv. 3. 6.
Helianthus tuberoſus, xvi. 3. 4.
Hepar of carbon with lime, x. 4. 7.
Hereditary diſeaſes of plants, xix. 1. 1. xix. 2. 1.
Hills ploughed horizontally, x. 11. 1. x. 3. 7.
Hoeing after the corn has bloſſomed, xv. 2. 3.
..... horſe-hoeing, ix. 3. 7. xii. 5.
..... hand-hoeing, xii. 5. xvi. 2. 2.
Honey, vi. 6.
..... differs from ſugar, v. 6. 4.
..... food of anthers and ſtigmas, vii. 2. 4.
..... dew, iii. 2. 8. xiv. 1. 7. xiv. 3. 2.
Hops, bogbean inſtead of, xviii. 1. 5.
Hotbeds turned over heat again, x. 8. 2.
Hydrocarbonate gas, x. 8. 3.

I. & J.

Incloſures if politically good? xvi. 9. 1.
Indigo, xviii. 1. 5.
Individuality of leaf-buds, i. 1.
..... of flower-buds, i. 4.
Ingrafting, iii. 2. 7. xv. 1. 4.
..... why in ſpring, iii. 2. 7.
..... on roots, ix. 3. 5.
..... ſtriped plants, v. 1. xix. 2. 2.
..... of different genera of plants, xv. 1. 4.
Inoculation, i. 3. ix. 2. 10.
..... why in ſummer? iii. 2. 7.
..... on roots, ix. 3. 5.
..... not by flower-buds, i. 4.
..... with mature buds, xv. 1. 2. xv. 1. 4.
Inſects propagated for manure, x. 10. 3.
..... depredations of, xiv. 3.
..... generation of, ix. 3. 1.
..... to deſtroy, xiv. 3. 3.
Joints of graſſes, ix. 3. 1. xvii. 3. 3.
Jonquil, xix. 3. 2.
Irritability, vegetable, viii. 2.
..... diſeaſes of, xiv. 1. 1.

L.

Land to eſtimate. See Soil.
Lateral progeny, vii. 1. 1.
..... reſembles the parent, vii. 1. 3.
..... degenerates, vii. 1. 3.
Lead corroded by oak-boards, xviii. 2. 5.
Leaf-buds converted into flower-buds, ix. 2. 11.
Leaves are lungs,
..... deſtroyed to produce flowers, ix. 2. 11.
..... withered ones firſt eaten, xiv. 3. 2.
..... enrich ſoil by carbonic acid, x. 7 7.
..... turn red in autumn, xv. 1. 4.
Lemon-trees ingrafted, xv. 1. 1.
Lichen rangiferinus, xiii. 2. 2.
Light, uſe of in vegetation, xiii. 1.
..... exceſs of injurious, xiv. 2. 4.
..... from rotten wood, x. 2. 1.
..... from reſpiration, x. 2. 7.
..... defect of, injurious, xiv. 2. 4.

INDEX.

Lightning injures wheat-fields, xiv. 2. 3.
..... deſtroys by exceſs of ſtimulus, xiv. 2. 3.
..... by burſting vegetable veſſels, xiv. 2. 3.
..... how to prevent, xiv. 2. 3.
Lime, uſes of, x. 6. Add. note xi.
..... promotes putrefaction, x. 6. 5.
..... promotes the ripening of grain, x. 6. 7. xvi. 3.
..... diſſolves carbon, x. 4. 7.
..... contains phoſphorus, x. 5. 5. x. 6. 3.
..... uſe of burning it, x. 4. 8.
..... emits heat, x. 4. 4.
..... ſlaked with boiling water, x. 4. 4.
..... broken into powder by ſteam, x. 4. 4.
..... on new walls is long moiſt, why? x. 4. 5. x. 6. 5.
..... nouriſhes plants, x. 4. 6.
..... approaches to fluidity, x. 4. 8. x. 6. 6.
..... of Breedon is half magneſia, x. 6. 8. Add. note xi.
..... decreaſes the coheſion of clay, x. 7. 7.
Livers of geeſe, xiv. 2. 8.
Loamy ſoil, x. 4. 3.
Lop nut trees early in ſummer, ix. 2. 9.
Lolium perenne, xviii. 1. 1.
Lycoperdon, puff-ball, xix. 6. 1.
Luxury in fleſh-food and ale, xvi. 9 1.

M.

Machines for raiſing water, xi. 3. 6.
..... by Hiero's fountain, xi. 3. 6.
..... by new horizontal windmill, xi. 3. 6.
Madder for colouring cheeſe, xvii. 2. 2.
Magneſia with gypſum, x. 6. 8.
Malt, its goodneſs diſcovered, how? xvi. 6. 1.
Manganeſe as a manure, x. 7. 2.
Manures, ſpontaneous, x. 8. 1.
..... chemical, x. 9. 1.
..... by inſects, x. 10. 1.
..... application of, x. 12. 1.
..... when to be applied, x. 12. 2.
..... economy of its application, x. 12. 2.
..... which moſt nutritive, x. 12. 4.
Marle, production of, x. 4. 3.
..... ſhell, x. 5. 5.
..... crumbles in the air, why? x. 7. 3.
Marine acid, x. 7. 1.
..... plants project a liquid, vii. 2. 2.
Maſonry, whence the myſteries of, xviii. 2. 5.
Meadows, flooding of, xi. 3.
..... eat late in ſpring, xviii. 1. 1.
Menyanthes uſed for hops, xviii. 1. 5. xi. 2. 5.
Mice-field, xiv. 4. 1.
Michel's method of raiſing vines, xv. 1. 3.
Mildew, to prevent, xiv. 1. 2.
Miſery is not immortal, xix. 7. 1.
Miſts injurious, xv. 3 6.
.... daſhed againſt trees, xv. 3. 6.
Moiſture, uſe of in vegetation, ix. 1. 3.
..... exceſs of, xiv. 2. 1.
Moles, to deſtroy, xiv. 4. 3.
Mole-plough, xi. 1. 7. Add. note xii.
Monſters, vegetable, ix. 2. 11. xv. 1. 4.
..... vegetable and animal, vii. 2. 8. xix. 1. 1.
Monuments of paſt felicity, xix. 7. 3.
..... of paſt animal life, xviii. 2. 14.
..... of paſt vegetable life, xviii. 2. 14.
Moraſſes, x. 4. 3.
Morels approach to animals, xvii. 2. 5.
..... converted into fat, xvii. 2. 5.
Moſs-roſe, its armour, xiv. 3. 2.
Mould, xiv. 1. 2. See Mucor.
Mucilage, vi. 1.
Mucor, or mould, grows without light, xiv. 1. xv. 3. 3.
..... poiſoned by vinous ſpirit, xv. 4. 3. xvii. 2. 4.
Mulberry leaves, xviii. 1. 2.
..... fruit by ingrafting, xv. 1. 1.
Mule-beans, vii. 2. 6.
.....cabbage, vii. 2. 6.
.....peas, xvi. 4. 1.
.....triple vegetable, vii. 3. 3.
Mules, animal, vii. 2. 7.
..... vegetable, vii. 2. 6.
Muſcles of vegetables, viii. 1.
Muſhrooms, of animal origin, xvii. 2. 5.
..... approach to animal nature, xix. 6. 1.

INDEX.

Muſhrooms conduct Galvaniſm, xvii. 2. 5.
..... ſtone, xvii. 2. 5.

N.

Nerves of vegetables, viii. 1.
Nevil-Holt water, x. 7. 8.
Nitre, production of, x. 7. 4.
Nutritious parts of Vegetables, xix. 6. 1.
Nut-tree twigs their armour, xiv. 3. 2.
Nymphæa alba, ix. 2. 5. xvii. 2. 3.
..... nelumbo eaten in China, xi. 2. 5.

O.

Oaks and willows why barked in ſpring, iii. 5. xvii. 3. 2.
.... ſhould be felled in winter, iii. 5. ix. 2. 8. xviii. 2. 11.
.... barked produce more flower-buds, ix. 2. 8. xv. 2. 3.
.... planted with pines, xviii. 2. 2.
.... 600 years old, xviii. 2. 16.
Oats leſs profitable provender than beans, xvi. 6, 2.
.... improve by keeping, xvi. 6. 4.
Ochre red, as a manure, x. 7. 1.
Oils eſſential, agreeable or poiſonous, vi. 8. 3.
.... fixed in a boiling heat, xvii. 2 5.
.... uſed to poiſon weapons and pools of water, vi. 8. 3.
.... expreſſed, not narcotic, vi. 4. 2.
Old corn preferable to new, xvi. 6 4,
Onions, roots of, ix. 3. 2.
..... magical, ix. 3. 4.
Orange bears by ingrafting, xv. 1. 1.
Orchis for ſalep, xvi. 3. 4. xvii. 1. 5.
. ... how to ripen the ſeeds, ix. 3. 2. xi. 2. 4.
Organs of reproduction, vii.
..... lateral in buds, vii. 1.
..... ſexual in flowers, vii. 2.
Owls ſhould be encouraged, xiv. 4. 1.
Oxydes of metals, x. 2. 3. x. 7. 1.
Oxygen, x. 2. x. 7. 2.
..... abounds in rain water and in ſnow, xiii. 2. 2.
Oxygen in vegetable fluids, whence? x. 4. 8.
..... from decompoſed carbonic acid, x. 4. 8. xiii. 1. 2.
..... from decompoſed water, x. 3. 3. xiii. 1. 2.
..... looſely combined in nitre, x. 8. 4.
..... promotes vegetation, x. 2. 8.
..... abounds by etiolation, xix. 1.
..... deſtroys plants by exceſs, xiv. 2. 7.
..... as a cauſe of irritability, xiv. 1. 1.
Oxygenated muriatic acid, x. 2. 8. xiv. 2. 5.
.....perſpirable matter, xiii. 1. 2. xiii. 1. 4.

P.

Papin's digeſter, x. 9. 3.
Papyrus, xvii. 3 7.
Paring and burning, x. 7. 4.
Paſturage compared to agriculture, xvi. 9. 1.
Pauſe in vegetation at Midſummer, iii. 2. 8. ix. 2. 9.
Pear-tree in part decorticated, ix. 2. 10. xv. 2. 3.
..... compreſſed by wire, xv. 3. 4.
..... bears at the extremities, why? ix. 2. 7.
..... ripens by baking, x. 8. 1.
Peas grow in water, xi. 3. 4.
.... rows of from ſouth-eaſt to north-weſt, xiii. 2. 2.
.... contain more meal than oats, xvi. 6. 2.
.... boil ſoft, xvi. 4. 2.
.... mule, vii. 2. 6. xvi. 4. 1.
.... their pods nutritious, xi, 3. 2.
.... economical provender, xvi. 6. 2.
Penetrability of ſoils, x. 3. 6
Perſpiration vegetable oxygenated, xiii. 1. 4.
Petals are reſpiratory organs, iv. 5. 1. vii. 2. 3.
Phoſphorus in rotten wood, x. 5. 1.
..... in all vegetables, x. 5. 3.
..... hepar of, x. 6. 3.
..... gives ſolidity to timber, x. 5. 6.
Phoſphate of lime, x. 5. 5. x. 7. 6.
..... in the gluten of wheat. Additional note vi.
Pignut, bunium, xvii. 1. 3.

Pine-apple cultivated in water, xv. 3. 4.
Piping buds, ix. 2. 1.
Pith like brain or ſpinal marrow, i. 8. ix. 2. 4. xviii. 2. 13.
Placental veſſels of buds, ii. 4. iii. 2. 6.
..... of ſeeds, iii. 1. 3.
..... of eggs, iii. 1. 4.
Plants live longer if prevented from flowering, vii. 1. 3.
Plant trees ſhallow in the ſoil, xv. 2. 4.
Plough for draining, xi. 1. 7.
..... drill, xii. 5.
..... mole, xi. 1. 7. Add. note xii.
Ploughing if in ridge and furrow, x. 3. 8.
..... wheat in ſpring, xii. 7.
Plume of ſeed aſcends, why? ix. 1. 3.
Poems. See Verſes.
Points liberate air from water, xiii. 1. 5.
Poiſon of yew leaves, xiv. 3. 2.
..... of euphorbium, vi. 8. 3.
..... to vegetables, xiv. 2. 7.
Poiſonous exhalations, xiv. 2. 6.
Polypus, ix. 3. 1.
Potatoes, early ones, xvii. 1. 3.
..... curled ones, ix. 3. 4. xvii. 1. 2.
..... aerial ones, xvii. 1 2.
..... increaſed by tranſplanting, ix. 3. 7.
..... increaſed by pinching off the flowers, ix. 3. 3. xvii. 1. 2.
..... better ſet in drills, xvi. 2. 2.
..... to ripen the ſeed, xvi. 3. 4.
..... how to improve, xvi. 5. 1.
..... to boil in ſteam, x. 9. 2.
..... to boil mealy, xvi. 4. 2.
..... killed by drying on a kiln, x. 9. 2. xvii. 2. 4.
..... bread of, vi. 3.
..... may be planted whole, xvii. 1. 2.
Pottery, Breedon-lime for, x. 6. 8.
Preſervation of fruits, xv. 4. 1.
..... of ſeeds, xvi. 7. 1.
..... of roots by cold and by heat, xvii. 2. 4.
Progreſs of nature to perfection, xx. 2. xiv. 3. 2.
Propagation of good trees, ix. 3. 7.
Props for tranſplanted trees, xviii. 2. 11.
Puberty of plants, ix. 3. 1. xv. 1. 1.
Pulmonary organs, iv.
Putrefaction, x. 8. 3.
Putrid exhalations, x. 4. 3 x. 7. 8.

R.

Raddle as a manure, x. 7. 1.
Radiſhes to procure early, xvii. 1. 1.
Rafts of hollow timber, xviii. 2. 10.
Rain contains oxygen, xiii 2. 2.
.... injures the anther-duſt, x. 3. 9.
Rats to deſtroy, xiv. 4. 2.
.... are liable to the tape-worm, xiv. 4. 2.
Red leaves in autumn, xv. 1. 4.
Rein-deer moſs, xiii. 2. 2.
Reſin elaſtic from bark of holly, xvii. 3. 3.
..... of wheat-flour, vi 8. 5. xvii. 3. 3.
Reſpiration of animals, x. 2. 7.
..... of plants requires light, xiii. 1. 4.
..... of plants not in their ſleep, iv. 5. 5. xiii. 1. 4.
..... of glow-worms is luminous, x. 2. 7.
Rheum hybridum, mule rhubarb. Additional notes i. and ii.
Rhubarb roots when to be taken up, xvii. 2. 1.
..... leaves deſtroyed by mud. Additional note i.
Rice in Valencia, xi. 3. 4.
.... grounds, x. 3. 9.
Ridges and furrows, x. 3. 7. xvi. 2. 2.
..... advantages of, xvi. 2. 2.
Rime perpendicular or lateral, xv. 3. 6.
..... froſts and black froſts, xiii. 2. 2.
Rings of timber concentric, xviii. 2. 12.
Ripening of fruit by wounding it, xiv. 2. 9. x. 8. 1. xv. 3. 7.
..... to diſcover. Additional note x.
Roll wheat in ſpring, xii. 8.
Roots deſcend, why? ix. 1. 3. xv. 2. 4.
..... at Midſummer, ix. 2. 9.
..... decay internally, ix. 3. 5.
..... end-bitten, ix. 3. 5.
..... ſhould be plucked up for tranſplanting, xv. 2. 4.
..... from wounds of the bark, ix. 3. 7.
..... etiolation of, xvii. 2. 1.
Root-grafting, ix. 3. 5.
.... inoculation, ix. 3. 5.
.... propagation, ix. 3. 5.
.... ſcions for planting, xv. 1. 2.
Roſe plaintain, ix. 2. 11.
Roſes to forward, xvi. 2. 5.
..... double ones, xix. 2. 1.
Rot of timber, iii. 2. 3. ix. 2. 8. xviii. 2. 5.

Rot of ſheep, xiv. 2. 8. Additional note v.
Rubia tinctoria to colour cheeſe, xvii. 2. 2.
Rubigo, ruſt, a diſeaſe, xiv. 1. 3.
Rye-graſs, xvi. 6. 1. xviii. 1. 1.

S.

Saccharine proceſs in malt, x. 8. 1.
..... may exiſt beneath the ſoil, x. 8. 1.
..... in baked pears, x. 8. 1.
..... how haſtened in fruit, xiv. 2. 9.
Sage-leaves for tea, xviii. 1. 4.
Sagoe from the palm, xviii. 2. 13.
..... from artichoke ſtalks, xix. 4. 1.
Salep, orchis, xvi. 3. 4. xvii. 1. 5.
Salt marine as a manure, x. 7. 5.
... as a condiment, xiv. 2. 8.
Sand fine white near Derby, xi. 1. 3.
Sap-flow, a diſeaſe of, xiv. 1. 9.
... juice, great force of, v. 3.
... flows in ſpring, iii. 2. 2. ix. 2. 8.
... at Midſummer, iii. 2. 8.
... from herbaceous plants. Add. note x.
... component parts of, x. 1. 1.
Scarcity, food in times of, x. 9. 4.
Scarifier, xviii. 1. 1.
Scions from roots, xv. 1. 2.
..... for grafting, xv. 1. 4.
..... for planting, xv. 1. 3.
Sea-cale, how to cultivate, xiv. 2. 4.
Secretions of vegetables, vi.
..... of the graft and ſtock different, xv. 1 4.
..... of gum, a diſeaſe of, xiv. 1. 10.
Secret concerning fruit-trees, ix. 3. 2.
Seeds before impregnation, vii. 2. 1. vii. 2. 5.
.... growth of, ix. 1.
.... plume grows upwards, why? ix. 1. 3.
.... root downwards, why? ix. 1. 3.
.... production of, xvi.
.... ſteeped in dunghill-water, xvi. 8. 3.
.... of hay ſpoiled by fermentation, x. 11. 7.
.... of wheat ſpoiled by fermentation, xv. 7. 1.
.... of wheat, how to preſerve, xvi. 7. 1.
.... of wheat, how improved, xvi. 5. 1.
.... of potatoes and orchis to ripen, xvi. 3. 4.
Seeds diſperſion of, vii. 2. 5.
.... change of not neceſſary, xv. 5. 1.
.... when ripe to diſcover. Add. note x.
.... how to preſerve, xvi. 7. 6.
.... ſhould be ſown ſoon after ploughing, x. 7. 5.
.... require oxygen, xiii. 1. 5.
Seedling trees, xv. 1. 1.
Senſes of vegetables, viii. 6.
Senſibility of vegetables, viii. 3.
Sexual generation, vii. 1. 7.
..... progeny, vii. 2.
..... of inſects, ix. 3. 1.
Sheep, flewk worm of, xiv. 2. 8.
Showers injurious, x. 11. 1.
Shepherd kings, xvi. 9. 1.
Shrubberies of mulberries, xviii. 1. 2.
Silkworms fed with aſh-leaves, xviii. 1. 2.
Situation for a garden, xv. 3. 5. xiii. 2. 2.
Slaughter-houſe of nature, xix. 6. 5.
Sleep of plants, iv. 5. 5.
Slugs, xiv. 3. 5.
Smoke and ſteam of poiſonous plants, xiv. 3. 2.
Smut of wheat, vii. 2. 2. xiv. 1. 5. xvi. 8. 2.
Smyrna wheat, xvi. 2. 2.
Snails and Slugs, xiv. 3. 5.
Snow contains oxygen, xiii. 2. 2.
Soap-ſtone ſteatites, x. 6. 8.
Soils to analize. Add. note ix.
.... by burning them. Add. note ix.
.... by their ſpecific gravity. Add. note ix.
.... by their native plants. Add. note ix.
.... cracks in them, to prevent, xvi. 2. 2.
Soup leſs nutritive than the ſolid meat, x. 9. 4.
Sour graſs, how to deſtroy, xviii. 1. 1.
Sow thick for herbage, xviii. 1. 1.
.... early on wet ſoils, x. 3. 6. xvi. 8. 1.
.... ſoon after the plough, x. 6. 5.
.... wet, xvi. 8. 4.
Spirituous liquors, xvi. 9. 1. Add. note xi.
..... from roots, xvii. 1. 1.
..... from barks, xvii. 3. 3.
..... from leaves, xviii. 1. 6.
Springs, origin of, xi. 1. 2.
..... wall-ſprings and pipe-ſprings, xi. 1. 3.
....., how to diſcover, xi. 1. 12.

Spur of rye, ergot, xiv. 1. 4.
Stacks of hay, x. 11. 7. xviii. 1. 1.
..... of grain, to preſerve, xvi. 7. 1.
Starch, vi. 3. xvi. 3. ix. 1. 4.
Steam, uſe of in cookery, xix. 4. 1.
..... etiolates ſome vegetables, xix. 4. 1.
Steatites ſoap-ſtone, x. 6. 8.
Stigma bends to the anther, vii. 2. 2.
Straw chopped with green food, xviii. 1. 1.
Strawberries, xv. 2. 4.
..... barren, ix. 3. 4. xv. 1. 4.
Suffuſio mellita, honey-dew, xiv. 1. 7.
Sugar, vi. 5. x. 8. 1. xix. 6. 2.
..... ſugar from ſap-juice of herbs. Additional note xi.
..... may injure the teeth, vi. 5. 2.
..... exiſts in malt. Add. note x.
..... ſeparated from mucilage, vi. 5. 3. x. 8. 2.
..... from beats and carrots, xvii. 1. 1.
..... converted into ſtarch, v. 5. 5.
..... preſerves ſeeds, xvi. 7. 6.
..... nutritious, xix. 6. 1.
Sweat miliary, xiv. 1. 8.
Swine-troughs moveable, x. 11. 6.
Swilcar oak, xviii. 2. 16.

T.

Tennant on limes. Add. note xi.
Tanning, xvii. 3. 5.
Tape-worm in water-rats. Add. note viii.
Tar-water deſtroys ſome inſects, xiv. 3. 5.
Tea recommended, xviii. 1. 4.
Tellure or tiller, xvi. 2. 2. xvi. 2. 3. xii. 7.
Teucrium ſcorodonia, wood-ſage, xviii. 1. 5.
Thiſtles, to deſtroy, xiv. 1. 9. Additional note xi.
Thunder ſhowers, xiii. 3. 3.
Tiller, or tellure, xii. 7. xvi. 2. 2.
Timber, concentric rings of, xviii. 2. 12.
..... rot of, to prevent, xviii. 2. 5.
..... how decompoſed, xviii. 2. 14.
..... political to cultivate, xviii. 2. 15.
..... durability of, xviii. 2. 7.
..... See Trees.
Tranſplantation of wheat, ix. 3. 7. xii. 6.
Tranſplantation of trees at Midſummer, ix. 2. 9.
..... of fruit trees, xv. 2. 4. xviii. 2. 11.
..... of timber trees, xviii. 2. 11.
..... not too deep, why? xv. 2. 4.
..... of turnips, ix. 3. 5. xii. 6.
..... of brocoli, xv. 2. 4. xix. 4. 2.
..... of ſtrawberries, xv. 2. 4.
Trees crooked, how to ſtraighten, xviii. 2. 1.
..... ſmeared with pitch die, iii. 2. 6.
..... do not bleed in ſummer, iii. 2. 5.
..... triple by ingraftment, vii. 3. 1.
..... their ſize bounded, xviii. 2. 14.
..... to make tall and ſtraight, xviii. 2. 2.
..... to make them crooked, xviii. 2. 2.
..... when to fell, iii. 2. 3. ix. 2. 8. xviii. 2. 12.
..... tranſplanted when large, how, xviii. 2. 11.
..... tranſplanted, how to prop, xviii. 2. 11.
Trefoil, xviii. 1. 1.
Trifolium pratenſe & repens, xviii. 1. 1.
Truffle, lycoperdon tuber, xvii. 2. 5.
Tulip, xv. 1. 1.
..... ſeed is five years before it flowers, ix. 1. 5. ix. 3. 1.
..... leſs when coloured, xix. 1. 2.
Tull's huſbandry, 9. 3. 7. xvi. 2. 2.
..... advantages of, xii. 5.
Turnips ſowed deep in drills, xiv. 3. 5.
..... do not impoveriſh the ſoil, why, xii. 3.
..... tranſplanted, ix. 3. 5. xii. 6.
..... affected by the fly, xiv. 3. 5.
Turpentines, vi. 8.
Tuſſocks of graſs, how to deſtroy, x. 6. 7. xviii. 1. 1.
..... of wheat, xii. 6. xiv. 4. 1.
..... of trees, xviii. 2. 2.
Twitch-graſs, xviii. 1. 1.

INDEX.

U.

Umbilical veſſels of vegetables, iii.
..... in ſeeds, iii. 1. 3.
..... in eggs, iii. 1. 3.
..... of buds, iii. 2. 2.
..... of the alburnum, ix. 2. 9.
..... live after the arterial ones, ix. 2. 10.
Uredo frumenti, xiv. 1. 3.
Uſtilago, ſmut, xiv. 1. 5.

V.

Variegation by ingrafting, v. 1. xv. 1. 4. xix. 2. 2.
Vegetables differ from animals, i. 5.
..... reſemble animals, i. 6.
..... how to boil them green, xix. 4. 1.
Vegetation, pauſe of at Midſummer, iii. 2. 8. ix. 2. 9.
Verſes on ingrafting, xv. 1. 5.
..... on producing flower-buds, xv. 2. 6.
..... on cultivation of brocoli, xix. 8.
..... on pruning wall trees, xv. 5.
..... on pruning melons, xv. 5.
..... on Swilcar oak, xviii. 2. 16.
Vigorous and weak trees, x. 2. 1.
Vines, art of raiſing, xv. 1. 3.
..... management of, xv. 2. 5.
..... to ripen the grapes, xiv. 3. 3.
..... leaves to colour wine, xviii. 1. 5.
Vitrification, x. 7. 2.
Volition, vegetable, viii. 4.

W.

Wall-trees horizontal, xv. 2. 1.
Walls long in drying, why, x. 4. 4.
Walnut bears by ingrafting, xv. 1. 1.
Waſps, to poiſon, vi. 6. 3.
Water, uſes of in agriculture, x. 3.
..... ſolidified, xviii. 1. 1. x. 4 4.
..... is an acid, x. 2. 6.
Water is decompoſed in vegetables, x 3. 3.
..... of ſome ſprings contains limeſtone, x. 6. 2. x. 3. 5.
..... of rain contains oxygen, xiii. 2. 2.
..... poiſoned by euphorbia, vi. 8. 4.
Watering meadows, xi. 3.
..... plants, xv. 3. 4. xviii. 2. 1.
..... not in ſunſhine, why, xi. 3. 4.
..... nor in froſt, why, xv. 3. 4.
..... muſt be repeated, xi. 3. 4.
..... not ſo as to cover them, xi. 3. 3.
Wax, vi. 7.
Weeds, to deſtroy. Add. note xi.
Wet ſeaſons injurious, x. 3. 9.
..... injure wheat, vi. 7. 1.
.... ſoils, ſow and reap early in, x. 3. 6.
Wheat, ix. 1. 6. ix. 3. 1. xii. 5.
..... with branching ears, xvi. 2. 2.
..... number of grains from one, ix. 3. 7.
..... tranſplanted, xii 6. xvi. 1. 2. ix. 1. 6. ix. 3. 7. xiv. 4. 1.
..... rolled in ſpring, xii. 8. xvi. 2. 2. xvi. 2. 5.
..... harrowed in ſpring, xii. 7.
..... conſiſts of ſeparate plants, ix. 3. 1.
..... gluten of, vi. 8. 5. xvi. 7. 1. xvii. 3. 3. xix.
..... has no nectary, ix. 1. 6.
..... injured by wet ſeaſons, vi. 7. 1.
..... ſowed but one inch deep, xiv. 3. 6.
..... how to diſcover its goodneſs, xvi. 6. 1.
..... ſow two kinds of, xvi. 8. 2.
..... caudex of produces other ſtems, ix. 1. 6.
..... caudex injured by inſects, xiv. 3. 6.
..... dibbling of, xvi. 2. 2.
..... eaten down by ſheep, ix. 3. 7. xvi. 2. 3.
..... dried on a kiln, xvi. 7. 1.
..... hoarded by mice, xiv. 4. 1.
White parts of flowers from compreſſion, xix. 3. 2.
Willow-bark, ix. 2. 10.
Winds, ſouth-weſt ſalubrious, xv. 3. 6.
..... north-eaſt injurious, xv. 3. 6.

Wines,

INDEX.

Wines, means to fine them. Add. note x.
Woad, xviii. 1. 5.
Wood, to increaſe, xviii. 2. 1.
..... durability of, xviii. 2. 7. xviii. 2. 14.
..... triturated for food, x. 9. 4.
Wood-fires impoveriſh a country, x. 11. 5.
Wood-ſage, teucrium ſcorodonia, xviii. 1. 5.
Woods ſhould be planted on hills, xviii. 2. 15.
Worm of ſheep, xiv. 2. 8. Add. note v.
Wounds of trees bleed in ſpring, iii. 2. 2. v. 3.
..... imbibe fluids in ſummer, v. 3.
..... of the bark, xvii. 3. 10.
..... upper lip only grows, i. 3.
..... of fruit by inſects, xiv. 2. 9.
..... by caprification, xiv. 2. 9.

THE END.

ERRATA.

Page 139, line laſt but one, *read* diſtinguiſhes, *for* diſtinguiſh.
—— 121, line 14, *for* from, *read* form.
—— 528, line laſt but two, *for* ſo, *read* no.

DIRECTIONS TO THE BINDER.

Pleaſe to put Plate I. and the Explanation of it, facing each other, at the end of Section I. between pages 8 and 9.

Plate II. at the end of Sect. II. between p. 18 and 19.

Plate III. at the end of Sect. III. between p. 38 and 39.

Plate IV. at the end of Sect. IX. between p. 182 and 183.

Plate V. VI. VII. at the end of Sect. XI. between p. 282 and 283.

Plate VIII. at the end of Sect. XIII. between p. 314 and 315.

Plate IX. at the end of Sect. XIV. between p. 372 and 373.

Plate X. XI. XII. at the end.

Printed by T. BENSLEY, *Bolt Court, Fleet Street, London.*

Plate X.




Fig. 1.

London, Published Jan.y 1.st 1800, by J. Johnson, St. Paul's Church Yard.

Plat

Plate XI.

Fig. 2.




Fig. 3.




Fig. 4.



London, Published Jan.ʸ 1.st 1800, by J. Johnson, S.t Paul's Church Yard.

Plate

Plate XII.

Fig. 1.






Fig. 2.

Fig. 3.



Fig. 4.




Fig. 5.





Fig. 6.



London, Published Jan.ʸ 1.ˢᵗ 1800, by J. Johnson, St. Paul's Church Yard.